

CITY OF MERCER ISLAND

Fire Marshal's Office

3030 78th Ave SE | MERCER ISLAND, WA 98040

PHONE: 206.275.7966 | www.mercerisland.gov



2020 RESIDENTIAL FIRE AREA SQUARE FOOTAGE CALCULATION

Project Type: <input type="checkbox"/> New Single Family <input type="checkbox"/> Alteration <input checked="" type="checkbox"/> Addition
Project Address: 5472 West Mercer Way
Contact Name: Patricia Brennan / Patricia Brennan Architects Phone No. (206) 328-2886
Owner Name: Maya & Pierre Nader

Gross floor area shall be that area in square feet under the roof line of the structure including all usable area whether heated or not, above and below grade. This includes the garage and any unheated storage rooms or attachments including covered decks. If it is *usable space*, then it is included in the **Gross** square footage calculation. *This is not the same calculation for floor area ratio.*

For all construction types, add all the interior wall measurements of each floor and the basement and total that figure.

NEW CONSTRUCTION *(over for addition or alteration)*

<input checked="" type="checkbox"/> N/A	<table border="1"><thead><tr><th>Measurements</th><th>Square Footage</th></tr></thead><tbody><tr><td>Main Floor interior</td><td></td></tr><tr><td>Lower Floor Interior</td><td></td></tr><tr><td>Other Floors interior</td><td></td></tr><tr><td>Basement interior</td><td></td></tr><tr><td>Attached Garage interior</td><td></td></tr><tr><td>Covered Decks interior</td><td></td></tr><tr><td>Other interior</td><td></td></tr><tr><td>TOTALS</td><td>0.00</td></tr></tbody></table>	Measurements	Square Footage	Main Floor interior		Lower Floor Interior		Other Floors interior		Basement interior		Attached Garage interior		Covered Decks interior		Other interior		TOTALS	0.00
Measurements	Square Footage																		
Main Floor interior																			
Lower Floor Interior																			
Other Floors interior																			
Basement interior																			
Attached Garage interior																			
Covered Decks interior																			
Other interior																			
TOTALS	0.00																		

ADDITION or ALTERATION

Does this house have an existing **Fire Sprinkler System?** Yes No / **Fire Alarm System** Yes No

Measurements	Existing Square Footage	Standardized Value	Added Footage	Final Square Footage
Main Floor interior	2,283	x \$177.76 <u>405,826.10</u>	0	2,283
Lower Floor Interior	0	x \$177.76 <u>\$ 0.00</u>		0
2nd Other Floors interior	1,181	x \$177.76 <u>209,934.60</u>	638	1,819
Basement interior	2,429	x \$177.76 <u>431,779.00</u>	-92	2,337
Attached Garage interior	0	x \$36.88 <u>\$ 0.00</u>	696	696
Covered Decks interior	552	x \$36.88 <u>20,357.76</u>	167	719
Other interior		x \$177.76 <u>\$ 0.00</u>		0
TOTALS	6,445	\$1,067,897.00	1,409	7,854

Construction Cost \$ 1,391,609.64 _____

Official Use

Verified Cost \$ _____

Higher of Verified or Cost \$ _____ / Value _____ \$0.00 = % _____

- Valuation Ratio
- Exempt structure – detached garage or similar structure less than 750 sf.
 - Less than 10% (fire review not required)
 - 10 – 49% (monitored Household Fire Alarm System per NFPA 72 Chapter 29, if fire deficiency)
 - 50% or greater (substantial alteration)

2015 INT'L FIRE CODE

901.4.4 Additional Fire Protection Systems. In occupancies of a hazardous nature, where special hazards exist in addition to the normal hazards of the occupancy, or where the fire code official determines that access for fire apparatus is unduly difficult, the fire code official shall have the authority to require additional safeguards. Such safeguards include, but shall not be limited to, the following:

- Automatic fire detection systems,
- Fire alarm systems,
- Automatic fire-extinguishing systems,
- Standpipe systems, or
- Portable or fixed extinguishers.

Fire protection equipment required under this section shall be installed in

accordance with this code and the applicable referenced standards.

2015 INT'L RESIDENTIAL CODE

AV107.1 Fire Sprinklers. An approved automatic fire sprinkler system shall be installed in new one-family and two-family dwellings and townhouses in accordance with Appendix Q.

AV107.2 Fire Sprinklers in Existing Buildings. An approved automatic fire sprinkler system shall be installed throughout the residence in existing one-family and two-family dwellings (and townhouses) in accordance with Appendix Q when undergoing a remodel or addition when the construction value of all additions, alterations or repairs performed within

a sixty-month period exceeds 50% of the value of the residence. Value shall be determined by a method approved by the fire code official.

AV107.3 Household Fire Alarm System. An approved household fire alarm system shall be installed throughout the residence in existing one-family and two-family dwellings (and townhouses) that have deficiencies in fire flow, hydrants or access. This system shall be installed in accordance with NFPA 72 Chapter 29 when undergoing a remodel or addition when the construction value of all additions, alterations or repairs performed within a sixty-month period is within 10% to 50% of the value of the residence. Value shall be determined by a method approved by the fire code official.