


Nov 14, 2019 9:41:00am - User: Keith Lenkowski
 N:\PROJECTS\2551 SARAH & AMIR BASTAWROUS\2551.01 THE MAPLE GROVE RESIDENCE\PHASE 03 - PERMIT ASSISTANCE\CAD\2551-1A1.1 SITE PLAN-MAPLE PERMITTING



NO WORK IN THIS AREA

4909 E. Mercer Way
Mercer Island Wa, 98040

NOTE:

- ACCESS GRANTED BY ADJACENT PROPERTY OWNER
- DISTURBED TEMPORARY ACCESS AREA TO BE REVEGETATED WITH NEW LANDSCAPE PLANTINGS AFTER REMOVAL OF TEMPORARY ACCESS ROAD.

GENERAL LANDSCAPE NOTES:

- LANDSCAPE CONSTRUCTION SHALL CONFORM TO ALL APPLICABLE STATE AND LOCAL CODES AND SPECIFICATIONS.
- ALL MATERIAL AND WORKMANSHIP SHALL BE MAINTAINED AND GUARANTEED FOR A PERIOD OF 12 MONTHS FOLLOWING THE SUBSTANTIAL COMPLETION DATE.
- LANDSCAPE CONTRACTOR SHALL EXAMINE THE SITE CONDITIONS UNDER WHICH THE WORK IS TO BE PERFORMED, NOTIFY OWNER OF UNSATISFACTORY CONDITIONS. CONTRACTOR SHALL NOT PROCEED UNTIL CONDITIONS HAVE BEEN CORRECTED.
- BEFORE COMMENCING WORK, LANDSCAPE CONTRACTOR SHALL CONTACT APPROPRIATE UTILITY COMPANIES FOR UTILITY LOCATIONS, AND COORDINATE WITH OWNER IN REGARD TO LOCATION OF PROPOSED UTILITIES, IRRIGATION SLEEVES, CONDUITS, ETC.
- COMPLY WITH MANUFACTURERS RECOMMENDATIONS FOR INSTALLING PRODUCTS IN APPLICATIONS INDICATED.
- CONDUCT CONSTRUCTION OPERATIONS SO THAT NO PART OF FINISHED WORK IS SUBJECT TO DAMAGE DURING SUBSEQUENT CONSTRUCTION OPERATIONS. COVER, FLAG AND PROTECT FINISHED WORK AS NECESSARY TO AVOID DAMAGE.
- CLEAN SITE AND WORK AREAS DAILY.
- DO NOT WASH WASTE MATERIAL DOWN SEWERS, DRAINS OR INTO WATERWAYS. DO NOT BURY WASTE MATERIAL ON SITE. DISPOSE OF ALL WASTE MATERIAL AT AN APPROVED WASTE HANDLING FACILITY.

PROJECT DATA:
 PARCEL#: 2162000230
 ZONING: R-15
 SITE ADDRESS: 4909 E. MERCER WAY,
 MERCER ISLAND, WA 98059
 EAST MERCER HIGHLANDS
 ADD LESS POR ELY OF LN BEG 18 FT W OF NE COR TH S
 09-26-31 E 96.13 FT TO SE COR & UND INT IN PVT RD

LOT SLOPE CALCULATIONS:
 HIGHEST ELEVATION OF LOT: 510'
 LOWEST ELEVATION OF LOT: 454'
 ELEVATION DIFFERENCE: 56'
 HORIZONTAL DISTANCE: 238'
 LOT SLOPE: 24%

LOT COVERAGE CALCULATIONS:

A. ALLOWED LOT COVERAGE:	35%
B. ALLOWED LOT COVERAGE AREA:	6,099 S.F.
C. GROSS LOT AREA:	17,425 S.F.
D. NET LOT AREA:	11,326 S.F.
E. MAIN STRUCTURE ROOF AREA:	3,625 S.F.
F. ACCESSORY BUILDING ROOF AREA:	0
G. VEHICULAR USE AREA:	1,830 S.F.
H. TOTAL EXISTING LOT COVERAGE AREA:	5,455 S.F.
I. TOTAL LOT COVERAGE AREA REMOVED:	0
J. TOTAL NEW LOT COVERAGE AREA:	0
K. TOTAL PROJECT LOT COVERAGE AREA (H-I)+J:	5,455 S.F.
L. PROPOSED ADJUSTMENT FOR SINGLE STORY:	0
M. PROPOSED ADJUSTMENT FOR FLAG LOT:	0
N. PROPOSED LOT COVERAGE (K/I)X100:	31%

HARDSCAPE COVERAGE CALCULATIONS:
 ALLOWABLE HARDSCAPE AREA: 1,568 S.F. MAX
 TOTAL EXISTING HARDSCAPE: 712 S.F.
 HARDSCAPE TO BE REMOVED: 108 S.F.
 PROPOSED HARDSCAPE: 232 S.F.
 TOTAL EXISTING DECKS: 378 S.F. 1/8" PERVIOUS SPACING
 PROPOSED DECKS: 0 S.F.
 TOTAL HARDSCAPE AREA: 836 S.F.


REFERENCE NOTES SCHEDULE

SYMBOL	DESCRIPTION	QTY	DETAIL
1	PLANTING AREA	1,715 SF	
2	LAWN TERRACE	1,656 SF	
3	LANDSCAPE EDGING PERMALOC CLEANLINE	104 LF	
4	MILD STEEL STEPS WITH CRUSHED GRANITE INFILL	152 LF	3/LA3.3
5	CRUSHED GRANITE PATH 4" DEPTH	160 SF	3/LA3.3
6	PROPOSED C.I.P. CONCRETE RETAINING WALL NATURAL COLOR AND FINISH SEE SHEET LA3.1 & LA3.2 FOR DETAILS	237 LF	
7	CEDAR GUARD RAIL AND GATE APPEARANCE GRADE CEDAR SANDED STAINED	55 LF	2/LA3.3
8	CABLE GUARD RAIL AND GATE MILD STEEL RUSTED FINISH STAINLESS STEEL WIRE AND HARDWARE	39 LF	1/LA3.3
9	MILD STEEL PLANTER 12"W X 37"H X 84"L NATURAL FINISH	4/LA3.3	
SYMBOL	DESCRIPTION	QTY	DETAIL
D-101	REMOVE EXISTING PLAY STRUCTURE		
D-102	REMOVE FAILING RAILROAD TIE RETAINING WALL		
D-103	REMOVE WOOD STAIRS		


SHEET INDEX

SHEET	DESCRIPTION
LA1.1	Site Plan
LA2.1	Wall Plan
LA3.1	Structural Notes
LA3.2	Structural Details
LA3.3	Permit Details

REVISIONS PERMIT PLAN DATE: 10/17/2019 BY: KJ	SCJ STUDIO LANDSCAPE ARCHITECTURE 1148 NW LEARY WAY, SEATTLE, WA 98107 206.706.1862 SCJSTUDIO.COM	Site Plan Maple Grove Residence 4909 E. Mercer Way Mercer Island, WA 98040	SHEET TITLE: PROJECT NAME: SEAL: 	DESIGNER: KJ DRAWN BY: JL APPROVED BY: MG DATE: OCTOBER 2019 JOB No: 2551 DRAWING FILE No: LA1.1 SHEET No: 1 OF 6
--	--	--	--	--



Nov 14, 2019 11:50:04am - User: Keith Jankovsky
 N:\PROJECTS\2551 SARAH & AMR BASTIAROWSKI\2551.01 THE MAPLE GROVE RESIDENCE\PHASE 03 - PERMIT ASSISTANCE\CAD\2551-LA1.2 TREE RETENTION PLAN-MAPLE PERMIT.DWG



NOTE:

- ACCESS GRANTED BY ADJACENT PROPERTY OWNER
- DISTURBED TEMPORARY ACCESS AREA TO BE REVEGETATED WITH NEW LANDSCAPE PLANTINGS AFTER REMOVAL OF TEMPORARY ACCESS ROAD.



TREES #3, #4, & #5



TREES #3



TREES #4



TREES #5




VISIBLE FAILURE OF SLOPE

Tree Inventory / Retention Schedule

Tree #	Species	Latin Name	DBH	Appr Ht.	Condition	Drip line Radius	Req'd Replacement Trees	Retain yes/no
DF1	Fir	<i>Pseudotsuga menziesii</i>	32"	110'	Fair	13'	N/A	YES
DF2	Fir	<i>Pseudotsuga menziesii</i>	44"	120'	Good	18'	N/A	YES
DF3	Fir	<i>Pseudotsuga menziesii</i>	43"	120'	Good	18'	6	NO
DF4	Fir	<i>Pseudotsuga menziesii</i>	17"	90'	Fair	10'	2	NO
DF5	Fir	<i>Pseudotsuga menziesii</i>	25"	95'	Fair	13'	3	NO
DF6	Fir	<i>Pseudotsuga menziesii</i>	13"	65'	Fair	11'	N/A	YES
DF7	Fir	<i>Pseudotsuga menziesii</i>	38"	120'	Good	18'	N/A	YES
DF8	Fir	<i>Pseudotsuga menziesii</i>	23"	95'	Fair	13'	N/A	YES
DF9	Fir	<i>Pseudotsuga menziesii</i>	16"	85'	Fair	11'	N/A	YES
DF10	Fir	<i>Pseudotsuga menziesii</i>	25"	80'	Good	13'	N/A	YES
DF11	Fir	<i>Pseudotsuga menziesii</i>	18"	85'	Fair	11'	N/A	YES
CE12	Cedar	<i>Thuja plicata</i>	16"	75'	Good	10'	N/A	YES
CE13	Cedar	<i>Thuja plicata</i>	18"	60'	Fair	8'	N/A	YES
CE14	Cedar	<i>Thuja plicata</i>	20"	70'	Good	10'	N/A	YES
CE15	Cedar	<i>Thuja plicata</i>	18"	60'	Fair	8'	N/A	YES
CE16	Cedar	<i>Thuja plicata</i>	16"	60'	Fair	8'	N/A	YES

Note: Replacement trees shall be conifers at least 6' tall and / or deciduous trees at least 1-1/2" Caliper

CE = CEDAR
 DF = DOUGLAS FIR
 MP = MAPLE
 PL = PLUM




REVISIONS DATE BY KJ 10/17/2019 PERMIT PLAN	SCJ STUDIO LANDSCAPE ARCHITECTURE 1148 NW LEARY WAY, SEATTLE, WA 98107 206-709-1862 SCJSTUDIOA.COM	SHEET TITLE: Tree Inventory / Retention Plan PROJECT NAME: Maple Grove Residence 4909 E. Mercer Way Mercer Island, WA 98040 SHEET: 2 OF 6	SEAL: DESIGNER: KJ DRAWN BY: JL APPROVED BY: MG DATE: OCTOBER 2019 JOB No: 2551 DRAWING FILE No: DRAWING No: LA1.2 SHEET No: 2 OF 6
--	--	---	---

WALL SCHEDULE


SYMBOL	DESCRIPTION	QTY	DETAIL
W-01	C.I.P. RETAINING WALL 8"W TYP.	118 LF	LA3.1 & LA3.2
W-02	C.I.P. FOOTING WIDTH VARIES	118 LF	5/LA3.2
W-03	2" DIA. SCH. 80 PIPE PILE DRIVEN TO REFUSAL PLACE AS SHOWN ON PLAN	38	LA3.1 & LA3.2
W-04	4" DIA. SCH 80 PVC DRAIN DAYLIGHT THROUGH WALL AS SHOWN	150 LF	LA3.1 & LA3.2
W-05	HELICAL ANCHOR TYPICAL	6/LA3.2	

ABBREVIATIONS

SG: SUBGRADE
 TW: TOP OF WALL
 BW: BOTTOM OF WALL



Nov 14, 2019, 9:41:26am - User: Keith Jankovsky
 N:\PROJECTS\2551_SARAH & AMR BASTARROS\2551.01_THE MAPLE GROVE RESIDENCE\PHASE 03 - PERMIT ASSISTANCE\CAD\2551-1-A2.1_WALL PLAN-MARLE PERMIT.DWG



DATE	10/17/2019	BY	KJ		
REVISIONS					
PERMIT PLAN					
1148 NW LEARY WAY, SEATTLE, WA 98107 4909 E. MERCER WAY MERCER ISLAND, WA 98040 SCJSTUDIO.COM					
Wall Plan			Maple Grove Residence 4909 E. Mercer Way Mercer Island, WA 98040		
SHEET TITLE					
PROJECT NAME					
SEAL					
DESIGNER	KJ				
DRAWN BY	JL				
APPROVED BY	MG				
DATE	OCTOBER 2019				
JOB No:	2551				
DRAWING FILE No:					
DRAWING No:	LA2.1				
SHEET No:	3 OF 6				

GENERAL NOTES

(The following apply unless shown otherwise on the plan)

1. CODE REQUIREMENTS:

ALL MATERIALS, WORKMANSHIP, DESIGN, AND CONSTRUCTION SHALL CONFORM TO THE DRAWINGS, SPECIFICATIONS, THE 2015 IBC, AND THE LATEST EDITION OF THE PTI DOCUMENT, "RECOMMENDATIONS FOR PRE-STRESSED ROCK AND SOIL ANCHORS".

2. REFERENCE DOCUMENTS:

TOPOGRAPHIC AND BOUNDARY SURVEY INFORMATION BY SCJ STUDIO. REPORT ON GEOTECHNICAL INVESTIGATION BY EARTH SOLUTIONS NW, ES-6510 DATED 10-3-19.

3. GENERAL REQUIREMENTS:

CONTRACTOR SHALL BE RESPONSIBLE FOR ALL SAFETY PRECAUTIONS AND THE METHODS, TECHNIQUES, SEQUENCES OR PROCEDURES REQUIRED TO PERFORM THE CONTRACTOR'S WORK. THE STRUCTURAL ENGINEER HAS NO OVERALL OR ACTUAL SUPERVISORY AUTHORITY AND/OR DIRECT RESPONSIBILITY FOR THE SPECIFIC WORKING CONDITIONS AT THE SITE AND/OR FOR ANY HAZARDS RESULTING FROM THE ACTIONS OF ANY TRADE CONTRACTOR.

UTILITY LOCATION: THE SHORING CONTRACTOR SHALL DETERMINE THE HORIZONTAL AND VERTICAL LOCATION OF ALL ADJACENT UNDERGROUND UTILITIES PRIOR TO DRIVING PILES OR TIEBACK ANCHORS. THE UTILITIES INFORMATION SHOWN ON THE PLANS MAY NOT BE COMPLETE. THIS INCLUDES CALLING UTILITY LOCATE AT 1-800-424-5555 AND THEN POT-HOLING ALL UTILITIES PRIOR TO CONSTRUCTION TO CONFIRM DEPTHS AND LOCATIONS AND TO VERIFY THAT THERE ARE NO CONFLICTS WITH THE PILE AND TIEBACK CROSSING ELEVATIONS.

CONTRACTOR SHALL VERIFY ALL DIMENSIONS OF EXISTING STRUCTURES IN THE FIELD AND SHALL NOTIFY THE ENGINEER OF ALL FIELD CHANGES PRIOR TO FABRICATION AND INSTALLATION OF ANY STRUCTURAL MEMBER.

ANY DISCREPANCIES FOUND AMONG THE DRAWINGS, THE SPECIFICATIONS, THESE GENERAL NOTES AND THE SITE CONDITIONS SHALL BE REPORTED TO THE ENGINEER AND ARCHITECT, WHO SHALL CORRECT SUCH DISCREPANCY IN WRITING. SHOULD ANY DISCREPANCIES BE FOUND IN THE PROJECT DOCUMENTS, THE CONTRACTOR WILL BE DEEMED TO HAVE INCLUDED IN THE PRICE THE MOST EXPENSIVE WAY OF COMPLETING THE WORK, UNLESS PRIOR TO SUBMISSION OF THE PRICE THE CONTRACTOR ASKS FOR A DECISION FROM THE ENGINEER AND ARCHITECT AS TO WHICH SHALL GOVERN.

4. GEOTECHNICAL INFORMATION AND CRITERIA:

INSTALLATION OF PILES AND TIEBACKS, SUBGRADE PREPARATION INCLUDING DRAINAGE, EXCAVATION, COMPACTION AND FILLING REQUIREMENTS SHALL CONFORM WITH THE RECOMMENDATIONS CONTAINED IN THE SOILS REPORT AND/OR AS DIRECTED BY THE GEOTECHNICAL ENGINEER. THE SUBSURFACE CHARACTERIZATIONS USED TO DESIGN THE SHORING ARE CONTAINED IN THE SOILS REPORT AS REFERENCED ABOVE.

EXCAVATIONS FOR FOUNDATIONS SHALL BE PER PLAN DOWN PER THE GEOTECHNICAL ENGINEERING RECOMMENDATIONS. OVER EXCAVATED AREAS SHALL BE BACKFILLED WITH LEAN CONCRETE OR PER GEOTECHNICAL RECOMMENDATIONS AT THE CONTRACTOR'S EXPENSE. EXCAVATION SLOPES SHALL BE SAFE AND SHALL NOT BE GREATER THAN THE LIMITS SPECIFIED BY LOCAL, STATE, AND NATIONAL SAFETY REGULATIONS.

DESIGN LOADS ARE DETERMINED BY THE GEOTECHNICAL ENGINEER. THE SOIL PRESSURES INDICATED ON THE SOIL PRESSURE DIAGRAM WERE USED FOR DESIGN. IN ADDITION TO THE DEAD AND LIVE LOADS. SEE REPORT OF GEOTECHNICAL INVESTIGATION FOR MORE COMPLETE INFORMATION, INCLUDING RECOMMENDATIONS FOR PILES AND TIEBACKS IN GENERAL, MONITORING, EXCAVATION, AND DRAINAGE.

DESIGN PARAMETERS AS APPROVED BY THE GEOTECHNICAL ENGINEER ARE AS FOLLOWS:

Table with 2 columns: LATERAL EARTH PRESSURES (EQUIVALENT FLUID PRESSURE) and E.F.P. Values include 35 PCF, 55 PCF, 6H PSF, 250 PCF/100 PCF, and 3 TON.

PILE AND TIEBACK DURATION: THE PILES AND TIEBACKS ARE PERMANENT.

5. SHOP DRAWINGS:

SHOP DRAWINGS ARE REQUIRED FOR THE FOLLOWING ITEMS:

- STRUCTURAL STEEL
MISCELLANEOUS METALS
HELICAL ANCHORS

CONTRACTOR SHALL ALSO COORDINATE APPROVED SHORING SUBMITTALS WITH BUILDING DEPARTMENT REQUIREMENTS.

SHOP DRAWING REVIEW: DIMENSIONS AND QUANTITIES ARE NOT REVIEWED BY THE ENGINEER OF RECORD. THEREFORE MUST BE VERIFIED BY THE CONTRACTOR. CONTRACTOR SHALL REVIEW AND STAMP DRAWINGS PRIOR TO REVIEW BY ENGINEER OF RECORD.

SHOP DRAWING SUBMITTALS PROCESSED BY THE ENGINEER ARE NOT CHANGE ORDERS. THE PURPOSE OF SHOP DRAWING SUBMITTALS BY THE CONTRACTOR IS TO DEMONSTRATE TO THE ENGINEER THAT THE CONTRACTOR UNDERSTANDS THE DESIGN CONCEPT, BY INDICATING WHICH MATERIAL IS INTENDED TO BE FURNISHED AND INSTALLED AND BY DETAILING THE INTENDED FABRICATION AND INSTALLATION METHODS.

6. INSPECTIONS:

THE CONTRACTOR SHALL BE RESPONSIBLE TO COORDINATE ALL INSPECTIONS REQUIRED BY THE LOCAL BUILDING DEPARTMENT. IN ADDITION TO INSPECTIONS REQUIRED BY THE LOCAL BUILDING DEPARTMENT, THE OWNER OR A REGISTERED DESIGN PROFESSIONAL IN RESPONSIBLE CHARGE ACTING AS THE OWNER'S AGENT SHALL EMPLOY ONE OR MORE SPECIAL INSPECTORS TO PROVIDE INSPECTIONS FOR ITEMS NOTED IN THE SPECIFICATIONS AND IBC SECTIONS 108 AND 1704.

SOILS INSPECTION: INSPECTION BY THE SOILS ENGINEER SHALL BE PERFORMED FOR PILE PLACEMENT, EXCAVATION, AND TIEBACK PLACING AND STRESSING. THE GEOTECHNICAL ENGINEER SHALL ALSO ADVISE ON WATER CONTROL AND SLAB ON GRADE CONSTRUCTION.

PILE AND ANCHOR INSTALLATION AS WELL AS REQUIRED TESTING SHALL BE PERFORMED UNDER DIRECT AND CONTINUOUS OBSERVATION OF THE GEOTECHNICAL SPECIAL INSPECTOR.

TESTING AND SPECIAL INSPECTION REPORTS ARE TO BE DISTRIBUTED TO THE ARCHITECT, OWNER, BUILDING DEPARTMENT AND STRUCTURAL ENGINEER WITHIN TWO WEEKS OF COMPLETION OF EACH PHASE OF WORK UNLESS DISCREPANCIES ARE NOT CORRECTED AS NOTED ABOVE.

THE FOLLOWING ITEMS REQUIRE SPECIAL INSPECTIONS:

Table with 2 columns: CONSTRUCTION TYPE and TYPE OF INSPECTION. Includes rows for CONCRETE CONSTRUCTION, STRUCTURAL STEEL FABRICATION AND ERECTION, DRIVEN PILE INSTALLATION, TIEBACK CONSTRUCTION, and EXCAVATION AND GRADING.

PERIODIC INSPECTION ALLOWS INSPECTION AT INTERVALS NECESSARY TO CONFIRM THAT WORK REQUIRING SPECIAL INSPECTION IS IN COMPLIANCE WITH REQUIREMENTS. CONTINUOUS SPECIAL INSPECTION REQUIRES THAT THE INSPECTOR BE ONSITE AT ALL TIMES THAT WORK REQUIRING SPECIAL INSPECTION IS PERFORMED.

7. CONCRETE:

CONCRETE CONSTRUCTION SHALL CONFORM TO ALL REQUIREMENTS OF IBC CHAPTER 19 AND THE ACI STANDARD 318-02 "BUILDING CODE REQUIREMENTS FOR STRUCTURAL CONCRETE".

CONCRETE SHALL BE MIXED, PROPORTIONED, CONVEYED AND PLACED IN ACCORDANCE WITH ACI 301, INCLUDING TESTING PROCEDURES. CONCRETE SHALL ATTAIN A 28-DAY STRENGTH OF fc = 3,000 PSI AND MIX SHALL CONTAIN NOT LESS THAN 5-1/2 SACKS OF CEMENT PER CUBIC YARD AND SHALL BE PROPORTIONED TO PRODUCE A SLUMP OF 5" OR LESS.

8. REINFORCING STEEL SHALL CONFORM TO ASTM A615, GRADE 60, FY = 60,000 PSI.

9. STEEL:

STEEL SPECIFICATIONS: DESIGN, FABRICATION AND ERECTION SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE AISC MANUAL, AISC 360 AND IBC SECTION 2205.

STRUCTURAL STEEL SHALL CONFORM TO THE FOLLOWING REQUIREMENTS:

Table with 3 columns: TYPE OF MEMBER, ASTM SPECIFICATION, and Fy. Includes rows for OTHER SHAPES, PLATES, AND RODS, PIPE COLUMNS, and CONNECTION BOLTS.

ALL WELDING SHALL BE IN CONFORMANCE WITH A.I.S.C. AND A.W.S. STANDARDS AND SHALL BE PERFORMED BY W.A.B.O. CERTIFIED WELDERS USING E70 XX ELECTRODES. ONLY PREQUALIFIED WELDS (AS DEFINED BY A.W.S.) SHALL BE USED.

10. HELICAL ANCHORS:

HELICAL ANCHORS MAY BE PROVIDED BY EARTH CONTACT PRODUCTS, MACLEAN DIXIE, GRIP-TITE, OR EQUAL. HELICAL ANCHORS SHALL BE DESIGNED TO MEET THE LOADING REQUIREMENTS SHOWN ON THE DRAWINGS AND SHALL INCLUDE A MINIMUM SAFETY FACTOR OF 2.

THE CENTRAL STEEL SHAFT, CONSISTING OF LEAD SECTIONS, HELICAL EXTENSIONS, AND PLAIN EXTENSIONS, SHALL BE SOLID SQUARE SHAFT.

SOLID SQUARE SHAFT MATERIAL (1.5"x1.5") SHALL BE HOT ROLLED ROUND-CORNERED-SQUARE(RCS) SOLID STEEL BARS MEETING DIMENSIONAL AND WORKMANSHIP REQUIREMENTS OF ASTM A29. THE BAR SHALL BE MODIFIED MEDIUM CARBON STEEL GRADE WITH IMPROVED STRENGTH DUE TO FINE GRAIN SIZE AS FOLLOWS:

RCS 1.5"x1.5"
MINIMUM TORSIONAL STRENGTH RATING = 5,500 FT-LB
MINIMUM YIELD STRENGTH = 70 KSI
MINIMUM ULTIMATE CAPACITY = 55 KIPS

SEE PLANS FOR ACTUAL DESIGN LOAD REQUIREMENTS.

HELIX PLATE MATERIAL SHALL BE HOT ROLLED CARBON STEEL SHEET, STRIP, OR PLATE FORMED ON MATCHING METAL DIES TO TRUE HELICAL SHAPE AND UNIFORM PITCH. BEARING PLATE MATERIAL SHALL CONFORM TO ASTM A572 WITH MINIMUM YIELD STRENGTH OF 50 KSI.

THE SIZE AND TYPE OF BOLTS USED TO CONNECT THE CENTRAL STEEL SHAFT SECTIONS TOGETHER SHALL CONFORM TO 3/4" MINIMUM DIAMETER BOLTS PER ASTM A325 AND AS REQUIRED TO MEET THE DESIGN LOAD REQUIREMENTS.

COUPLINGS SHALL BE CAPABLE OF TRANSMITTING BOTH THE MAXIMUM INSTALLATION TORQUE FROM THE TOOL STRING TO THE HELIX PLATES, AND THE MAXIMUM AXIAL LOAD FROM THE END OF THE ANCHOR TO THE HELICAL BEARING PLATES.

HELICAL TIEBACK ANCHOR THREAD BAR SHALL BE EITHER A THREADED STUD ADAPTER, OR A COMBINATION OF PRESTRESSING STEEL THREAD BAR AND ADAPTER, BOTH OF WHICH ARE ATTACHED TO THE PREVIOUSLY INSTALLED CENTRAL STEEL SHAFT VIA A COUPLING AS DESCRIBED ABOVE.

STRESSING ANCHORAGES SHALL BE A STEEL BEARING PLATE WITH A THREADED ANCHOR NUT. ANCHORAGE DEVICES SHALL BE CAPABLE OF DEVELOPING 95 PERCENT OF THE GUARANTEED ULTIMATE TENSILE STRENGTH OF THE THREAD BAR.

ANCHOR NUTS AND OTHER THREADABLE HARDWARE SHALL BE DESIGNED TO COMPLY WITH THE LOAD CARRYING REQUIREMENTS OF THE ANCHORAGE.

THE BEARING PLATE SHALL BE FABRICATED FROM STEEL CONFORMING TO ASTM A36, A588, A709 OR A572 SPECIFICATIONS OR SUITABLE EQUIVALENT.

ALL HELICAL ANCHORS AND RELATED HELICAL HARDWARE SHALL BE HOT DIP GALVANIZED.

11. HELICAL ANCHOR PERFORMANCE VERIFICATION TESTS (200% TESTS):

TENSION VERIFICATION TESTING SHALL BE PERFORMED ON AT LEAST ONE PERFORMANCE ANCHOR SELECTED BY THE GEOTECHNICAL ENGINEER. ALL REQUIRED TEST DATA SHALL BE RECORDED BY THE GEOTECHNICAL SPECIAL INSPECTOR.

- A. VERIFICATION TESTS SHALL BE PERFORMED TO 200% OF THE ALLOWABLE DESIGN LOAD.
B. THE ANCHOR SHALL BE SEATED BY APPLYING AN ALIGNMENT LOAD. THE ALIGNMENT LOAD SHALL BE BETWEEN 2% AND 15% OF THE DESIGN LOAD.
C. VERIFICATION TESTS SHALL BE PERFORMED BY INCREMENTALLY LOADING THE ANCHOR IN ACCORDANCE THE SCHEDULE BELOW.

Table with 2 columns: Load (AL, 25 DL, 50 DL, 75 DL, 1.0 DL, 1.25 DL, 1.50 DL, 1.75 DL, 2.00 DL) and Time (2 MINUTES*). Includes legend for AL and DL.

THE LOAD-HOLD PERIOD SHALL START AS SOON AS THE LOAD IS APPLIED AND THE ANCHOR MOVEMENT SHALL BE MEASURED AND RECORDED AT EACH LOAD INCREMENT.

AFTER ACCEPTANCE BY THE GEOTECHNICAL ENGINEER, THE ANCHOR MAY THEN BE UNLOADED AND ATTACHED TO THE FINAL CONDITION BY THE SNUG TIGHT METHOD, HOWEVER, THE LOCK-OFF LOAD NEED NOT EXCEED 50 PERCENT OF THE TIEBACK ANCHOR DESIGN LOAD TO MINIMIZE WALL DEFLECTIONS.

D. AN ANCHOR SHOULD BE DEEMED ACCEPTABLE IF IT MEETS THE FOLLOWING CRITERIA:

THE TOTAL ELASTIC MOVEMENT OBTAINED FROM THE VERIFICATION AND PROOF TESTS EXCEEDS 80 PERCENT OF THE THEORETICAL ELASTIC ELONGATION OF THE LENGTH.

TOTAL ANCHOR MOVEMENT BETWEEN THE 2 AND THE 10 MINUTE INTERVALS SHOULD NOT EXCEED 0.05 INCHES MORE THAN THE THEORETICAL ELASTIC MOVEMENT, REGARDLESS OF THE LENGTH OR LOAD.

ANCHOR MOVEMENT AT THE VERIFICATION LOAD SHALL NOT EXCEED .08 TIMES THE LARGEST HELIX DIAMETER.

THE LIFT-OFF MEASUREMENT INDICATES AN ANCHOR LOAD WITHIN 5 PERCENT OF THE DESIGN LOCK-OFF LOAD.

12. PROOF TESTS:

ALL ANCHORS NOT PERFORMANCE TESTED SHALL BE INSTALLED TO 200 PERCENT OF THE DESIGN LOAD AS PERFORMED BY THE TORQUE METHOD WHEN APPROVED BY THE STRUCTURAL AND GEOTECHNICAL ENGINEERS.

13. TORQUE METHOD INSTALLATION:

ANCHORS INSTALLED BY THE TORQUE METHOD MUST FIRST MEET THE EMBEDMENT REQUIREMENTS NOTED ON THE STRUCTURAL DRAWINGS OR APPROVED BY BOTH THE STRUCTURAL AND GEOTECHNICAL ENGINEER IN WRITING. ONCE THE REQUIRED MINIMUM EMBEDMENT HAS BEEN MET, THE CONTRACTOR SHALL PROVIDE GAUGES OR SHEAR BOLTS TO DETERMINE THAT THE ANCHOR HAS BEEN TORQUED TO A MINIMUM OF 200 PERCENT OF THE DESIGN LOAD BASED ON THE EMPIRICAL RELATIONSHIP THAT THE 200 PERCENT LOAD MEASURED IN POUNDS IS APPROXIMATELY EQUAL TO 10 TIMES THE INSTALLATION TORQUE AS MEASURED IN FOOT POUNDS.

14. PIN PILES:


PIN PILES SHOWN ON THE PLAN SHALL BE 2" DIAMETER SCHEDULE 80. THE MAXIMUM CAPACITY OF 2" PILES SHALL BE 3 TONS. ALL PILES SHALL BE DRIVEN TO REFUSAL IN ACCORDANCE WITH THE GEOTECHNICAL REPORT. AS A MINIMUM, PILE REFUSAL SHALL BE DEFINED AS 1 INCH OF PENETRATION IN 60 SECONDS DURING CONTINUOUS DRIVING OF A 90 LB JACK HAMMER UNDER THE FULL WEIGHT AND EFFORT OF THE OPERATOR OR THE CONVENTIONAL DRIVING OF A RHINO PD-140.

15. ANCHORAGE


EXPANSION BOLTS INTO CONCRETE SHALL BE "STRONG-BOLT 2" WEDGE ANCHORS AS MANUFACTURED BY THE SIMPSON STRONG TIE COMPANY AND INSTALLED IN STRICT CONFORMANCE TO ICC-ES REPORT NUMBER ESR-3037. PERIODIC SPECIAL INSPECTION IS REQUIRED TO VERIFY ANCHOR TYPE, ANCHOR DIMENSIONS, ANCHOR LOCATION, TIGHTENING TORQUE, HOLE DIMENSIONS, ANCHOR EMBEDMENT, AND ADHERENCE TO THE INSTALLATION INSTRUCTIONS.

Vertical sidebar containing: REVISIONS table, SCJ STUDIO LANDSCAPE ARCHITECTURE logo, address (1148 NW LEARY WAY, SEATTLE, WA 98107), Structural Notes, PROJECT NAME (Maple Grove Residence), SHEET TITLE, SEAL, DESIGNER (KJ), DRAWN BY (JL), APPROVED BY (MG), DATE (OCTOBER 2019), JOB No. (2551), DRAWING FILE No., DRAWING No. (LA3.1), SHEET No. (4 OF 6).


Oct 17, 2019 3:57:23pm - User: Keith Larkowky N:\PROJECTS\2551-SARAH & AMIR-BASTAWROUS\2551-01-THE MAPLE GROVE RESIDENCE\PHASE 03 - PERMIT ASSISTANCE\CAD\2551-LA3.1-DETAILS-MAPLE-PERMIT.DWG




1 CAST-IN-PLACE RETAINING WALL - SECTION-1
1/2" = 1'-0" P-RE-MAP1-01




3 CAST-IN-PLACE RETAINING WALL - SECTION-3
1/2" = 1'-0" P-RE-MAP1-03




4 CAST-IN-PLACE RETAINING WALL - SECTION-4
1/2" = 1'-0" P-RE-MAP1-04



2 CAST-IN-PLACE RETAINING WALL - SECTION-2
1/2" = 1'-0" P-RE-MAP1-02






5 CAST-IN-PLACE RETAINING WALL - FOOTING AND DOUBLE-ROW TIEBACK PLACEMENT
1/2" = 1'-0" P-RE-MAP1-05



6 HELICAL ANCHOR
3/4" = 1'-0" P-RE-MAP1-15





Oct 17, 2019, 3:57:28pm - User: Keith Jenkins
 N:\PROJECTS\2551 SARAH & AMIR BASTAWOUS\2551.01 - PERMIT ASSISTANCE\CAD\2551-1A31 DETAILS MAPLE PERMIT.DWG

BY	KJ
DATE	10/17/2019
REVISIONS	PERMIT PLAN
1148 NW Leary Way, Seattle, WA 98107 P: 206.708.1862 SCSTUDIO.COM	
Structural Details Maple Grove Residence 4909 E. Mercer Way Mercer Island, WA 98040	
SHEET TITLE	PROJECT NAME
SEAL	
DESIGNER	KJ
DRAWN BY	JL
APPROVED BY	MG
DATE	OCTOBER 2019
JOB No.	2551
DRAWING FILE No.	
DRAWING No.	LA3.2
SHEET No.	5 OF 6



1 CABLE GUARD RAIL AND GATE



1" = 1'-0"



NOTES:
 • POSTS ARE TO BE 4" SQ. APPEARANCE GRADE TREATED LUMBER.
 • METAL GATE FRAME TO BE HIDDEN, POWDER COATED BLACK.
 • ALL FENCE AND GATE HARDWARE TO BE HIDDEN WHERE PRACTICAL.
 • DO NOT DIRECT BURY POSTS IN CONCRETE. USE POST-ON-PIPE OR POST-ON-BRACKET CONSTRUCTION.
 • ALL FENCE AND GATE BOARDS TO BE APPEARANCE GRADE CEDAR, STAINED AND SEALED. COLOR: NATURAL OR APPROVED EQUAL.

2 CEDAR GUARD RAIL AND GATE

1" = 1'-0"



3 MILD STEEL STEPS WITH CRUSHED GRANITE INFILL

1/2" = 1'-0"

4 MILD STEEL PLANTER

1/2" = 1'-0"

BY	KJ
DATE	10/17/2019
REVISIONS	PERMIT PLAN

SCJ STUDIO
 LANDSCAPE ARCHITECTURE

1148 NW LEARY WAY, SEATTLE, WA 98107
 206-706-1862
 SCJSTUDIO.COM

Permit Details

Maple Grove Residence
 4909 E. Mercer Way
 Mercer Island, WA 98040

SHEET TITLE: PROJECT NAME:

SEAL:

DESIGNER:	KJ
DRAWN BY:	JL
APPROVED BY:	MG
DATE:	OCTOBER 2019
JOB No:	2551
DRAWING FILE No:	
DRAWING No:	LA3.3
SHEET No:	6 OF 6

Nov 14, 2019, 9:42:19am - User: Keith Lenkowski
 N:\PROJECTS\2551 SARAH & AMR BASTARROS\2551.01 THE MAPLE GROVE RESIDENCE\PHASE 03 - PERMIT ASSISTANCE\CAD\2551-1A3.1 DETAILS-MARLE PERMILING