

a s s o c i a t e d
e a r t h s c i e n c e s
i n c o r p o r a t e d

May 22, 2014
Project No. KE140288A

JayMarc Homes, LLC
7525 SE 24th Street, Suite 487
Mercer Island, Washington 98040

Attention: Mr. Gary Upper


Subject: Subsurface Exploration, Geologic Hazards,
and Geotechnical Engineering Report
Anbalagan Residence
2761 70th Avenue SE
Mercer Island, Washington

Dear Mr. Upper:

We are pleased to present these copies of our report for the referenced project. This report summarizes the results of our subsurface exploration, geologic hazards, and geotechnical engineering studies, and offers recommendations for the design and development of the proposed project. Our report is preliminary since project plans were under development at the time this report was written. We should be allowed to review the recommendations presented in this report and modify them, if needed, once final project plans have been formulated.

We have enjoyed working with you on this study and are confident that the recommendations presented in this report will aid in the successful completion of your project. If you should have any questions, or if we can be of additional help to you, please do not hesitate to call.


Sincerely,
ASSOCIATED EARTH SCIENCES, INC.
Kirkland, Washington


Kurt D. Merriman, P.E.
Senior Principal Engineer

KDM/pc
KE140288A2
Projects\20140288\KE\WP



Geotechnical Engineering




Water Resources



*Environmental Assessments
and Remediation*



Sustainable Development Services



Geologic Assessments

Associated Earth Sciences, Inc.

Serving the Pacific Northwest Since 1981

Subsurface Exploration, Geologic Hazards,
and Geotechnical Engineering Report

ANBALAGAN RESIDENCE

Mercer Island, Washington

Prepared for

JayMarc Homes, LLC

Project No. KE140288A

May 22, 2014

**SUBSURFACE EXPLORATION, GEOLOGIC HAZARDS,
AND GEOTECHNICAL ENGINEERING REPORT**

ANBALAGAN RESIDENCE

Mercer Island, Washington

Prepared for:

JayMarc Homes, LLC
7525 SE 24th Street, Suite 487
Mercer Island, Washington 98040

Prepared by:

Associated Earth Sciences, Inc.
911 5th Avenue
Kirkland, Washington 98033
425-827-7701
Fax: 425-827-5424

May 22, 2014
Project No. KE140288A

I. PROJECT AND SITE CONDITIONS

1.0 INTRODUCTION

This report presents the results of our subsurface exploration, geologic hazard, and geotechnical engineering study for the proposed single-family residence. The location of the site is shown on the “Vicinity Map,” Figure 1, and the approximate locations of the proposed residence and the explorations accomplished for this study are presented on the “Site and Exploration Plan,” Figure 2. In the event that any changes in the nature, design, or location of the planned residence are planned, the conclusions and recommendations contained in this report should be reviewed and modified, or verified, as necessary.

1.1 Purpose and Scope

The purpose of this study was to provide geotechnical engineering design recommendations to be utilized in the design of the project. This study included a review of selected available geologic literature, observation of exploration pits, and performing geologic studies to assess the type, thickness, distribution, and physical properties of the subsurface sediments and shallow ground water. Geotechnical engineering studies were completed to establish recommendations for the type of suitable foundations and floors, allowable foundation soil bearing pressure, anticipated foundation and floor settlement, and drainage considerations. This report summarizes our fieldwork and offers recommendations based on our present understanding of the project. We recommend that we be allowed to review the recommendations presented in this report and revise them, if needed, when a project design has been finalized.

1.2 Authorization

Our work was completed in general accordance with our scope of work and cost proposal dated May 15, 2014. This report has been prepared for the exclusive use of JayMarc Homes, LLC, and their agents for specific application to this project. Within the limitations of scope, schedule, and budget, our services have been performed in accordance with generally accepted geotechnical engineering and engineering geology practices in effect in this area at the time our report was prepared. No other warranty, express or implied, is made.

2.0 PROJECT AND SITE DESCRIPTION

The subject site includes an existing two-story residential structure with a daylight basement, located at 2761 70th Avenue SE in Mercer Island, Washington (King County Parcel No.

5093300885). The property is generally gently to moderately sloping downward to the west. The property is bordered on the north by 69th Avenue SE, on the east by 70th Avenue SE, and on the south and west by other single-family residential properties. The subject site is currently vegetated with grass lawn areas, landscaping shrubbery, and small- to medium-sized trees.

We understand that the project includes the demolition of the existing structure and the construction of a new two-story residence, with a daylight basement level and two attached garages, at the approximate location of the existing building. The proposed residence will be accessed via driveways extending from both 69th Avenue SE and 70th Avenue SE. This subject site is delineated as including Seismic, Erosion and Landslide Hazard Areas in the *City of Mercer Island Geologic Hazards* maps.

3.0 SUBSURFACE EXPLORATION

Our field study included excavating a series of exploration pits to gain subsurface information about the site. The various types of sediments, as well as the depths where characteristics of the sediments changed, are indicated on the exploration logs presented in the Appendix. The depths indicated on the logs where conditions changed may represent gradational variations between sediment types in the field. Our explorations were approximately located in the field relative to known site features shown on the topographic site plan. The locations of the exploration pits are shown on Figure 2.

The conclusions and recommendations presented in this report are based, in part, on the exploration pits completed for this study. The number, locations, and depths of the explorations were completed within site and budgetary constraints. Because of the nature of exploratory work below ground, interpolation of subsurface conditions between field explorations is necessary. It should be noted that differing subsurface conditions may sometimes be present due to the random nature of deposition and the alteration of topography by past grading and/or filling. The nature and extent of any variations between the field explorations may not become fully evident until construction. If variations are observed at that time, it may be necessary to re-evaluate specific recommendations in this report and make appropriate changes.

3.1 Exploration Pits

Exploration pits were excavated with a client-provided track-mounted excavator. The pits permitted direct, visual observation of subsurface conditions. Materials encountered in the exploration pits were studied and classified in the field by an engineering geologist from our firm. All exploration pits were backfilled immediately after examination and logging.

Selected samples were then transported to our laboratory for further visual classification and testing, as necessary.

4.0 SUBSURFACE CONDITIONS

Subsurface conditions at the project site were inferred from the field exploration accomplished for this study, visual reconnaissance of the site, and review of selected applicable geologic literature. Because of the nature of exploratory work below ground, extrapolation of subsurface conditions beyond the field exploration is necessary. It should be noted that differing subsurface conditions may sometimes be present due to the random nature of deposition and the alteration of topography by past grading and/or filling. The nature and extent of any variations beyond the field exploration may not become fully evident until construction.

4.1 Stratigraphy

Fill

Fill soils (soils not naturally placed) were encountered at the locations of exploration pits EP-1 and EP-2 to approximate respective depths of 1 foot and 2.5 feet below the ground surface. The fill encountered at EP-1 consisted chiefly of angular gravel, likely surfacing material for the existing driveway. The fill encountered at EP-2 generally consisted of loose silty sand with gravel. Fill thicknesses can vary over short distances and may be deeper than observed in our explorations. Fill is also expected in unexplored areas of the site, such as the area surrounding and under the existing structure foundations, or at the locations of buried utilities or driveway areas. Due to their variable density, the existing fill soils are not suitable for foundation support.

Topsoil

A buried organic topsoil layer was encountered at exploration pit EP-1. The thickness of the topsoil layer was approximately 1 foot. The organic topsoil is not suitable for foundation support or for use in a structural fill.

Vashon Lodgement Till

Sediments encountered below the topsoil or fill at the locations of exploration pits EP-1 and EP-2 generally consisted of loose to medium dense, silty sand with gravel. These sediments were observed to generally become dense to very dense below depths of approximately 3 to 4 feet below the ground surface. We interpret these sediments to be representative of Vashon

lodgement till. The Vashon lodgement till was deposited directly from basal, debris-laden glacial ice during the Vashon Stade of the Fraser Glaciation approximately 12,500 to 15,000 years ago. The reduced density observed within a few feet of the ground surface is interpreted to be due to weathering. The high relative density of the unweathered till is due to its consolidation by the massive weight of the glacial ice from which it was deposited. At the locations of our exploration pits, the till extended beyond the maximum depths explored of approximately 6.5 and 8.5 feet.

4.2 Geologic Mapping

Review of the regional geologic map titled *The Geologic Map of Mercer Island, Washington* (K.G. Troost and A.P. Wisher, October 2006) indicates that the area of the subject site is underlain by Vashon advance outwash, with Vashon lodgement till mapped nearby. Our interpretation of the sediments encountered at the subject site is in general agreement with the nearby lodgement till shown on the regional geologic map.

4.3 Hydrology

We did not encounter ground water in our exploration pits. We expect ground water seepage across much of the site to be limited to interflow. Interflow occurs when surface water percolates down through the surficial weathered or higher permeability sediments and becomes perched atop underlying, lower permeability sediments. It should be noted that the occurrence and level of ground water seepage at the site may vary in response to such factors as changes in season, precipitation, and site use.

II. GEOLOGIC HAZARDS AND MITIGATIONS

The following discussion of potential geologic hazards is based on the geologic, slope, and ground and surface water conditions, as observed and discussed herein. The discussion will be limited to seismic and erosion issues.

5.0 SEISMIC HAZARDS AND MITIGATIONS

Earthquakes occur regularly in the Puget Lowland. The majority of these events are small and are usually not felt by people. However, large earthquakes do occur, as evidenced by the 1949, 7.2-magnitude event; the 2001, 6.8-magnitude event; and the 1965, 6.5-magnitude event. The 1949 earthquake appears to have been the largest in this region during recorded history and was centered in the Olympia area. Evaluation of earthquake return rates indicates that an earthquake of the magnitude between 5.5 and 6.0 is likely within a given 20-year period.

Generally, there are four types of potential geologic hazards associated with large seismic events: 1) surficial ground rupture, 2) seismically induced landslides, 3) liquefaction, and 4) ground motion. The potential for each of these hazards to adversely impact the proposed project is discussed below.

5.1 Surficial Ground Rupture

The project site is located within the Seattle Fault Zone. Recent studies by the United States Geological Survey (USGS) (e.g., Johnson, et al., 1994, *Origin and Evolution of the Seattle Fault and Seattle Basin, Washington*, Geology, v. 22, p.71-74; and Johnson, et al., 1999, *Active Tectonics of the Seattle Fault and Central Puget Sound Washington - Implications for Earthquake Hazards*, Geological Society of America Bulletin, July 1999, v. 111, n. 7, p. 1042-1053) have provided evidence of surficial ground rupture along a northern splay of the Seattle Fault. The recognition of this fault is relatively new, and data pertaining to it are limited, with the studies still ongoing. According to the USGS studies, the latest movement of this fault was about 1,100 years ago when about 20 feet of surficial displacement took place. This displacement can presently be seen in the form of raised, wave-cut beach terraces along Alki Point in West Seattle and Restoration Point at the south end of Bainbridge Island. The recurrence interval of movement along this fault system is still unknown, although it is hypothesized to be in excess of several thousand years. Due to the suspected long recurrence interval, the potential for surficial ground rupture is considered to be low during the expected life of the structures, and no mitigation efforts beyond complying with the current (2012) *International Building Code* (IBC) are recommended.

5.2 Seismically Induced Landslides

The lodgement till is a high shear strength, relatively low-permeability material and is not overly sensitive to landsliding given the topographic conditions at the site. In addition, no evidence of historical landslide activity was observed, such as landslide scarps, hummocky topography, tension cracks, or unusually distorted or leaning tree trunks. Given the subsurface and topographic conditions within and adjacent to the proposed development area and the apparent lack of historical landslide activity, it is our opinion that the risk of damage to the proposed project by landsliding under either static or seismic conditions is low. This opinion is dependent upon site grading and construction practices being completed in accordance with the geotechnical recommendations presented in this report.

5.3 Liquefaction

Liquefaction is a process through which unconsolidated soil loses strength as a result of vibrations, such as those which occur during a seismic event. During normal conditions, the weight of the soil is supported by both grain-to-grain contacts and by the fluid pressure within the pore spaces of the soil below the water table. Extreme vibratory shaking can disrupt the grain-to-grain contact, increase the pore pressure, and result in a temporary decrease in soil shear strength. The soil is said to be liquefied when nearly all of the weight of the soil is supported by pore pressure alone. Liquefaction can result in deformation of the sediment and settlement of overlying structures. Areas most susceptible to liquefaction include those areas underlain by non-cohesive silt and sand with low relative densities, accompanied by a shallow water table.

The subsurface conditions encountered at the site pose little risk of liquefaction due to relatively high density and lack of shallow ground water. No detailed liquefaction analysis was completed as part of this study, and none is warranted, in our opinion.

5.4 Ground Motion

Structural design of the building should follow 2012 IBC standards using Site Class “C” as defined in Table 20.3-1 of *American Society of Civil Engineers (ASCE) 7 – Minimum Design Loads for Buildings and Other Structures*.

6.0 EROSION HAZARDS AND MITIGATIONS

As of October 1, 2008, the Washington State Department of Ecology (Ecology) Construction Storm Water General Permit (also known as the National Pollutant Discharge Elimination System [NPDES] permit) requires weekly Temporary Erosion and Sedimentation Control

(TESC) inspections and turbidity monitoring of site runoff for all sites 1 or more acres in size that discharge storm water to surface waters of the state. Although we anticipate that the proposed project will require disturbance of less than 1 acre, we provide in the following sections recommendations to address these inspection and reporting requirements. The following sections also include recommendations related to general erosion control and mitigation.

The TESC inspections and turbidity monitoring of runoff must be completed by a Certified Erosion and Sediment Control Lead (CESCL) for the duration of the construction. The weekly TESC reports do not need to be sent to Ecology, but should be logged into the project Storm Water Pollution Prevention Plan (SWPPP). Ecology requires a monthly summary report of the turbidity monitoring results signed by the NPDES permit holder. If the monitored turbidity equals or exceeds 25 nephelometric turbidity units (NTU) (Ecology benchmark standard), the project best management practices (BMPs) should be modified to decrease the turbidity of storm water leaving the site. Changes and upgrades to the BMPs should be documented in the weekly TESC reports and continued until the weekly turbidity reading is 25 NTU or lower. If the monitored turbidity exceeds 250 NTU, the results must be reported to Ecology via phone within 24 hours and corrective actions should be implemented as soon as possible. Daily turbidity monitoring is continued until the corrective actions lower the turbidity to below 25 NTU, or until the discharge stops. This description of the sampling benchmarks and reporting requirements is a brief summary of the Construction Storm Water General Permit conditions. The general permit is available on the internet¹.

In order to meet the current Ecology requirements, a properly developed, constructed, and maintained erosion control plan consistent with City of Mercer Island standards and best management erosion control practices will be required for this project. Associated Earth Sciences, Inc. (AESI) is available to assist the project civil engineer in developing site-specific erosion control plans. Based on past experience, it will be necessary to make adjustments and provide additional measures to the TESC plan in order to optimize its effectiveness. Ultimately, the success of the TESC plan depends on a proactive approach to project planning and contractor implementation and maintenance.

The most effective erosion control measure is the maintenance of adequate ground cover. Maintaining cover measures atop disturbed ground provides the greatest reduction to the potential generation of turbid runoff and sediment transport. During the local wet season (October 1st through March 31st), exposed soil should not remain uncovered for more than 2 days unless it is actively being worked. Ground-cover measures can include erosion control matting, plastic sheeting, straw mulch, crushed rock or recycled concrete, or mature hydroseed.

¹ <http://www.ecy.wa.gov/programs/wq/stormwater/construction/constructionfinalpermit.pdf>

Surface drainage control measures are also essential for collecting and controlling the site runoff. Flow paths across slopes should be kept to less than 50 feet in order to reduce the erosion and sediment transport potential of concentrated flow. Ditch/swale spacing will need to be shortened with increasing slope gradient. Ditches and swales that exceed a gradient of about 7 to 10 percent, depending on their flow length, should have properly constructed check dams installed to reduce the flow velocity of the runoff and reduce the erosion potential within the ditch. Flow paths that are required to be constructed on gradients between 10 to 15 percent should be placed in a riprap-lined swale with the riprap properly sized for the anticipated flow conditions. Flow paths constructed on slope gradients steeper than 15 percent should be placed in a pipe slope drain. AESI is available to assist the project civil engineer in developing a suitable erosion control plan with proper flow control.

With respect to water quality, having ground cover prior to rain events is one of the most important and effective means to maintain water quality. Once very fine sediment is suspended in water, the settling times of the smallest particles are on the order of weeks and months. Therefore, the typical retention times of sediment traps or ponds will not reduce the turbidity of highly turbid site runoff to the benchmark turbidity of 25 NTU. Reduction of turbidity from a construction site is almost entirely a function of cover measures and drainage control that have been implemented prior to rain events. Temporary sediment traps and ponds are necessary to control the release rate of the runoff and to provide a catchment for sand-sized and larger soil particles, but are very ineffective at reducing the turbidity of the runoff.

Silt fencing should be utilized as buffer protection and not as a flow-control measure. Silt fencing is meant to be placed parallel with topographic contours to prevent sediment-laden runoff from leaving a work area or entering a sensitive area. Silt fences should not be placed to cross contour lines without having separate flow control in front of the silt fence. A swale/berm combination should be constructed to provide flow control rather than let the runoff build up behind the silt fence and utilize the silt fence as the flow-control measure. Runoff flowing in front of a silt fence will cause additional erosion and usually will cause a failure of the silt fence. Improperly installed silt fencing has the potential to cause a much larger erosion hazard than if the silt fence was not installed at all. The use of silt fencing should be limited to protect sensitive areas, and swales should be used to provide flow control.

6.1 Erosion Hazard Mitigation

To mitigate the erosion hazards and potential for off-site sediment transport, we would recommend the following:

1. Construction activity should be scheduled or phased as much as possible to reduce the amount of earthwork activity that is performed during the winter months.

2. The winter performance of a site is dependent on a well-conceived plan for control of site erosion and storm water runoff. It is easier to keep the soil on the ground than to remove it from storm water. The owner and the design team should include adequate ground-cover measures, access roads, and staging areas in the project bid to give the selected contractor a workable site. The selected contractor needs to be prepared to implement and maintain the required measures to reduce the amount of exposed ground. A site maintenance plan should be in place in the event storm water turbidity measurements are greater than the Ecology standards.
3. TESC measures for a given area to be graded or otherwise worked should be installed soon after ground clearing. The recommended sequence of construction within a given area after clearing would be to install sediment traps and/or ponds and establish perimeter flow control prior to starting mass grading.
4. During the wetter months of the year, or when large storm events are predicted during the summer months, each work area should be stabilized so that if showers occur, the work area can receive the rainfall without excessive erosion or sediment transport. The required measures for an area to be “buttoned-up” will depend on the time of year and the duration the area will be left un-worked. During the winter months, areas that are to be left un-worked for more than 2 days should be mulched or covered with plastic. During the summer months, stabilization will usually consist of seal-rolling the subgrade. Such measures will aid in the contractor’s ability to get back into a work area after a storm event. The stabilization process also includes establishing temporary storm water conveyance channels through work areas to route runoff to the approved treatment facilities.
5. All disturbed areas should be revegetated as soon as possible. If it is outside of the growing season, the disturbed areas should be covered with mulch, as recommended in the erosion control plan. Straw mulch provides a cost-effective cover measure and can be made wind-resistant with the application of a tackifier after it is placed.
6. Surface runoff and discharge should be controlled during and following development. Uncontrolled discharge may promote erosion and sediment transport. Under no circumstances should concentrated discharges be allowed to flow over the top of steep slopes.
7. Soils that are to be reused around the site should be stored in such a manner as to reduce erosion from the stockpile. Protective measures may include, but are not limited to, covering with plastic sheeting, the use of low stockpiles in flat areas, or the use of silt fences around pile perimeters. During the period between October 1st and March 31st, these measures are required.

8. On-site erosion control inspections and turbidity monitoring (if required) should be performed in accordance with Ecology requirements. Weekly and monthly reporting to Ecology should be performed on a regularly scheduled basis. A discussion of temporary erosion control and site runoff monitoring should be part of the weekly construction team meetings. Temporary and permanent erosion control and drainage measures should be adjusted and maintained, as necessary, for the duration of project construction.

It is our opinion that with the proper implementation of the TESC plans and by field-adjusting appropriate mitigation elements (BMPs) throughout construction, as recommended by the erosion control inspector, the potential adverse impacts from erosion hazards on the project may be mitigated.

7.0 STATEMENT OF RISK

For Section 19.07.060(D) of the *Mercer Island Unified Land Development Code (ULDC)*, the City of Mercer Island requires a statement of risk by the geotechnical engineer. It is AESI's opinion that the development practices proposed for the alteration would render the development as safe as if it were not located in a geologic hazard area provided the recommendations in this report are followed.

III. DESIGN RECOMMENDATIONS

8.0 INTRODUCTION

Our exploration indicates that, from a geotechnical standpoint, the parcel is suitable for the proposed development provided the recommendations contained herein are properly followed. The proposed building area is underlain by a layer of existing fill and weathered soil that is variable in thickness and density. Existing fill or loose soils are not suitable for support of new foundations, and warrant remedial preparation where occurring below paving and similar lightly loaded structures. Structural fill or at least medium dense native lodgment till deposits are suitable for support of shallow foundations with proper preparation.

9.0 SITE PREPARATION

Existing buried utilities, vegetation, topsoil, and any other deleterious materials should be removed where they are located below planned construction areas. All disturbed soils resulting from demolition activities should be removed to expose underlying, undisturbed, native sediments and replaced with structural fill, as needed. All excavations below final grade made for demolition activities should be backfilled, as needed, with structural fill. Erosion and surface water control should be established around the clearing limits to satisfy local requirements.

Once demolition has been completed, existing fill, where encountered, should be addressed. We recommend that existing fill or loose, weathered soils be removed from below areas of planned foundations to expose underlying, medium dense to very dense native sediments, followed by restoration of the planned foundation grade with structural fill. Removal of existing fill should extend laterally beyond the building footprint by a distance equal to the depth of overexcavation. For example, if existing fill is removed to a depth of 2 feet below a planned footing area, the excavation should also extend laterally 2 feet beyond the building footprint in that area. Where existing fill or loose soils are removed and replaced with structural fill, conventional shallow foundations may be used for building support. The required depth of removal should be determined in the field based on actual conditions encountered during excavation.

9.1 Site Drainage and Surface Water Control

The site should be graded to prevent water from ponding in construction areas and/or flowing into excavations. Exposed grades should be crowned, sloped, and smooth drum-rolled at the end of each day to facilitate drainage. Accumulated water must be removed from subgrades

and work areas immediately prior to performing further work in the area. Equipment access may be limited, and the amount of soil rendered unfit for use as structural fill may be greatly increased, if drainage efforts are not accomplished in a timely sequence. If an effective drainage system is not utilized, project delays and increased costs could be incurred due to the greater quantities of wet and unsuitable fill, or poor access and unstable conditions.

We anticipate that perched ground water could be encountered in excavations completed during construction. We do not anticipate the need for extensive dewatering in advance of excavations. The contractor should be prepared to intercept any ground water seepage entering the excavations and route it to a suitable discharge location.

Final exterior grades should promote free and positive drainage away from the buildings at all times. Water must not be allowed to pond or to collect adjacent to foundations or within the immediate building area. We recommend that a gradient of at least 3 percent for a minimum distance of 10 feet from the building perimeters be provided, except in paved locations. In paved locations, a minimum gradient of 1 percent should be provided, unless provisions are included for collection and disposal of surface water adjacent to the structures.

9.2 Subgrade Protection

To the extent that it is possible, existing pavement should be used for construction staging areas. If building construction will proceed during the winter, we recommend the use of a working surface of sand and gravel, crushed rock, or quarry spalls to protect exposed soils, particularly in areas supporting concentrated equipment traffic. In winter construction staging areas and areas that will be subjected to repeated heavy loads, such as those that occur during construction of masonry walls, a minimum thickness of 12 inches of quarry spalls or 18 inches of pit run sand and gravel is recommended. If subgrade conditions are soft and silty, a geotextile separation fabric, such as Mirafi 500X or approved equivalent, should be used between the subgrade and the new fill. For building pads where floor slabs and foundation construction will be completed in the winter, a similar working surface should be used, composed of at least 6 inches of pit run sand and gravel or crushed rock. Construction of working surfaces from advancing fill pads could be used to avoid directly exposing the subgrade soils to vehicular traffic.

Foundation subgrades may require protection from foot and equipment traffic and ponding of runoff during wet weather conditions. Typically, compacted crushed rock or a lean-mix concrete mat placed over a properly prepared subgrade provides adequate subgrade protection. Foundation concrete should be placed and excavations backfilled as soon as possible to protect the bearing surface.

9.3 Proof-Rolling and Subgrade Compaction

Following the recommended demolition, site stripping, and planned excavation, the stripped subgrade within the building areas should be proof-rolled with heavy, rubber-tired construction equipment, such as a fully loaded, tandem-axle dump truck. Proof-rolling should be performed prior to structural fill placement or foundation excavation. The proof-roll should be monitored by the geotechnical engineer so that any soft or yielding subgrade soils can be identified. Any soft/loose, yielding soils should be removed to a stable subgrade. The subgrade should then be scarified, adjusted in moisture content, and recompacted to the required density. Proof-rolling should only be attempted if soil moisture contents are at or near optimum moisture content. Proof-rolling of wet subgrades could result in further degradation. Low areas and excavations may then be raised to the planned finished grade with compacted structural fill. Subgrade preparation and selection, placement, and compaction of structural fill should be performed under engineering-controlled conditions in accordance with the project specifications.

9.4 Overexcavation/Stabilization

Construction during extended wet weather periods could create the need to overexcavate exposed soils if they become disturbed and cannot be recompacted due to elevated moisture content and/or weather conditions. Even during dry weather periods, soft/wet soils, which may need to be overexcavated, may be encountered in some portions of the site. If overexcavation is necessary, it should be confirmed through continuous observation and testing by AESI. Soils that have become unstable may require remedial measures in the form of one or more of the following:

1. Drying and recompaction. Selective drying may be accomplished by scarifying or windrowing surficial material during extended periods of dry and warm weather.
2. Removal of affected soils to expose a suitable bearing subgrade and replacement with compacted structural fill.
3. Mechanical stabilization with a coarse-crushed aggregate compacted into the subgrade, possibly in conjunction with a geotextile.
4. Soil/cement admixture stabilization.

9.5 Wet Weather Conditions

If construction proceeds during an extended wet weather construction period and the moisture-sensitive site soils become wet, they will become unstable. Therefore, the bids for site grading operations should be based upon the time of year that construction will proceed. It is

expected that in wet conditions additional soils may need to be removed and/or other stabilization methods used, such as a coarse crushed rock working mat to develop a stable condition if silty subgrade soils are disturbed in the presence of excess moisture. The severity of construction disturbance will be dependent, in part, on the precautions that are taken by the contractor to protect the moisture- and disturbance-sensitive site soils. If overexcavation is necessary, it should be confirmed through continuous observation and testing by a representative of our firm.

9.6 Temporary and Permanent Cut Slopes

In our opinion, stable construction slopes should be the responsibility of the contractor and should be determined during construction. For estimating purposes, however, we anticipate that temporary, unsupported cut slopes in the existing fill can be made at a maximum slope of 1.5H:1V (Horizontal:Vertical) or flatter. Temporary slopes in lodgement till deposits may be planned at 1H:1V. As is typical with earthwork operations, some sloughing and raveling may occur, and cut slopes may have to be adjusted in the field. If ground water seepage is encountered in cut slopes, or if surface water is not routed away from temporary cut slope faces, flatter slopes will be required. In addition, WISHA/OSHA regulations should be followed at all times. Permanent cut and structural fill slopes that are not intended to be exposed to surface water should be designed at inclinations of 2H:1V or flatter. All permanent cut or fill slopes should be compacted to at least 95 percent of the modified Proctor maximum dry density, as determined by ASTM:D 1557, and the slopes should be protected from erosion by sheet plastic until vegetation cover can be established during favorable weather.

9.7 Frozen Subgrades

If earthwork takes place during freezing conditions, all exposed subgrades should be allowed to thaw and then be recompacted prior to placing subsequent lifts of structural fill or foundation components. Alternatively, the frozen material could be stripped from the subgrade to reveal unfrozen soil prior to placing subsequent lifts of fill or foundation components. The frozen soil should not be reused as structural fill until allowed to thaw and adjusted to the proper moisture content, which may not be possible during winter months.

10.0 STRUCTURAL FILL

All references to structural fill in this report refer to subgrade preparation, fill type and placement, and compaction of materials, as discussed in this section. If a percentage of compaction is specified under another section of this report, the value given in that section should be used.

After stripping, planned excavation, and any required overexcavation have been performed to the satisfaction of the geotechnical engineer, the upper 12 inches of exposed ground in areas to receive fill should be recompacted to 90 percent of the modified Proctor maximum density using *American Society for Testing and Materials (ASTM):D 1557* as the standard. If the subgrade contains silty soils and too much moisture, adequate recompaction may be difficult or impossible to obtain and should probably not be attempted. In lieu of recompaction, the area to receive fill should be blanketed with washed rock or quarry spalls to act as a capillary break between the new fill and the wet subgrade. Where the exposed ground remains soft and further overexcavation is impractical, placement of an engineering stabilization fabric may be necessary to prevent contamination of the free-draining layer by silt migration from below.

After recompaction of the exposed ground is tested and approved, or a free-draining rock course is laid, structural fill may be placed to attain desired grades. Structural fill is defined as non-organic soil, acceptable to the geotechnical engineer, placed in maximum 8-inch loose lifts, with each lift being compacted to 95 percent of the modified Proctor maximum density using *ASTM:D 1557* as the standard. In the case of roadway and utility trench filling, the backfill should be placed and compacted in accordance with current City of Mercer Island codes and standards. The top of the compacted fill should extend horizontally outward a minimum distance of 3 feet beyond the locations of the roadway edges before sloping down at an angle of 2H:1V.

The contractor should note that any proposed fill soils must be evaluated by AESI prior to their use in fills. This would require that we have a sample of the material 72 hours in advance to perform a Proctor test and determine its field compaction standard. Soils in which the amount of fine-grained material (smaller than the No. 200 sieve) is greater than approximately 5 percent (measured on the minus No. 4 sieve size) should be considered moisture-sensitive. Use of moisture-sensitive soil in structural fills should be limited to favorable dry weather conditions. The native and existing fill soils present on-site contained significant amounts of silt and are considered moisture-sensitive. In addition, construction equipment traversing the site when the soils are wet can cause considerable disturbance. If fill is placed during wet weather or if proper compaction cannot be obtained, a select import material consisting of a clean, free-draining gravel and/or sand should be used. Free-draining fill consists of non-organic soil with the amount of fine-grained material limited to 5 percent by weight when measured on the minus No. 4 sieve fraction with at least 25 percent retained on the No. 4 sieve.

A representative from our firm should inspect the stripped subgrade and be present during placement of structural fill to observe the work and perform a representative number of in-place density tests. In this way, the adequacy of the earthwork may be evaluated as filling progresses, and any problem areas may be corrected at that time. It is important to understand that taking random compaction tests on a part-time basis will not assure uniformity or

acceptable performance of a fill. As such, we are available to aid in developing a suitable monitoring and testing program.

11.0 FOUNDATIONS

Spread footings may be used for building support when founded directly on the medium dense to very dense natural sediments, or on structural fill placed over these materials, as described above. We recommend that an allowable foundation soil bearing pressure of 2,500 pounds per square foot (psf) be utilized for design purposes, including both dead and live loads. An increase of one-third may be used for short-term wind or seismic loading. Higher foundation soil bearing pressures are possible for foundations supported entirely on undisturbed, dense to very dense lodgement till deposits; however, we do not expect that higher bearing pressures will be needed. If higher foundation soil bearing pressures are needed, we should be allowed to offer situation-specific recommendations

Perimeter footings should be buried at least 18 inches into the surrounding soil for frost protection. However, all footings must penetrate to the prescribed bearing stratum, and no footing should be founded in or above organic or loose soils. All footings should have a minimum width of 18 inches.

It should be noted that the area bound by lines extending downward at 1H:1V from any footing must not intersect another footing or intersect a filled area that has not been compacted to at least 95 percent of ASTM:D 1557. In addition, a 1.5H:1V line extending down from any footing must not daylight because sloughing or raveling may eventually undermine the footing. Thus, footings should not be placed near the edge of steps or cuts in the bearing soils.

Anticipated settlement of footings founded as described above should be on the order of $\frac{3}{4}$ inch or less. However, disturbed soil not removed from footing excavations prior to footing placement could result in increased settlements. All footing areas should be inspected by AESI prior to placing concrete to verify that the design bearing capacity of the soils has been attained and that construction conforms to the recommendations contained in this report. Such inspections may be required by the governing municipality. Perimeter footing drains should be provided, as discussed under the "Drainage Considerations" section of this report.

11.1 Drainage Considerations

Foundations should be provided with foundation drains placed at the base of footing elevation. Drains should consist of rigid, perforated, polyvinyl chloride (PVC) pipe surrounded by washed pea gravel. The drains should be constructed with sufficient gradient to allow gravity discharge away from the proposed buildings. Roof and surface runoff should not discharge

into the footing drain system, but should be handled by a separate, rigid, tightline drain. In planning, exterior grades adjacent to walls should be sloped downward away from the proposed structures to achieve surface drainage.

12.0 FLOOR SUPPORT

Slab-on-grade floors may be used over medium dense to very dense native soils, or over structural fill placed as recommended in the “Site Preparation” and “Structural Fill” sections of this report. Slab design can assume a soil subgrade modulus of 200 pounds per cubic inch (pci) for slabs cast over the dense to very dense, natural sediments or a limited thickness of properly compacted structural fill placed over these materials. Slab-on-grade floors should be cast atop a minimum of 4 inches of washed pea gravel or washed crushed “chip” rock with less than 3 percent passing the U.S. No. 200 sieve to act as a capillary break. The floors should also be protected from dampness by covering the capillary break layer with an impervious moisture barrier at least 10 mils in thickness.

13.0 FOUNDATION WALLS

All backfill behind foundation walls or around foundation units should be placed as per our recommendations for structural fill and as described in this section of the report. Horizontally backfilled walls, which are free to yield laterally at least 0.1 percent of their height, may be designed using an equivalent fluid equal to 35 pounds per cubic foot (pcf). Fully restrained, horizontally backfilled, rigid walls that cannot yield should be designed for an equivalent fluid of 50 pcf. Walls with sloping backfill up to a maximum gradient of 2H:1V should be designed using an equivalent fluid of 55 pcf for yielding conditions or 75 pcf for fully restrained conditions. If parking areas are adjacent to walls, a surcharge equivalent to 2 feet of soil should be added to the wall height in determining lateral design forces.

As required by the 2012 IBC, retaining wall design should include a seismic surcharge pressure in addition to the equivalent fluid pressures presented above. Considering the site soils and the recommended wall backfill materials, we recommend a seismic surcharge pressure of 5H and 10H psf, where H is the wall height in feet for the “active” and “at-rest” loading conditions, respectively. The seismic surcharge should be modeled as a rectangular distribution with the resultant applied at the mid-point of the walls.

The lateral pressures presented above are based on the conditions of a uniform backfill consisting of excavated on-site soils, or imported structural fill compacted to 90 percent of ASTM:D 1557. A higher degree of compaction is not recommended, as this will increase the pressure acting on the walls. A lower compaction may result in settlement of the slab-on-grade

or other structures supported above the walls. Thus, the compaction level is critical and must be tested by our firm during placement. Surcharges from adjacent footings or heavy construction equipment must be added to the above values. Perimeter footing drains should be provided for all retaining walls, as discussed under the “Drainage Considerations” section of this report.

It is imperative that proper drainage be provided so that hydrostatic pressures do not develop against the walls. This would involve installation of a minimum, 1-foot-wide blanket drain to within 1 foot of finish grade for the full wall height using imported, washed gravel against the walls. A prefabricated drainage mat is not a suitable substitute for the gravel blanket drain unless all backfill against the wall is free-draining.

13.1 Passive Resistance and Friction Factors

Lateral loads can be resisted by friction between the foundation and the natural glacial soils or supporting structural fill soils, and by passive earth pressure acting on the buried portions of the foundations. The foundations must be backfilled with structural fill and compacted to at least 95 percent of the maximum dry density to achieve the passive resistance provided below. We recommend the following allowable design parameters:

- Passive equivalent fluid = 350 pcf
- Coefficient of friction = 0.30

14.0 PROJECT DESIGN AND CONSTRUCTION MONITORING

Our report is preliminary since project plans were not finalized at the time this report was written. We recommend that AESI perform a geotechnical review of the plans prior to final design completion. In this way, we can confirm that our earthwork and foundation recommendations have been properly interpreted and implemented in the design.

We are also available to provide geotechnical engineering and monitoring services during construction. The integrity of the foundation system depends on proper site preparation and construction procedures. In addition, engineering decisions may have to be made in the field in the event that variations in subsurface conditions become apparent. Construction monitoring services are not part of this current scope of work. If these services are desired, please let us know, and we will prepare a cost proposal.

We have enjoyed working with you on this study and are confident that these recommendations will aid in the successful completion of your project. If you should have any questions or require further assistance, please do not hesitate to call.

Sincerely,
ASSOCIATED EARTH SCIENCES, INC.
Kirkland, Washington



Jeffrey P. Laub, L.G., L.E.G.
Senior Project Engineering Geologist



Kurt D. Merriman, P.E.
Senior Principal Engineer

Attachments: Figure 1: Vicinity Map
 Figure 2: Site and Exploration Plan
 Appendix: Exploration Logs



NOTE: BLACK AND WHITE REPRODUCTION OF THIS COLOR ORIGINAL MAY REDUCE ITS EFFECTIVENESS AND LEAD TO INCORRECT INTERPRETATION.


REFERENCE: USGS TOPO!

140288 Anbalagan Residence \ 140288 Vicinity.d.cdr




VICINITY MAP
 ANBALAGAN RESIDENCE
 MERCER ISLAND, WASHINGTON

FIGURE 1
 DATE 5/14
 PROJ. NO. KE140288A



REFERENCE: ARCHITECTS NORTHWEST



140288 Anbalagan Residence \140288 Site and Explr.d.cdr



associated
earth sciences
incorporated

SITE AND EXPLORATION PLAN
ANBALAGAN RESIDENCE
MERCER ISLAND, WASHINGTON

FIGURE 2
DATE 5/14
PROJ. NO. KE140288A

APPENDIX


Soil Classification		Terms Describing Relative Density and Consistency	
		Density	SPT ⁽²⁾ blows/foot
Coarse-Grained Soils - More than 50% ⁽¹⁾ Retained on No. 200 Sieve	Gravels - More than 50% ⁽¹⁾ of Coarse Fraction Retained on No. 4 Sieve	GW	Well-graded gravel and gravel with sand, little to no fines
	Sands - 50% ⁽¹⁾ or More of Coarse Fraction Passes No. 4 Sieve	GP	Poorly-graded gravel and gravel with sand, little to no fines
		GM	Silty gravel and silty gravel with sand
		GC	Clayey gravel and clayey gravel with sand
		SW	Well-graded sand and sand with gravel, little to no fines
	Fine-Grained Soils - 50% ⁽¹⁾ or More Passes No. 200 Sieve	Sands - 50% ⁽¹⁾ or More of Coarse Fraction Passes No. 4 Sieve	SP
SM			Silty sand and silty sand with gravel
Sils and Clays Liquid Limit Less than 50		SC	Clayey sand and clayey sand with gravel
		ML	Silt, sandy silt, gravelly silt, silt with sand or gravel
		CL	Clay of low to medium plasticity; silty, sandy, or gravelly clay, lean clay
		OL	Organic clay or silt of low plasticity
Sils and Clays Liquid Limit 50 or More		MH	Elastic silt, clayey silt, silt with micaceous or diatomaceous fine sand or silt
		CH	Clay of high plasticity, sandy or gravelly clay, fat clay with sand or gravel
		OH	Organic clay or silt of medium to high plasticity
		PT	Peat, muck and other highly organic soils
Highly Organic Soils			

Component Definitions	
Descriptive Term	Size Range and Sieve Number
Boulders	Larger than 12"
Cobbles	3" to 12"
Gravel	3" to No. 4 (4.75 mm)
Coarse Gravel	3" to 3/4"
Fine Gravel	3/4" to No. 4 (4.75 mm)
Sand	No. 4 (4.75 mm) to No. 200 (0.075 mm)
Coarse Sand	No. 4 (4.75 mm) to No. 10 (2.00 mm)
Medium Sand	No. 10 (2.00 mm) to No. 40 (0.425 mm)
Fine Sand	No. 40 (0.425 mm) to No. 200 (0.075 mm)
Silt and Clay	Smaller than No. 200 (0.075 mm)

(3) Estimated Percentage		Moisture Content
Component	Percentage by Weight	
Trace	<5	Dry - Absence of moisture, dusty, dry to the touch
Few	5 to 10	Slightly Moist - Perceptible moisture
Little	15 to 25	Moist - Damp but no visible water
With	- Non-primary coarse constituents: $\geq 15\%$ - Fines content between 5% and 15%	Very Moist - Water visible but not free draining
		Wet - Visible free water, usually from below water table

Symbols	
Sampler Type	Description
2.0" OD Split-Spoon Sampler (SPT)	3.0" OD Split-Spoon Sampler
Bulk sample	3.25" OD Split-Spoon Ring Sampler
Grab Sample	3.0" OD Thin-Wall Tube Sampler (including Shelby tube)
	Portion not recovered

Classifications of soils in this report are based on visual field and/or laboratory observations, which include density/consistency, moisture condition, grain size, and plasticity estimates and should not be construed to imply field or laboratory testing unless presented herein. Visual-manual and/or laboratory classification methods of ASTM D-2487 and D-2488 were used as an identification guide for the Unified Soil Classification System.



LOG OF EXPLORATION PIT NO. EP-1

Depth (ft)	DESCRIPTION
	<p>This log is part of the report prepared by Associated Earth Sciences, Inc. (AESI) for the named project and should be read together with that report for complete interpretation. This summary applies only to the location of this trench at the time of excavation. Subsurface conditions may change at this location with the passage of time. The data presented are a simplification of actual conditions encountered.</p>
	Fill
1	Loose, moist, angular GRAVEL, with trace organics and grass roots (GP).
	Buried Topsoil
2	Loose, moist, dark brown, silty SAND, with trace gravel, with trace burned wood fragments (SM).
	Weathered Vashon Lodgement Till
3	Loose to medium dense, moist, reddish brown, silty fine SAND, with gravel (SM).
	Medium dense to dense, moist, rust stained brownish gray, silty fine SAND, with gravel (SM).
4	
	Vashon Lodgement Till
5	Dense to very dense, moist, brownish gray, silty fine SAND, with gravel (SM).
6	
7	Bottom of exploration pit at depth 6.5 feet No seepage. No caving.
8	
9	
10	
11	
12	
13	
14	
15	
16	
17	
18	
19	
20	

KCTP3 140288.GPJ May 20, 2014

Anbalagan Residence Mercer Island, WA

Associated Earth Sciences, Inc.

Project No. KE140288A

Logged by: JPL

Approved by:



5/15/14

LOG OF EXPLORATION PIT NO. EP-2

Depth (ft)	DESCRIPTION
	<p>This log is part of the report prepared by Associated Earth Sciences, Inc. (AESI) for the named project and should be read together with that report for complete interpretation. This summary applies only to the location of this trench at the time of excavation. Subsurface conditions may change at this location with the passage of time. The data presented are a simplification of actual conditions encountered.</p>
	Grass Sod
1	Fill
	Loose, moist, brown and gray, silty SAND, with gravel (SM).
2	
	Weathered Vashon Lodgement Till
3	Medium dense to dense, moist, rust stained brownish gray, silty fine SAND, with gravel (SM).
4	
	Vashon Lodgement Till
5	Dense to very dense, moist, brownish gray, silty fine SAND, with gravel (SM).
6	
7	
8	
9	Bottom of exploration pit at depth 8.5 feet No seepage. No caving.
10	
11	
12	
13	
14	
15	
16	
17	
18	
19	
20	

KCTP3 140288.GPJ May 20, 2014

Anbalagan Residence Mercer Island, WA

Associated Earth Sciences, Inc.

Project No. KE140288A

Logged by: JPL

Approved by:



5/15/14