



GENERAL SPECIFICATIONS FOR GAME COURT SITE PREPARATION – using Sport Base

FRAMING: The area should be framed to retain the fill material, SportBase and court surface. The interior area of the frame should be the overall court size. A recommended material for framing is 4" x 6" pressure treated timber.

GRADE:

1. Area must be excavated and fine graded to a **0% grade** (flat).
2. A layer of landscaping fabric should be installed.
3. We require that a **minimum of 3"** of crushed rock (5/8" clean or minus) be added to the entire area and compacted.
4. Another layer of landscaping fabric should be installed.
5. An additional **minimum of 1"** of smaller crushed rock (e.g. ¼" minus or smaller) should be installed and compacted.
6. The finished area needs to be compacted and graded perfectly flat.
7. Please note that court surface height will be **2.5" above the final grade height** (unless otherwise specified).

DRAINAGE: If necessary, excess water **must be controlled with appropriate drainage** – the court area must also be free of any water before construction can begin.

ANCHOR SETTING: All lines (e.g. drainage, irrigation, power, cable, etc) must be **capped 2' away from the court location**. When staking or setting anchors, **Sport Court (Court Development Inc.) is NOT responsible for any damage to unmarked lines** – Please use a utilities locator service to locate any lines.

- **Sport Court (Court Development Inc.) must approve all site preparation before court construction begins.**

Please call **(425) 823-0461** with any questions or visit our showroom
12805 NE 126th PL . KIRKLAND . WA . 98034