

6515 SE 30th St.

MECER ISLAND, WA - MIS072

GENERAL INFORMATION
APPLIES FULL SET



7525 SE 24th St., 487
Mercer Island, WA
98040
425.266.9100

FLOOR PLAN GENERAL NOTES

GENERAL

- ALL ANGLED WALLS (OTHER THAN 90°) SHALL BE CONSTRUCTED AS NOTED BY ANGLE (DEGREES) CALLOUT OR CONFIGURED AS DIMENSIONED. (UNO.)
- ALL DIMENSIONS AT WALLS ARE TO THE FACE OF FRAMING STUDS.
- ALL EXTERIOR WALLS ENCLOSING CONDITIONED SPACE SHALL BE ADVANCED FRAMING w/2x6 STUDS at 16" OC, and INTERIOR WALLS TO BE 2x4 STUDS at 16" OC, per IRC, R602.3.2 (UNO.)
- ALL DIMENSIONS AT WINDOWS ARE TO THE CENTERLINE
- WINDOW SIZES NOTED ON PLANS ARE NOMINAL SO CONTRACTOR MUST VERIFY EXACT ROUGH OPENINGS PRIOR TO FRAMING. WINDOW AND DOOR HEAD HEIGHTS SHOULD BE COORDINATED SO THAT ALL WINDOW AND DOOR TRIMS ALIGN.
- PROVIDE WEATHER PROTECTION SYSTEM w/WATER-RESISTIVE BARRIERS IN COMBINATION w/FLASHINGS at EXT. WALLS, OPENINGS, PROJECTIONS, PENETRATIONS and INTERSECTIONS TO LOCK OUT ALL MOISTURE per IRC, R103.1-103.4
- TILE INSTALLATION SHALL COMPLY w/APPLICABLE SECTIONS OF THE TILE COUNCIL OF AMERICA'S "HANDBOOK FOR CERAMIC TILE INSTALLATION" and ITS REFERENCED STANDARDS including IRC, R102.4.1
- ALL COUNTERS, TUB DECKS & WALLS AT TUBS & SHOWERS SHALL HAVE SMOOTH, HARD, NON-ABSORBENT SURFACE w/CEMENTITIOUS BACKER BOARD and MOISTURE RESISTANT UNDERLAYMENT per IRC, R102.4.2 UNDERLAYMENT AT TUB & SHOWER WALLS SHALL BE TO A HEIGHT OF 1"2" MIN. ABOVE DRAIN INLET per IRC, R301.2
- ALL SHOWERS TO COMPLY w/IRC, P2108.1 through P2108.5 ALL SHOWER RECEPTORS TO COMPLY w/IRC, P2104.1 through P2104.4
- CALCULATIONS AND DETAILS FOR MOUNTING HEIGHTS & CONNECTION OF METAL GUARDRAILS (IF USED) SHALL BE PROVIDED FOR REVIEW AND APPROVAL BY RAILING FABRICATOR PRIOR TO INSTALLATION FOR COMPLIANCE w/IRC, R311.4 & R312
- ALL REQUIREMENTS FOR BUILDING ENVELOPE TO COMPLY WITH THE 2015 WASHINGTON STATE ENERGY CODE (WSEC). SEE REQ'D ENERGY CREDITS ON THIS SHEET ALONG w/SHEETS A11 & A12 FOR PRESCRIPTIVE REQUIREMENTS and COMPLIANCE NOTES FOR SINGLE FAMILY RESIDENTIAL IN CLIMATE ZONE 5 and MARINE 4.
- WSEC COMPLIANCE CERTIFICATE REQUIRED WITHIN 3' OF ELECTRICAL PANEL.
- EXHAUST FANS LARGER THAN 50cfm, MAY BE CONNECTED TO 4" SMOOTH WALL VENT PIPE IF RUNS DO NOT EXCEED 20' IN LENGTH, THE MINIMUM SIZE OF FLEX DUCT IS 5" DIAMETER WITH MAXIMUM RUN OF 15'.
- COMBUSTION AIR REQUIRED FOR ALL FUEL BURNING APPLIANCES. ALL INTAKE SOURCES TO BE MIN. 18" ABV. GARAGE FLOOR per IRC, M301.3
- PROVIDE FIREBLOCKING TO CUT OFF DRAFT OPENINGS AT LOCATIONS w/MATERIALS per IRC, R302.11 PROVIDE DRAFTSTOPPING AT FLOOR/CEILING ASSEMBLIES per IRC, R302.12
- ALL WASTE PLUMBING DROPS TO BE ON INTERIOR WALLS or FURRED OUT EXTERIOR WALLS.
- PROVIDE ACOUSTICAL PIPE WRAP AT ALL UPPER LEVEL WASTE LINES
- ALL OPENINGS MADE IN WALLS, FLOORS or CEILINGSS FOR THE PASSAGE OF PIPES, STRAINER PLATES ON DRAIN INLETS, TUB WASTE OPENINGS TO CRAWLSPACE and METER BOXES TO COMPLY w/THE CODE REQUIREMENTS OF THE GOVERNING UPC.
- ENTRY STEPS SHALL HAVE SUFFICIENT GRADE BUILT UP AROUND THEM SO THE NUMBER OF STAIR RISERS DOES NOT EXCEED 3, w/MAX. RISER HEIGHT OF 7 1/2" - NOT REQUIRING A HANDRAIL per IRC, R311.7.6
- ALL EXTERIOR ROSE BIBS TO HAVE NON-REMOVABLE VACUUM BREAKERS, MUST BE FROSTPROOF and BE CAULKED and SECURED AT EXT. WALLS.
- INTERIOR CEILING HEIGHTS ARE AS FOLLOWS:
MAIN FLOOR 10'-0" (UNO.)
UPPER FLOOR 9'-1 1/8" (UNO.)

SAFETY GLAZING

- SAFETY GLAZING INSTALLED IN HAZARDOUS LOCATIONS AS REQUIRED BY THIS SECTION SHALL HAVE MFG'S DESIGNATION w/TYPE, THICKNESS and SAFETY GLAZING STANDARD with WHICH IT COMPLIES MARKED BY PERMANENT MEANS THAT CANNOT BE REMOVED WITHOUT DESTROYING GLASS per IRC, R308.1
- IRC, R308.4 REQUIRES THAT SAFETY GLAZING TO BE INSTALLED IN ALL HAZARDOUS LOCATIONS per DEFINED REQUIREMENTS and EXCEPTIONS SPECIFIED IN IRC, R308.4.1 through R308.4.7
- GLAZING IN DOORS.
 - GLAZING ADJACENT TO DOORS.
 - GLAZING IN WINDOWS MEETING ALL (4) CONDITIONS LISTED.
 - GLAZING IN GUARDS and RAILINGS
 - GLAZING IN and NEAR NET SURFACES.
 - GLAZING ADJACENT TO STAIRS and RAMPS
 - GLAZING ADJACENT TO THE BOTTOM STAIR LANDING.

SKYLIGHTS and SLOPED GLAZING SHALL COMPLY WITH THE MATERIALS and REQUIREMENTS OF IRC, R308.6.1 through R308.6.4

EGRESS WINDOWS

- WINDOWS PROVIDING EMERGENCY ESCAPE and RESCUE OPENING REQUIRED AT BASEMENTS, HABITABLE ATTICS and ALL SLEEPING ROOMS and SHALL OPEN DIRECTLY INTO A PUBLIC WAY or YARD TO SAME per IRC, R310.1
- WINDOW CANNOT REQUIRE KEYS, TOOLS or SPECIAL KNOWLEDGE TO OPEN per IRC, R310.1
 - MUST HAVE AN OPENING AREA OF NOT LESS THAN 5.7 Sq.Ft. with 20" min. WIDTH and 24" min. HEIGHT per IRC, R312.2.1
 - MUST HAVE A SILL HEIGHT OF NOT MORE THAN 44" ABV. FLOOR per IRC, R310.2.2
 - GUARDS MUST BE PROVIDED AS WINDOW FALL PROTECTION AT LOW WINDOWS LOCATED GREATER THAN 12" ABV, FINISHED GRADE per IRC, R312.2

STAIRS and HANDRAILS

- STAIRWAYS PROVIDING EGRESS FROM HABITABLE LEVELS NOT PROVIDED w/EGRESS DOOR per IRC, R311.2 SHALL MEET THE REQUIREMENTS and EXCEPTIONS OF IRC, R311.1 through R311.7.4 INCLUDING:
- SHALL PROVIDE A MIN. CLEAR WIDTH OF 36" ABOVE HANDRAIL w/MAX. HANDRAIL PROJECTION INTO STAIRWAY OF 4 1/2" ON EITHER SIDE per R311.1
 - SHALL PROVIDE A MIN. HEADROOM OF 6'-8" MEASURED VERTICALLY FROM THE NOSE OF TREADS or LANDINGS per R311.2
 - SHALL NOT HAVE A VERTICAL RISE GREATER THAN 14" BTWN. FLOOR LEVELS or LANDINGS per R311.7.3
 - SHALL MEET THE WALKLINE REQUIREMENTS AT WINDER TREADS per R311.7.4
 - SHALL HAVE A MAX. RISER HEIGHT OF 7 1/2" and HAVE A MIN. TREAD DEPTH OF 10" THE GREATEST DIMENSION OF ANY RISER or TREAD MUST NOT EXCEED THE SMALLEST DIMENSION BY MORE THAN 3/8". TREADS LESS THAN 11" SHALL MEET NOSING REQUIREMENTS. THE OPENINGS AT OPEN RISERS SHALL NOT PERMIT THE PASSAGE OF A 4"ø SPHERE per R311.5.1 through R311.5.4
 - LANDINGS AT TOP and BOTTOM OF STAIRS SHALL MEET THE REQUIREMENTS OF R311.7.6
 - THE WALKING SURFACE OF TREADS and LANDINGS SHALL NOT BE SLOPED MORE THAN 2% PER R311.7.7
 - HANDRAILS SHALL BE PROVIDED ON AT LEAST ONE SIDE OF EACH CONTINUOUS RUN OF TREADS w/(4) or MORE RISERS. THE TOP OF HANDRAIL SHALL BE 34-38" ABV. LINE CONNECTING NOSINGS. HAVE MIN. 1 1/2" SPACE BTWN. RAIL and WALL. HANDRAIL MUST RUN CONTINUOUS FOR FULL LENGTH OF EACH FLIGHT and MEET APPROVED GRIP-SIZE per IRC, R311.7.8
 - SHALL BE PROVIDED w/ILLUMINATION per IRC, R303.7 at INTERIOR STAIRWAYS and R303.8 at EXTERIOR STAIRWAYS.

GUARDS

- GUARDS SHALL BE PROVIDED IN ACCORDANCE w/REQUIREMENTS and EXCEPTIONS OF IRC, R312.1 through R312.2 INCLUDING:
- ALONG OPEN-SIDED WALKING SURFACES, INCLUDING STAIRS, RAMPS and LANDINGS LOCATED 30" or GREATER ABOVE ADJACENT FLOOR LEVEL per IRC, R312.1
 - OPENINGS MUST PREVENT THE PASSAGE OF A 4" SPHERE or 4 1/2" AT OPEN SIDES OF STAIRS or 6" AT TRIANGLE OF TREAD, RISER & BOTTOM RAIL per R312.3
 - GUARDS MUST BE PROVIDED AS WINDOW FALL PROTECTION AT LOW WINDOWS LOCATED GREATER THAN 12" ABV, FINISHED GRADE per IRC, R312.2
- GUARDS and HANDRAILS MUST RESIST A SINGLE CONCENTRATED LOAD OF 200lbs. IN ANY DIRECTION ALONG THE TOP and GUARD INFILL MUST RESIST A 50lb. LOAD APPLIED HORIZ. OVER 1 Sq.Ft. per IRC, TABLE R301.5

ALARMS

- SMOKE ALARMS and CARBON MONOXIDE ALARMS REQUIRED IN ALL NEW DWELLINGS SHALL MEET REQUIREMENTS and EXCEPTIONS OF NFPA 72, IRC, R314 and R315.
- SMOKE ALARMS TO BE LISTED and INSTALLED IN ACCORDANCE w/IRC, R314.1 and CARBON MONOXIDE ALARMS IN ACCORDANCE w/IRC, R315.1
 - SMOKE ALARMS SHALL BE INSTALLED IN FOLLOWING LOCATIONS per R314.3 :
 - IN EACH SLEEPING ROOM.
 - OUTSIDE EACH SEPARATE SLEEPING AREA.
 - ON EACH STORY OF THE DWELLINGS.
 - NOT LESS THAN 3' FROM A BATHROOM w/TUB or SHOWER.
 - NOT NEAR COOKING APPLIANCES per R314.3.1
 - SMOKE ALARMS SHALL BE INTERCONNECTED per R314.4
 - CARBON MONOXIDE ALARMS SHALL BE INSTALLED IN THE FOLLOWING LOCATIONS per R315.3 :
 - ON EACH STORY OF THE DWELLINGS
 - ADJACENT TO EACH SEPARATE SLEEPING AREA.
 - WITHIN BEDROOMS WHERE A FUEL BURNING FIREPLACE IS LOCATED IN THE ROOM or ITS ATTACHED BATH.
 - ALL ALARMS SHALL RECEIVE THEIR PRIMARY POWER FROM BUILDING WIRING w/BATTERY BACKUP per R314.6 and R315.5
 - COMBINATION SMOKE and CARBON MONOXIDE LOCAL JURISDICTION REQUIRES DWELLING UNIT FIRE SPRINKLER SYSTEM PER IRC APPENDIX R
 - LOCAL JURISDICTION DOES NOT REQUIRE DWELLING UNIT FIRE SPRINKLER SYSTEM PER IRC APPENDIX R

ALARMS SHALL BE PERMITTED IN LIEU OF SEPARATE ALARMS per R314.5 and R315.4

FIRE PROTECTION

ABBREVIATIONS

# Pound OR Number	ELEC Electrical	MC Medicine Cabinet	SLB Slab
& And	ELEV Elevation	MDO Medium Density Overlay	SPEC Specification
@ At	EQ Equal	MECH Mechanical	SQ Square
A/C Air Conditioner	EW Each Way	MED Medium	SQ IN Square inches
AB Anchor Bolt	EXC Excavate	MEMB Membrane	SQFT Square feet
ABV Above	EXH Exhaust	MFR Manufacturer	STC Sound Transmission Coefficient
AD Area Drain	EXIST Existing	MN Minimum	STD Standard
ADL Additional	EXT Exterior	MIR Mirror	STL Steel
ADH Adhesive	FBD Fiberboard	MISC Miscellaneous	STR Structural
ADJ Adjustable	FCB Fiber Cement Board	MLB Micro Laminated Beam	STRUCT Structure or Structural
AFF Above Finish Floor	FCO Floor clean out	MMB Membrane	T Tread
AGG Aggregate	FD Floor drain	MW Millwork	T&G Tongue and Groove
ALT Alternate	FRN Finish	NIC Not in Contract	TEL Telephone
ALUM Aluminum	FIXT Fixture	NO Number	TEMP Tempered
ANC Anchor	FLR Fluorescent	NOM Nominal	TK Tight Knot
APX Approximate	FLR Floor	NTS Not to Scale	TME To Match Existing
ASPH Asphalt	FLSH Flashing	O Non-Operable Window	TOB Top of Beam
AUTO Automatic	FND Foundation	OBS Obscure	TOC Top of curb/ Top of Concrete
AVR Average	FO Face Of	OP Overhang	TOJ Top of joist
AW American Wire Gauge	FOD Face of Concrete	OPG Opaque	TOU Top of wall
AWN Awning	FOM Face of Masonry	OSB Oriented Strand Board	TP Toilet Paper Hanger
B/O By Others	FOS Face of Studs	OSB Galvanized	VB Vapor barrier
BD Board	FOW Face of Wall	OSB Particle Board	VERT Vertical
BLDG Building	FFL Fireplace	PBF Prefabricated	VF Verify in field
BLK Blocking	FRM Frame(ing)	PERF Perforate(d)	W/ With
BLW Below	FRFF Fireproof	PL Property Line	W/O Without
BM Beam	FT Fast	PLAM Plastic Laminated Plate	WC Toilet (water closet)
BOF Bottom of footing	FTG Footing	PLYW Plywood	WD Wood
BOT Bottom	FUR Furred	PNT Paint or Painted	WH Water Heater
BOW Bottom of wall	GA Gauge	PSF Pounds Per Square Foot	WP Water Proofing
BR Bedroom	GALV Galvanized	PSI Pounds Per Square Inch	WR Weatherproof
BST Basement	GFCI Ground Fault Circuit Interrupt	PT Pressure Treated Polyvinyl Chloride	WRB Weather Resistant Barrier
BTW Between	GF Ground Fault Interrupt	PVC Polyvinyl Chloride	WWF Welded Wire Fabric Section
BYND Beyond	GLB Glass Laminated Beam	R Riser	X Operable Window Section
CAB Cabinet	GLB Glass Block	HW Hot water	
CAS Casement	GLB Glass Block	ID Inside Diameter	
CB Catch Basin	GYP Gypsum Wall Board	ILO in Lieu Of	
VENTILATING	GP Cast-in-place	IN Inch	
CC Center to Center	CC Control joint	INCL Include	
CCJ Cast-in-place	CL Centerline	INS Insulate(tion)	
CL Centerline	CLR Clear	INSUL Insulation	
CLG Ceiling	CMU Concrete Masonry Unit	INT Interior	
CLR Clear	CO Clean Out	J=Box Junction box	
CMU Concrete Masonry Unit	COL Column	JNT Joint	
CO Clean Out	CONC Concrete	JST Joist	
COL Column	CONT Continuous	KD Klim Dried	
CONC Concrete	CRPT Carpet	KIT Kitchen	
CONT Continuous	CT Ceramic Tile	LAM Laminated(d)	
CRPT Carpet	CTYD Courtyard	LAV Lavatory	
CU YD Cubic Yard	CU FT Cubic Feet	LB Pound Feet	
CU YD Cubic Yard	DBL Double	LF Lineal Feet	
DBL Double	DEMO Demolish or Demolition	LL Live Load	
DEMO Demolish or Demolition	DH Double Hung	LT Light	
DH Double Hung	DIA Diameter	LTG Lighting	
DIA Diameter	DM Dimension	LVL Laminated Veneer Lumber	
DM Dimension	DN Down	LVR Louver	
DN Down	DP Damp proofing	MAS Masonry	
DP Damp proofing	DR Door	MAX Maximum	
DR Door	DRWR Drawer	MGR Member	
DRWR Drawer	DS Downspout		
DS Downspout	DT Drain Tile		
DT Drain Tile	DW Dishwasher		
DW Dishwasher	DWG Drawing		
DWG Drawing	EJ Exhaust fan		
EJ Exhaust fan	EA Each		
EA Each	EF Expansion Joint		
EF Expansion Joint	EL Elevation		
EL Elevation			

SHEET INDEX

SHEET #	DESCRIPTION
A1	COVERSHEET
A2	SITE PLAN
A3	FOUNDATION PLAN
A4	MAIN FLOOR FRAMING PLAN
A5	MAIN FLOOR PLAN
A6	UPPER FLOOR FRAMING PLAN
A7	UPPER FLOOR PLAN
A8	ROOF FRAMING PLAN
A9	ROOF PLAN
A10	EXTERIOR ELEVATIONS
A11	EXTERIOR ELEVATIONS
A12	BUILDING SECTIONS
SO.0	LATERAL - STRUCTURAL GENERAL NOTES
LB-1	LATERAL - DETAILS
LB-2	LATERAL - DETAILS
SD.01	FOUNDATION DETAILS
D1	WATER INTRUSION DETAILS
E1	MAIN FLOOR ELECTRICAL LAYOUT
E2	UPPER FLOOR ELECTRICAL LAYOUT
EN1	2018 ENERGY CODE CALCULATIONS
EN2	2018 ENERGY CODE NOTES
EN3	2018 ENERGY CODE NOTES

BUILDING CODES FOR THIS SET

CITY OF MERCER ISLAND CODES AT THE DATE OF THIS DRAWING SET:

- 2018 INTERNATIONAL BUILDING CODE (IBC)
- 2018 INTERNATIONAL RESIDENTIAL CODE (IRC)
- 2018 WASHINGTON STATE ENERGY CODES
- 2009 ICC A117.1, BARRIER-FREE STANDARD
- 2018 INTERNATIONAL FIRE CODE (IFC)
- 2018 NATIONAL ELECTRIC CODE (NEC)
- 2018 UNIFORM PLUMBING CODE (UPC)
- 2018 INTERNATIONAL MECHANICAL CODE (IMC)
- 2015 INTERNATIONAL FUEL GAS CODE (IFGC)
- 2015 POOL AND SPA CODE

PROJECT TEAM

ARCHITECTURAL DESIGN - JAYMARC HOMES

ARCHITECTURAL DRAFTING
JAYMARC HOMES - 425.226.9100 - JAYMARCHOMES.COM
RYAN REDMAN - RYAN@JAYMARCHOMES.COM

M&K ENGINEERING
MULHERN & KULP - 215.646.8001 - MULHERNKULP.COM
RICHARD ZABEL - RZABEL@MULHERNKULP.COM

COVER SHEET
1/4" = 1'-0"

SQUARE FOOTAGE SUMMARY

SQUARE FOOTAGE SUMMARY	
MAIN FLOOR/ MAIN LIVING	1,700 S.F.
MAIN FLOOR A.D.U.	448 S.F.
GARAGE	448 S.F.
SUB TOTAL	2,246 S.F.
UPPER FLOOR/ MAIN LIVING	1,347 S.F.
UPPER FLOOR A.D.U.	492 S.F.
MINUS A.D.U. STAIRS	-42 S.F.
MINUS MAIN STAIRS	-56 S.F.
SUB TOTAL	1,741 S.F.
TOTAL G.F.A.	3,987 S.F.
ALLOWABLE F.A.R. 45% PROPOSED	4,050 S.F.
	44.3%
TOTAL NET AREA MAIN HOUSE	2,491 S.F.
GARAGE	448 S.F.
TOTAL NET A.D.U.	548 S.F.
SUB TOTAL	3,487 S.F.
COVID PATIO	259 S.F.
COVID PORCH	40 S.F.
OVERALL WIDTH	71'-11 1/2"
OVERALL DEPTH	44'-1 1/2"
Updated : 03/04/2018	
Method for Calculating Square Footage - ANSI Z165-2013 except, no separate distinction of "above-grade or below-grade" areas and each level is measured to the outside of studs not the exterior finished surface.	
Square Footage calculations for this house were made based on plan dimensions only and may vary from the finished square footage of the house as built.	
See Sheet "CODES" for additional Zoning required Area Calculations.	

Issue Issue Date By
Description

02.03.22
CITY PLAN REVIEW COMMENTS

04.05.22
CITY PLAN REVIEW COMMENTS

6515 SE 30th St.
Mercer Island, WA.
Job Number:
MIS072

plan name: -
marketing name: -
plan number: -
mark sys. number: -

Conditions not specifically represented graphically or in writing or which conflict with the current International Residential Code (IRC.) or those of the local municipality then the current standards and requirements of each respectively shall govern.

The drawings in this set are instruments of service and shall remain the property of JayMarc Homes, LLC.

© 2017 JayMarc Homes, LLC; All rights reserved.

04.15.21
Submittal Date

Sheet Title/Description

JAYMARC HOMES
Design Firm

R.R.
Drawn by:

R.R./S.K.
Checked by:

Primary Scale

A1
of .

Sheet Title/Description

Sheet Title/Description

MIS072

JayMarc Homes, LLC
 7525 SE 24th St, #487
 Mercer Island, WA 98040
 425 281 2706

Site Plan
 6515 SE 30th Street


Drawn by
 Gary Upper

5-10-21

425-281-2706

1-26-22

A2.0



SE 30th Height Table

Segment	Midpoint Elevation	Length	Product
A	102.2	6	613.2
B	103.4	1	103.4
C	103.8	7	726.6
D	103.8	1	103.8
E	104	7	728.0
F	104	1	104.0
G	104.1	12	1,249.2
H	104.4	7	730.8
I	104.8	6.5	681.2
J	105	7	735.0
K	104.3	12	1,251.6
L	104.4	1	104.4
M	104.4	21.5	2,244.6
N	104.2	21	2,188.2
O	104.2	1	104.2
P	104.2	10	1,042.0
Q	103.7	7	725.9
R	103.7	1	103.7
S	103.7	21.5	2,229.6
T	105.2	3.5	368.2
U	105.1	24	2,522.4
V	103.5	17.5	1,811.3
W	100.3	21	2,106.3
X	101	44	4,444.0
Sub Totals	261.5	27,021.5	
ABE		103.3	
Max Height		30.0	
Max Elevation		133.3	

Lot Slope Calculations

High Point	107.5 ft
Low Point	96.5 ft
Elevation Difference	11 ft
Distance	128 ft
Slope%	8.60%

GENERAL INFORMATION

PROPERTY OWNER
 Jaymarc Emerald, LLC

STREET ADDRESS
 6515 SE 30th St

PARCEL #
 2174500800

LEGAL DESCRIPTION
 Lots 31, 32 and 33, Block 5, East Seattle, Volume 3, PP 22 and 23.

ZONE: R-8.4

SETBACKS:
 Front Yard - 20'
 Rear Yard - 25'
 Sides Yard on Street Side - 20'
 Remaining side yard 5'

HEIGHT LIMIT: 30' above ABE to roof peak

MAXIMUM LOT COVERAGE: 40%

MAXIMUM HARDSCAPE: 9%

MAXIMUM FAR: 40%

PARKING SPACES PROVIDED: 2 GARAGE 2 DRIVEWAY

NO CRITICAL AREAS IMPACTED

NO ONSITE EASEMENTS

LOT COVERAGE

Lot Area	9,000
Allowed	40%
Allowed sf	3,600

New

Main Structure Roof Area	2,677
Driveway	393
Cov'd Patio or Deck	-
New sf	3,070

Existing

Existing	2,073
Existing Removed	(2,073)
Net Existing	-


Total

Total New and Existing	3,070
	% 34.1%

Gross Floor Area

Main Floor Main House Living	1,700 sf
Main Floor ADU	98 sf
Garage	448 sf
Sub Total	2,246 sf
Second Floor Main House Living	1,347 sf
Second Floor ADU	492 sf
Less ADU stairs	-42 sf
Less Main stairs	-56 sf
Sub Total	1,741 sf
Total GFA	3,987 sf
Allowed 45%	4,050 sf
Proposed	44.3%

Total Net Main House	2,991 sf
Garage	448 sf
Total Net ADU	548 sf
	3,987 sf



DEMOLITION

Remove all existing buildings and hardscape
 Except a portion of rockery as shown

PARKING


Covered	2 ea.
Driveway	2 ea.

Hardscape

EXISTING	
Uncovered Patio	373
Walkways	99
Stairs	70
Rockery/Retaining Walls	200
Total Existing	742
Existing Removed	640
Net Existing Retained	102
NEW	
Walkways	172
Stairs	36
Retaining Walls	127
Uncovered Decks	36
Total New	371
Total New and Existing	473
Total Hardscape	5.3%

Tree Table

ID	Species	DSHS	Drip	Saved	Exceptional
267	Western Red Cedar	36.4	N-20	Yes	Yes




JayMarc Homes, LLC
 7525 SE 24th St, #487
 Mercer Island, WA 98040
 425 281 2706

DEMOLITION PLAN
 6515 SE 30th Street

Drawn by
 Gary Upper
 1/25/22

425-281-2706



FOUNDATION PLAN

1/4" = 1'-0"

NOTES:

HOLD-DOWN SCHEDULE	
SYMBOL	SPECIFICATION
HD-1	SIMPSON 5THD14 (R.J) HOLD-DOWN
HD-5	SIMPSON C516 STRAP TIE (14" END LENGTH)
HD-6	SIMPSON MSTC40 STRAP TIE (12" END LENGTH)
HD-7	SIMPSON MSTC66 STRAP TIE (24" END LENGTH)

LEGEND	
	INTERIOR BEARING WALL
	EXTERIOR WALL ABOVE
	METAL HANGER
	INDICATES POST ABOVE. PROVIDE SOLID BLOCKING UNDER POST OR JAMB ABOVE.
	INDICATES HOLD-DOWN.

4x10 DROPPED CONT. BEAM (TYP. U.N.O.) w/ 4x4 P.T. POSTS ON 24"x24"x8" PLAIN CONC. FTG. (U.N.O.)

TYP. CRAWLSPACE POSTS:
 4x4 P.T. POST w/ 2x4 CLEATS EA. SIDE + SIMPSON ABN44Z BASE @ BASE OF POST FASTENED TO FTG. BELOW w/ (1) 1/2"x5" SIMPSON TITEN HD ANCHOR ON ASPHALT SHINGLE ON 24"x24"x8" PLAIN CONC. FTG. (TYP. U.N.O.)

REFER TO S-O FOR TYPICAL STRUCTURAL NOTES & SCHEDULES

JAYMARC HOMES
 7525 SE 24th St., 487
 Mercer Island, WA
 98040
 425.266.9100

Issue	Issue Date	By	Description
	02.03.22		CITY PLAN REVIEW COMMENTS
	04.05.22		CITY PLAN REVIEW COMMENTS

6515 SE 30th St.
Mercer Island, WA.
 Job Number:
MIS072

plan name: _____
 marketing name: _____
 plan number: _____
 mark sys. number: _____

Conditions not specifically represented graphically or in writing or which conflict with the current International Residential Code (IRC.) or those of the local municipality then the current standards and requirements of each respectively shall govern.

The drawings in this set are instruments of service and shall remain the property of JayMarc Homes, LLC.

© 2017 JayMarc Homes, LLC. All rights reserved.

04.15.21
 Submittal Date

Sheet Title/Description
 JAYMARC HOMES
 Design Firm

R.R.
 Drawn by:

R.R./S.K.
 Checked by:

Primary Scale

A3
 of .

Sheet Title/Description

HOLD-DOWN SCHEDULE	
SYMBOL	SPECIFICATION
HD-1	SIMPSON STHD14 (R.J.) HOLD-DOWN
HD-5	SIMPSON CS16 STRAP TIE (14" END LENGTH)
HD-6	SIMPSON MSTC40 STRAP TIE (12" END LENGTH)
HD-7	SIMPSON MSTC66 STRAP TIE (24" END LENGTH)

LEGEND	
	J.L. METAL HANGER
	* INDICATES POST ABOVE. PROVIDE SOLID BLOCKING UNDER POST OR JAMB ABOVE.
	▲ INDICATES HOLD-DOWN.

INDICATES 11-7/8" TJI FLOOR JOISTS @ 16" O.C. (TYP. U.N.O.)

REFER TO S-O FOR TYPICAL STRUCTURAL NOTES & SCHEDULES

4x10 DROPPED CONT. BEAM (TYP. U.N.O.) B10 & B20

FOUNDATION VENTILATION			
Crawlspace Area:	1800 s.f.		
Ventilation Required:	1800 s.f. / 300 =	864 s.i. Req'd	
Use:	14" x 7" Foundation Vents		
Vent Area =	98 s.i. - 25% reduct., 1/4" mesh =	73.5 s.i.	
Vents Required =	864 s.i. / Vent Area =	11.76 s.i.	
Provide:	12 14" x 7" Vents, Area =	882 s.i.	
Ventilation Provided =	882.00 s.i. is Greater than	864 s.i. Req'd	
Use:	12 14" x 7" Foundation Vents		
* FOUNDATION VENTS SHALL NOT INTERFERE WITH DIRECT LOAD PATH OF COLUMNS			
* INSTALL 6 MIL BLACK POLYETHYLENE VAPOR RETARDER GROUND COVER			
* LOCATE ONE VENT WITHIN 3 FEET OF EACH CORNER OF THE BUILDING, EXCEPT ONE SIDE OF THE BUILDING SHALL BE PERMITTED TO HAVE NO VENTS.			

Issue	Issue Date	By	Description
	02.03.22		CITY PLAN REVIEW COMMENTS
	04.05.22		CITY PLAN REVIEW COMMENTS

6515 SE 30th St.
Mercer Island, WA.
Job Number:
MIS072

plan name:	-
marketing name:	-
plan number:	-
mark sys. number:	-

Conditions not specifically represented graphically or in writing or which conflict with the current International Residential Code (IRC) or those of the local municipality then the current standards and requirements of each respectively shall govern.

The drawings in this set are instruments of service and shall remain the property of JayMarc Homes, LLC.

© 2017 JayMarc Homes, LLC. All rights reserved.

04.15.21
Submittal Date

Sheet Title/Description

JAYMARC HOMES
Design Firm


R.R.
Drawn by:

R.R./S.K.
Checked by:

Primary Scale

A4
of: .

Sheet Title/Description



MAIN FLOOR FRAMING PLAN
1/4" = 1'-0"



7525 SE 24th St. 487
Mercer Island, WA
98040
425.266.9100

6515 SE 30th St.
Mercer Island, WA.
Job Number:
MIS072

MAIN FLOOR PLAN NOTES

PLAN SPECIFIC 2018 WSEC SECTION R406
R406.2 ADDITIONAL ENERGY EFFICIENCY REQUIREMENTS (MANDATORY). THIS RESIDENTIAL DWELLING SHALL COMPLY W/SUFFICIENT OPTIONS FROM TABLE R406.2 TO ACHIEVE THE FOLLOWING MIN. NUMBER OF CREDITS: 6 FOR A 1501sf TO 4,999sf HOME.
CREDITS PROVIDED IN THIS HOME AS FOLLOWS:

EFFICIENT BUILDING ENVELOPE OPT. 1.3 - 0.5 CREDITS
PRESCRIPTIVE COMPLIANCE IS BASED ON TABLE R402.1.1 WITH FOLLOWING MODIFICATIONS:
VERTICAL FENESTRATION U = 0.28 WINDOWS
FLOORS TO BE R-38 AND SLAB ON GRADE TO BE R-10 PERIMETER AND UNDER ENTIRE SLAB BELOW GRADE.
AIRLEAKAGE & EFFICIENT VENTILATION OPT. 2.1 - 0.5 CREDITS
REDUCE THE TESTED AIR LEAKAGE TO 3.0 AIR CHANGES PER HOUR MAXIMUM @ 50 PASCALS AND ALL WHOLE HOUSE VENTILATION REQUIREMENTS AS DETERMINED BY SECTION M507.3 OF THE I.R.C. OR SECTION 404.8 OF THE IMC SHALL BE MET WITH A HIGH EFFICIENCY FAN(S) (MAXIMUM OF 0.35 WATTS/CFM) NOT INTERLOCKED WITH THE FURNACE FAN (IF PRESENT). VENTILATION SYSTEMS USING A FURNACE INCLUDING AN EMC MOTOR ARE ALLOWED, PROVIDED THAT THEY ARE CONTROLLED TO OPERATE AT LOW SPEED IN THE VENTILATION ONLY MODE.
HIGH EFFICIENCY HVAC EQUIPMENT OPT. 3.5a - 1.5 CREDITS
HVAC EQUIPMENT AND ASSOCIATED DUCT SYSTEM(S) INSTALLATION SHALL COMPLY WITH THE REQUIREMENTS OF SECTION R403.3.1. LOCATING SYSTEM COMPONENTS IN CONDITIONED CRAWL SPACE IS NOT PERMITTED UNDER THIS OPTION. ELECTRIC RESISTANCE HEAT AND DUCTLESS HEAT PUMPS ARE NOT PERMITTED UNDER THIS OPTION. DIRECT COMBUSTION HEATING EQUIPMENT WITH AFUE LESS THAN 80% IS NOT PERMITTED UNDER THIS OPTION.
FULL NORMALIZATION CREDIT (MUST USE OPT. 3.5a) - 1.0 CREDITS
HIGH EFFICIENCY HVAC DISTRIBUTION OPT. 4.2 - 1.0 CREDITS
HVAC EQUIPMENT AND ASSOCIATED DUCT SYSTEM(S) SHALL COMPLY WITH THE REQUIREMENTS OF SECT R403.3.1. LOCATING SYSTEM COMPONENTS IN UNCONDITIONED CRAWL SPACES IS NOT PERMITTED UNDER THIS OPTION. ELECTRIC RESISTANCE HEAT AND DUCTLESS HEAT PUMPS ARE NOT PERMITTED UNDER THIS OPTION. DIRECT COMBUSTION HEATING EQUIPMENT WITH AFUE LESS THAN 80% IS NOT PERMITTED UNDER THIS OPTION.
EFFICIENT WATER HEATING 5.5 - 2.0 CREDITS
WATER HEATING SYSTEMS SHALL INCLUDE ONE OF THE FOLLOWING:
ELECTRIC HEAT PUMP WATER HEATER MEETING THE STANDARDS FOR TIER III OF NEEA'S ADVANCED WATER HEATING SPECIFICATION. IF ONE WATER HEATER IS SERVING MORE THAN ONE DWELLING UNIT, ALL OF WATER SUPPLY AND RE-CIRCULATION PIPING SHALL BE INSULATED WITH R-8 MINIMUM PIPE INSULATION.
EFFICIENT WATER HEATING 5.6 - 2.5 CREDITS
WATER HEATING SYSTEM SHALL INCLUDE ONE OF THE FOLLOWING:
ELECTRIC HEAT PUMP WATER HEATER WITH A MIN. OF 2.9 AND UTILIZING A SPLIT SYSTEM CONFIGURATION WITH THE AIR-TO-REFRIGERANT HEAT EXCHANGER LOCATED OUTDOORS. EQUIPMENT SHALL MEET SECTION 4. REQUIREMENTS FOR ALL UNITS, OF THE NEEA STANDARD ADVANCED WATER HEATING SPECIFICATION WITH THE UEF NOTED ABOVE.

WHOLE HOUSE VENTILATION
PROVIDE WHOLE HOUSE VENTILATION PER 2015 IRC, M507 AND IMC R403.8 USING A MAKE UP AIR SYSTEM INTEGRATED INTO FORCED AIR SYSTEM (FAU) PROVIDE OUTDOOR FRESH AIR W/DUCTS CONNECTED TO THE RETURN SIDE OF THE AIR HANDLER.


SYMBOL	LOCATION	MIN. FAN REQUIREMENTS (ALL FANS VENT TO OUTSIDE)
Ⓜ	BATH & POWDER	Min. 50cfm, INTERMITTENT at .025avg per TABLE M507.4
Ⓚ	KITCHEN	Min. 100cfm, INTERMITTENT at .025avg per TBL M507.4
Ⓛ	LAUNDRY ROOM	MIN 420cfm, INTERMITTENT at .025avg TO FUNCTION AS WHOLE HOUSE FAN (WHF)

MECHANICAL CONTRACTOR TO PROVIDE 420cfm WHF, FAN AND SET OPERATING TIMER PER TABLE M507.3(3) FOR A 4501-6,000sq. FT. DWELLING W/6-7 BEDRMS. TO OPERATE INTERMITTENTLY PER TABLE M507.3(2)
PROVIDE CONTROLS FOR WHF PER M507.3.2 AFFIX LABEL TO CONTROLS THAT READS "WHOLE HOUSE VENTILATION - SEE OPERATING INSTRUCTIONS"
WHOLE HOUSE FAN RUN TIME PERCENTAGE IN EACH 4 HR. SEGMENT TO BE 25% WITH A FACTOR OF 4.

SQUARE FOOTAGE SUMMARY

MAIN FLOOR/ MAIN LIVING	1,700	S.F.
MAIN FLOOR A.D.U.	48	S.F.
GARAGE	448	S.F.
SUB TOTAL	2,246	S.F.
UPPER FLOOR/ MAIN LIVING	1,347	S.F.
UPPER FLOOR A.D.U.	442	S.F.
MINUS A.D.U. STAIRS	-42	S.F.
MINUS MAIN STAIRS	-56	S.F.
SUB TOTAL	1,741	S.F.
TOTAL G.F.A.	3,987	S.F.
ALLOWABLE F.A.R. 45%	4,050	S.F.
PROPOSED	44.3%	
TOTAL NET AREA MAIN HOUSE	2,991	S.F.
GARAGE	448	S.F.
TOTAL NET A.D.U.	548	S.F.
SUB TOTAL	3,987	S.F.
COVD PATIO	254	S.F.
COVD PORCH	40	S.F.
OVERALL WIDTH	71'-11 1/2"	
OVERALL DEPTH	44'-1 1/2"	
Updated	03/01/2018	

Method for Calculating Square Footage - ANSI Z390-2013 except, no separate distribution of above-grade or below-grade areas and each level is measured to the outside of studs not the exterior finished surface.
Square footage calculations for this house were made based on plan dimensions only and may vary from the finished square footage of the house as built.
See Sheet "CODES" for additional Zoning required Area Calculations.



MAIN FLOOR PLAN

1/4" = 1'-0"

Issue	Issue Date	By
Issue	02.03.22	
Issue	04.05.22	

CITY PLAN REVIEW COMMENTS

CITY PLAN REVIEW COMMENTS

CITY PLAN REVIEW COMMENTS

CITY PLAN REVIEW COMMENTS

CITY PLAN REVIEW COMMENTS

CITY PLAN REVIEW COMMENTS

Conditions not specifically represented graphically or in writing or which conflict with the current International Residential Code (IRC), or those of the local municipality then the current standards and requirements of each respectively shall govern.

The drawings in this set are instruments of service and shall remain the property of JayMarc Homes, LLC.

© 2017 JayMarc Homes, LLC; All rights reserved.

04.15.21
Submission Date

Sheet Title/Description

JAYMARC HOMES
Design Firm

R.R.
Drawn by:

R.R./S.K.
Checked by:

Primary Scale

A5
of .

Sheet Title/Description

HOLD-DOWN SCHEDULE	
SYMBOL	SPECIFICATION
HD-1	SIMPSON 5THD14 (R.J.) HOLD-DOWN
HD-5	SIMPSON C516 STRAP TIE (14" END LENGTH)
HD-6	SIMPSON MSTC40 STRAP TIE (12" END LENGTH)
HD-7	SIMPSON MSTC66 STRAP TIE (24" END LENGTH)

LEGEND	
	INTERIOR BEARING WALL
	BEAM / HEADER
	10" FLOOR TRUSS @ 24" O.C. (U.N.O.)
	INTERIOR SHEAR WALL PANEL OR EXTERIOR SHEAR WALL w/ 3" O.C. EDGE NAILING
	JL METAL HANGER
	* INDICATES POST ABOVE. PROVIDE SOLID BLOCKING UNDER POST OR JAMB ABOVE.
	◀ INDICATES HOLD-DOWN.

REFER TO S-O FOR TYPICAL STRUCTURAL NOTES & SCHEDULES


4x10 HDR @ ALL EXT. WINDOWS/DOORS (TYP. U.N.O.)

NOTE #1:
PROVIDE 3/8" OSB/PLYWOOD SHTG. + FASTEN PER TYP. WALL SHTG. SPECS. (SEE NOTES)

NOTE #2:
PROVIDE SIMPSON C516 STRAP FROM TOP OF FLUSH BEAM/ BLOCKING (13" END LENGTH TO TOP OF BLKG. PROVIDE BLKG BETWEEN TRUSSES FOR STRAP FASTENING AS SHOWN (3' BAY MIN.) FASTEN FLOOR SHTG. TO BLOCKING w/ 3"x 0.131" NAILS @ 6" O.C. @ SHTG. EDGES.

NOTE #3:
PROVIDE SIMPSON C516 STRAP FROM TOP OF DBL. TOP PLATE (13" END LENGTH) TO UNDERSIDE OF FULL HT. SOLID BLOCKING. PROVIDE BLOCKING BETWEEN TRUSSES FOR STRAP FASTENING AS SHOWN (3-BAY MIN.) FASTEN FLOOR SHTG. TO BLOCKING w/ 3"x 0.131" NAILS @ 6" O.C. @ SHTG. EDGES.

NOTE #4:
PROVIDE SIMPSON C516 STRAP FROM TOP OF DOUBLE TOP PLATE (13" END LENGTH) TO UNDERSIDE OF FLOOR DRAG TRUSS. FASTEN FLOOR SHTG. TO DRAG TRUSS w/ 3"x 0.131" NAILS @ 6" O.C. @ SHTG. EDGES.



UPPER FLOOR & LOWER ROOF FRAMING PLAN

1/4" = 1'-0"

Sheet Title/Description

UPPER FLOOR PLAN NOTES:

PLAN SPECIFIC 2018 WSEC SECTION R06

R406.2 ADDITIONAL ENERGY EFFICIENCY REQUIREMENTS (MANDATORY). THIS RESIDENTIAL DWELLING SHALL COMPLY WITH EFFICIENT OPTIONS FROM TABLE R406.2 TO ACHIEVE THE FOLLOWING MIN. NUMBER OF CREDITS: 6 FOR A 1501sf to 4,999sf HOME.

CREDITS PROVIDED IN THIS HOME AS FOLLOWS:
EFFICIENT BUILDING ENVELOPE - OPT. 1.3 - 0.5 CREDITS

PRESCRIPTIVE COMPLIANCE IS BASED ON TABLE R402.11 WITH FOLLOWING MODIFICATIONS:

VERTICAL FENESTRATION U = 0.28 WINDOWS

FLOORS TO BE R-38 AND SLAB ON GRADE TO BE R-10 PERIMETER AND UNDER ENTIRE SLAB BELOW GRADE.

AIRLEAKAGE & EFFICIENT VENTILATION - OPT. 2.1 - 0.5 CREDITS

REDUCE THE TESTED AIR LEAKAGE TO 3.0 AIR CHANGES PER HOUR MAXIMUM @ 50 Pascals AND ALL WHOLE HOUSE VENTILATION REQUIREMENTS AS DETERMINED BY SECTION M507.3 OF THE IRC, OR SECTION 404.B OF THE IMC SHALL BE MET WITH A HIGH EFFICIENCY FAN(S) (MAXIMUM OF 0.35 WATTS/CFM), NOT INTERLOCKED WITH THE FURNACE FAN (IF PRESENT). VENTILATION SYSTEMS USING A FURNACE INCLUDING AN EMC MOTOR ARE ALLOWED, PROVIDED THAT THEY ARE CONTROLLED TO OPERATE AT LOW SPEED IN THE VENTILATION ONLY MODE.

HIGH EFFICIENCY HVAC EQUIPMENT - OPT. 3.5g - 1.5 CREDITS

HVAC EQUIPMENT AND ASSOCIATED DUCT SYSTEM(S) INSTALLATION SHALL COMPLY WITH THE REQUIREMENTS OF SECTION R403.3.1. LOCATING SYSTEM COMPONENTS IN CONDITIONED CRAWL SPACE IS NOT PERMITTED UNDER THIS OPTION. ELECTRIC RESISTANCE HEAT AND DUCTLESS HEAT PUMPS ARE NOT PERMITTED UNDER THIS OPTION. DIRECT COMBUSTION HEATING EQUIPMENT WITH AFUE LESS THAN 80% IS NOT PERMITTED UNDER THIS OPTION.

FULL NORMALIZATION CREDIT (MUST USE OPT. 3.5g) - 1.0 CREDITS

HIGH EFFICIENCY HVAC DISTRIBUTION - OPT. 4.2 - 1.0 CREDITS

HVAC EQUIPMENT AND ASSOCIATED DUCT SYSTEM(S) SHALL COMPLY WITH THE REQUIREMENTS OF SECT R403.3.1. LOCATING SYSTEM COMPONENTS IN CONDITIONED CRAWL SPACE IS NOT PERMITTED UNDER THIS OPTION. ELECTRIC RESISTANCE HEAT AND DUCTLESS HEAT PUMPS ARE NOT PERMITTED UNDER THIS OPTION. DIRECT COMBUSTION HEATING EQUIPMENT WITH AFUE LESS THAN 80% IS NOT PERMITTED UNDER THIS OPTION.

EFFICIENT WATER HEATING 5.5 - 2.0 CREDITS

WATER HEATING SYSTEMS SHALL INCLUDE ONE OF THE FOLLOWING: ELECTRIC HEAT PUMP WATER HEATER MEETING THE STANDARDS FOR TIER III OF NEEA'S ADVANCED WATER HEATING SPECIFICATION. IF ONE WATER HEATER IS SERVING MORE THAN ONE DWELLING UNIT, ALL OF WATER SUPPLY AND RECIRCULATION PIPING SHALL BE INSULATED WITH R-8 MINIMUM PIPE INSULATION.

EFFICIENT WATER HEATING 5.6 - 2.5 CREDITS

WATER HEATING SYSTEM SHALL INCLUDE ONE OF THE FOLLOWING: ELECTRIC HEAT PUMP WATER HEATER WITH A MIN. OF 2.8 AND UTILIZING A SPLIT SYSTEM CONFIGURATION WITH THE AIR-TO-REFRIGERANT HEAT EXCHANGER LOCATED OUTDOORS. EQUIPMENT SHALL MEET SECTION 4. REQUIREMENTS FOR ALL UNITS, OF THE NEEA STANDARD ADVANCED WATER HEATING SPECIFICATION WITH THE UEF NOTED ABOVE.

WHOLE HOUSE VENTILATION

PROVIDE WHOLE HOUSE VENTILATION per 2015 IRC, M507 and IMC R403.8 USING A MAKE UP AIR SYSTEM INTEGRATED INTO FORCED AIR SYSTEM (FAU) PROVIDE OUTDOOR FRESH AIR W/DUCTS CONNECTED TO THE RETURN SIDE OF THE AIR HANDLER.

SYMBOL	LOCATION	MIN. FAN REQUIREMENTS (ALL FANS VENT TO OUTSIDE)
A	BATH #1 POUDEY	Min. 50cfm. INTERMITTENT at .025mg per TABLE M507.4
B	KITCHEN	Min. 100cfm. INTERMITTENT at .025mg per TEL. M507.4
C	RANGE HOOD or DOWN DRAFT EXHAUST FAN RATED at min. 100cfm. at 0.10mg may be used FOR EXHAUST FAN REQUI. EXHAUST HOODS IN EXCESS OF 400cfm. SHALL BE INTERLOCKED AND PROVIDE MAKE UP AIR per W/M503.4	
D	LAUNDRY ROOM	Min. 420cfm. INTERMITTENT at .025mg to FUNCTION AS WHOLE HOUSE FAN (WHF)

MECHANICAL CONTRACTOR TO PROVIDE 420cfm WHF, FAN AND SET OPERATING TIMER per TABLE M507.3(1) FOR A 4501-6,000sf. DWELLING w/6-1 BEDRMS. TO OPERATE INTERMITTENTLY and CONTINUOUSLY per TABLE M507.3(2)

PROVIDE CONTROLS FOR WHF per M507.3.2 AFFIX LABEL TO CONTROLS THAT READS "WHOLE HOUSE VENTILATION - SEE OPERATING INSTRUCTIONS"

WHOLE HOUSE FAN RUN TIME PERCENTAGE IN EACH 4 HR. SEGMENT TO BE 25% WITH A FACTOR OF 4.

SQUARE FOOTAGE SUMMARY

MAIN FLOOR/ MAIN LIVING	1,700 S.F.
MAIN FLOOR A.D.U.	48 S.F.
GARAGE	448 S.F.
SUB TOTAL	2,246 S.F.
UPPER FLOOR/ MAIN LIVING	1,341 S.F.
UPPER FLOOR A.D.U.	492 S.F.
MINUS A.D.U. STAIRS	-42 S.F.
MINUS MAIN STAIRS	-56 S.F.
SUB TOTAL	1,741 S.F.
TOTAL G.F.A.	3,987 S.F.
ALLOWABLE F.A.R. 45%	4,050 S.F.
PROPOSED	44.3%
TOTAL NET AREA MAIN HOUSE	2,991 S.F.
GARAGE	448 S.F.
TOTAL NET A.D.U.	540 S.F.
SUB TOTAL	3,987 S.F.
COVID PATIO	259 S.F.
COVID PORCH	40 S.F.

OVERALL WIDTH 71'-11 1/2"
OVERALL DEPTH 44' - 1 1/2"

Updated - 03/04/2018

Method for Calculating Square Footage - ANSI Z765-2013 except, no separate distinction of above-grade or below-grade areas and each level is measured to the outside of studs not the exterior finished surface.

Square Footage calculations for this house were made based on plan dimensions only and may vary from the finished square footage of the house as built.

See Sheet "CODES" for additional Zoning required Area Calculations.



7525 SE 24th St., 487
Mercer Island, WA
98040
425.266.9100

Issue	Issue Date By
Issue <td>02.03.22</td>	02.03.22
Description <td>CITY PLAN REVIEW COMMENTS</td>	CITY PLAN REVIEW COMMENTS
Issue <td>04.05.22</td>	04.05.22
Description <td>CITY PLAN REVIEW COMMENTS</td>	CITY PLAN REVIEW COMMENTS

6515 SE 30th St.
Mercer Island, WA.
Job Number:
MIS072

plan name: -
marketing name: -
plan number: -
mark sys. number: -

Conditions not specifically represented graphically or in writing or which conflict with the current International Residential Code (IRC.) or those of the local municipality then the current standards and requirements of each respectively shall govern.

The drawings in this set are instruments of service and shall remain the property of JayMarc Homes, LLC.

© 2017 JayMarc Homes, LLC; All rights reserved.

04.15.21
Submittal Date

Sheet Title/Description


JAYMARC HOMES
Design Firm

R.R.
Drawn by:

R.R./S.K.
Checked by:

Primary Scale

A7
of .



UPPER FLOOR PLAN

1/4" = 1'-0"

Sheet Title/Description



7525 SE 24th St., 487
Mercer Island, WA
98040
425.266.9100

Issue	Issue Date	Description
△	02.03.22	CITY PLAN REVIEW COMMENTS
△	04.05.22	CITY PLAN REVIEW COMMENTS

6515 SE 30th St.
Mercer Island, WA
Job Number:
MIS072

plan name: -
marketing name: -
plan number: -
mark sys. number: -

Conditions not specifically represented graphically or in writing or which conflict with the current International Residential Code (IRC.) or those of the local municipality then the current standards and requirements of each respectively shall govern.

The drawings in this set are instruments of service and shall remain the property of JayMarc Homes, LLC.

© 2017 JayMarc Homes, LLC; All rights reserved.

04.15.21
Submittal Date

Sheet Title/Description
JAYMARC HOMES
Design Firm


R.R.
Drawn by:

R.R./S.K.
Checked by:



Primary Scale

A8
of .

ROOF VENTILATION		
Standard Truss / Scissor Truss Roof Framing Assembly:		ZONE 1
Roof Area :	1794 s.f.	
Ventilation Required:	1794 s.f. x 144 s.i. / s.f. / 300 =	861.12 s.i. Req'd
Provide between 40% & 50% of the total required ventilation no more than 3 ft below the ridge or the highest point of the space. Remainder to be installed at eave vents.		
Ridge Ventilation: 50% of ventilation		430.56
Continuous Ridge Vent =		18.00 s.i. per l.f.
Upper Ventilation MIN. Req'd =	430.56 s.i. x 0.4 / s.i. per linear foot =	20 l.f.
Upper Ventilation MAX. Req'd =	430.56 s.i. x 0.5 / s.i. per linear foot =	23 l.f.
Provide:	50 l.f. ridge vent. Ventilation =	900.00 s.i.
Ventilation area remainder for AF50 vents =	(469)	
Upper Roof Ventilation: as needed to achieve 50% of ventilation		
AF50 Roof Jack (10" x 7") =		50.00 s.i. each.
AF50 Ventilation Req'd TO GET 50%=	(469.44) s.i. / s.i. of each vent =	-10 vent
Provide:	0 -10"x7" roof jacks. Ventilation =	0.00 s.i.
Eave Ventilation:		
Birdblocking: (3/2" dia holes per bay =	4.71 s.i. / l.f. -25% reduction =	3.53 s.i. / l.f.
Eave Ventilation Req'd =	430.56 s.i. / s.i. per l.f. =	-469.44 l.f.
Provide Minimum:	133 l.f. birdblocking. Ventilation =	469.82 s.i.
Minimum Ventilation Provided =	1369.82 s.i. IS GREATER THAN :	861.12 s.i. Req'd



ROOF PLAN
1/4" = 1'-0"



Sheet Title/Description

Issue	Issue Date	By	Description
△	02.03.22		CITY PLAN REVIEW COMMENTS
△	04.05.22		CITY PLAN REVIEW COMMENTS

6515 SE 30th St.
Mercer Island, WA
Job Number: MIS072

plan name: -
marketing name: -
plan number: -
mark sys. number: -

Conditions not specifically represented graphically or in writing or which conflict with the current International Residential Code (IRC), or those of the local municipality then the current standards and requirements of each respectively shall govern.

The drawings in this set are instruments of service and shall remain the property of JayMarc Homes, LLC.

© 2017 JayMarc Homes, LLC; All rights reserved.

04.15.21
Submittal Date

Sheet Title/Description
JAYMARC HOMES
Design Firm

R.R.
Drawn by:

R.R./S.K.
Checked by:

Primary Scale

A9
of .

LEGEND


- ▨ INTERIOR BEARING WALL
- ▬ BEAM / HEADER
- ▬ ROOF TRUSS @ 24" O.C. (U.N.O.)
- ▬ GIRDER TRUSS
- ▬ INTERIOR SHEAR WALL PANEL OR EXTERIOR SHEAR WALL w/ 3" O.C. EDGE NAILING
- ▬ JL METAL HANGER
- ▨ INDICATES OVER FRAMED TRUSS AREA

REFER TO S-O FOR TYPICAL STRUCTURAL NOTES & SCHEDULES

4x10 HDR @ ALL EXT. [B1]
WINDOWS/DOORS (TYP. U.N.O.)

PROVIDE CONT. EXT. SHEATHING BEHIND LOW TRUSSES DOWN TO SECOND FLOOR SOLE PLATE (TYP. @ LOW ROOF)

NOTE #1:
PROVIDE 1/8" OSB/ PLYWOOD SHTG. & FASTEN PER TYP. WALL SHTG. SPEC. (SEE NOTES)



ROOF FRAMING PLAN

1/4" = 1'-0"

ROOF VENTILATION


Standard Truss / Scissor Truss Roof Framing Assembly:		ZONE 1
Roof Area:	1794 s.f.	
Ventilation Required:	1794 s.f. x 144 s.i. / s.f. / 300 =	861.12 s.i. Req'd
Provide between 40% & 50% of the total required ventilation no more than 3 ft below the ridge or the highest point of the space. Remainder to be installed at eave vents.		
Ridge Ventilation: 50% of ventilation		430.56
Continuous Ridge Vent =	18.00 s.i. per l.f.	
Upper Ventilation MIN. Req'd =	430.56 s.i. x 0.4 / s.i. per linear foot =	20 l.f.
Upper Ventilation MAX. Req'd =	430.56 s.i. x 0.5 / s.i. per linear foot =	23 l.f.
Provide:	50 l.f. ridge vent. Ventilation =	900.00 s.i.
Ventilation area remainder for AF50 vents =		(469)
Upper Roof Ventilation: as needed to achieve 50% of ventilation		
AF50 Roof Jack (10" x 7") =	50.00 s.i. each.	
Upper Ventilation Req'd TO GET 50% =	(469.44) s.i. / s.i. of each vent =	-10 vent
Provide:	0 -10"x7" roof jacks. Ventilation =	0.00 s.i.
Eave Ventilation:		
Birdblocking: (3/2" dia holes per bay =	4.71 s.i. / l.f. - 25% reduction =	3.53 s.i. / l.f.
Eave Ventilation Req'd =	430.56 s.i. / s.i. per l.f. =	-469.44 l.f.
Provide Minimum:	133 l.f. birdblocking. Ventilation =	469.82 s.i.
Minimum Ventilation Provided =	1369.82 s.i. IS GREATER THAN :	861.12 s.i. Req'd

Sheet Title/Description



NORTH / FRONT ELEVATION

1/4" = 1'-0"



EAST / LEFT ELEVATION

1/4" = 1'-0"

Issue	Issue Date	By	Description
△	02.03.22		CITY PLAN REVIEW COMMENTS
△	04.05.22		CITY PLAN REVIEW COMMENTS

6515 SE 30th St.
 Mercer Island, WA.
 Job Number:
MIS072

plan name: -
 marketing name: -
 plan number: -
 mark sys. number: -

Conditions not specifically represented graphically or in writing or which conflict with the current International Residential Code (IRC) or those of the local municipality then the current standards and requirements of each respectively shall govern.

The drawings in this set are instruments of service and shall remain the property of JayMarc Homes, LLC.

© 2017 JayMarc Homes, LLC. All rights reserved.

04.15.21
 Submittal Date

Sheet Title/Description
 JAYMARC HOMES
 Design Firm

R.R.
 Drawn by:
 R.R./S.K.
 Checked by:

Primary Scale

A10
 of: .

Sheet Title/Description

Issue	Issue Date	By	Description
△	02.03.22		CITY PLAN REVIEW COMMENTS
△	04.05.22		CITY PLAN REVIEW COMMENTS

6515 SE 30th St.
 Mercer Island, WA.
 Job Number:
MIS072

plan name:	-
marketing name:	-
plan number:	-
mark sys. number:	-

Conditions not specifically represented graphically or in writing or which conflict with the current International Residential Code (IRC), or those of the local municipality then the current standards and requirements of each respectively shall govern.

The drawings in this set are instruments of service and shall remain the property of JayMarc Homes, LLC.

© 2017 JayMarc Homes, LLC; All rights reserved.

04.15.21
 Submittal Date

Sheet Title/Description
 JAYMARC HOMES
 Design Firm

R.R.
 Drawn by:

R.R./S.K.
 Checked by:

Primary Scale

A11
 of .



SOUTH / REAR ELEVATION

1/4" = 1'-0"




WEST / RIGHT ELEVATION

1/4" = 1'-0"

Sheet Title/Description

NOTES:



A BUILDING SECTION
 1/4" = 1'-0"

JM
JAYMARC
 HOMES
 7525 SE 24th St., 487
 Mercer Island, WA
 98040
 425.266.9100

Issue Description	Issue Date	By
△ CITY PLAN REVIEW COMMENTS	02.03.22	
△ CITY PLAN REVIEW COMMENTS	04.05.22	

6515 SE 30th St.
 Mercer Island, WA.
 Job Number:
MIS072

plan name:	-
marketing name:	-
plan number:	-
mark sys. number:	-

Conditions not specifically represented graphically or in writing or which conflict with the current international Residential Code (IRC.) or those of the local municipality then the current standards and requirements of each respectively shall govern.

The drawings in this set are instruments of service and shall remain the property of JayMarc Homes, LLC.

© 2017 JayMarc Homes, LLC; All rights reserved.

04.15.21
 Submittal Date

Sheet Title/Description
 JAYMARC HOMES
 Design Firm


R.R.
 Drawn by:

R.R./S.K.
 Checked by:


Primary Scale

A12
 of .


Sheet Title/Description




1 TYPICAL SHEAR TRANSFER DETAIL @ ROOF
SCALE: 3/4"=1'-0" HEEL HEIGHT LESS THAN 4"




1A TYPICAL SHEAR TRANSFER DETAIL @ VAULTED CEILING
SCALE: 3/4"=1'-0"




2 TYPICAL GABLE END DETAIL
SCALE: 3/4"=1'-0"




3 TYPICAL SHEAR TRANSFER DETAIL BETWEEN FLOORS @ EXTERIOR WALL
SCALE: 3/4"=1'-0" PERPENDICULAR FRAMING




4 TYPICAL SHEAR TRANSFER DETAIL BETWEEN FLOORS @ EXTERIOR WALL
SCALE: 3/4"=1'-0" PARALLEL FRAMING




14 SHEAR TRANSFER DETAIL @ SHEAR WALL BELOW
SCALE: 3/4"=1'-0"




20 SHEAR TRANSFER DETAIL @ INT. SHEARWALL ABOVE
SCALE: 3/4"=1'-0"




31 SHEAR TRANSFER DETAIL BETWEEN FLOORS @ CANT'D EXT. WALL
SCALE: 3/4"=1'-0"




49 TYPICAL SHEAR TRANSFER DETAIL BETWEEN FLOORS
SCALE: 3/4"=1'-0" PERPENDICULAR FRAMING




54 SHEAR TRANSFER DETAIL AT INTERIOR SHEARWALL BELOW
SCALE: 3/4"=1'-0"



58 SHEAR TRANSFER DETAIL @ EXTERIOR SHEARWALL ABOVE
SCALE: 3/4"=1'-0"




59 SHEAR TRANSFER DETAIL @ EXTERIOR SHEARWALL ABOVE
SCALE: 3/4"=1'-0"



© copyright: MULHERN+KULP Structural Engineering, Inc.

MULHERN+KULP
RESIDENTIAL STRUCTURAL ENGINEERING
7720 Trade Street, Suite 350, San Diego, CA 92121
p 619-550-0010 > mulhernkulp.com



M&K project number:
154-21007


project mgr: RJJ
drawn by: RJD
issue date: 04-12-21

REVISIONS:
date: 02-03-22 initial: RJD
PLAN REVIEW COMMENTS/MARCH REVISIONS




STRUCTURAL DETAILS
6515 SE 30TH ST
MERCER ISLAND, WASHINGTON


sheet:
LB-1




81 TYPICAL SHEAR TRANSFER DETAIL BETWEEN FLOORS @ INTERIOR WALL
SCALE: 3/4"=1'-0" PERPENDICULAR FRAMING




85 SHEAR TRANSFER DETAIL @ EXTERIOR SHEARWALL ABOVE
SCALE: 3/4"=1'-0"




86 SHEAR TRANSFER DETAIL @ EXTERIOR SHEARWALL ABOVE
SCALE: 3/4"=1'-0"




92 EXT. WALL & INT. SHEARWALL OPENING ELEVATION
SCALE: NTS




93 EXT. WALL & INT. SHEARWALL OPENING ELEVATION
SCALE: NTS




94 EXT. WALL & INT. SHEARWALL OPENING ELEVATION
SCALE: NTS




95 SHEAR TRANSFER DETAIL @ INTERSECTING INT. SHEARWALL
SCALE: 3/4"=1'-0" SHTS. ON SAME FACE




99 SHEAR TRANSFER DETAIL @ INTERSECTING INT. SHEARWALL
SCALE: 3/4"=1'-0" SHTS. OPPOSITE FACES




117 STRAP DETAIL
SCALE: 3/4"=1'-0"




135 SHEAR TRANSFER DETAIL @ INTERIOR SHEARWALL ABOVE
SCALE: 3/4"=1'-0" PARALLEL FRAMING



136 SHEAR TRANSFER DETAIL @ SHEAR WALL BELOW
SCALE: 3/4"=1'-0"



140 SECTION
SCALE: 3/4"=1'-0"



MULHERN+KULP
RESIDENTIAL STRUCTURAL ENGINEERING
7720 Trade Street, Suite 350, San Diego, CA 92121
p 619-560-0010 > mulhernkulp.com

M&K project number: 154-21007








project mgr: RJJ
drawn by: RJD
issue date: 04-12-21

REVISIONS:

date:	initial:
02-03-22	RJD
PLAN REVIEW COMMENTS/MARCH REVISIONS	




STRUCTURAL DETAILS
6515 SE 30TH ST
MERCER ISLAND, WASHINGTON




A TYPICAL HOLD-DOWN INSTALLATION
NOT TO SCALE
SIMPSON STHD HD @ FOUNDATION

B TYPICAL HOLD-DOWN INSTALLATION
NOT TO SCALE
SIMPSON STHD HD @ FLOOR FRAMING



C TYPICAL HOLD-DOWN INSTALLATION
NOT TO SCALE
SIMPSON STRAP HD @ FLOOR FRAMING

1 APA PORTAL FRAME DETAIL WITH HOLD-DOWNS
SCALE: N.T.S.




MULHERN+KULP
RESIDENTIAL STRUCTURAL ENGINEERING
7220 Trade Street, Suite 350, San Diego, CA 92121
p 619-550-0010 > mulhernkulp.com

M&K project number:
154-21007
project mgr: RJJ
drawn by: RJD
issue date: 04-12-21
REVISIONS:
date: 02-03-22 initial: RJD
PLAN REVIEW COMMENTS/MARCH REVISIONS




STRUCTURAL DETAILS
6515 SE 30TH ST
MERCER ISLAND, WASHINGTON


sheet:
LB-3




1 TYPICAL CRAWLSPACE FOUNDATION
SCALE: 3/4"=1'-0"




2 TYPICAL CRAWLSPACE FOUNDATION @ PORCH SLAB
SCALE: 3/4"=1'-0"




3 TYPICAL FOOTING @ PORCH SLAB
SCALE: 3/4"=1'-0"




4 TYPICAL CRAWLSPACE FOUNDATION @ GARAGE
SCALE: 3/4"=1'-0"




5 TYPICAL CONCRETE FOOTING @ GARAGE DOOR OPENING
SCALE: 3/4"=1'-0"




6 TYPICAL EXT. GARAGE FOUNDATION
SCALE: 3/4"=1'-0"



7 TYPICAL CRAWL SPACE FOOTING DETAIL
SCALE: 3/4"=1'-0"



A TYPICAL STEPPED FOOTING
SCALE: 3/4"=1'-0"



MULHERN+KULP
RESIDENTIAL STRUCTURAL ENGINEERING
7220 Trade Street, Suite 350, San Diego, CA 92121
p 619-550-0010 • mulhernkulp.com

M&K project number:
154-21007
project mgr: RJJ
drawn by: RJD
issue date: 04-12-21
REVISIONS:
date: 02-03-22 initial: RJD
PLAN REVIEW COMMENTS/ARCH REVISIONS



STRUCTURAL DETAILS
6515 SE 30TH ST
MERCER ISLAND, WASHINGTON

sheet:
SD.01



Vertical wall Installation


Install TYPAR® HouseWrap over an approved exterior sheathing after the framing is complete and before the windows and doors have been installed. Plastic capped fasteners should be used and spaced at 32" OC (vertically and horizontally) when being applied over 7/16" OSB or 15/32" plywood. When installing over metal framing use screws with washers. If the windows and doors have already been installed, trim the TYPAR WRB close to the window frame and flash according to the TYPAR Flashing instructions.

STEP 1

Start at the bottom of one end of the wall with the printed side facing out. When starting at a corner, overlap by a minimum of 12".

Place the housewrap roll horizontally and roll out the first course evenly, covering rough window and door openings. A minimum of a 1" (25.4 mm) overlap on the sill plate is required; however, for maximum protection, a 2-4" (51-102 mm) overlap on the sill plate is recommended.

Pull the TYPAR snug and avoid wrinkles and creases. Ensure that the product is level.



STEP 2

Fasten the TYPAR to the stud using plastic capped nails or plastic capped staples at 32" O.C. both horizontally and vertically.



STEP 3

The upper layer of TYPAR housewrap should overlap the bottom layer by a minimum of 6" (152 mm) vertically and horizontally. Ensure proper shingling throughout the installation to properly shed water. Once the structure is completely covered, tape all seams and penetrations using TYPAR® construction tape. (Please refer to the TYPAR® flashing instructions for more detailed instruction on penetrations and window flashing installation).

STEP 4

After the installation complete and before the exterior cladding is installed, inspect the TYPAR® for tears. Repair the issues with TYPAR Construction tape or TYPAR Flashing.



Window and Door Preparation

Preparing for Window Installation

STEP 1

After wrapping the structure and covering all rough openings. Cut a horizontal line across the top of the window opening. The cut should not extend past the rough opening.

STEP 2

Start at the top center and make a vertical cut running two-thirds of the way down the opening.

STEP 3


From that stopping point, cut diagonally to both lower left and right corners of the opening.

STEP 4

Pull each of the flaps tightly inside the rough opening and attach them to the frame with nails, staples, or tape.

STEP 5

At the window header, make a 6" diagonal cut at a 45 degree angle on both corners. Fold the material up exposing the sheathing. Now install the window or door according to the manufacturer instructions. The final step is to flash all seams and flanges securely (refer to TYPAR® Flashing instructions). TYPAR® flashing should also be installed in accordance with window manufacturer instructions and according to the ASTM 2112 standard.



Typical Window Flashing

STEP 1

Install the window sill pan according to the manufacturer's instructions. Alternatively, you can create a sill pan using TYPAR Flashing Flex. Cut a piece that is 12" longer than the length of the rough opening window sill.

Carefully pull off the release liner. Center the Flashing in the center of the rough opening and work your way toward the corners and then up the sides. Note: the flex flashing should overlap to the outside of the wall by 2-3". Only stretch the flashing in the corners.

Alternatively to above, you can create a sill pan by installing TYPAR Straight Flashing along the bottom sill and installing TYPAR Flashing Flex on the corners only.

If needed, secure the fanned edges of the TYPAR Flashing Flex with a plastic capped nail/ plastic capped staple.

STEP 2

Apply a continuous bead of sealant to the back of the window or on the wall. Do not apply the sealant across the bottom of the sill or on the bottom of the window. This area is left open to allow for proper drainage.

Install the window according to the manufacturer's installation instructions.


STEP 3

Cut two pieces of TYPAR Flashing long enough to extend 1" above the window head flange and 1" below the window sill flange. Carefully peel off the release liner and apply the flashing on both sides of the window. Make sure to cover the entire window flange, press firmly either by hand or using a J-roller. Ensure there are no wrinkles or bubbles.

Cut a piece of TYPAR Flashing for the head flashing. Ensure that the piece is long enough to extend by 1" on both sides of the jamb flashing. Remove the release liner and carefully install the flashing. Cover the window flange and press firmly by hand or using a J-roller.

STEP 4

Release the upper flap of the WRB that you cut earlier. Tape the 45 degree cuts using TYPAR Construction Tape or TYPAR Flashing. DO NOT tape the WRB along the top of the window flange.



Flashing Penetrations

Penetrations such as exhaust fans, exterior electrical outlets, dryer vents, exterior lights, and gas outlets are a common entrance for bulk water into the wall cavity. Using TYPAR flashing will ensure proper water hold out and maintain the integrity of the structure.

The method is similar to the flashing a window. Start by flashing the bottom of the penetration. Ensure to shingle the upper tape over the bottom tape.

Some penetrations have flanges, such as dryer vents. These penetrations should be flashed according to the details below.


1)



STEP 1

Install the vent according to the manufacturer's recommendations. Trim the housewrap as close as possible around the perimeter of the vent.


2)



STEP 2

Flash the vent using the same method as windows. Starting at the bottom flange; cut the flashing so that it extends past the flanges by 1" on both sides. Now apply the flashing to the sides of the vent. Remember to extend the flashing 1" on both top and bottom. Make sure to smooth out wrinkles and air bubbles. The use of a J-roller is optional.

3)



STEP 3

The Final step is to install the flashing across the top. Extend the flashing out at least 1" on both sides.

Note:

This type of installation is suitable for several different penetrations. Always use the shingling method and ensure a tight seal around the flange/penetration.

TYPAR® HouseWrap is part of a complete Weather Protection System, which also includes TYPAR® Metro Wrap, TYPAR® Flashings and Construction tape

For more information, visit www.Typar.com



MADE IN USA. ICC #ESR-1404 • CCMC #12884-R • CCMC #12892-R
Please visit typar.com for installation instructions and warranty information



7525 SE 24th St., 487
Mercer Island, WA
98040
425.266.9100

Issue Description	Issue Date	By

Job Number:

plan name:	--
marketing name:	--
plan number:	--
mark sys. number:	--

Conditions not specifically represented graphically or in writing or which conflict with the current International Residential Code (IRC), or those of the local municipality then the current standards and requirements of each respectively shall govern.

The drawings in this set are instruments of service and shall remain the property of JayMarc Homes, LLC.

© 2017 JayMarc Homes, LLC; All rights reserved.

Submittal Date

Sheet Title/Description

Design Firm

Drawn by:

Checked by:


Primary Scale

D1 of .

Sheet Title/Description

EXISTING UTILITY LOCATIONS SHOWN HEREON ARE APPROXIMATE ONLY. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE EXACT VERTICAL AND HORIZONTAL LOCATION OF ALL EXISTING UNDERGROUND UTILITIES PRIOR TO COMMENCING CONSTRUCTION. NO REPRESENTATION IS MADE THAT ALL EXISTING UTILITIES ARE SHOWN HEREON. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR UTILITIES NOT SHOWN OR UTILITIES NOT SHOWN IN THEIR PROPER LOCATION.

CALL BEFORE YOU DIG: 811



STORM PIPE TABLE

1	22LF., 4" PVC SDR-35 @ S=2.00%
2	15LF., 4" PVC SDR-35 @ S=2.00%
3	17LF., 4" PVC SDR-35 @ S=2.00%
4	21LF., 4" PVC SDR-35 @ S=5.71%
5	100LF., 4" PVC SDR-35 @ S=3.20%
6	12LF., 4" PVC SDR-35 @ S=7.06%
7	6LF., 6" PVC SDR-35 @ S=25.00%
8	13LF., 4" PVC SDR-35 @ S=8.10%
9	14LF., 4" PVC SDR-35 @ S=8.10%
10	15LF., 4" PVC SDR-35 @ S=8.10%


DOWNSPOUT TABLE

DS#1	GROUND=104.70 DOWNSPOUT LINE=102.50
DS#2	GROUND=104.70 DOWNSPOUT LINE=102.95
DS#3	GROUND=104.70 DOWNSPOUT LINE=103.25
DS#4	GROUND=104.70 DOWNSPOUT LINE=103.60
DS#5	GROUND=105.00 DOWNSPOUT LINE=103.40
DS#6	GROUND=104.20 DOWNSPOUT LINE=102.20
DS#7	GROUND=102.00 DOWNSPOUT LINE=100.67
DS#8	GROUND=101.00 DOWNSPOUT LINE=99.10
DS#9	GROUND=102.25 DOWNSPOUT LINE=100.15
DS#10	GROUND=103.50 DOWNSPOUT LINE=101.30


STORM PIPE PVC SHALL BE SDR-35 PVC AT SLOPE=2.00% MINIMUM (TYPICAL) UNLESS OTHERWISE NOTED

IMPERVIOUS SURFACES:
ROOF AREA W/EAVES = 2,675 SQ. FEET
UNCOVERED DRIVEWAY = 399 SQ. FEET
UNCOVERED DECK = 8 SQ. FEET
UNCOVERED STAIRS & LANDING = 51 SQ. FEET
UNCOVERED WALKWAY = 91 SQ. FEET
TOTAL IMPERVIOUS AREAS = 3,224 SQ. FEET

LANDSCAPE AREAS NOTE:
DISTURBED LANDSCAPE AREAS SHALL BE TREATED AS AMENDED SOILS PER DOE FIGURE V-5.3.3, TYPICAL






NOTE
A 4" FOOTING DRAIN CONNECTION



PROJECT	6515 SE 30th Street	CLIENT	JayMarc Emerald, LLC	SHEET CONTENT	Utility & Tree Plan
DATE	01/28/2022	JOB NO.		DWG NO.	1 OF 2
DESIGNED BY	DLO	DRAWN BY	VS	CHECKED BY	DLO
DESIGNED BY	DLO	DRAWN BY	VS	CHECKED BY	DLO
DATE	01/28/2022	REV. NO.		DATE	
DESCRIPTION					


pH TO BE BETW
6-10
ORGANIC MATTER
TO BE GREATER

Figure V-5.3.3 Planting bed Cross-Section




PROJECT: 6515 SE 30th Street
CLIENT: JayMarc Emerald, LLC
SHEET CONTENT: Storm Water Details

DATE: 01/28/2022
JOB NO.:
DWG NO.:
SHEET 2 OF 2



DESIGNED BY: DLO
DRAWN BY: VS
CHECKED BY: DLO



OFFE ENGINEERS
13902 SOUTHEAST 159TH PLACE
RENTON, WASHINGTON 98058
PHONE: 425-260-3412
CONTACT: DARRELL OFFE, P.E.

REV. NO.	DATE	DESCRIPTION
01/28/2022		

TOPOGRAPHIC & BOUNDARY SURVEY

LEGAL DESCRIPTION

(PER QUIT CLAIM DEED RECORDING #20010815001315)

LOTS 31, 32 AND 33, BLOCK 5, EAST SEATTLE ACCORDING TO THE PLAT THEREOF, RECORDED IN VOLUME 3 OF PLATS, PAGE 22, IN KING COUNTY, WASHINGTON.

BASIS OF BEARINGS

HELD A BEARING OF N 89°51'12" E BETWEEN FOUND MONUMENTS ON CENTERLINE OF SE 32ND ST PER R1

REFERENCES

R1. RECORD OF SURVEY, VOL. 244, PG. 067, RECORDS OF KING COUNTY, WASHINGTON.

VERTICAL DATUM

NAVD88 PER GPS OBSERVATIONS.

SURVEYOR'S NOTES

1. THE TOPOGRAPHIC SURVEY SHOWN HEREON WAS PERFORMED IN DECEMBER OF 2020. THE FIELD DATA WAS COLLECTED AND RECORDED ON MAGNETIC MEDIA THROUGH AN ELECTRONIC THEODOLITE. THE DATA FILE IS ARCHIVED ON DISC OR CD. WRITTEN FIELD NOTES MAY NOT EXIST. CONTOURS ARE SHOWN FOR CONVENIENCE ONLY. DESIGN SHOULD RELY ON SPOT ELEVATIONS.
2. ALL MONUMENTS SHOWN HEREON WERE LOCATED DURING THE COURSE OF THIS SURVEY UNLESS OTHERWISE NOTED.
3. THE TYPES AND LOCATIONS OF ANY UTILITIES SHOWN ON THIS DRAWING ARE BASED ON INFORMATION PROVIDED TO US, BY OTHERS OR GENERAL INFORMATION READILY AVAILABLE IN THE PUBLIC DOMAIN INCLUDING, AS APPLICABLE, IDENTIFYING MARKINGS PLACED BY UTILITY LOCATE SERVICES AND OBSERVED BY TERRANE IN THE FIELD. AS SUCH, THE UTILITY INFORMATION SHOWN ON THESE DRAWINGS ARE FOR INFORMATIONAL PURPOSES ONLY AND SHOULD NOT BE RELIED ON FOR DESIGN OR CONSTRUCTION PURPOSES; TERRANE IS NOT RESPONSIBLE OR LIABLE FOR THE ACCURACY OR COMPLETENESS OF THIS UTILITY INFORMATION. FOR THE ACCURATE LOCATION AND TYPE OF UTILITIES NECESSARY FOR DESIGN AND CONSTRUCTION, PLEASE CONTACT THE SITE OWNER AND THE LOCAL UTILITY LOCATE SERVICE (800-424-5555).
4. SUBJECT PROPERTY TAX PARCEL NO. 2174500800.
5. SUBJECT PROPERTY AREA PER THIS SURVEY IS 9,000± S.F. (0.21 ACRES)
6. THIS SURVEY WAS PERFORMED WITHOUT THE BENEFIT OF A TITLE REPORT. EASEMENTS AND OTHER ENCUMBRANCES MAY EXIST THAT ARE NOT SHOWN HEREON.
7. FIELD DATA FOR THIS SURVEY WAS OBTAINED BY DIRECT FIELD MEASUREMENTS WITH A CALIBRATED ELECTRONIC 5-SECOND TOTAL STATION AND/OR SURVEY GRADE GPS OBSERVATIONS. ALL ANGULAR AND LINEAR RELATIONSHIPS ARE ACCURATE AND MEET THE STANDARDS SET BY WAC 332-130-090.

LEGEND

	ASPHALT SURFACE		OIL FILL CAP
	BUILDING		PAVER SURFACE
	CENTERLINE ROW		POST
	CULVERT PIPE		POWER METER
	CONCRETE SURFACE		POWER (OVERHEAD)
	RETAINING WALL		POWER POLE
	DITCH (FLOWLINE)		REBAR AS NOTED (FOUND)
	FENCE LINE (CHAIN LINK)		REBAR & CAP (SET)
	FENCE LINE (WOOD)		ROCKERY
	FIRE HYDRANT		SEWER LINE
	FLAGSTONE SURFACE		SEWER MANHOLE
	GAS LINE		SIGN (AS NOTED)
	GAS VALVE		STORM DRAIN LINE
	GRAVEL SURFACE		TREE (AS NOTED)
	HEDGE FOLIAGE LINE		WATER LINE
	INLET (TYPE 1)		WATER METER
	NAIL AS NOTED		WATER VALVE
	MAILBOX (RESIDENTIAL)		

VICINITY MAP

