

Simple Heating System Size: Washington State

This heating system sizing calculator is based on the Prescriptive Requirements of the 2018 Washington State Energy Code (WSEC) and ACCA Manuals J and S. This tool will calculate heating loads only. ACCA procedures for sizing cooling systems should be used to determine cooling loads.

Please complete the green drop-downs and boxes that are applicable to your project. As you make selections in the drop-downs for each section, some values will be calculated for you. If you do not see the selection you need in the drop-down options, please contact the WSU Energy Program at energycode@energy.wsu.edu or (360) 956-2042 for assistance.

Project Information

Pierce Residence
5635 84th Ave SE
Mercer Island, WA 98040

Contact Information

Brad Sturman
Sturman Architects
9 103rd Ave NE Suite 203, Bellevue, WA 98004

Heating System Type: All Other Systems Heat Pump

To see detailed instructions for each section, place your cursor on the word "Instructions"

Design Temperature

[Instructions](#)

Bellevue

Design Temperature Difference (ΔT) 46
 $\Delta T = \text{Indoor (70 degrees)} - \text{Outdoor Design Temp}$

Area of Building

Conditioned Floor Area

[Instructions](#)

Conditioned Floor Area (sq ft)

163

Average Ceiling Height

[Instructions](#)

Average Ceiling Height (ft)

7.7

Conditioned Volume
1,255

Glazing and Doors

[Instructions](#)

U-0.28

U-Factor X Area = UA
0.280 X 110 = 30.77

Skylights

[Instructions](#)

U-0.50

U-Factor X Area = UA
0.50 X 18 = 8.75

Insulation

Attic

[Instructions](#)

R-49

U-Factor X Area = UA
0.026 X [] = []

Single Rafter or Joist Vaulted Ceilings

[Instructions](#)

No Vaulted Ceilings in this project.

U-Factor X Area = UA
--- X [] = []

Above Grade Walls (see Figure 1)

[Instructions](#)

R-21 Intermediate

U-Factor X Area = UA
0.056 X [] = []

Floors

[Instructions](#)

R-38

U-Factor X Area = UA
0.025 X 163 = 4.08

Below Grade Walls (see Figure 1)

[Instructions](#)

No Below Grade Walls in this project.

U-Factor X Area = UA
0.028 X [] = []

Slab Below Grade (see Figure 1)

[Instructions](#)

No Slab Below Grade in this project.

F-Factor X Length = UA
0.303 X [] = []

Slab on Grade (see Figure 1)

[Instructions](#)

No Slab on Grade in this project.


F-Factor X Length = UA
--- X [] = []

Location of Ducts

[Instructions](#)

Unconditioned Space

Duct Leakage Coefficient
1.10



Sum of UA	43.60
Envelope Heat Load	2,005 Btu / Hour
<i>Sum of UA x ΔT</i>	
Air Leakage Heat Load	624 Btu / Hour
<i>Volume x 0.6 x ΔT x 0.018</i>	
Building Design Heat Load	2,629 Btu / Hour
<i>Air leakage + envelope heat loss</i>	
Building and Duct Heat Load	2,892 Btu / Hour
<i>Ducts in unconditioned space: sum of building heat loss x 1.10</i>	
<i>Ducts in conditioned space: sum of building heat loss x 1</i>	
Maximum Heat Equipment Output	3,615 Btu / Hour
<i>Building and duct heat loss x 1.40 for forced air furnace</i>	
<i>Building and duct heat loss x 1.25 for heat pump</i>	