

Phone 425-351-5999 Kiaeng.ali@gmail.com

EDWARD & CATHERINE MORAN RESIDENCE SITE SHORING

5000 WEST MERCER WAY MERCER ISLAND, WASHINGTON 98040

STRUCTURAL CALCULATIONS

NOVEMBER 30, 2021 JOB NO: 171-2101



SOIL DATA:

Active Pressure = 40 pcf
Passive Pressure = 200 pcf
Passive Pressure to Neglect = 24"

Seismic Loading = 8H

Max HT. = 10.5 FT Pile Spacing = 8'-0" o.c. Max Pile Diameter = 30"

Steel Fy = 50 ksi

SEISMIC:

Zip Code: 98040

Ss = 1.439 S1 = 0.552

Fa = 1.00Fv = 1.50

Sds = 0.959Sd1 = 0.552

Above values per Soil's Report by: Nelson Geotech. Associates, Inc., File No. 1211520, November 20, 2020.

Conc. F'c = 1,000 psiRebar Fy = 60,000 psi

Soil Bearing = 1500 psf (Per Soil's Report)

Project Name/Number: ali reza

Title ...New... Dsgnr: Ali Reza Description....

Page: 1 Date: 17 AUG 2021

This Wall in File: d:\users\ross baharmast-drive d\documents-d\retainpro 10 project files\ali reza.R

RetainPro (c) 1987-2019, Build 11.19.11.12 License : KW-06062136 License To : RB Engineers


Soldier Pile Retaining Wall

Code: IBC 2018,AISC 360-16

Design Parameters

Wall height (retained height)	6.50	ft
Backfill slope	0.00	deg
Soil Density	125.00	pcf
Soil Phi angle		deg

Soil Phi angle	deg
and the same of th	ueg
Surcharge top of soil @ retained	52 psf
Allow. Passive	200 psf / ft
Apply S.F. to Passive	1.0
Pile Spacing	8.0 ft
Diameter of encasement	5.50 in
Multiplier to Passive Wedge	2.0
Required Embedment	12.15 ft
Total Pile Embedment	13.00 ft
Soldier Beam Selection	W16x26
Lagging Depth	0.00 ft
Lagging Selection	PT4x8
Steel Design Method	ASD
Lateral Presure Method	EPF
Passive Pressure to Neglect	24.00 in
	0
Tieback Location	None
Steel Fy	50 ksi
Consider pile unbraced for lateral to	orsional buckling
	and the second of an artist and the second of the second of



Design Results

Required embedment

12.15 ft 12.15ft = 10.15 + 2 ft neglecte

Ma

Va

Embedment Used

Deflection at top of pile

0.04 in

Pile Pw

2,704 Flange W

Pile Total Lateral

9,464 lb

Status Checks			Ratio	Status	
10,969 ft-lbs	Mn/Omega	95,116 ft-lbs	0.43	OK	

Mmax in Pile (Service)

Depth to Max M

2.79 ft 40,969 ft-lbs

9,464 lb Embedment Required Vn/Omega

0.13 OK

Vmax in Pile (Service)

9,464 lb

70,509 lb

8-1/17

Project Name/Number : ali reza

Title ...New... Dsgnr: Ali Reza Description....

Page: 2 Date: 17 AUG 2021


This Wall in File: d:\users\ross baharmast-drive d\documents-d\retainpro 10 project files\ali reza.R

RetainPro (c) 1987-2019, Build 11.19.11.12 License : KW-06062136 License To : RB Engineers

Soldier Pile Retaining Wall

Code: IBC 2018,AISC 360-16

Construction Diagram



8-2/17

Title ...New... Dsgnr: Ali Reza Description....

Page: 3 Date: 17 AUG 2021


This Wall in File: d:\users\ross baharmast-drive d\documents-d\retainpro 10 project files\ali reza.R

RetainPro (c) 1987-2019, Build 11.19.11.12 License : KW-06062136 License To : RB Engineers

Soldier Pile Retaining Wall

Code: IBC 2018,AISC 360-16

Wall Loading Diagram



P-3/17

Pile Section		W16x26	and the confidence of the statement of the
Pile Spacing	- Land control of the	8.00 - 1 ft	
Pile is encased in concrete	Examination	Yes 🔻	
Diameter of encasement		30.00 - in	
Multiplier to Passive Wedge (Arching Fac	ctor)	2.00	
Total Pile Embedment		13.00 - A ft	
Pile Yield Stress, Fy	_	50 v ksi	
Unbraced Length for Soldier Pile		aling an application and appropriate an appropriate to the control of the control	
Consider pile unbraced for late			
O Consider pile fully-braced for I	lateral torsional buckling	kitalijatikitaniini densitäitimmeeden dee vermaline see	
☑ Use Lagging (Used to	o calculate design press	sure on lagging at specified de	pth.)
Lagging Depth	0.00	ft	
Lagging Pressure @ Depth	16.6	psf	
**Lagging Mom. @ Depth	106	ft-lbs	
Lagging Shear @ Depth	67	lbs/vert. ft	
Lagging Section:	PT4x8		
	THE RESIDENCE OF THE PROPERTY OF THE PARTY O	MAPS OF CONTRACTOR OF STANDARD CONTRACTOR OF	and the second s

8-4/17

^{**}Moment is 0.8 * WL^2/8 where the factor 0.8 accounts for arching action in the soil.

Project Name/Number: ali reza

Title ...New...
Dsgnr: Project Designer...

Description....

Page: 1 Date: 17 AUG 2021

This Wall in File: d:\users\ross baharmast-drive d\documents-d\retainpro 10 project files\ali reza.R

RetainPro (c) 1987-2019, Build 11.19.11.12 License : KW-06062136 License To : RB Engineers


Soldier Pile Retaining Wall

Code: IBC 2018,AISC 360-16

Design Parameters

Wall height (retained height)	8.50	ft
Backfill slope	0.00	deg
Soil Density	125.00	pcf
Soil Phi angle		deg

Surcharge top of soil @ retained	68 psf
Allow. Passive	200 psf / ft
Apply S.F. to Passive	1.0
Pile Spacing	8.0 ft
Diameter of encasement	5.53 in
Multiplier to Passive Wedge	2.0
Required Embedment	15.94 ft
Total Pile Embedment	16.00 ft
Soldier Beam Selection	W16x31
Lagging Depth	8.50 ft
Lagging Selection	PT 4x8
Steel Design Method	ASD
Lateral Presure Method	EPF
Passive Pressure to Neglect	24.00 in
	0
Tieback Location	None
Steel Fy	50 ksi
Consider pile unbraced for lateral t	orsional buckling
Design Results	rappanya at are reministrations



15.94 ft 15.94ft = 13.94 + 2 ft neglecte

Required embedment **Embedment Used**

ft

Deflection at top of pile

0.13 in

P	il	e	P	W

4,624 Flange W

Pile Total Lateral	16,184 lb	1	Status Ch	ecks	and the second s	Ratio	Status
		Ma	95,783 ft-lbs	Mn/Omega	105,215 ft-lbs	0.91	
Depth to Max M	4.03 ft	Va	16,184 lb	Vn/Omega	87,450 lb	0.19	OK
Mmax in Pile (Service)	95,783 ft-lbs	Embed	dment Required				OK
Vmax in Pile (Service)	16,184 lb						

Project Name/Number: ali reza

Title ...New...

Dsgnr: Project Designer...
Description....

Page: 2 Date: 17 AUG 2021


This Wall in File: d:\users\ross baharmast-drive d\documents-d\retainpro 10 project files\ali reza.R

RetainPro (c) 1987-2019, Build 11.19.11.12 License : KW-06062136 License To : RB Engineers

Soldier Pile Retaining Wall

Code: IBC 2018,AISC 360-16

Construction Diagram



P-6/1

...New...

Dsgnr: Project Designer...

Description....

Page: 3 Date: 17 AUG 2021


This Wall in File: d:\users\ross baharmast-drive d\documents-d\retainpro 10 project files\ali reza.R

RetainPro (c) 1987-2019, Build 11.19.11.12 License : KW-06062136 License To : RB Engineers

Soldier Pile Retaining Wall

Code: IBC 2018,AISC 360-16

Wall Loading Diagram



Minimum Required Embedment Depth

Pile Section		W16x31	
Pile Spacing		8.00 - 1 ft	
Pile is encased in concrete	Statements	Yes 💌	
Diameter of encasement	ra-	30.00 - in	
Multiplier to Passive Wedge (Arching Fac	ctor)	2.00 -	
Total Pile Embedment		16.00 - ft	
Pile Yield Stress, Fy	The control of the co	50 🗸 ksi	
Unbraced Length for Soldier Pile		ragginasing spilipera gagagani yanamil o nalipera an anasan asla abelia manamilihasanahilia a	
 Consider pile unbraced for late 	eral torsional buckling		
O Consider pile fully-braced for la	ateral torsional buckling	ng	
☑ Use Lagging (Used to	calculate design pres	ssure on lagging at specified depth.)	
Lagging Depth	8.50	ft	
Lagging Pressure @ Depth	361.8	B psf	
**Lagging Mom. @ Depth	2,315	5 ft-lbs	
Lagging Shear @ Depth	1,447	7 lbs/vert. ft	
Lagging Section:	PT 4x8		

8-8/17

^{**}Moment is 0.8 * WL^2/8 where the factor 0.8 accounts for arching action in the soil.

Project Name/Number : ali reza

Title ...New... Dsgnr: Ali Reza Kia

Description....

Page: 1 Date: 17 AUG 2021

This Wall in File: d:\users\ross baharmast-drive d\documents-d\retainpro 10 project files\ali reza.R

RetainPro (c) 1987-2019, Build 11.19.11.12 License : KW-06062136 License To : RB Engineers


Soldier Pile Retaining Wall

Code: IBC 2018,AISC 360-16

Design Parameters

Wall height (retained height)	10.50	ft
Backfill slope	0.00	deg
Soil Density	125.00	pcf
Soil Phi angle		deg

Soil Phi angle	deg
Surcharge top of soil @ retained	84 psf
Allow. Passive	200 psf / ft
Apply S.F. to Passive	1.0
Pile Spacing	8.0 ft
Diameter of encasement	7.07 in
Multiplier to Passive Wedge	2.0
Required Embedment	19.77 ft
Total Pile Embedment	20.00 ft
Soldier Beam Selection	W16x50
Lagging Depth	10.50 ft
Lagging Selection	PT 4x8
Steel Design Method	ASD
Lateral Presure Method	EPF
Passive Pressure to Neglect	24.00 in
	0
Tieback Location	None
Steel Fy	50 ksi
Consider pile unbraced for lateral	torsional buckling
And the state of the second	and the second s



Design Results

Required embedment

19.77 ft 19.77ft = 17.77 + 2 ft neglecte

Ma

Va

Embedment Used

ft

Deflection at top of pile

0.22 in

Pi	le	P	W
----	----	---	---

7,056 Flange W

Pile Total Lateral

24,696 lb

Status Checks			Ratio	Status	
185,978 ft-lbs	Mn/Omega	192,454 ft-lbs	0.97	OK	

Depth to Max M Mmax in Pile (Service)

5.31 ft 185,978 ft-lbs

24,696 lb Embedment Required . Vn/Omega

0.20 OK

Vmax in Pile (Service)

24,696 lb

123,880 lb

Project Name/Number : alí reza

Title ...New...
Dsgnr: Ali Reza Kia Description....

Page: 2 Date: 17 AUG 2021


This Wall in File: d:\users\ross baharmast-drive d\documents-d\retainpro 10 project files\ali reza.R

RetainPro (c) 1987-2019, Build 11.19.11.12 License : KW-06062136 License To : RB Engineers

Soldier Pile Retaining Wall

Code: IBC 2018,AISC 360-16

Construction Diagram



Title ...New...
Dsgnr: Ali Reza Kia Description....

Page: 3 Date: 17 AUG 2021


This Wall in File: d:\users\ross baharmast-drive d\documents-d\retainpro 10 project files\ali reza.R

RetainPro (c) 1987-2019, Build 11.19.11.12 License : KW-06062136 License To : RB Engineers

Soldier Pile Retaining Wall

Code: IBC 2018,AISC 360-16

Wall Loading Diagram




Minimum Required Embedment Depth

8-11/1

Pile Section	W16x50
Pile Spacing	8.00 - T
Pile is encased in concrete	Yes V
Diameter of encasement	30.00 - in
Multiplier to Passive Wedge (Arching Fac	ctor) 2.00
Total Pile Embedment	20.00 - ft
Pile Yield Stress, Fy	50 v ksi
Unbraced Length for Soldier Pile	
Consider pile unbraced for late Consider pile fully-braced for late	
☑ Use Lagging (Used to	calculate design pressure on lagging at specified depth.)
Lagging Depth	10.50 ft
Lagging Pressure @ Depth	446.9 psf
**Lagging Mom. @ Depth	2,860 ft-lbs
Lagging Shear @ Depth	1,788 lbs/vert. ft
Lagging Section:	PT 4x8

12-13/1

^{**}Moment is 0.8 * WL^2/8 where the factor 0.8 accounts for arching action in the soil.



Project Name/Number : ali reza

Title Moran Res. Dsgnr: Ali Reza Kia Description....

Page: 1 Date: 17 AUG 2021

This Wall in File: d:\users\ross baharmast-drive d\documents-d\retainpro 10 project files\all reza.r

RetainPro (c) 1987-2019, Build 11.19.11.12 License : KW-06062136 License To : RB Engineers


Soldier Pile Retaining Wall

Code: IBC 2018,AISC 360-16

Design Parameters

Wall height (retained height)	12.00	ft
Backfill slope	0.00	deg
Soil Density	125.00	pcf
Soil Phi angle		deg

Surcharge top of soil @ retained	235 psf			
Allow. Passive	200 psf / ft			
Apply S.F. to Passive	1.0			
Pile Spacing	8.0 ft			
Diameter of encasement	10.40 in			
Multiplier to Passive Wedge	2.0			
Required Embedment	26.65 ft			
Total Pile Embedment	27.00 ft			
Soldier Beam Selection	W16x100			
Lagging Depth	12.00 ft			
Lagging Selection	PT 6x8			
Steel Design Method	ASD			
Lateral Presure Method	EPF			
Passive Pressure to Neglect	24.00 in			
	0			
Tieback Location	None			
Steel Fy	50 ksi			
Consider pile unbraced for lateral torsional buckling				



Design Results

Required embedment

26.65 ft 26.65ft = 24.65 + 2 ft neglecte

Ma

Va

Embedment Used Deflection at top of pile

0.30 in

Pile Pw

Depth to Max M

Mmax in Pile (Service)

22,560 Flange W

7.76 ft

463,592 ft-lbs

Pile Total Lateral 45,600 lb

Status Checks Ratio Status Mn/Omega 463,592 ft-lbs 469,236 ft-lbs 0.99 OK 45,600 lb Vn/Omega 198,900 lb 0.23 OK

Vmax in Pile (Service) 45,600 lb

P-14/17

Project Name/Number : ali reza

Title Moran Res. Dsgnr: Ali Reza Kia Description....

Page: 2 Date: 17 AUG 2021


This Wall in File: d:\users\ross baharmast-drive d\documents-d\retainpro 10 project files\ali reza.r

RetainPro (c) 1987-2019, Build 11.19.11.12 License : KW-06062136 License To : RB Engineers

Soldier Pile Retaining Wall

Code: IBC 2018,AISC 360-16

Construction Diagram



8-15/17

Title Moran Res. Dsgnr: Ali Reza Kia Description....

Page: 3 Date: 17 AUG 2021


This Wall in File: d:\users\ross baharmast-drive d\documents-d\retainpro 10 project files\ali reza.r

RetainPro (c) 1987-2019, Build 11.19.11.12 License : KW-06062136 License To : RB Engineers

Soldier Pile Retaining Wall

Code: IBC 2018,AISC 360-16

Wall Loading Diagram



Minimum Required Embedment Depth

P-16/7

Title Moran Res. Dsgnr: Ali Reza Kia Description....


Page: 1 Date: 17 AUG 2021

This Wall in File: d:\users\ross baharmast-drive d\documents-d\retainpro 10 project files\all reza.r

RetainPro (c) 1987-2019, Build 11.19.11.12 License : KW-06062136 License To : RB Engineers

Soldier Pile Retaining Wall

Code: IBC 2018,AISC 360-16



8-17/1

APPENDIX

A-1/T



17311-135th Ave. N.E. Suite A-500 Woodinville, WA 98072 (425) 486-1669 www.nelsongeotech.com

MEMORANDUM

DATE:

August 6, 2021

TO:

Bill Gottlieb

wmgottlieb@planone.biz

Edward Moran

Edmoran82@gmail.com

Catherine Moran

Catherine.b.moran@gmail.com

FROM:


Khaled M. Shawish, PE

Katelyn S. Brower, GIT

RE:

Plan Review Memorandum 5000 West Mercer Way Mercer Island, Washington

NGA File No. 1211520



This memorandum presents our supplemental geotechnical recommendations and opinions regarding the proposed Moran Residence development project located at 5000 West Mercer Way in Mercer Island, Washington.

INTRODUCTION

We previously prepared a geotechnical report titled "Geotechnical Engineering Evaluation – Moran Residence Development – 5000 West Mercer Way – Mercer Island," dated November 20, 2020. The site is located within a mapped ancient slide area, but the core of the site slopes are interpreted to consist of native, competent soils. The plans include the construction of a single family residence in close proximity of the base of the site slopes. Within the report, we provided recommendations for the incorporation of a residence debris retaining wall or separate catchment wall to safeguard the residence from possible upslope soil and debris. We have since reviewed preliminary grading plans, where the residence and driveway are planned to be located within 5 to 10-feet from the planned retaining wall. We discussed options for the wall with you, and determined the most feasible approach would be a soldier pile wall. Based on anticipated loads and the final height of the wall, tiebacks may be required for lateral support. In the following sections, we review the plans for the wall alignment and provide recommendations for a soldier pile wall design and construction.

NGA File No. 1211520 August 6, 2021 Page 2

We were provided with a site plan titled "Site & Grading Plan," prepared by Justin Jones, PE, and dated April 22, 2021.

PLAN REVIEW

The proposed residence will be located within the west-central portion of the site and is planned to cover approximately 2,300 square feet. Associated driveways and attached garage will be located on the northern portion of the site. The wall alignment is planned to span the base of the slope along the length of the planned residence, located approximately 5-10 feet from the structure and driveway, depending on specific locations. The wall will continue and wrap around to the north side of the driveway, and around to the southeast portion of the residence to protect the proposed structures from potential soil movement. In general, the plans appear to reflect our general recommendations, as long as foundation support and retaining wall recommendations within the previous report and this memorandum are followed during construction.

RECOMMENDATIONS

Soldier Pile Wall

General: A solider pile shoring wall could be utilized to support cut excavations around the proposed structures. A soldier pile wall typically consists of a series of steel H-beams placed vertically at a certain spacing from one another (typically six to ten feet). The beams are usually placed in drilled shafts that are filled with a structural concrete or a lean mix. The concrete shafts are typically embedded below the bottom of the planned excavation a distance equal to one to two times the exposed height of the wall. The steel beams are extended above finished ground surface to provide shoring capabilities for the area to be retained. The beams are typically spanned by pressure treated timber lagging or concrete panels. The H-beam size, shaft diameter, shaft embedment, and pile spacing are dependent on the nature of the soils anticipated to be retained by the wall and the soils at depth, wall height, drainage conditions, and the final geometry.

Wall Design: The wall should be designed by an experienced structural engineer licensed in the State of Washington. The lateral earth pressure acting on the shoring wall will be dependent on the nature and density of the soil behind the wall, structure and traffic loads on the wall, and the amount of lateral wall movement that may occur as material is excavated from the front of the wall. If the shoring wall is free to yield at least one-thousandth of the retained height, an "active" loading condition develops. If the wall is restrained from movement by stiffness or bracing, the wall is considered in an "at-rest" loading condition. Active and at-rest earth pressure can be calculated based on equivalent fluid densities.

A-3/7

NGA File No. 1211520 August 6, 2021 Page 3

The shoring wall should be designed to resist a lateral load resulting from a fluid with a unit weight of 40 and 60 pounds per cubic foot (pcf) for the active and at-rest loading conditions, respectively. An additional uniform surcharge of 8H should be applied to the wall design to account for seismic loading, if the shoring walls are intended to provide permanent support; H in this case is the exposed height of the wall. These loads should be applied across the pile spacing above the excavation line. These loads can be resisted by a passive pressure of 200 pcf on the below grade medium dense or better native glacial soils encountered at depth. The passive pressure should be applied on two-pile diameters under the excavation line. These values of the passive pressure incorporate a factor of safety of 2.0. The upper two feet of pile embedment should be neglected when calculating the passive resistance for the permanent condition. Also, for the permanent condition, the below-grade portion of the wall should be no less than 1.5 times the wall stick-up height (exposed height).

The above loads should be applied on the full center-to-center pile spacing above the base of the exposed portion of the wall. A 50 percent reduction of the active pressure could be applied for the purpose of designing the wall lagging.

The above pressures assume that the on-site soils retained by the shoring wall are not significantly disturbed and that hydrostatic forces are not allowed to build up behind the wall. These values do not include the effects of surcharges other than what is described above. The retained soils should be readily drained and collected water should be routed into a permanent storm system. Adequate gaps should be maintained between the lagging elements to allow for any potential water seepage buildup to flow through the wall.

The wall designer should calculate the predicted wall deflection, including deflection resulting from the below-grade movement of the piles. The predicted deflection values should be confirmed in the field through a survey monitoring program. Also, surrounding structures should be monitored for any adverse effects resulting from shoring wall installation.

Tieback Anchors

General: If tiebacks are needed to support lateral loads, we recommend that these systems consist of drilled, grouted tieback anchors. If tiebacks are utilized to support lateral loads for the shoring wall, we anticipate these systems may extend into neighboring properties and easements. Permission to extend these systems onto the neighboring properties and/or easements should be obtained prior to finalizing plans utilizing tieback anchors. All nearby existing utilities and structures should also be fully understood prior to finalizing the tieback design.

A-4/7

NGA File No. 1211520 August 6, 2021 Page 4

We recommend that at least two of the anchors be performance tested to a minimum of 200 percent of the design loads to confirm design values. We recommend that measurements be made by the contractor in the field at the time of tieback installation to ensure that tiebacks do not encounter any existing structures or underground utilities.

No-Load Zone: The anchor portion of all tiebacks must be located a sufficient distance behind the wall face to develop resistance within a stable soil mass. We recommend the anchorage be obtained behind an assumed no-load zone at an inclination of 15 degrees below horizontal. The no-load zone is defined by a line extending horizontally from the base of the shoring wall back towards the cut a distance of six feet. This line should then extend up from the base elevation at an angle from the horizontal of 60 degrees. We recommend that we monitor soil conditions during anchor installation in order to evaluate adequate penetration into competent soils.

Soil Design Values: The tiebacks must terminate in native, competent soil interpreted to exist below the fill. For use in design of the anchors, we estimate an allowable grout to soil adhesion of 2,000 pounds per square foot (psf) be utilized for sizing the bonded portion of anchors terminated within the competent native soils. This value should be verified through two performance tests prior to ordering the production anchors.

Tieback Installation and Testing: The contractor should be responsible for using equipment suited for the site conditions. We do not recommend the use of an open-hole method for the purpose of installing the tiebacks due to the potential for soil caving. Secondary grouting to increase soil adhesion may be used; however, if secondary grouting is used, the anchors should be tested using the methods outlined for the performance testing. All anchors should be installed at an approximate inclination of 15 to 20 degrees below horizontal.

Two anchors should be performance-tested to 200 percent of the anchor design capacity. The performance test should consist of cyclic loading in increments of 25 percent of the design load, as outlined in the Federal Highways Administration (FHA) report No. FHWA/RD-82/047. The test locations should be determined in the field by NGA, based on soil conditions observed during anchor installation. All other tiebacks should be proof-tested to at least 130 percent of design capacity.

All other recommendations outlined in our previous report should be followed. We trust this memorandum should satisfy your needs at this time. Please contact us if you have any questions or require additional services.

A-5/1



Moran Residence Development Clarifications

2 messages

Carston Curd <carstonc@nelsongeotech.com>

Tue, Oct 5, 2021 at 6:26 PM

To: Catherine Moran <catherine.b.moran@gmail.com>, "edmoran82@gmail.com" <edmoran82@gmail.com>,

"kiaeng.ali@gmail.com" <kiaeng.ali@gmail.com>

Cc: William Gottlieb wmgottlieb@planone.biz, Khaled Shawish khals@nelsongeotech.com

Hi Team,

I'm starting this email chain to facilitate communication and make sure everyone is on the same page.

Catherine and Ed.

We have had discussions separately with both Ali and Bill about our recommendations for debris protection for the residence, but wanted to outline our assumptions and understanding so that you can confirm you understand the limits of the design and verify it meets your expectations.

- The property is expected to experience occasional, small slope failures which may result in debris falling down the steeper portions of the slope. This is normal for steeply sloping properties.
- A stick-up portion of the uphill retaining wall should be able to trap debris from falling over the wall and blocking
 access or impacting the residence. The height of this stickup portion will determine the frequency of over-topping
 failures which could result in impacts to the areas underlying the wall. Increasing the stickup to completely stop
 any amount of failure would require significant structural improvements to the wall to ensure that it can absorb
 those failures without bending. Thus, there's a cost-benefit calculation going on right now that needs your input.
- Based on discussions with Bill, the current design for the stickup is about <u>18-inches</u>, which will trap *most* of the expected failures and will likely not bump up the design in terms of cost too much (TBD, based on Ali's calculations). Additional measures will need to be followed to maintain this low-risk level:
 - Foundations on that side of the house will need to be buffed up a bit (already in the plans for the design).
 - You should keep in mind that there is potential for debris to fall over the wall in extreme circumstances. This
 possibility will be greatly reduced by regularly inspecting the slope for recent failures and clearing the debris
 to maintain the stick-up shield height in-tact.
 - Vegetation on the slope should be properly maintained. An arborist should check large trees if their health or risk level is in question. Vegetation should not be removed from the slope without a restoration plan.
 Water should not be allowed to concentrate onto the slope from uphill properties.

At a minimum, this stickup protection should be present along the wall wherever the house is located downhill. You should decide if additional areas along the wall should incorporate this debris protection, given the assumptions above – we don't anticipate there will be failures every winter storm that happens, but there remains an inherent risk for areas left unprotected. Let me know if you have questions or concerns! I'd be happy to go over any portion of the geotechnical report with you in greater detail – I know it's a very technical document and sometimes important stuff can seem hidden in jargon.

Ali,

Khal is okay with the existing earth pressures of 40 pcf for portions of the wall with overlying slopes up to 1.5H:1V, such that the height of those overlying slopes are limited to 4-feet. If this is not the case, please forward me the grading plan and I can go over it in greater detail.

Hope this helps bring clarity!

Many thanks,

A-6/1



Carston Curd, GIT | Project Geologist

NGA: 17311-135 $^{\rm th}$ Ave NE #A500, Woodinville, WA 98072 carstonc@nelsongeotech.com | www.nelsongeotech.com

cell: 425-523-8642 office: 425-486-1669

Edward Moran <edmoran82@gmail.com>

Wed, Oct 6, 2021 at 12:14 PM

To: Carston Curd <carstonc@nelsongeotech.com>

Cc: Catherine Moran <catherine.b.moran@gmail.com>, "kiaeng.ali@gmail.com" <kiaeng.ali@gmail.com>, William Gottlieb <wmgottlieb@planone.biz>, Khaled Shawish <khals@nelsongeotech.com>

Hi Carston,

Thanks for outlining everything above. Based on our understanding and conversations with Bill and Ali, we are comfortable with the stickup of the wall remaining at 18 inches.

Ali - do you have what you need to move forward?

Thanks,

Ed Moran
[Quoted text hidden]

A-1/1