

K I A C O

P.O. Box 7255
Bellevue, WA 98008

Phone 425-351-5999
Kiaeng.ali@gmail.com

**EDWARD & CATHERINE MORAN
RESIDENCE**

**5000 WEST MERCER WAY
MERCER ISLAND, WASHINGTON 98040**

STRUCTURAL CALCULATIONS

**NOVEMBER 30, 2021
JOB NO: 171-2101**




TABLE OF CONTENTS

| | |
|----------------|----------------------------|
| D-1 | Design Data |
| RB-1 To RB-6 | Framing design |
| FB-1 To FB-14 | Upper Level Framing design |
| MFB-1 To MFB-7 | Min Level Framing design |
| L-1 To L-14 | Lateral analysis |
| F-1 To F-3 | Foundation design |
| RTW-1 To RTW-6 | Retaining Wall design |

DESIGN DATA:

Roof Loads-

Dead Load = 15 psf

Live Load = 25 psf (Snow)

Floor Loads-

Dead Load = 15 psf

Live Load = 40 psf

WIND:

110 MPH

Exposure "B"

SEISMIC:

Zip Code: 98040

Ss = 1.439

S1 = 0.552

Fa = 1.00

Fv = 1.50

Sds = 0.959

Sd1 = 0.552

Above values per Soil's Report by: Nelson Geotech. Associates, Inc.,
File No. 1211520, September 27, 2021.

Soil Bearing = 1500 psf (Per Soil's Report)

D-1/1

ROOF JOIST-1:

SPAN = 11.00 FT

USE: 2x12 HF #2

Fb = 980 PSI
Fv = 75 PSI

b = 1.5 IN
h = 11.25 IN

A = 16.88 IN²
S = 31.64 IN³
I = 177.98 IN⁴
E = 1600 KSI

Duration Factor = 1.15

Turb. W = 2.00 FT

DL = 15.00 PSF

LL = 25.00 PSF

W(DL) = 30.00 PLF

W(LL) = 50.00 PLF

W(TL) = 80.00 PLF

M. (max) = 1.21 K-FT

R (max) = 0.44 K

V (max) = 0.37 K

fb = 0.40 KSI OK

fv = 0.03 KSI OK

TL-Deflection = 0.09 IN L/ 1426

DL-Deflection = 0.03 IN L/ 3804

KIA CO



Project/Subject

MALAD RESID.
MELLER ISLAND, WA

By

A.G.

Sheet No.

EB-1/6

Date

11-21

Job No.

171-1901

ROOF JOIST-2: (Double joist @ Dormer)

SPAN = 11.00 FT

USE: (2)-2x12 HF #2

Fb = 980 PSI
Fv = 75 PSI

b = 3 IN
h = 11.25 IN

A = 33.75 IN²
S = 63.28 IN³
I = 355.96 IN⁴
E = 1600 KSI

Duration Factor = 1.15

Turb. W = 5.00 FT

DL = 15.00 PSF

LL = 25.00 PSF

W(DL) = 75.00 PLF

W(LL) = 125.00 PLF

W(TL) = 200.00 PLF

M. (max) = 3.03 K-FT

R (max) = 1.10 K

V (max) = 0.91 K

fb = 0.50 KSI OK

fv = 0.04 KSI OK

TL-Deflection = 0.12 IN L/ 1141

DL-Deflection = 0.04 IN L/ 3043



ROOF BEAM-1:

SPAN = 3.50 FT

USE: 4x6 DF #2

Fb = 1140 PSI
Fv = 95 PSI

b = 3.5 IN
h = 5.5 IN

A = 19.25 IN²
S = 17.65 IN³
I = 48.53 IN⁴
E = 1600 KSI

Duration Factor = 1.15

Turb. W = 11.00 FT

DL = 15.00 PSF

LL = 25.00 PSF

W(DL) = 165.00 PLF

W(LL) = 275.00 PLF

W(TL) = 440.00 PLF

M (max) = 0.67 K-FT

R (max) = 0.77 K

V (max) = 0.57 K

fb = 0.40 KSI OK

fv = 0.04 KSI OK

TL-Deflection = 0.02 IN L/ 2195

DL-Deflection = 0.01 IN L/ 5853



Project/Subject

MORAN RESID.
MELCEL ISLAND, WA.

By

A.G.

Sheet No.

RB-3/6

Date

11-2)

Job No.

171-1901

ROOF BEAM-2:

SPAN = 5.50 FT

USE: 4x6 DF #2

Fb = 1140 PSI

Fv = 95 PSI

b = 3.5 IN

h = 5.5 IN

A = 19.25 IN²

S = 17.65 IN³

I = 48.53 IN⁴

E = 1600 KSI

Duration Factor = 1.15

Turb. W = 10.00 FT

DL = 15.00 PSF

LL = 25.00 PSF

W(DL) = 150.00 PLF

W(LL) = 250.00 PLF

W(TL) = 400.00 PLF

M (max) = 1.51 K-FT

R (max) = 1.10 K

V (max) = 0.92 K

fb = 0.89 KSI OK

fv = 0.06 KSI OK

TL-Deflection = 0.11 IN L/ 622

DL-Deflection = 0.04 IN L/ 1659

KIA CO



Project/Subject

MORAN RESID.
MARCEL ISLAND, WA.

By

A. G.

Sheet No.

BB-9/6

Date

11-21

Job No.

171-1901

ROOF BEAM-3

SPAN = 4.00 FT

USE: 6x8 DF #1

Fb = 1300 PSI

Fv = 85 PSI

b = 5.5 IN

h = 7.5 IN

A = 41.25 IN²

S = 51.56 IN³

I = 193.36 IN⁴

E = 1700 KSI

Duration Factor = 1.15

Turb. W = 2.00 FT

X = 1.75 FT

DL = 15.00 PSF

LL = 25.00 PSF

P(DL) = 1568.00 LBS

P(LL) = 2613.00 LBS

P(TL) = 4181.00 LBS

W(DL) = 30.00 PLF

W(LL) = 50.00 PLF

W(TL) = 80.00 PLF

M (max) = 4.28 K-FT

R (max) = 1.99 K

V (max) = 1.94 K

fb = 0.865 KSI OK

fv = 0.061 KSI OK

TL-Deflection = 0.031 IN L/ 1563

DL-Deflection = 0.018 IN L/ 2605



Project/Subject

MORAN RESID.
MELCEL ISLAND, WA,

By

A.G.

Sheet No.

RB-5/6

Date

11-21

Job No.

171-1901

ROOF BEAM-4:

SPAN = 18.00 FT

USE: 3.5"x14" 1.9E Microllam LVL

Fb = 2600 PSI

Fv = 285 PSI

b = 3.5 IN

h = 14 IN

A = 49.00 IN²

S = 114.33 IN³

I = 800.33 IN⁴

E = 1900 KSI

Duration Factor = 1.15

Turb. W = 11.00 FT

DL = 15.00 PSF

LL = 25.00 PSF

W(DL) = 165.00 PLF

W(LL) = 275.00 PLF

W(TL) = 440.00 PLF

M (max) = 17.82 K-FT

R (max) = 3.96 K

V (max) = 3.45 K

fb = 1.63 KSI OK

fv = 0.09 KSI OK

TL-Deflection = 0.68 IN L/ 316

DL-Deflection = 0.26 IN L/ 843

KIA CO



Project/Subject

MORAN RESID.
MORCEL ISLAND, WA,

By

A.G.

Sheet No.

RB-6/6

Date

11-21

Job No.

171-1901

FB-1:

(GYP. HEADER)

SPAN = 4.50 FT

USE: 4x8 DF #2

Fb = 1140 PSI

Fv = 95 PSI

b = 3.5 IN

h = 7.25 IN

A = 25.38 IN²

S = 30.66 IN³

I = 111.15 IN⁴

E = 1600 KSI

Duration Factor = 1.00

Turb. W = 1.00 FT

DL = 325.00 PSF (15x7.5'+15x7.5'+10x10')

LL = 488.00 PSF (25x7.5'+40x7.5')

W(DL) = 325.00 PLF

W(LL) = 488.00 PLF

W(TL) = 813.00 PLF

M (max) = 2.06 K-FT

R (max) = 1.83 K

V (max) = 1.34 K

fb = 0.81 KSI OK

fv = 0.08 KSI OK

TL-Deflection = 0.04 IN L/ 1280

DL-Deflection = 0.02 IN L/ 3203

KIA CO



Project/Subject

MORAN RESID.
MOLCEL ISLAND, WA,

By

A. G.

Sheet No.

FB-1/14

Date

11-21

Job No.

171-1901

FB-2:

(Roof Beam @ Great Room)

SPAN = 6.50 FT

USE: 4x8 DF #2

Fb = 1140 PSI

Fv = 95 PSI

b = 3.5 IN

h = 7.25 IN

A = 25.38 IN²

S = 30.66 IN³

I = 111.15 IN⁴

E = 1600 KSI

Duration Factor = 1.15

Turb. W = 11:00 FT

DL = 15:00 PSF

LL = 25:00 PSF

W(DL) = 165.00 PLF

W(LL) = 275.00 PLF

W(TL) = 440.00 PLF

M (max) = 2.32 K-FT

R (max) = 1.43 K

V (max) = 1.16 K

fb = 0.79 KSI OK

fv = 0.06 KSI OK

TL-Deflection = 0.10 IN L/ 785

DL-Deflection = 0.04 IN L/ 2093

USE 4x10 D.F. #2



Project/Subject

*MORAN RESID.
MELCEL ISLAND, WA,*

By

P. G.

Sheet No.

FB-2/4

Date

11-21

Job No.

171-1901

FB-3:

(BTWN DEN & PORCH)

SPAN = 5.50 FT

USE: 4x10 DF #2

Fb = 1050 PSI

Fv = 95 PSI

b = 3.5 IN

h = 9.25 IN

A = 32.38 IN²

S = 49.91 IN³

I = 230.84 IN⁴

E = 1600 KSI

Duration Factor = 1.00

Turb. W = 1.00 FT

DL = 385.00 PSF (15x11'+15x8'+10x10')

LL = 595.00 PSF (25x11'+40x8')

W(DL) = 385.00 PLF

W(LL) = 595.00 PLF

W(TL) = 980.00 PLF

M (max) = 3.71 K-FT

R (max) = 2.70 K

V (max) = 1.94 K

fb = 0.89 KSI OK

fv = 0.09 KSI OK

TL-Deflection = 0.05 IN L/ 1208

DL-Deflection = 0.02 IN L/ 3075

KIA CO



Project/Subject

MORAN RESID.
MELCEL ISLAND, WA,

By

A.G.

Sheet No.

FB-3/14

Date

11-21

Job No.

171-1901

FB-4:

(BTWN MVD 202 & PALCH)

SPAN = 5.50 FT

USE: 4x10 DF #2

Fb = 1050 PSI

Fv = 95 PSI

b = 3.5 IN

h = 9.25 IN

A = 32.38 IN²

S = 49.91 IN³

I = 230.84 IN⁴

E = 1600 KSI

Duration Factor = 1.00

Turb. W = 1.00 FT

DL = 370.00 PSF (15x13'+15x5'+10x10')

LL = 525.00 PSF (25x13'+40x5')

W(DL) = 370.00 PLF

W(LL) = 525.00 PLF

W(TL) = 895.00 PLF

M (max) = 3.38 K-FT

R (max) = 2.46 K

V (max) = 1.77 K

fb = 0.81 KSI OK

fv = 0.08 KSI OK

TL-Deflection = 0.05 IN L/ 1323

DL-Deflection = 0.02 IN L/ 3200



Project/Subject

MORAN RESID.
MOLCEL ISLAND, WA,

By

A.G.

Sheet No.

FB-4/14

Date

11-21

Job No.

175-1901

FB-5:

(C. J. P. C. H.)

SPAN = 8.50 FT

USE: 4x12 DF #2

Fb = 965 PSI

Fv = 95 PSI

b = 3.5 IN

h = 11.25 IN

A = 39.38 IN²

S = 73.83 IN³

I = 415.28 IN⁴

E = 1600 KSI

Duration Factor = 1.00

Turb. W. = 1.00 FT

DL = 280.00 PSF (15x11'+15x1'+10x10')

LL = 315.00 PSF (25x11'+40x1')

W(DL) = 280.00 PLF

W(LL) = 315.00 PLF

W(TL) = 595.00 PLF

M (max) = 5.37 K-FT

R (max) = 2.53 K

V (max) = 1.97 K

fb = 0.87 KSI OK

fv = 0.08 KSI OK

TL-Deflection = 0.11 IN L/ 970

DL-Deflection = 0.05 IN L/ 2061

KIA CO



Project/Subject

*MORAN RESID.
MELCEL ISLAND, WA,*

By

A. G.

Sheet No.

FB-5/14

Date

11-21

Job No.

171-1901

FB-6: (At Porch)

SPAN = 12.50 FT

USE: 6x12 DF #1

Fb = 1350 PSI

Fv = 170 PSI

b = 5.5 IN

h = 11.5 IN

A = 63.25 IN²

S = 121.23 IN³

I = 697.07 IN⁴

E = 1500 KSI

Duration Factor = 1.00

Turb. W = 1.00 FT

DL = 228.00 PSF (15x2'+15x6.5'+10x10')

LL = 310.00 PSF (25x2'+40x6.5')

W(DL) = 228.00 PLF

W(LL) = 310.00 PLF

W(TL) = 538.00 PLF

M (max) = 10.51 K-FT

R (max) = 3.36 K

V (max) = 2.85 K

Cv = 1.00

Fb = 1355 PSI

fb = 1.04 KSI OK

fv = 0.07 KSI OK

TL-Deflection = 0.28 IN L/ 531

DL-Deflection = 0.12 IN L/ 1252



Project/Subject

MOLAD RESID.
MELLER ISLAND, WA

By

A.G.

Sheet No.

FB-6/14

Date

11-21

Job No.

171-1901

FB-7:

(C. GARAGE)

SPAN = 19.00 FT

USE: 5-1/8x16.5 GLB

Fb = 2400 PSI

Fv = 165 PSI

b = 5.125 IN

h = 16.5 IN

A = 84.56 IN²

S = 232.55 IN³

I = 1918.51 IN⁴

E = 1800 KSI

Duration Factor = 1.00

Turb. W = 1.00 FT

DL = 15.00 PSF

LL = 40.00 PSF

W(DL) = 355.00 PLF (15x6'+15x11'+10x10')

W(LL) = 590.00 PLF (25x6'+40x11')

W(TL) = 945.00 PLF

M (max) = 42.64 K-FT

R (max) = 8.98 K

V (max) = 7.68 K

Cv = 0.9590

F_b' = F_b x Cv = 2.30 KSI

f_b = 2.20 KSI OK

f_v = 0.14 KSI OK

TL-Deflection = 0.80 IN L/ 284

DL-Deflection = 0.30 IN L/ 756

Camber = 0.30 IN



Project/Subject

*MORAN RESID.
MERCER ISLAND, WA*

By

A. G.

Sheet No.

FB-7/14

Date

11-21

Job No.

171-1901

FB-8: (BRAIN DRIVING & GREAT ETC)

SPAN = 14.00 FT

USE: 5 1/4 x 11 7/8" 1.9E, Microllam LVL

Fb = 2600 PSI

Fv = 285 PSI

b = 5.25 IN

h = 11.875 IN

A = 62.34 IN²

S = 123.39 IN³

I = 732.62 IN⁴

E = 1900 KSI

Duration Factor = 1.00

Turb. W = 1.00 FT

DL = 385.00 PSF (15x11'+15x8'+10x10')

LL = 595.00 PSF (25x11'+40x8')

W(DL) = 385.00 PLF

W(LL) = 595.00 PLF

W(TL) = 980.00 PLF

M (max) = 24.01 K-FT

R (max) = 6.86 K

V (max) = 5.89 K

fb = 2.34 KSI OK

fv = 0.14 KSI OK

TL-Deflection = 0.61 IN L/ 276

DL-Deflection = 0.24 IN L/ 703



Project/Subject

MORAN RESID,
MERCER ISLAND, WA,

By

A. G.

Sheet No.

FB-8/14

Date

11-21

Job No.

171-1901

FB-9:

(BTWN KITCHEN & FOYER)

SPAN = 10.50 FT

USE: 5' 1/4 x 11 7/8" 1.9E, Microllam LVL

Fb = 2600 PSI

Fv = 285 PSI

b = 5.25 IN

h = 11.875 IN

A = 62.34 IN²

S = 123.39 IN³

I = 732.62 IN⁴

E = 1900 KSI

Duration Factor = 1.00

Turb. W = 12.00 FT

DL = 15.00 PSF

LL = 40.00 PSF

W(DL) = 180.00 PLF

W(LL) = 480.00 PLF

W(TL) = 660.00 PLF

M (max) = 9.10 K-FT

R (max) = 3.47 K

V (max) = 2.81 K

fb = 0.88 KSI OK

fv = 0.07 KSI OK

TL-Deflection = 0.13 IN L/ 972

DL-Deflection = 0.04 IN L/ 3563

KIA CO



Project/Subject

MORAN RESID.
MERCER ISLAND, WA,

By

A.G.

Sheet No.

FB-9/14

Date

11-21

Job No.

171-1901

FB-10: (BTWN FLOOR & STAIR)

SPAN = 8.50 FT

USE: 4x12 DF #2

Fb = 965 PSI

Fv = 95 PSI

b = 3.5 IN

h = 11.25 IN

A = 39.38 IN²

S = 73.83 IN³

I = 415.28 IN⁴

E = 1600 KSI

Duration Factor = 1.00

Turb. W = 10.00 FT

DL = 15.00 PSF

LL = 40.00 PSF

W(DL) = 150.00 PLF

W(LL) = 400.00 PLF

W(TL) = 550.00 PLF

M (max) = 4.97 K-FT

R (max) = 2.34 K

V (max) = 1.82 K

fb = 0.81 KSI OK

fv = 0.07 KSI OK

TL-Deflection = 0.10 IN L/ 1049

DL-Deflection = 0.03 IN L/ 3847



Project/Subject

MORAN RESID.
MELCEL ISLAND, WA,

By

A. G.

Sheet No.

FB-10/14

Date

11-21

Job No.

171-1901

FB-11:

(C. G. GARDNER)

SPAN = 5.50 FT

USE: 4x8 DF #2

Fb = 1140 PSI

Fv = 95 PSI

b = 3.5 IN

h = 7.25 IN

A = 25.38 IN²

S = 30.66 IN³

I = 111.15 IN⁴

E = 1600 KSI

Duration Factor = 1.00

Turb. W = 12.00 FT

DL = 15.00 PSF

LL = 40.00 PSF

W(DL) = 180.00 PLF

W(LL) = 480.00 PLF

W(TL) = 660.00 PLF

M (max) = 2.50 K-FT

R (max) = 1.82 K

V (max) = 1.42 K

fb = 0.98 KSI OK

fv = 0.08 KSI OK

TL-Deflection = 0.08 IN L/ 864

DL-Deflection = 0.02 IN L/ 3167



Project/Subject

MORAN RESID.
MERCER ISLAND, WA,

By

A. G.

Sheet No.

FB-11/14

Date

11-21

Job No.

171-1901

FB-12:

(REVISED)

SPAN = 3.50 FT

USE: 4x6 DF #2

Fb = 1140 PSI

Fv = 95 PSI

b = 3.5 IN

h = 5.5 IN

A = 19.25 IN²

S = 17.65 IN³

I = 48.53 IN⁴

E = 1600 KSI

Duration Factor = 1.00

Turb. W = 12.00 FT

DL = 15.00 PSF

LL = 40.00 PSF

W(DL) = 180.00 PLF

W(LL) = 480.00 PLF

W(TL) = 660.00 PLF

M (max) = 1.01 K-FT

R (max) = 1.16 K

V (max) = 0.85 K

fb = 0.69 KSI OK

fv = 0.07 KSI OK

TL-Deflection = 0.03 IN L/ 1463

DL-Deflection = 0.01 IN L/ 5366

USE: 4x8



Project/Subject

*MORAN RESID,
MERCER ISLAND, WA,*

By

A. G.

Sheet No.

FB-12/14

Date

11-21

Job No.

171-1901

FB-13:

(CROWN KITCHEN & STAIR)

SPAN = 4.50 FT

USE: 4 x 12 DF #2

Fb = 965 PSI

Fv = 95 PSI

b = 3.5 IN

h = 11.25 IN

A = 39.38 IN²

S = 73.83 IN³

I = 415.28 IN⁴

E = 1600 KSI

Duration Factor = 1.00

Turb. W = 1.00 FT

X = 2.50 FT

DL = 15.00 PSF

LL = 40.00 PSF

P(DL) = 640.00 LBS

P(LL) = 1700.00 LBS

P(TL) = 2340.00 LBS

W(DL) = 15.00 PLF

W(LL) = 40.00 PLF

W(TL) = 55.00 PLF

M(max) = 2.74 K-FT

R(max) = 1.42 K

V(max) = 1.37 K

fb = 0.445 KSI OK

fv = 0.052 KSI OK

TL-Deflection = 0.012 IN L/ 4384

DL-Deflection = 0.005 IN L/ 11692

KIA CO



Project/Subject

*MORAN RESID.
MERCER ISLAND, WA,*

By

A.G.

Sheet No.

FB-13/4

Date

11-21

Job No.

171-1901

FB-14:

(Porch Roof Beam)

SPAN = 11.00 FT

USE: 4x8 DF #2

Fb = 1140 PSI

Fv = 95 PSI

b = 3.5 IN

h = 7.25 IN

A = 25.38 IN²

S = 30.66 IN³

I = 111.15 IN⁴

E = 1600 KSI

Duration Factor = 1.15

Turb. W = 3.50 FT

DL = 15.00 PSF

LL = 25.00 PSF

W(DL) = 52.50 PLF

W(LL) = 87.50 PLF

W(TL) = 140.00 PLF

M (max) = 2.12 K-FT

R (max) = 0.77 K

V (max) = 0.69 K

fb = 0.72 KSI OK

fv = 0.04 KSI OK

TL-Deflection = 0.26 IN L/ 509

DL-Deflection = 0.10 IN L/ 1357



Project/Subject

MORAN RESID.
MERCER ISLAND, WA,

By

A.G.

Sheet No.

FB-14/14

Date

11-21

Job No.

171-1901

FLOOR JOIST-1: (Porch Joists)

SPAN = 13.00 FT

USE: 2x10 HF #2 @ 12" o.c.

Fb = 1075 PSI

Fv = 75 PSI

b = 1.5 IN

h = 9.25 IN

A = 13.88 IN²

S = 21.39 IN³

I = 98.93 IN⁴

E = 1600 KSI

Duration Factor = 1.00

Turb. W = 1.00 FT

DL = 15.00 PSF

LL = 60.00 PSF

W(DL) = 15.00 PLF

W(LL) = 60.00 PLF

W(TL) = 75.00 PLF

M (max) = 1.58 K-FT

R (max) = 0.49 K

V (max) = 0.43 K

fb = 0.89 KSI OK

fv = 0.05 KSI OK

TL-Deflection = 0.30 IN L/ 512

DL-Deflection = 0.06 IN L/ 2562

KIA CO



Project/Subject

MOLAD RESID.
MERCER ISLAND, WA

By

A.G.

Sheet No.

19FB-1/7

Date

11-21

Job No.

171-1901

MFB-1:

SPAN = 8.00 FT

USE: 4x10 DF #2

Fb = 1050 PSI

Fv = 95 PSI

b = 3.5 IN

h = 9.25 IN

A = 32.38 IN²

S = 49.91 IN³

I = 230.84 IN⁴

E = 1600 KSI

Duration Factor = 1.00

Turb. W = 8.50 FT

DL = 15.00 PSF

LL = 40.00 PSF

W(DL) = 127.50 PLF

W(LL) = 340.00 PLF

W(TL) = 467.50 PLF

M (max) = 3.74 K-FT

R (max) = 1.87 K

V (max) = 1.51 K

fb = 0.90 KSI OK

fv = 0.07 KSI OK

TL-Deflection = 0.12 IN L/ 823

DL-Deflection = 0.03 IN L/ 3018

KIA CO



Project/Subject

MORAN RESID.
MORCEL ISLAND, WA,

By

A.C.

Sheet No.

MFB-2/7

Date

11-21

Job No.

171-1901

MFB-2:

SPAN = 11.00 FT

USE: 6x10 DF #1

Fb = 1350 PSI

Fv = 170 PSI

b = 5.5 IN

h = 9.5 IN

A = 52.25 IN²

S = 82.73 IN³

I = 392.96 IN⁴

E = 1600 KSI

Duration Factor = 1.00

Turb. W = 5.50 FT

DL = 15.00 PSF

LL = 40.00 PSF

W(DL) = 82.50 PLF

W(LL) = 220.00 PLF

W(TL) = 302.50 PLF

M (max) = 4.58 K-FT

R (max) = 1.66 K

V (max) = 1.42 K

fb = 0.66 KSI OK

fv = 0.04 KSI OK

TL-Deflection = 0.16 IN L/ 833

DL-Deflection = 0.04 IN L/ 3054



Project/Subject

MOLAD RESID.
MELCOR ISLAND, WA

By

A.G.

Sheet No.

MFB-3/7

Date

11-21

Job No.

171-1901

MFB-3:

SPAN = 9.00 FT

USE: 4x12 DF #2

Fb = 965 PSI
Fv = 95 PSI

b = 3.5 IN
h = 11.25 IN

A = 39.38 IN²
S = 73.83 IN³
I = 415.28 IN⁴
E = 1600 KSI

Duration Factor = 1.00

Turb. W = 8.25 FT

DL = 15.00 PSF

LL = 40.00 PSF

W(DL) = 123.75 PLF

W(LL) = 330.00 PLF

W(TL) = 453.75 PLF

M (max) = 4.59 K-FT

R (max) = 2.04 K

V (max) = 1.62 K

fb = 0.75 KSI OK

fv = 0.06 KSI OK

TL-Deflection = 0.10 IN L/ 1071

DL-Deflection = 0.03 IN L/ 3928

KIA CO



Project/Subject

MORAN RESID.
MELCEL ISLAND, WA,

By

A. G.

Sheet No.

MFB-4/7

Date

11-21

Job No.

171-1901

MFB-4:

SPAN = 9.00 FT

USE: 3 1/2x11 7/8 1.5E LSL

Fb = 2250 PSI

Fv = 285 PSI

b = 3.5 IN

h = 11.875 IN

A = 41.56 IN²

S = 82.26 IN³

I = 488.41 IN⁴

E = 1500 KSI

Duration Factor = 1.00

Turb. W = 12.00 FT

DL = 30.00 PSF

LL = 80.00 PSF

W(DL) = 360.00 PLF

W(LL) = 960.00 PLF

W(TL) = 1320.00 PLF

M (max) = 13.37 K-FT

R (max) = 5.94 K

V (max) = 4.63 K

Cv = 0.9197

F'b = Fb x Cv = 2.07 KSI

fb = 1.95 KSI OK

fv = 0.17 KSI OK

TL-Deflection = 0.27 IN L/ 406

DL-Deflection = 0.07 IN L/ 1489



Project/Subject

MORAN RESID.
MERCER ISLAND, WA,

By

A.C.

Sheet No.

MFB-5/7

Date

11-21

Job No.

171-1901

MFB-5:

SPAN = 7.50 FT

USE: 6x10 DF #1

Fb = 1350 PSI
Fv = 170 PSI

b = 5.5 IN
h = 9.5 IN

A = 52.25 IN²
S = 82.73 IN³
I = 392.96 IN⁴
E = 1600 KSI

Duration Factor = 1.00

Turb. W = 1.00 FT

DL = 255.00 PSF

LL = 681.00 PSF

← (15 x 8.5 x 2)
← (40 x 8.5 x 2)

W(DL) = 255.00 PLF

W(LL) = 681.00 PLF

W(TL) = 936.00 PLF

M (max) = 6.58 K-FT

R (max) = 3.51 K

V (max) = 2.77 K

fb = 0.95 KSI OK

fv = 0.08 KSI OK

TL-Deflection = 0.11 IN L/ 849

DL-Deflection = 0.03 IN L/ 3117



Project/Subject

MORAD RESID.
MERCER ISLAND, WA

By

A.G.

Sheet No.

MFB-5

Date

11-21

Job No.

171-1901

MFB-6:

SPAN = 6.67 FT

USE: 6x10 DF #1

Fb = 1350 PSI

Fv = 170 PSI

b = 5.5 IN

h = 9.5 IN

A = 52.25 IN²

S = 82.73 IN³

I = 392.96 IN⁴

E = 1600 KSI

Duration Factor = 1.00

Turb. W = 1.00 FT

DL = 412.00 PSF

LL = 951.00 PSF

RAIN, UPPER ROOF
→ (15 × 8.5 + 15 × 9 + 15 × 10)
→ (40 × 8.5 + 40 × 9 + 25 × 10)

W(DL) = 412.00 PLF

W(LL) = 951.00 PLF

W(TL) = 1363.00 PLF

M (max) = 7.58 K-FT

R (max) = 4.55 K

V (max) = 3.47 K

fb = 1.10 KSI OK

fv = 0.10 KSI OK

TL-Deflection = 0.10 IN L/ 829

DL-Deflection = 0.03 IN L/ 2743



LATERAL ANALYSIS:

CODES: IRC 2018, ASCE 7-10

SEISMIC:

PROJECT ADDRESS: 5000 WEST MERCER WAY
MERCER ISLAND, WA 98040

$$* \begin{cases} S_s = 1.439 \\ S_1 = 0.552 \end{cases}$$

$$* \begin{cases} F_a = 1.000 \\ F_v = 1.500 \end{cases}$$

$$* \begin{cases} S_{DS} = 0.959 \\ S_{D1} = 0.552 \end{cases}$$

* ABOVE VALUES PER SOIL'S REPORT BY "NELSON GEOTECH.
ASSOC., INC." FILE NO. 1211520, NOVEMBER 20, 2020.

$$I = 1.0$$

$$R = 6.5 \text{ (WOOD SHEAR WALLS)}$$

$$\Omega = 3.0$$

$$C_d = 4.0$$

$$f = 1.0 \text{ (BY INSPECTION)}$$



Project/Subject

5000 WEST MERCER WAY
MERCER ISLAND, WA

By

A.G.

Sheet No.

2-1/1A

Date

11-21

Job No.

17)-210)

$$C_s = \frac{S_{DS}}{(R/I)} = \frac{0.959}{(6.5/1)} = 0.1475$$

$$w_{\text{ROOF}} = 15 \text{ PSF} + 5 \text{ PSF (WALLS)} = 20 \text{ PSF}$$

$$w_{\text{FLOOR}} = 15 \text{ PSF} + 10 \text{ PSF (WALLS)} = 25 \text{ PSF}$$

$$V = C_s \cdot W = 0.1475 (20 + 25) = 6.64 \text{ PSF}$$

| LEVEL | w _i | H _i | w _i H _i | F _i (PSF) | V _i (PSF) | V _i (ASD) |
|-------|----------------|----------------|-------------------------------|----------------------|----------------------|-----------------------|
| ROOF | 20 | 20' | 400 | 4.09 | 4.09 | 4.09 / 1.4 = 2.92 PSF |
| MAIN | 25 | 10' | 250 | 2.55 | 6.64 | 6.64 / 1.4 = 4.74 PSF |
| | | | <u>Σ = 650</u> | | | |

WIND:

$$I_w = 1.0$$

EXPOSURE → "B"

BASIC WIND SPEED = 110 MPH

$$K_{zt} = 1.0$$

$$\lambda = 1.0$$

ZONE "A" = 21.6

ZONE "B" = 14.8

ZONE "C" = 17.2

ZONE "D" = 11.8


$$\text{WIND SPEED} = 21.6 \text{ PSF} / 1.6 = 13.5 \text{ PSF} < 16 \text{ PSF (MIN.)}$$

USE: 16 PSF




Project/Subject
5000 WEST MERCER WAY
MERCER ISLAND, WA

| | |
|---------------|---------------------|
| By A. G. | Sheet No. L-2/14 |
| Date 11-21 | Job No. 171-2101 |



UPPER LEVEL



MAIN LEVEL

A HIGH PITCH
CONCRETE
WALL

L-9/14

SHEAR @ UPPER FLOOR:

(SEE L-3 FOR NET PLAN)

$$R_1 = 240 \text{ PLF} \times 26.5' / 2 = 3,180 \#$$

$$V_1 = 3,180 \# / 7'$$

$$= 454 \text{ PLF}$$

→ USE: P-3

$$R_2 = 240 \text{ PLF} \times 47.5' / 2 = 5,700 \#$$

$$V_2 = 5,700 \# / 19'$$

$$= 300 \text{ PLF}$$

→ USE: P-2

$$R_3 = 240 \text{ PLF} \times 52' / 2 = 6,240 \#$$

$$V_3 = 6,240 / 13'$$

$$= 480 \text{ PLF}$$

→ USE: P-3

$$R_4 = 240 \text{ PLF} \times 31' / 2 = 3,720 \#$$

$$V_4 = 3,720 / 14'$$

$$= 266 \text{ PLF}$$

→ USE: P-2

$$R_5 = 240 \text{ PLF} \times 23' / 2 = 2,760 \#$$

$$V_5 = 2,760 / (14.5' + 7.5') = 126 \text{ PLF}$$

→ USE: P-1

$$R_6 = 240 \text{ PLF} \times 41.5' / 2 = 4,980 \#$$

$$V_6 = 4,980 / (6' + 4' + 8' + 20') = 131 \text{ PLF}$$

→ USE: P-1

$$R_7 = 240 \text{ PLF} \times 28.5' / 2 = 2,220 \#$$

$$V_7 = 2,220 / (8' + 4' + 24' + 4') = 58 \text{ PLF}$$

→ USE: P-1



Project/Subject

5000 WEST MERCER WAY
MERCER ISLAND, WA.

By

A.G.

Sheet No.

25/14

Date

11-21

Job No.

171-2101

SHEAR @ MAIN LEVEL:

(SEE L-5 FOR KEY PLAN)

$$R_8 = 16 \text{ PSF} \times 4' \times \frac{8.5'}{2} + 3180 \# (\text{UPPER}) = 3,452 \#$$

$$V_8 = 3,452 \# / (3' + 1.5 \times 2) = 575 \text{ PLF} \longrightarrow \boxed{\text{USE: SIMPSON S.W.}}$$

$$R_9 = 240 \text{ PLF} \times 18' / 2 = 2,160 \#$$

$$V_9 = 2,160 \# / (3.5' + 2') = 393 \text{ PLF} \longrightarrow \boxed{\text{P-3 + SIMPSON S.W.}}$$

$$R_{10} = 160 \text{ PLF} \times 47.5' / 2 + 5,100 \# (\text{UPPER}) = 9,500 \#$$

$$V_{10} = 9,500 \# / (4' + 8.5' + 2 \times 2) = 576 \text{ PLF} \longrightarrow \boxed{\text{USE: P-4} + \text{SIMPSON S.W.}}$$

$$R_{11} = 160 \text{ PLF} \times 52' / 2 + 6,240 \# (\text{UPPER}) = 10,400 \#$$

$$V_{11} = 10,400 \# / (16' + 7' + 3') = 400 \text{ PLF} \longrightarrow \boxed{\text{USE: P-3}}$$

$$R_{12} = 160 \text{ PLF} \times 3' / 2 + 3,720 \# (\text{UPPER}) = 6,200 \#$$

$$V_{12} = 6,200 \# / (8' + 4' + 4') = 388 \text{ PLF} \longrightarrow \boxed{\text{USE: P-3}}$$

$$R_{13} = 160 \text{ PLF} \times 23' / 2 + 2,760 \# (\text{UPPER}) = 4,600 \#$$

$$V_{13} = 4,600 \# / (18' + 9.5' + 5') = 142 \text{ PLF} \longrightarrow \boxed{\text{USE: P-1}}$$

$$R_{14} = 160 \text{ PLF} \times 41.5' / 2 + 4,980 \# (\text{UPPER}) = 8,300 \#$$

$$V_{14} = 8,300 \# / (\underbrace{3' + 2' + 6.5' + 2' + 11' + 4'}_{34'}) = 244 \text{ PLF} \longrightarrow \boxed{\text{USE: P-1}}$$

$$R_{15} = 160 \text{ PLF} \times 30.5' / 2 + 2,220 \# (\text{UPPER}) = 4,660 \#$$

$$V_{15} = 4,660 \# / (\underbrace{4' \times 2 + 5.5' + 2' + 12' + 6.5'}_{37.5'}) = 124 \text{ PLF} \longrightarrow \boxed{\text{USE: P-1}}$$



Project/Subject

5000 WEST MERCER WAY
MERCER ISLAND, WA

By

A.G.

Sheet No.

L-6/14

Date

11-21

Job No.

171-2101

HOLD DOWN @ R1:


$P_{OT} = 31,800 \#'$

$0.609P = 1,911 \#'$

$P_{NET} = 29,889 \#'$

$T = 4,428 \# \leq 4,585 \#$

USE: CM5TC16



HOLD DOWN @ R8:

USE: (2) - 24" WALLS

$\sqrt{I}_{WALL} = 3452 / 2 = 1,726 \#$

W3W 24X10

ALLOW. LOAD = 2,125 # - O.K.



Project/Subject
5000 W MERCER WAY
MERCER ISLAND, WA


By
A.G.
Date
11-21

Sheet No.
2-7/54
Job No.
171-2101

HOLD DOWNS RZ & R10:

UPPER LEVEL

$M_{o.T.} = 257,000 \#'$
 $M_R = 29,165 \#'$
 $0.6 M_R = 17,499 \#'$
 $M_{NET} = 39,501 \#'$
 $T_1 = 2,135 \# < 4,585 \#$
 USE: CM5TC16



LOWER LEVEL

4'-WALL

$M_{o.T.} = 25,330 \#'$
 $M_R = 5,600 \#'$
 $0.6 M_R = 3,360 \#'$
 $M_{NET} = 21,970 \#'$
 $T_2 = 2,929 \#$

8'-WALL

$M_{o.T.} = 12,670 \#'$
 $M_R = 2,800 \#'$
 $0.6 M_R = 1,680 \#'$
 $M_{NET} = 11,470 \#'$
 $T_2 = 3,277 \#$

$T_1 + T_2 = 5,064 \# < 9,230 \#$

$T_1 + T_2 = 5,412 \# < 9,230 \#$

HD28
 w/ 4x6 DF POST

HD28
 w/ 4x6 DF POST



Project/Subject

MORAN RESID.
 MERCEL ISLAND, WA,

By

A. G.

Sheet No.

L-8/14



Date

11-21

Job No.

171-1901

HOLDOWN @ R3 & R11:



UPPER LEVEL:

$M_o.T. = 62,400 \#'$
 $M_R = 14,885 \#'$
 $0.6M_R = 8,931 \#'$
 $M_{NET} = 53,469 \#'$
 $T_1 = 4,194 \# < 4,670 \#$
 HTTS HOLDOW w/ 4x6
 OR 4x6

$M_o.T. = 11,200 \#'$
 $M_R = 5,285 \#'$
 $0.6M_R = 3,171 \#'$
 $M_{NET} = 8,029 \#'$
 $T = 1,190 \#$

$M_o.T. = 4,800 \#'$
 $M_R = 1,485 \#'$
 $0.6M_R = 891 \#'$
 $M_{NET} = 3,909 \#'$
 $T = 1,042 \#$

USE: STAD 10.RS

USE: STAD 10.RS

LOWER LEVEL:

$M_o.T. = 150,400 \#'$
 $M_R = 40,165 \#'$
 $0.6M_R = 24,099 \#'$
 $M_{NET} = 126,301 \#'$
 $T = 8,148 \# < 9,230 \#$
 HDDB w/ 4x6 DF POST



Project/Subject

5000 WEST MENNER WAY
MELCEL ISLAND, WA.

By

A.G.

Sheet No.

2-9/14


Date

11-21

Job No.

171-2101

HOLDOWN @ RA & RIZ:



UPPER LEVEL:

$M_{OT} = 18,600 \#$

$M_R = 8,716 \#$

$0.6 M_R = 5,230 \#$

$M_{NET} = 13,370 \#$

$T_1 = 1,445 \#$

USE: (2) - C316

LOWER LEVEL:

4' WALL

$M_{OT} = 6,200 \#$

$M_R = 2,000 \#$

$0.6 M_R = 1,200 \#$

$M_{NET} = 5,000 \#$

$T_2 = 1,429 \#$

$T_1 + T_2 = 2,874 \#$

USE: STD. 14

8' WALL

$M_{OT} = 12,400 \#$

$M_R = 5,600 \#$


$0.6 M_R = 3,360 \#$

$M_{NET} = 9,040 \#$

$T_2 = 1,205 \#$

$T_1 + T_2 = 2,150 \#$

USE: STD. 14



Project/Subject

NONAN RESIDENCE
MEYER ISLAND, WA

By

A.G.

Sheet No.

L-10/14





Date

11-21

Job No.

171-1901


HOLD DOWN @ R5 & R13:




Project/Subject
 5000 W MERCER WAY
 MERCER ISLAND, WA

| | |
|---------------|----------------------|
| By A.G. | Sheet No. L-11/14 |
| Date 11-21 | Job No. 171-2101 |


HOLD DOWN @ N6 & N14;



USE: C516




USE: C516



$T_1 + T_2 = 3,232\# < 3,500\#$

USE: STD 14



$T_1 + T_2 = 1,591\# < 2175\#$

USE: STD 10



Project/Subject

5000 W. MELLER WAY
MELLER ISLAND, WA

By

A. G. I.

Sheet No.

2-12/14





Date

11-21

Job No.

171-2101

HOLD DOWN @ 87 & 115:



Project/Subject

5000 WEST MERCER WAY
 MERCER ISLAND, WA

By

A.G.

Sheet No.

L-13/14

Date

11-21

Job No.

171-2101

HOLD DOWN @ R9'

$$V_g = 2,160 \frac{165}{100}$$

$$M_{DT} = 2,160 \#'$$


$$M_R = 1,846 \#'$$

$$0.6 M_R = 1,108 \#'$$

$$M_{NET} = 20,492 \#'$$

$$T = 6,831 \# \quad L9,230 \#$$

HDBB w/ 4x6 DF POST



FOUNDATION DESIGN:

① TYP. EXT. CONT. FTG

$$\text{ROOF TL} = 40 \text{ PSF} \times 10' = 400 \text{ PLF}$$

$$\text{UPPER FLR} = 55 \text{ PSF} \times \frac{14'}{2} = 385$$

$$\text{MAIN FLR} = 55 \text{ PSF} \times \frac{14'}{2} = 385$$

$$\text{FOUND. WALL} = 150 \times \frac{8''}{12} \times 6' = 600$$

$$\text{FTG} = 150 \times \frac{8''}{12} \times 1.5' = 150$$

$$\text{TL} = 1920 \text{ PLF} < 1500 \text{ PSF} \times 1.5' = 2250 \text{ PLF}$$

② TYP. INT. CONT. FTG

$$\text{ROOF TL} = 40 \text{ PSF} \times 18' = 720 \text{ PLF}$$

$$\text{UPPER FLR} = 55 \text{ PSF} \times \frac{19'}{2} = 522$$

$$\text{MAIN FLR} = 55 \times \frac{17'}{2} = 468$$

$$\text{FOUND. WALL} = 150 \times \frac{8''}{12} \times 4' = 400$$

$$\text{FTG} = 150 \times \frac{8''}{12} \times 1.5' = 150$$

$$2260 \text{ PLF}$$

USE 2'-0" WIDE CONT. FTG

$$1500 \times 2 = 3000 \text{ PLF} > 2260 \text{ PLF}$$

O.K.



Project/Subject

MORAN RESID,
MERCER ISLAND, WA

By

A.G.

Sheet No.

F-1/3

Date

11-21

Job No.

171-1901

③ TYP. INT. PAD FTG -

$$\text{UPPER FLR} = 55 \text{ PSF} \times \frac{18'}{2} \times 8' = 3960 \#$$

$$\text{LOWER FLR} = 55 \text{ PSF} \times \frac{18'}{2} \times 8' = 3960 \#$$

$$\text{FTG DL} = 150 \times \frac{10''}{12} \times 2.5' \times 2.5' = 780 \#$$

$$\text{TL} = 8700 \#$$

$$3012 \text{ BRG} = 1500 \text{ PSF}$$

$$\text{Area'd} = 8700 / 1500 = 5.8 \text{ sf}^2$$

$$2'-6'' \times 2'-6'' \times 10''$$

W/ (3) - #4 E.W.

④ TYP. EXT. FTG @ CASCHMENT WALL -

$$\text{ROOF TL} = 40 \text{ PSF} \times 10' = 400 \text{ PLF}$$

$$\text{UPPER FLR} = 55 \text{ PSF} \times 14' / 2 = 385$$

$$\text{MAIN FLR} = 55 \text{ PSF} \times 14' / 2 = 385$$

$$\text{FOURD. WALL} = 150 \times 1' \times 6' = 900$$

$$\text{FTG} = 150 \times \frac{10''}{12} \times 2' = 250$$

$$\text{TL} = 2320 \text{ PLF}$$

USE 2'-0" WIDE CONT. FTG



Project/Subject

MORAN BESSD.
MERCER ISLAND, WA

By

A.G.

Sheet No.

F-2/3

Date

11-21

Job No.

171-1901

⑤ INT. PAD FTG BELOW DECK/FOYER:

$$P_{T2} = 5.94 \text{ K} \times 2 = 11.88 \text{ K}$$

↑ FROM MFB-4

$$\text{Area} = 11.88 / 1.5 = 7.92 \text{ SF} \approx$$

$$3'-0" \times 3'-0" \times 12"$$

W/ (4) - #4 E.W.

KIA CO



Project/Subject

MORAD RESID.
MECCER ISLAND, WA

By

A.G.

Sheet No.

F-3/3

Date

11-21

Job No.

171-1901

Project Title: Moran Residence
 Engineer: KIA CO
 Project ID: 171-2101
 Project Descr:

Cantilevered Retaining Wall

File: 171-2101.ec6
 Software copyright ENERCALC, INC. 1983-2020, Build:12.20.8.24

Lic. #: KW-06009143

Kia CO

DESCRIPTION: 4' Building Ret. wall, without building load and Seismic

Calculations per ACI 318-14, TMS 402-16, IBC 2018,
 CBC 2019, ASCE 7-16

Criteria

| | | |
|--|---|----------|
| Retained Height | = | 3.00 ft |
| Wall height above soil | = | 0.00 ft |
| Slope Behind Wall | = | 0.00 : 1 |
| Height of Soil over Toe | = | 12.00 in |
| Water height over heel | = | 0.0 ft |
| Vertical component of active Lateral soil pressure options: | | |
| NOT USED for Soil Pressure. | | |
| NOT USED for Sliding Resistance. | | |
| NOT USED for Overturning Resistance. | | |

Soil Data

| | | |
|---|---|--------------|
| Allow Soil Bearing | = | 1,500.0 psf |
| Equivalent Fluid Pressure Method | | |
| Heel Active Pressure | = | 45.0 psf/ft |
| Toe Active Pressure | = | 30.0 psf/ft |
| Passive Pressure | = | 200.0 psf/ft |
| Soil Density, Heel | = | 110.00 pcf |
| Soil Density, Toe | = | 110.00 pcf |
| Friction Coeff btwn Ftg & Soil | = | 0.350 |
| Soil height to ignore for passive pressure | = | 0.00 in |

Design Summary

Wall Stability Ratios

| | | |
|--|-----|------------|
| Overturning | = | 3.43 OK |
| Sliding | = | 2.59 OK |
| Total Bearing Load | = | 1,078 lbs |
| ...resultant ecc. | = | 3.12 in |
| Soil Pressure @ Toe | = | 700 psf OK |
| Soil Pressure @ Heel | = | 162 psf OK |
| Allowable | = | 1,500 psf |
| Soil Pressure Less Than Allowable | | |
| ACI Factored @ Toe | = | 841 psf |
| ACI Factored @ Heel | = | 195 psf |
| Footing Shear @ Toe | = | 0.9 psi OK |
| Footing Shear @ Heel | = | 4.6 psi OK |
| Allowable | = | 82.2 psi |
| Sliding Calcs (Vertical Component NOT Used) | | |
| Lateral Sliding Force | = | 300.0 lbs |
| less 100% Passive Force | = - | 400.0 lbs |
| less 100% Friction Force | = - | 370.0 lbs |
| Added Force Req'd | = | 0.0 lbs OK |
| ...for 1.5 : 1 Stability | = | 0.0 lbs OK |

Stem Construction

Design Height Above Ftg

| | |
|--------------------------|-------------|
| ft = | 0.00 |
| Wall Material Above "Ht" | = Concrete |
| Thickness | in = 8.00 |
| Rebar Size | = # 5 |
| Rebar Spacing | in = 16.00 |
| Rebar Placed at | = User Spec |

Design Data

| | | |
|-------------------------|--------|---------|
| fb/FB + fa/Fa | = | 0.057 |
| Total Force @ Section | lbs = | 300.0 |
| Moment....Actual | ft-l = | 316.0 |
| Moment....Allowable | ft-l = | 5,515.2 |
| Shear.....Actual | psi = | 4.5 |
| Shear.....Allowable | psi = | 82.2 |
| Wall Weight | psf = | 100.0 |
| Rebar Depth 'd' | in = | 5.50 |
| Lap splice if above | in = | 12.00 |
| Lap splice if below | in = | 6.00 |
| Hook embed into footing | in = | 6.00 |

Concrete Data

| | | |
|-----|-------|---------|
| f'c | psi = | 3,000.0 |
| Fy | psi = | |

Top Stem

Stem OK

Load Factors

| | |
|------------|-------|
| Dead Load | 1.200 |
| Live Load | 1.600 |
| Earth, H | 1.600 |
| Wind, W | 1.600 |
| Seismic, E | 1.000 |

RTW-1/6

Cantilevered Retaining Wall

DESCRIPTION: 4' Building Ret. wall, without building load and Seismic

Footing Dimensions & Strengths

| | | |
|--------------------------|---|----------------------|
| Toe Width | = | 0.92 ft |
| Heel Width | = | 1.58 |
| Total Footing Width | = | 2.50 |
| Footing Thickness | = | 12.00 in |
| Key Width | = | 0.00 in |
| Key Depth | = | 0.00 in |
| Key Distance from Toe | = | 0.00 ft |
| f _c | = | 3,000 psi |
| Footing Concrete Density | = | 150.00 pcf |
| Min. As % | = | 0.0018 |
| Cover @ Top | = | 2.00 @ Btm.= 3.00 in |
| F _y | = | 60,000 psi |

Footing Design Results

| | Toe | Heel |
|--------------------|------------------|-----------|
| Factored Pressure | = 841 | 195 psf |
| Mu' : Upward | = 320 | 0 ft-lb |
| Mu' : Downward | = 131 | 242 ft-lb |
| Mu: Design | = 189 | 242 ft-lb |
| Actual 1-Way Shear | = 0.93 | 4.63 psi |
| Allow 1-Way Shear | = 82.16 | 82.16 psi |
| Toe Reinforcing | = # 5 @ 16.00 in | |
| Heel Reinforcing | = # 5 @ 16.00 in | |
| Key Reinforcing | = None Spec'd | |

Other Acceptable Sizes & Spacings

Toe: Not req'd, Mu < S * Fr
 Heel: Not req'd, Mu < S * Fr
 Key: No key defined

Summary of Overturning & Resisting Forces & Moments

| Item |OVERTURNING..... | | | |RESISTING..... | | |
|---|-----------------------|---------------|--------------|---------------------------|---------------------|---------------|----------------|
| | Force lbs | Distance ft | Moment ft-lb | | Force lbs | Distance ft | Moment ft-lb |
| Heel Active Pressure | = 360.0 | 1.33 | 480.0 | Soil Over Heel | = 302.5 | 2.04 | 617.6 |
| Surcharge over Heel | = | | | Sloped Soil Over Heel | = | | |
| Toe Active Pressure | = -60.0 | 0.67 | -40.0 | Surcharge Over Heel | = | | |
| Surcharge Over Toe | = | | | Adjacent Footing Load | = | | |
| Adjacent Footing Load | = | | | Axial Dead Load on Stem | = | | |
| Added Lateral Load | = | | | * Axial Live Load on Stem | = | | |
| Load @ Stem Above Soil | = | | | Soil Over Toe | = 100.8 | 0.46 | 46.2 |
| | | | | Surcharge Over Toe | = | | |
| | | | | Stem Weight(s) | = 300.0 | 1.25 | 375.0 |
| | | | | Earth @ Stem Transitions | = | | |
| | | | | Footing Weight | = 375.0 | 1.25 | 468.8 |
| | | | | Key Weight | = | | |
| | | | | Vert. Component | = | | |
| Total | = 300.0 | O.T.M. | = 440.0 | | | | |
| Resisting/Overturning Ratio | | = | 3.43 | | | | |
| Vertical Loads used for Soil Pressure = | | 1,078.3 lbs | | | | | |
| | | | | Total = | 1,078.3 lbs | R.M. = | 1,507.6 |

* Axial live load NOT included in total displayed, or used for overturning resistance, but is included for soil pressure calculation.

RTW-2/6

Cantilevered Retaining Wall

Lic. #: KW-06009143

DESCRIPTION: 6' Building Ret. wall, without building load and Seismic

Calculations per ACI 318-14, TMS 402-16, IBC 2018,
 CBC 2019, ASCE 7-16

Criteria

| | | |
|--|---|----------|
| Retained Height | = | 5.00 ft |
| Wall height above soil | = | 0.00 ft |
| Slope Behind Wall | = | 0.00 : 1 |
| Height of Soil over Toe | = | 12.00 in |
| Water height over heel | = | 0.0 ft |
| Vertical component of active Lateral soil pressure options: | | |
| NOT USED for Soil Pressure. | | |
| NOT USED for Sliding Resistance. | | |
| NOT USED for Overturning Resistance. | | |

Soil Data

| | | |
|---|---|--------------|
| Allow Soil Bearing | = | 1,500.0 psf |
| Equivalent Fluid Pressure Method | | |
| Heel Active Pressure | = | 45.0 psf/ft |
| Toe Active Pressure | = | 30.0 psf/ft |
| Passive Pressure | = | 200.0 psf/ft |
| Soil Density, Heel | = | 110.00 pcf |
| Soil Density, Toe | = | 110.00 pcf |
| Friction Coeff btwn Ftg & Soil | = | 0.350 |
| Soil height to ignore for passive pressure | = | 0.00 in |

Design Summary

Wall Stability Ratios

| | | |
|--|-----|----------------------|
| Overturning | = | 2.94 OK |
| Sliding | = | 1.50 OK |
| Total Bearing Load ...resultant ecc. | = | 2,079 lbs 4.80 in |
| Soil Pressure @ Toe | = | 910 psf OK |
| Soil Pressure @ Heel | = | 200 psf OK |
| Allowable | = | 1,500 psf |
| Soil Pressure Less Than Allowable | | |
| ACI Factored @ Toe | = | 1,092 psf |
| ACI Factored @ Heel | = | 240 psf |
| Footing Shear @ Toe | = | 5.2 psi OK |
| Footing Shear @ Heel | = | 11.4 psi OK |
| Allowable | = | 82.2 psi |
| Sliding Calcs (Vertical Component NOT Used) | | |
| Lateral Sliding Force | = | 750.0 lbs |
| less 100% Passive Force | = - | 400.0 lbs |
| less 100% Friction Force | = - | 720.8 lbs |
| Added Force Req'd | = | 0.0 lbs OK |
| ...for 1.5 : 1 Stability | = | 0.0 lbs OK |

Load Factors

| | |
|------------|-------|
| Dead Load | 1.200 |
| Live Load | 1.600 |
| Earth, H | 1.600 |
| Wind, W | 1.600 |
| Seismic, E | 1.000 |

Stem Construction

| | | |
|--------------------------------|------|-----------|
| Design Height Above Ftg | ft = | 0.00 |
| Wall Material Above "Ht" | = | Concrete |
| Thickness | in = | 8.00 |
| Rebar Size | = | # 5 |
| Rebar Spacing | in = | 12.00 |
| Rebar Placed at | = | User Spec |

Design Data

| | | |
|-------------------------|--------|---------|
| fb/FB + fa/Fa | = | 0.206 |
| Total Force @ Section | lbs = | 876.0 |
| Moment....Actual | ft-l = | 1,492.0 |
| Moment....Allowable | ft-l = | 7,247.3 |
| Shear....Actual | psi = | 13.3 |
| Shear....Allowable | psi = | 82.2 |
| Wall Weight | psf = | 100.0 |
| Rebar Depth 'd' | in = | 5.50 |
| Lap splice if above | in = | 12.00 |
| Lap splice if below | in = | 6.00 |
| Hook embed into footing | in = | 6.00 |

Concrete Data

| | | |
|----------------|-------|---------|
| f _c | psi = | 3,000.0 |
| F _y | psi = | |

RTW-3/6

Project Title: Moran Residence
 Engineer: KIA CO
 Project ID: 171-2101
 Project Descr:

Cantilevered Retaining Wall

File: 171-2101.ec6
 Software copyright ENERCALC, INC. 1983-2020, Build:12.20.8.24
 Kia CO

Lic. #: KW-06009143

DESCRIPTION: 6' Building Ret. wall, without building load and Seismic

Footing Dimensions & Strengths

Toe Width = 1.54 ft
 Heel Width = 2.21 ft
 Total Footing Width = 3.75 ft
 Footing Thickness = 12.00 in
 Key Width = 0.00 in
 Key Depth = 0.00 in
 Key Distance from Toe = 5.17 ft
 f'c = 3,000 psi Fy = 60,000 psi
 Footing Concrete Density = 150.00 pcf
 Min. As % = 0.0018
 Cover @ Top 2.00 @ Btm. = 3.00 in

Footing Design Results

| | Toe | Heel |
|--------------------|------------------|-----------|
| Factored Pressure | = 1,092 | 240 psf |
| Mu' : Upward | = 1,158 | 0 ft-lb |
| Mu' : Downward | = 371 | 998 ft-lb |
| Mu: Design | = 787 | 998 ft-lb |
| Actual 1-Way Shear | = 5.23 | 11.36 psi |
| Allow 1-Way Shear | = 82.16 | 82.16 psi |
| Toe Reinforcing | = # 5 @ 12.00 in | |
| Heel Reinforcing | = # 5 @ 12.00 in | |
| Key Reinforcing | = None Spec'd | |

Other Acceptable Sizes & Spacings

Toe: Not req'd, $Mu < S * Fr$
 Heel: Not req'd, $Mu < S * Fr$
 Key: No key defined

Summary of Overturning & Resisting Forces & Moments

| Item |OVERTURNING..... | | | |RESISTING..... | | |
|---|-----------------------|-----------------|-----------------|---------------------------|---------------------|----------------|-----------------|
| | Force lbs | Distance ft | Moment ft-lb | | Force lbs | Distance ft | Moment ft-lb |
| Heel Active Pressure | = 810.0 | 2.00 | 1,620.0 | Soil Over Heel | = 847.6 | 2.98 | 2,524.5 |
| Surcharge over Heel | = | | | Sloped Soil Over Heel | = | | |
| Toe Active Pressure | = -60.0 | 0.67 | -40.0 | Surcharge Over Heel | = | | |
| Surcharge Over Toe | = | | | Adjacent Footing Load | = | | |
| Adjacent Footing Load | = | | | Axial Dead Load on Stem | = | | |
| Added Lateral Load | = | | | * Axial Live Load on Stem | = | | |
| Load @ Stem Above Soil | = | | | Soil Over Toe | = 169.5 | 0.77 | 130.6 |
| | | | | Surcharge Over Toe | = | | |
| | | | | Stem Weight(s) | = 500.0 | 1.87 | 937.2 |
| | | | | Earth @ Stem Transitions | = | | |
| | | | | Footing Weight | = 562.3 | 1.87 | 1,054.1 |
| | | | | Key Weight | = | 5.17 | |
| | | | | Vert. Component | = | | |
| Total | = 750.0 | O.T.M. = | 1,580.0 | Total = | 2,079.5 lbs | R.M. = | 4,646.5 |
| Resisting/Overturing Ratio | = | 2.94 | | | | | |
| Vertical Loads used for Soil Pressure = | | 2,079.5 lbs | | | | | |

* Axial live load NOT included in total displayed, or used for overturning resistance, but is included for soil pressure calculation.

RT-A/B

Project Title: Moran Residence
 Engineer: KIA CO
 Project ID: 171-2101
 Project Descr:

Cantilevered Retaining Wall

File: 171-2101.ec6
 Software copyright ENERCALC, INC. 1983-2020, Build:12.20.8.24

Lic. #: KW-06009143

Kia CO

DESCRIPTION: 8' Building Ret. wall, without building load and Seismic

Calculations per ACI 318-14, TMS 402-16, IBC 2018,
 CBC 2019, ASCE 7-16

Criteria

Retained Height = 6.83 ft
 Wall height above soil = 0.00 ft
 Slope Behind Wall = 0.00 : 1
 Height of Soil over Toe = 12.00 in
 Water height over heel = 0.0 ft
 Vertical component of active
 Lateral soil pressure options:
 NOT USED for Soil Pressure.
 NOT USED for Sliding Resistance.
 NOT USED for Overturning Resistance.

Soil Data

Allow Soil Bearing = 1,500.0 psf
 Equivalent Fluid Pressure Method
 Heel Active Pressure = 45.0 psf/ft
 Toe Active Pressure = 30.0 psf/ft
 Passive Pressure = 200.0 psf/ft
 Soil Density, Heel = 110.00 pcf
 Soil Density, Toe = 110.00 pcf
 Friction Coeff btwn Ftg & Soil = 0.350
 Soil height to ignore
 for passive pressure = 0.00 in

Design Summary

Wall Stability Ratios

Overturning = 3.74 OK
 Sliding = 1.38 Ratio < 1.5!

Total Bearing Load = 4,065 lbs
 ...resultant ecc. = 3.87 in

Soil Pressure @ Toe = 945 psf OK
 Soil Pressure @ Heel = 469 psf OK
 Allowable = 1,500 psf
 Soil Pressure Less Than Allowable

ACI Factored @ Toe = 1,134 psf
 ACI Factored @ Heel = 563 psf
 Footing Shear @ Toe = 7.4 psi OK
 Footing Shear @ Heel = 22.8 psi OK
 Allowable = 82.2 psi

Sliding Calcs (Vertical Component NOT Used)

Lateral Sliding Force = 1,368.4 lbs
 less 100% Passive Force = - 469.4 lbs
 less 100% Friction Force = - 1,420.9 lbs
 Added Force Req'd = 0.0 lbs OK
for 1.5 : 1 Stability = 160.2 lbs NG

Load Factors

Dead Load 1.200
 Live Load 1.600
 Earth, H 1.600
 Wind, W 1.600
 Seismic, E 1.000

Stem Construction

Design Height Above Ftg

ft = 0.00
 Wall Material Above "Ht" = Concrete
 Thickness in = 8.00
 Rebar Size = # 5
 Rebar Spacing in = 12.00
 Rebar Placed at = User Spec

Design Data

fb/FB + fa/Fa = 0.526
 Total Force @ Section lbs = 1,655.4
 Moment....Actual ft-l = 3,815.3
 Moment....Allowable ft-l = 7,247.3
 Shear....Actual psi = 25.1
 Shear....Allowable psi = 82.2
 Wall Weight psf = 100.0
 Rebar Depth 'd' in = 5.50
 Lap splice if above in = 12.00
 Lap splice if below in = 9.59
 Hook embed into footing in = 9.59

Concrete Data

f_c psi = 3,000.0
 F_y psi =

Top Stem

Stem OK

RT-5/6

Cantilevered Retaining Wall

File: 171-2101.ec6

Lic. #: KW-06009143

Software copyright ENERCALC, INC. 1983-2020, Build:12.20.8.24

Kia CO

DESCRIPTION: 8' Building Ret. wall, without building load and Seismic

Footing Dimensions & Strengths

| | | | |
|--------------------------|--------|--------|-----|
| Toe Width | = | 2.25 | ft |
| Heel Width | = | 3.50 | |
| Total Footing Width | = | 5.75 | |
| Footing Thickness | = | 14.00 | in |
| Key Width | = | 0.00 | in |
| Key Depth | = | 0.00 | in |
| Key Distance from Toe | = | 5.17 | ft |
| f'_c = | 3,000 | psi | |
| F_y = | 60,000 | psi | |
| Footing Concrete Density | = | 150.00 | pcf |
| Min. As % | = | 0.0018 | |
| Cover @ Top | 2.00 | | |
| @ Btm. | = | 3.00 | in |

Footing Design Results

| | Toe | Heel |
|--------------------|------------------|-------------|
| Factored Pressure | = 1,134 | 563 psf |
| Mu' : Upward | = 2,682 | 0 ft-lb |
| Mu' : Downward | = 866 | 0 ft-lb |
| Mu: Design | = 1,817 | 3,815 ft-lb |
| Actual 1-Way Shear | = 7.42 | 22.82 psi |
| Allow 1-Way Shear | = 82.16 | 82.16 psi |
| Toe Reinforcing | = # 5 @ 12.00 in | |
| Heel Reinforcing | = # 5 @ 12.00 in | |
| Key Reinforcing | = None Spec'd | |

Other Acceptable Sizes & Spacings

Toe: Not req'd, $\mu < S * Fr$
 Heel: Not req'd, $\mu < S * Fr$
 Key: No key defined

Summary of Overturning & Resisting Forces & Moments

| Item |OVERTURNING..... | | | |RESISTING..... | | |
|---|-----------------------|----------------|-----------------|---------------------------|---------------------|-----------------|-----------------|
| | Force lbs | Distance ft | Moment ft-lb | | Force lbs | Distance ft | Moment ft-lb |
| Heel Active Pressure | = 1,438.8 | 2.67 | 3,835.2 | Soil Over Heel | = 2,128.7 | 4.33 | 9,224.3 |
| Surcharge over Heel | = | | | Sloped Soil Over Heel | = | | |
| Toe Active Pressure | = -70.4 | 0.72 | -50.9 | Surcharge Over Heel | = | | |
| Surcharge Over Toe | = | | | Adjacent Footing Load | = | | |
| Adjacent Footing Load | = | | | Axial Dead Load on Stem | = | | |
| Added Lateral Load | = | | | * Axial Live Load on Stem | = | | |
| Load @ Stem Above Soil | = | | | Soil Over Toe | = 247.5 | 1.13 | 278.4 |
| | | | | Surcharge Over Toe | = | | |
| | | | | Stem Weight(s) | = 683.0 | 2.58 | 1,764.4 |
| | | | | Earth @ Stem Transitions | = | | |
| | | | | Footing Weight | = 1,006.3 | 2.88 | 2,893.0 |
| | | | | Key Weight | = | 5.17 | |
| | | | | Vert. Component | = | | |
| Total | = 1,368.4 | O.T.M. | = 3,784.3 | Total | = 4,065.4 | lbs R.M. | = 14,160.1 |
| Resisting/Overturning Ratio | | = | 3.74 | | | | |
| Vertical Loads used for Soil Pressure = | | 4,065.4 | lbs | | | | |

* Axial live load NOT included in total displayed, or used for overturning resistance, but is included for soil pressure calculation.

ET-6/6