

CITY OF MERCER ISLAND

Fire Marshal's Office

3030 78th Ave SE | MERCER ISLAND, WA 98040 PHONE:

206.275.7966 | www.mercerisland.gov | V.2021-1



2022 RESIDENTIAL FIRE AREA SQUARE FOOTAGE CALCULATION

| | | | | |
|---|--|-------------------------------------|-----------------------------------|-----------------------------------|
| Project Type: <input checked="" type="checkbox"/> New Single Family | | <input type="checkbox"/> Alteration | <input type="checkbox"/> Addition | <input type="checkbox"/> ADU/DADU |
| Project Address: 8822 SE 62nd st, Mercer Island, wa | | | | |
| Contact Name: Ned Nelson, Architect | | Phone No. 425.444.6782 | | |
| Owner Name: Greg/Jennifer Headrick | | 206.999.73733582 | | |

Gross floor area shall be that area in square feet under the roof line of the structure including all usable area whether heated or not, above and below grade. This includes the garage and any unheated storage rooms or attachments including covered decks. If it is *usable space*, then it is included in the Gross square footage calculation. *This is not the same calculation for floor area ratio.*

For all construction types, add all the interior wall measurements of each floor and the basement and total that figure.

CONSTRUCTION VALUATION TYPE (verified with permit application)

| | | | |
|-------------------------------|------------------------------------|---|--|
| Good \$185.94 sq/ft | Very Good \$237.59 sq/ft | Very Good Custom \$289.24 sq/ft | Luxury Custom \$392.54 sq/ft |
| Select One: | | 289.24 | |

* Hit enter when done

NEW CONSTRUCTION (over for addition or alteration)

| | | | |
|--------------------------|--------------------------|--|-----------------------|
| <input type="checkbox"/> | N/A | | |
| | Measurements | | Square Footage |
| | Main Floor interior | | 3587 SF |
| | Lower Floor Interior | | |
| | Other Floors interior | | 1634SF |
| | Basement interior | | 1503SF |
| | Attached Garage interior | | 1114 SF |
| | Covered Decks interior | | |
| | Other interior | | |
| | TOTALS | | 7,838.00 |

ADDITION or ALTERATION

Does this house have an existing Fire Sprinkler System? Yes No / NFPA 72 Alarm System Yes No

| Measurements | Existing Square Footage | Standardized Value | Final Square Footage |
|--------------------------|-------------------------|---------------------------|----------------------|
| Main Floor interior | | x \$ 289.24 sq/ft \$ 0.00 | |
| Lower Floor Interior | | x \$ 289.24 sq/ft \$ 0.00 | |
| Other Floors interior | | x \$ 289.24 sq/ft \$ 0.00 | |
| Basement interior | | x \$ 289.24 sq/ft \$ 0.00 | |
| Attached Garage interior | | x \$ 38.97 sq/ft \$ 0.00 | |
| Covered Decks interior | | x \$ 38.97 sq/ft \$ 0.00 | |
| Other interior | | x \$ 289.24 sq/ft \$ 0.00 | |
| TOTALS | 0.00 | \$0.00 | 0.00 |

Construction Cost \$ _____

Official Use

Verified Cost \$ _____

Higher of Verified or Cost \$ _____ / Value \$ 0.00 = % 0

Valuation Ratio

Exempt structure - detached garage or similar structure less than 750 sf.

Less than 10% (fire review not required)

10 - 49% (monitored Household Fire Alarm System per NFPA 72 Chapter 29, if fire deficiency)

50% or greater (substantial alteration)

2018 INT'L FIRE CODE

901.4.4 Additional Fire Protection Systems. In occupancies of a hazardous nature, where special hazards exist in addition to the normal hazards of the occupancy, or where the fire code official determines that access for fire apparatus is unduly difficult, the fire code official shall have the authority to require additional safeguards. Such safeguards include, but shall not be limited to, the following:

- Automatic fire detection systems,
- Fire alarm systems,
- Automatic fire-extinguishing systems,
- Standpipe systems, or
- Portable or fixed extinguishers.

Fire protection equipment required under this section shall be installed in

accordance with this code and the applicable referenced standards.

2018 INT'L RESIDENTIAL CODE

AV107.1 Fire Sprinklers. An approved automatic fire sprinkler system shall be installed in new one-family and two-family dwellings and townhouses in accordance with Appendix Q.

AV107.2 Fire Sprinklers in Existing Buildings. An approved automatic fire sprinkler system shall be installed throughout the residence in existing one-family and two-family dwellings (and townhouses) in accordance with Appendix Q when undergoing a remodel or addition when the construction value of all additions, alterations or repairs performed within

a sixty-month period exceeds 50% of the value of the residence. Value shall be determined by a method approved by the fire code official.

AV107.3 Household Fire Alarm System. An approved household fire alarm system shall be installed throughout the residence in existing one-family and two-family dwellings (and townhouses) that have deficiencies in fire flow, hydrants or access. This system shall be installed in accordance with NFPA 72 Chapter 29 when undergoing a remodel or addition when the construction value of all additions, alterations or repairs performed within a sixty-month period is within 10% to 50% of the value of the residence. Value shall be determined by a method approved by the fire code official.