



QUANTUM | CONSULTING ENGINEERS

STRUCTURAL DESIGN CRITERIA

BRINDLEY RESIDENCE DETENTION VAULT
79TH AVE SE,
MERCER IS, WA, 98040.

QUANTUM JOB NUMBER: 21482.01

CODE CRITERIA:

BUILDING CODE	2018 INTERNATIONAL BUILDING CODE
BUILDING DEPARTMENT.....	MERCER ISLAND
DRIVE WAY LIVE LOAD.....	..250 PSF
SOIL WEIGHT	150 PCF

SOILS CRITERIA:

ALLOWABLE BEARING PRESSURE	2,500 PSF
MINIMUM FOOTING WIDTH	CONTINUOUS: 16" MIN., ISOLATED: 24" MIN.
FROST DEPTH	18" MIN.
PASSIVE SOIL PRESSURE.....	300 PCF
COEFFICIENT OF FRICTION.....	0.50 PCF

MATERIALS CRITERIA:

CONCRETE (28 DAY STRENGTH):

FOUNDATION/S.O.G.....	F'C=4,000 PSI
-----------------------	---------------

REINFORCING STEEL:

GRADE 60	FY=60,000 PSI
----------------	---------------