



Watering plan for Jaffe replacement trees: Addendum to arborist report 4/4/2023

1. Above ground soaker hoses to be installed around each replacement tree. Smaller diameter trees to have hose looped around them once and larger diameter trees to have hose looped around them twice. If using hoses with emitters then multiple emitters are required for larger trees.
2. Watering times will depend on soaker hose system but deeper, less frequent waterings is ideal (possibly a couple of hours once or twice per week.) Check soil periodically to determine how deeply the water is soaking in. Trees that are planted near other large, established trees will likely need more water.
3. Watering to be applied for at least two full seasons (April - October or longer if little rainfall.)
4. 2-3" mulch to be applied over soaker hoses to aid water retention. Care should be taken to keep soaker hose and mulch away from the trunks.