



Supplemental Structural Calculations For:

# Jaffe Residence

## Remodel and Addition

8455 SE 83<sup>rd</sup> St.

Mercer Island, WA 98040



Prepared for: Suyama Peterson Deguchi

Job #: 00043-2022-03

Date: April 5, 2023



SEATTLE  
TACOMA

2124 Third Ave, Suite 100, Seattle, WA 98121  
934 Broadway, Suite 100, Tacoma, WA 98402

○ 206.443.6212  
○ 253.284.9470

⊕ [ssfengineers.com](http://ssfengineers.com)

# SEISMIC WEIGHT

$$W_s(\text{Roof}) = \text{Roof} + 10\text{AW}$$

$$= 15(4210 \text{ S.F.}) + 10(375 \text{ S.F.})$$

$$= 93.900 \text{ k}$$

REVISED SEISMIC WEIGHT  
 $W_s(\text{Roof}) = 15(4160 \text{ SF}) + 10(2980 \text{ PSF})$   
 $= 92.2 \text{ kips}$   
 --> USE ORIGINAL VALUE OF 93.9 kips

NOTE: DAYLIT BUILDING w/ MAIN FLOOR AT GRAB3.  
 THEREFORE BASE SHEAR TAKEN AT MAIN FLOOR

## SEISMIC STORY SHEAR ( $\rho = 1.3$ , ASD, $C_s = 0.181$ )

$$V_s(\text{Roof}) = 15.43 \text{ kips}$$

## WIND LOADING (B-F HEIGHT)

$$W_w(\text{Roof}) = (4.5 \text{ ft} + 0.75(10 \text{ ft}))(12.42 \text{ PSF})$$

$$= 149.04 \text{ PLF}$$

## WIND LOADING ( $K_{zt} = 1.0$ , ASD, $V = 98 \text{ MPH}$ , EXP. C)

NORTH/SOUTH ( $L_f = 95.75 \text{ ft}$ )      EAST/WEST ( $L_f = 47.75 \text{ ft}$ )


$$V_w = 14.27 \text{ k}$$

$$V_w = 7.12 \text{ k}$$


WIND LOADING IS UNCHANGED.

BY OBSERVATION, SEISMIC GOV'S FOR BOTH DIRECTIONS

## DIVISION OF SEISMIC WEIGHT BY AREA




$A(I) = 715 \text{ S.F.}$	$V(I)_g = 0.233$	$V(I) = 3.60 \text{ k}$
$A(II) = 940 \text{ S.F.}$	$V(II)_g = 0.306$	$V(II) = 4.72 \text{ k}$
$A(III) = 1420 \text{ S.F.}$	$V(III)_g = 0.461$	$V(III) = 7.11 \text{ k}$
$\Sigma A = 3775 \text{ S.F.}$	$V_g = 1.00 \text{ :OK}$	$\Sigma V = 15.43 \text{ k} \text{ :OK}$



JAHE RESIDENCES Revised  
 PROJECT  
 LATERAL LOADING (WINDS + SEISMIC)

DATE 7/11/22 04-05-2023  
 PROJ. # VMS ETC  
 DESIGN  
 SHEET 2  
 01



Jaffe Residence - Permit Correction #1

PROJECT  
Revised Lateral Key Plan - Roof


04-05-2023


DATE  
00043-2022-03

PROJ. #  
ETC

DESIGN  
02

SHEET





Jaffe Residence - Permit Correction #1

PROJECT  
Revised Lateral Key Plan - Floor


04-05-2023

DATE  
00043-2022-03

PROJ. #  
ETC

DESIGN  
03

SHEET



LATERAL DESIGN (SHEAR WALLS, N/E)

$v(1) = 0.67 \text{ k (E)}$   
 $0.89 \text{ k (W)}$

$L_w = 16.25 \text{ ft}$

$r = 55 \text{ \# / ft}$

S.W. = (W6)

OT = 0.49 k

OTR = 0.56 k

OT' = 0

H<sub>b</sub> = (NO OT)

USE H<sub>b02</sub>

$v(2) = 2.99 \text{ k (E)}$   
 $2.60 \text{ k (W)}$

$L_w = 17.5 \text{ ft}$

$r = 171 \text{ \# / ft}$

S.W. = (W6)

OT = 1.54 k

OTR = 0.79 k

OT' = 0.75 k

H<sub>b</sub> = (H<sub>b02</sub>)

$v(4) = 3.70 \text{ k (E)}$   
 $3.49 \text{ k (W)}$

$L_w = 30.5 \text{ ft}$

$r = 121 \text{ \# / ft}$

S.W. = (W6)

OT = 1.09 k

OTR = 0.63 k

OT' = 0.46 k

H<sub>b</sub> = (H<sub>b02</sub>)

CR16

$v(7) = 4.32 \text{ k (E)}$   
 $3.55 \text{ k (W)}$

$L_w = 15 \text{ ft}$

$r = 288 \text{ \# / ft}$

S.W. = (W4)

OT = 2.59 k

OTR = 0.68 k

OT' = 1.91 k

H<sub>b</sub> = (H<sub>b02</sub>)

REVISED ON FOLLOWING PAGE REVISED ON FOLLOWING PAGE REVISED ON FOLLOWING PAGE

$v(9) = 3.36 \text{ k (E)}$   
 $2.78 \text{ k (W)}$

$L_w = 15.75 \text{ ft}$

$r = 213 \text{ \# / ft}$

S.W. = (W6)

OT = 1.92 k

OTR = 0.34 k

OT' = 1.58 k

H<sub>b</sub> = H<sub>b02</sub>

$v(10) = 0.41 \text{ k (E)}$   
 $0.78 \text{ k (W)}$

$L_w = 11.75 \text{ ft}$

$r = 68 \text{ \# / ft}$

S.W. = (W6)

OT = 0.60 k

OTR = 0.53 k

OT' = 0.03 k

H<sub>b</sub> = (H<sub>b02</sub>)

DEMAND-CAPACITY RATIO FOR THE REMAINING LINES OF RESISTANCE IS EITHER UNCHANGED OR REDUCED AS A RESULT OF THE PROPOSED WORK

NO S.W. BELOW @ STACK, C-D

$L_w' = 8.25 \text{ ft}$

$r = 407 \text{ \# / ft}$


S.W. = (W8)

OT = 3.67 k

OTR = 0.37 k

OT' = 3.30 k

H<sub>b</sub> = (H<sub>b04</sub>)



JAFFS DESIGNERS Revised

PROJECT

LATERAL DESIGN - NORTH / SOUTH

DATE 7/11/22 04-05-2023  
 PROJ. # VMA ETC  
 DESIGN  
 SHEET 3 04

GRID 1 REVISED:  
(E) = (451 SF / 17'3") = 26.1 SF / FT  
(N) = (542 SF / 26'9") = 20.3 SF / FT  
DECREASED DEMAND ON (E) WALLS

TRIB AREA: 11% ZONE I

V = 0.46 k  
L = 9'6"  
v = 48 PLF  
OT = 405 LBF

SHEARWALL: W6  
HOLD DOWN: CS16

GRID 2 REVISED:

TRIB AREA:  
11% ZONE I  
10% ZONE III

V = 1.21 k  
L = 11'6"  
v = 106 PLF  
OT = 880 LBF

SHEARWALL: W6  
HOLD DOWNS: CS16

GRID 4 UPPER REVISED:

TRIB AREA:  
34% ZONE III

V = 2.57 k  
L = 17'6"  
v = 147 PLF  
OT = 1.22 k


SHEARWALL: W6  
HOLD DOWNS: CS16 / HDU2

GRID 4 LOWER REVISED:

UPPER PLUS GRID 2  
(CANTILEVER)

V = 3.78 k  
L = 21'1"  
v = 179 PLF  
OT = 1.43 k  
WHERE ALIGNED OT<sub>tot</sub> = 2.65k

SHEARWALL: W6  
HOLD DOWNS: HDU2 (HDU4  
WHERE ALIGNED)



Jaffe Residence - Permit Correction #1

PROJECT  
Lateral Design - North / South Revised

04-05-2023

DATE  
00043-2022-03

PROJ. #  
ETC

DESIGN  
05

SHEET

# LATERAL DESIGN (SHEAR WALL, E/W)

$V(G) = 1.80 \text{ k (E)}$   
WEST  $1.64 \text{ k (W)}$

$L_w = 4.5 \text{ f}$   
 $v = 400 \text{ \#/f}$   
S.W. = W3  
OT = 3.60 k  
OTR = /  
OT' = 3.60 k  
Hb = Hb04

GRID G REVISED:

L(N) = L(E) -> NO WORK

$V(F) = 2.20 \text{ k (E)}$   
EAST  $2.76 \text{ k (W)}$

$L_w = 22.5 \text{ f}$   
 $v = 123 \text{ \#/f}$   
S.W. = W6  
OT = 1.10 k  
OTR = 0.83 k  
OT' = 0.21 k  
Hb = Hb02

GRID F REVISED:

(E) OPENING INFILLED, L(N)  
> L(E) -> NO WORK. (N)  
AREA OF WALL TO BE W6

$V(D) = 7.87 \text{ k (E)}$   
 $3.56 \text{ k (W)}$

$L_w = 39.5 \text{ f}$   
 $v = 200 \text{ \#/f}$   
S.W. = W6  
OT = 1.79 k  
OTR = 0.60 k  
OT' = 1.19 k  
Hb = Hb02

GRID D REVISED:

TRIB AREA:  
40% ZONE I  
34% ZONE II  
50% ZONE III

$V = 6.71 \text{ k}$   
 $L = 39'11"$   
 $v = 172 \text{ PLF}$   
OT = 1.94 k

SHEARWALL: W6  
HOLD DOWN: HDU2 / (2) CS16

$V(A) = 3.56 \text{ k (E)}$   
 $1.56 \text{ k (W)}$

$L_w = 12.25 \text{ RDX}$   
 $v = 290 \text{ \#/f}$   
S.W. = W4  
OT = 2.62 k  
OTR = /  
OT' = 2.62 k  
Hb = Hb04 / (2) CS16

GRID A UPPER REVISED:

TRIB AREA:  
50% ZONE III

$V = 3.79 \text{ k}$   
 $L = 13'9"$   
 $v = 276 \text{ PLF}$   
OT = 2.21k

SHEARWALL: W4  
HOLD DOWNS: (2) CS16

GRID D LOWER REVISED:

ADD FLOOR DIAPHRAGM WEIGHT  
Atrib = 565 SF

$W_s = (565 \text{ SF})(12 \text{ PSF}) = 6780 \text{ LBF}$

$V_s = (6780 \text{ LBF})(0.181)(0.7)(1.3) = 1.12 \text{ k}$

$V_{tot} = (1.12 \text{ k} + (18'0" \times 172 \text{ PLF})) = 4.12 \text{ k}$

$L = 15'11"$   
 $v = 259 \text{ PLF}$   
OT = 2.07 k  
OTnet = 1.85 k

WHERE ALIGNED OTtot = 3.79 k

SHEARWALL: W4  
HOLD DOWNS: HDU2 (HDU4 WHERE ALIGNED)

GRID A LOWER REVISED:

ADD FLOOR DIAPHRAGM WEIGHT  
Atrib = (67'2" x 10'6") = 705 SF

$W_s = (705 \text{ SF})(12 \text{ PSF}) = 8460 \text{ LBF}$

$V_s = (8460 \text{ LBF})(0.181)(0.7)(1.3) = 1.39 \text{ k}$

$V_{tot} = (1.39 + 3.79) \text{ k} = 5.18 \text{ k}$

$L = 18'11"$   
 $v = 286 \text{ PLF}$   
OT = 2.29 k  
WHERE ALIGNED OTtot = 4.5k

SHEARWALL: W4  
HOLD DOWNS: HDU2 (HDU4 WHERE ALIGNED)

GRID B'


TRIB AREA:  
16% ZONE I

$V = 0.67 \text{ k}$   
 $L = 12'2"$   
 $v = 55 \text{ PLF}$   
OT = 440 LBF  
OTR = 56 PLF  
OTnet = 270 LBF

SHEARWALL: W6  
HOLD DOWNS: CS16

2124 Third Ave, Suite 100, Seattle, WA 98121 | 206.443.6212  
934 Broadway, Suite 100, Tacoma, WA 98402 | 253.284.9470  
SEATTLE TACOMA

ssfengineers.com  
SWENSON SAY FAGET




PROJECT JAFS RESIDENCE Revised  
LATERAL DESIGN - EAST/WEST

DATE 7/11/22 04-05-2023  
PROJ. # VMS ETC  
DESIGN  
SHEET 4  
06






HSS Ridge (One Side) B2*		HF 4 x 12	
w=	150 plf	R=	1,200 lbs
L=	16 ft	M=	4,800 ft-lbs
b=	3.50 in	Fb=	780 psi
d=	11.25 in	Fv=	40 psi
E=	1300 ksi	Δ=	0.41 in
Cv=	1.00 ≤1.0	I/	469




Steel Size		HSS4-1/2X4-1/2X3/8	
I=	15.3 in	Fy=	50 ksi
Δ=	0.50 in	Mn/Ω=	20.9 k-ft
I/	385	Vn/Ω=	0.0 kips


Low Ridge Transfer Btr B3a		GL 3 1/2 x 10 1/2	
w1=	10 plf	R1=	-905 lbs
w2=	10 plf	R2=	3,491 lbs
L1=	6 ft	M+=	- lb-ft
L2=	2 ft	M-=	5,852 lb-ft
X=	3.00 ft	Fb=	1,092 psi
P=	2,500 lbs	Fv=	103 psi
b=	3.50 in	Δspan=	(0.039) in
d=	10.50 in	I span/	(1,901)
E=	1,800 ksi	Δcant=	0.11 in
Cv=	1.00	I cant/	508




Entry Hdr B6*		GL 5 1/2 x 16 1/2	
w=	277 plf	R=	3,077 lbs
L=	22.25 ft	M=	17,117 ft-lbs
b=	5.50 in	Fb=	823 psi
d=	16.50 in	Fv=	45 psi
E=	1800 ksi	Δ=	0.41 in
Cv=	0.96 ≤1.0	I/	649




Dining Header B9*		GL 3 1/2 x 10 1/2	
w=	310 plf	R=	2,248 lbs
L=	14.5 ft	M=	8,147 ft-lbs
b=	3.50 in	Fb=	1,520 psi
d=	10.50 in	Fv=	81 psi
E=	1800 ksi	Δ=	0.51 in
Cv=	1.00 ≤1.0	I/	343




Coffee Bar Header B10*		GL 3 1/2 x 10 1/2	
w=	310 plf	R=	1,201 lbs
L=	7.75 ft	M=	2,327 ft-lbs
b=	3.50 in	Fb=	434 psi
d=	10.50 in	Fv=	38 psi
E=	1800 ksi	Δ=	0.04 in
Cv=	1.00 ≤1.0	I/	2246





Dressing Pocket Hdr B16		HF 4 x 10	
w1=	310 plf	R1=	1,214 lbs
w2=	310 plf	R2=	1,214 lbs
L1=	4 ft	M=	2,376 lb-ft
L2=	4 ft	Fb=	571 psi
X=	3.9 ft	Fv=	45 psi
P=	- lbs	Δ=	0.09 in
b=	3.50 in	I/	1,075
d=	9.25 in	Cv=	1.00
E=	1,300 ksi		



Guest Bed Purlin Beam B17		DF-L 6 x 10	
w=	290 plf	R=	1,970 lbs
L=	13.583 ft	M=	6,688 ft-lbs
b=	5.50 in	Fb=	1,023 psi
d=	9.25 in	Fv=	51 psi
E=	1700 ksi	Δ=	0.36 in
Cv=	1.00 ≤1.0	I/	453



West Header B18		HF 3 x 8	
w=	277 plf	R=	865 lbs
L=	6.25 ft	M=	1,351 ft-lbs
b=	3.00 in	Fb=	617 psi
d=	7.25 in	Fv=	48 psi
E=	1300 ksi	Δ=	0.08 in
Cv=	1.00 ≤1.0	I/	978



Jaffe Residence - Permit Correction #1

PROJECT  
Gravity Design - Roof

04-05-2023


DATE  
00043-2022-03

PROJ. #  
ETC


DESIGN  
08

SHEET


Coffee Bar Header		B19	HF	4	x 6
w=	83	plf	R=	320	lbs
L=	7.75	ft	M=	620	ft-lbs
b=	3.50	in	Fb=	421	psi
d=	5.50	in	Fv=	22	psi
E=	1300	ksi	Δ=	0.11	in
Cv=	1.00	≤1.0	I/	876	




Guest Bed Rafters		R3*	HF	2	x 6
w=	53	plf	R=	195	lbs
L=	7.33	ft	M=	358	ft-lbs
b=	1.50	in	Fb=	568	psi
d=	5.50	in	Fv=	31	psi
E=	1300	ksi	Δ=	0.13	in
Cv=	1.00	≤1.0	I/	686	




Ridge Transfer		B21	DF-L	3	1/2 x 9	1/4
w1=	15	plf	R1 =	1,476	lbs	
w2=	15	plf	R2 =	633	lbs	
L1=	3	ft	M =	3,887	lb-ft	
L2=	7	ft	Fb =	935	psi	
X=	2.7	ft	Fv =	68	psi	
P=	1,969	lbs	Δ=	0.10	in	
b=	3.50	in	I/	1,085		
d=	9.25	in	Cv=	1.00		
E=	1,700	ksi				





Kitchen Beam		B4*	GL	5	1/2 x 21
w1=	290	plf	R1 =	4,732	lbs
w2=	440	plf	R2 =	6,268	lbs
L1=	16	ft	M =	38,592	lb-ft
L2=	9	ft	Fb =	1,146	psi
X=	16.0	ft	Fv =	71	psi
P=	2,400	lbs	Δ=	0.50	in
b=	5.50	in	I/	599	
d=	21.00	in	Cv=	0.92	
E=	1,800	ksi			



(E) Min Ridge		B22	HF	6	x 10
w=	300	plf	R=	1,613	lbs
L=	10.75	ft	M=	4,334	ft-lbs
b=	5.50	in	Fb=	663	psi
d=	9.25	in	Fv=	41	psi
E=	1300	ksi	Δ=	0.19	in
Cv=	1.00	≤1.0	I/	675	



Awning Rafter		R2*	DF-L	2	x 6
w1=	53	plf	R1=	96	lbs
w2=	53	plf	R2=	487	lbs
L1=	6.50	ft	M+=	87	lb-ft
L2=	3.50	ft	M-=	502	lb-ft
X=	3.25	ft	Fb=	796	psi
P=	50	lbs	Fv=	41	psi
b=	1.50	in	Δspan=	(0.004)	in
d=	5.50	in	I span/	(18,756)	
E=	1,700	ksi	Δcant=	0.17	in
Cv=	1.00		I cant/	508	



Jaffe Residence - Permit Correction #1

PROJECT  
Gravity Design - Roof

04-05-2023

DATE  
00043-2022-03

PROJ. #  
ETC

DESIGN  
09

SHEET

Beam:		B3'					
Load		Dead	Live	Roof Live	Seismic	Factored	Location
Distributed (k/ft)	w <sub>1</sub>	0.160				0.160	
	w <sub>2</sub>					0.000	
	w <sub>3</sub>					0.000	
	w <sub>4</sub>					0.000	
	w <sub>5</sub>					0.000	
	w <sub>6</sub>					0.000	
	w <sub>7</sub>					0.000	
	w <sub>8</sub>					0.000	
	w <sub>9</sub>					0.000	
	w <sub>10</sub>					0.000	
Trapezoidal (k/ft/ft)	t <sub>1</sub>					0.000	
	t <sub>2</sub>					0.000	
	t <sub>3</sub>					0.000	
	t <sub>4</sub>					0.000	
	t <sub>5</sub>					0.000	
	t <sub>6</sub>					0.000	
Point (k)	P <sub>1</sub>	0.9		1.5		2.025	6.92
	P <sub>2</sub>					0.000	
	P <sub>3</sub>					0.000	
	P <sub>4</sub>					0.000	
	P <sub>5</sub>					0.000	
	P <sub>6</sub>					0.000	
	P <sub>7</sub>					0.000	
	P <sub>8</sub>					0.000	
	P <sub>9</sub>					0.000	
	P <sub>10</sub>					0.000	

SW

HSS R1

Support Locations and Reactions		
# of Supports		2
Total Beam Length		14.50
Left End Condition		Pinned
Right End Condition		Pinned
R <sub>1</sub>	1.811	0.00
R <sub>2</sub>	2.534	12.17
R <sub>3</sub>	0.000	12.17
R <sub>4</sub>	0.000	12.17
R <sub>5</sub>	0.000	12.17
R <sub>6</sub>	0.000	12.17
R <sub>7</sub>	0.000	12.17
R <sub>8</sub>	0.000	12.17
R <sub>9</sub>	0.000	12.17
R <sub>10</sub>	0.000	12.17

Demand Output	
Location, ft	14.50
Shear, k	0.00
Moment, k-ft M =	0.00
Deflection, in D =	0.15
Δ/Span	L/363


Load Factors	
Dead	1.00
Live	0.75
Roof Live	0.75
Seismic	1.00

Stresses @ Input Location	
f <sub>v</sub> (psi)	0
f <sub>b</sub> (psi)	0


Max/Min Stresses	
f <sub>v</sub> _MAX (psi)	1302
f <sub>v</sub> _MIN (psi)	-1554
f <sub>b</sub> _MAX (psi)	10224
f <sub>b</sub> _MIN (psi)	-512

Beam Properties	
E (ksi)	29000
b (in)	5.5
d (in)	9
I (in <sup>4</sup> )	26.3
S (in <sup>3</sup> )	10.2
A (in <sup>2</sup> )	1.39
I (Override)	
S (Override)	
A (Override)	

Steel Beam Section		W5x19	
F <sub>y</sub> , ksi	50		
Beam Weight (plf)	19		
Axis of Bending	Strong		
Unbr. Length (L <sub>b</sub> ), ft	0		
C <sub>b</sub>	1		
A <sub>w</sub>	1.39 in <sup>2</sup>	V <sub>n</sub> /Ω <sub>v</sub>	27.8 k
S	10.2 in <sup>3</sup>	φ <sub>v</sub> V <sub>n</sub>	41.7 k
Z	11.6 in <sup>3</sup>	M <sub>n</sub> /Ω <sub>b</sub>	28.9 k-ft
I	26.3 in <sup>4</sup>	φ <sub>b</sub> M <sub>n</sub>	43.5 k-ft



Span	V <sub>L</sub> (kips)	V <sub>R</sub> (kips)	M(-) (k-ft)	M(+) (k-ft)	Δ <sub>TL</sub> (in)	@ x =	L/	Δ <sub>LL</sub> (in)	@ x =	L/
Span 1	1.81	-2.16	-0.435	8.69	-0.293 (†)	6.2	L/498	0	0	L/∞
Right Cantilever	0.373	-	-0.435	-	0.173 (†)	14.5	L/322	0	12.2	L/∞



Jaffe Residence - Permit Correction #1  
 PROJECT Gravity Design - Roof

04-05-2023  
 DATE 00043-2022-03  
 PROJ. # ETC  
 DESIGN 10  
 SHEET

Beam:		B5*					
Load	Dead	Live	Roof Live	Seismic	Factored	Location	
Distributed (k/ft)	w <sub>1</sub>	0.154		0.256	0.410		ROOF
	w <sub>2</sub>				0.000		
	w <sub>3</sub>				0.000		
	w <sub>4</sub>				0.000		
	w <sub>5</sub>				0.000		
	w <sub>6</sub>				0.000		
	w <sub>7</sub>				0.000		
	w <sub>8</sub>				0.000		
	w <sub>9</sub>				0.000		
	w <sub>10</sub>	0.02005			0.020		
Trapezoidal (k/ft/ft)	t <sub>1</sub>				0.000		SW
	t <sub>2</sub>				0.000		
	t <sub>3</sub>				0.000		
	t <sub>4</sub>				0.000		
	t <sub>5</sub>				0.000		
	t <sub>6</sub>				0.000		
Point (k)	P <sub>1</sub>				0.000		
	P <sub>2</sub>				0.000		
	P <sub>3</sub>				0.000		
	P <sub>4</sub>				0.000		
	P <sub>5</sub>				0.000		
	P <sub>6</sub>				0.000		
	P <sub>7</sub>				0.000		
	P <sub>8</sub>				0.000		
	P <sub>9</sub>				0.000		
	P <sub>10</sub>				0.000		

Support Locations and Reactions		
# of Supports		3
Total Beam Length		32.75
Left End Condition		Pinned
Right End Condition		Pinned
R <sub>1</sub>	4.297	0.00
R <sub>2</sub>	11.369	24.83
R <sub>3</sub>	-1.574	32.75
R <sub>4</sub>	0.000	32.75
R <sub>5</sub>	0.000	32.75
R <sub>6</sub>	0.000	32.75
R <sub>7</sub>	0.000	32.75
R <sub>8</sub>	0.000	32.75
R <sub>9</sub>	0.000	32.75
R <sub>10</sub>	0.000	32.75

Load Factors	
Dead	1.00
Live	1.00
Roof Live	1.00
Seismic	1.00


Stresses @ Input Location	
f <sub>v</sub> (psi)	-9
f <sub>b</sub> (psi)	1232

Max/Min Stresses	
f <sub>v</sub> MAX (psi)	90
f <sub>v</sub> MIN (psi)	-116
f <sub>b</sub> MAX (psi)	1245
f <sub>b</sub> MIN (psi)	-1507


Demand Output	
Location, ft	11.14
Shear, k	-0.49
Moment, k-ft M =	21.17
Deflection, in D =	-0.71
Δ/Span	L/419
L	6.500
A	3.500
FACTOR	7.692308

Beam Properties	
E (ksi)	1800
b (in)	5.5
d (in)	15
I (in <sup>4</sup> )	1546.9
S (in <sup>3</sup> )	206.25
A (in <sup>2</sup> )	82.5
I (Override)	
S (Override)	
A (Override)	

Steel Beam Section NONE



Span	V <sub>L</sub> (kips)	V <sub>R</sub> (kips)	M(-) (k-ft)	M(+) (k-ft)	Δ <sub>TL</sub> (in)	@ x =	L/	Δ <sub>LL</sub> (in)	@ x =	L/
Span 1	4.29	-6.38	-25.9	21.4	-0.787 (†)	11.1	L/379	0	0	L/∞
Span 2	4.97	1.57	-25.9	0	0.057 (†)	28	L/1655	0	24.9	L/∞



Jaffe Residence - Permit Correction #1

PROJECT Gravity Design - Roof


04-05-2023

DATE 00043-2022-03

PROJ. # ETC

DESIGN 11

SHEET



Jaffe Residence - Permit Correction #1

PROJECT  
Gravity Key Plan - Floor


04-05-2023

DATE  
00043-2022-03


PROJ. #  
ETC

DESIGN  
12


SHEET




Mudroom Joists		J1*	HF	2	x 10
w=	69	plf	R=	399	lbs
L=	11.5	ft	M=	1,146	ft-lbs
b=	1.50	in	Fb=	643	psi
d=	9.25	in	Fv=	37	psi
E=	1300	ksi	Δ=	0.21	in
Cv=	1.00	≤1.0	I/	650	




West Header		FB20	GL	3	1/2 x 10	1/2
w1=	798	plf	R1 =	3,088	lbs	
w2=	798	plf	R2 =	4,333	lbs	
L1=	3	ft	M =	5,859	lb-ft	
L2=	2	ft	Fb =	1,093	psi	
X=	3.3	ft	Fv =	148	psi	
P=	3,500	lbs	Δ=	0.03	in	
b=	3.50	in	I/	1,764		
d=	10.50	in	Cv=	1.00		
E=	1,800	ksi				




Joist D-F Bearing		J3	HF	3	x 10
w1=	69	plf	R1 =	761	lbs
w2=	69	plf	R2 =	691	lbs
L1=	6	ft	M =	3,401	lb-ft
L2=	9	ft	Fb =	954	psi
X=	7.3	ft	Fv =	38	psi
P=	407	lbs	Δ=	0.50	in
b=	3.00	in	I/	361	
d=	9.25	in	Cv=	1.00	
E=	1,300	ksi			





DECK GIRT		FB22	HF	6	x 12
w1=	276	plf	R1=	889	lbs
w2=	495	plf	R2=	4,594	lbs
L1=	11	ft	M+=	1,431	lb-ft
L2=	5	ft	M-=	6,395	lb-ft
X=	6.00	ft	Fb=	661	psi
P=	-	lbs	Fv=	50	psi
b=	5.50	in	Δspan=	(0.000)	in
d=	11.25	in	I span/	(569,470)	
E=	1,300	ksi	Δcant=	0.17	in
Cv=	1.00		I cant/	703	



Transfer Beam		FB13	GL	5	1/2 x 9
w1=	69	plf	R1 =	1,380	lbs
w2=	69	plf	R2 =	1,159	lbs
L1=	6	ft	M =	7,347	lb-ft
L2=	9	ft	Fb =	1,187	psi
X=	6.3	ft	Fv =	40	psi
P=	1,511	lbs	Δ=	0.40	in
b=	5.50	in	I/	440	
d=	9.00	in	Cv=	1.00	
E=	1,800	ksi			




Mid Span Flush Bm		FB16	PSL	7	x 9	1/4
w=	559	plf	R=	3,843	lbs	
L=	13.75	ft	M=	13,211	ft-lbs	
b=	7.00	in	Fb=	1,588	psi	
d=	9.25	in	Fv=	79	psi	
E=	2200	ksi	Δ=	0.44	in	
Cv=	1.00	≤1.0	I/	373		



Jaffe Residence - Permit Correction #1  
 PROJECT Gravity Design - Floor

04-05-2023  
 DATE 00043-2022-03  
 PROJ. # ETC  
 DESIGN 13  
 SHEET

2x10 DECK JOIST		DJ1	HF	2	x 10
w=	96	plf	R=	528	lbs
L=	11	ft	M=	1,452	ft-lbs
b=	1.50	in	Fb=	815	psi
d=	9.25	in	Fv=	49	psi
E=	1300	ksi	$\Delta$ =	0.25	in
Cv=	1.00	$\leq 1.0$	I/	537	



2x10 DECK JOIST		DJ1a	HF	2	x 10
w=	96	plf	R=	612	lbs
L=	12.75	ft	M=	1,951	ft-lbs
b=	1.50	in	Fb=	1,094	psi
d=	9.25	in	Fv=	58	psi
E=	1300	ksi	$\Delta$ =	0.44	in
Cv=	1.00	$\leq 1.0$	I/	345	



Jaffe Residence - Permit Correction #1

PROJECT Gravity Design - Floor

04-05-2023

DATE 00043-2022-03

PROJ. # ETC

DESIGN 14

SHEET

Beam:		FB1*					
Load		Dead	Live	Roof Live	Seismic	Factored	Location
Distributed (k/ft)	w <sub>1</sub>	0.016	0.053			0.056	
	w <sub>2</sub>					0.000	
	w <sub>3</sub>					0.000	
	w <sub>4</sub>					0.000	
	w <sub>5</sub>					0.000	
	w <sub>6</sub>					0.000	
	w <sub>7</sub>					0.000	
	w <sub>8</sub>					0.000	
	w <sub>9</sub>					0.000	
	w <sub>10</sub>		0.0118				0.012
Trapezoidal (k/ft/ft)	t <sub>1</sub>					0.000	
	t <sub>2</sub>					0.000	
	t <sub>3</sub>					0.000	
	t <sub>4</sub>					0.000	
	t <sub>5</sub>					0.000	
	t <sub>6</sub>					0.000	
Point (k)	P <sub>1</sub>	1.875		3.125		4.219	7.42
	P <sub>2</sub>					0.000	
	P <sub>3</sub>					0.000	
	P <sub>4</sub>					0.000	
	P <sub>5</sub>					0.000	
	P <sub>6</sub>					0.000	
	P <sub>7</sub>					0.000	
	P <sub>8</sub>					0.000	
	P <sub>9</sub>					0.000	
	P <sub>10</sub>					0.000	

FLOOR  
SW  
RF

Support Locations and Reactions	
# of Supports	2
Total Beam Length	12.83
Left End Condition	Pinned
Right End Condition	Pinned
R <sub>1</sub>	2.215 0.00
R <sub>2</sub>	2.874 12.83
R <sub>3</sub>	0.000 12.83
R <sub>4</sub>	0.000 12.83
R <sub>5</sub>	0.000 12.83
R <sub>6</sub>	0.000 12.83
R <sub>7</sub>	0.000 12.83
R <sub>8</sub>	0.000 12.83
R <sub>9</sub>	0.000 12.83
R <sub>10</sub>	0.000 12.83

Load Factors	
Dead	1.00
Live	0.75
Roof Live	0.75
Seismic	1.00


Stresses @ Input Location	
f <sub>v</sub> (psi)	56
f <sub>b</sub> (psi)	1877

Max/Min Stresses	
f <sub>v</sub> _MAX (psi)	61
f <sub>v</sub> _MIN (psi)	-121
f <sub>b</sub> _MAX (psi)	1971
f <sub>b</sub> _MIN (psi)	0


Demand Output	
Location, ft	5.80
Shear, k	1.82
Moment, k-ft M =	11.71
Deflection, in D =	-0.45
Δ/Span	L/342

Beam Properties	
E (ksi)	2200
b (in)	5.25
d (in)	9.25
I (in <sup>4</sup> )	346.26
S (in <sup>3</sup> )	74.867
A (in <sup>2</sup> )	48.563
I (Override)	
S (Override)	
A (Override)	

Steel Beam Section NONE



Span	V <sub>L</sub> (kips)	V <sub>R</sub> (kips)	M(-) (k-ft)	M(+) (k-ft)	Δ <sub>TL</sub> (in)	@ x =	L/	Δ <sub>TL</sub> (in)	@ x =	L/
Span 1	1.96	-3.91	-	12.3	-0.333 (↑)	5.8	L/384	-0.026 (↑)	5.3	L/4923



Jaffe Residence - Permit Correction #1

PROJECT  
Gravity Design - Floor

04-05-2023

DATE  
00043-2022-03

PROJ. #  
ETC

DESIGN  
15

SHEET



Beam:		FB13a					
Load	Dead	Live	Roof Live	Seismic	Factored	Location	
Distributed (k/ft)	w <sub>1</sub>	0.113		0.188		0.253	5
	w <sub>2</sub>	0.090	0.300			0.315	
	w <sub>3</sub>	-0.113		-0.188		-0.253	
	w <sub>4</sub>					0.000	
	w <sub>5</sub>					0.000	
	w <sub>6</sub>					0.000	
	w <sub>7</sub>					0.000	
	w <sub>8</sub>					0.000	
	w <sub>9</sub>					0.000	
	w <sub>10</sub>	0.00787				0.008	
Trapezoidal (k/ft/ft)	t <sub>1</sub>					0.000	5.00
	t <sub>2</sub>					0.000	
	t <sub>3</sub>					0.000	
	t <sub>4</sub>					0.000	
	t <sub>5</sub>					0.000	
	t <sub>6</sub>					0.000	
Point (k)	P <sub>1</sub>	0		0		0.000	RF
	P <sub>2</sub>					0.000	
	P <sub>3</sub>					0.000	
	P <sub>4</sub>					0.000	
	P <sub>5</sub>					0.000	
	P <sub>6</sub>					0.000	
	P <sub>7</sub>					0.000	
	P <sub>8</sub>					0.000	
	P <sub>9</sub>					0.000	
	P <sub>10</sub>					0.000	

Support Locations and Reactions	
# of Supports	2
Total Beam Length	7.17
Left End Condition	Pinned
Right End Condition	Pinned
R <sub>1</sub>	1.981
R <sub>2</sub>	1.598
R <sub>3</sub>	0.000
R <sub>4</sub>	0.000
R <sub>5</sub>	0.000
R <sub>6</sub>	0.000
R <sub>7</sub>	0.000
R <sub>8</sub>	0.000
R <sub>9</sub>	0.000
R <sub>10</sub>	0.000

Load Factors	
Dead	1.00
Live	0.75
Roof Live	0.75
Seismic	1.00


Stresses @ Input Location	
f <sub>v</sub> (psi)	-6
f <sub>b</sub> (psi)	816

Max/Min Stresses	
f <sub>v</sub> _MAX (psi)	92
f <sub>v</sub> _MIN (psi)	-74
f <sub>b</sub> _MAX (psi)	820
f <sub>b</sub> _MIN (psi)	0


Demand Output	
Location, ft	3.66
Shear, k	-0.13
Moment, k-ft M =	3.39
Deflection, in D =	-0.08
Δ/Span	L/1087

Beam Properties	
E (ksi)	1700
b (in)	3.5
d (in)	9.25
I (in <sup>4</sup> )	230.84
S (in <sup>3</sup> )	49.911
A (in <sup>2</sup> )	32.375
I (Override)	
S (Override)	
A (Override)	

Steel Beam Section NONE



Span	V <sub>L</sub> (kips)	V <sub>R</sub> (kips)	M(-) (k-ft)	M(+) (k-ft)	Δ <sub>L</sub> (in)	@ x = L/	Δ <sub>L</sub> (in)	@ x = L/
Span 1	1.98	-1.6	0	3.41	-0.096 (+)	3.5	-0.045 (+)	3.6



Jaffe Residence - Permit Correction #1

PROJECT Gravity Design - Floor

04-05-2023

DATE 00043-2022-03

PROJ. # ETC

DESIGN 16

SHEET

Beam: FB15		Dead	Live	Roof Live	Seismic	Factored	Location
Distributed (k/ft)	w <sub>1</sub>	0.016	0.053			0.056	
	w <sub>2</sub>					0.000	
	w <sub>3</sub>					0.000	
	w <sub>4</sub>					0.000	
	w <sub>5</sub>					0.000	
	w <sub>6</sub>					0.000	
	w <sub>7</sub>					0.000	
	w <sub>8</sub>					0.000	
	w <sub>9</sub>					0.000	
	w <sub>10</sub>	0.01404				0.014	
Trapezoidal (k/ft/ft)	t <sub>1</sub>					0.000	
	t <sub>2</sub>					0.000	
	t <sub>3</sub>					0.000	
	t <sub>4</sub>					0.000	
	t <sub>5</sub>					0.000	
	t <sub>6</sub>					0.000	
Point (k)	P <sub>1</sub>	0.78		1.3		1.755	7.25
	P <sub>2</sub>	0.78	3.6			3.480	1.92
	P <sub>3</sub>					0.000	
	P <sub>4</sub>					0.000	
	P <sub>5</sub>					0.000	
	P <sub>6</sub>					0.000	
	P <sub>7</sub>					0.000	
	P <sub>8</sub>					0.000	
	P <sub>9</sub>					0.000	
	P <sub>10</sub>					0.000	

FLOOR  
SW  
RF DECK

Support Locations and Reactions	
# of Supports	2
Total Beam Length	12.00
Left End Condition	Pinned
Right End Condition	Pinned
R <sub>1</sub>	4.039 0.00
R <sub>2</sub>	2.036 12.00
R <sub>3</sub>	0.000 12.00
R <sub>4</sub>	0.000 12.00
R <sub>5</sub>	0.000 12.00
R <sub>6</sub>	0.000 12.00
R <sub>7</sub>	0.000 12.00
R <sub>8</sub>	0.000 12.00
R <sub>9</sub>	0.000 12.00
R <sub>10</sub>	0.000 12.00

Load Factors	
Dead	1.00
Live	0.75
Roof Live	0.75
Seismic	1.00


Stresses @ Input Location	
f <sub>v</sub> (psi)	4
f <sub>b</sub> (psi)	1038

Max/Min Stresses	
f <sub>v_MAX</sub> (psi)	105
f <sub>v_MIN</sub> (psi)	-52
f <sub>b_MAX</sub> (psi)	1050
f <sub>b_MIN</sub> (psi)	0


Demand Output	
Location, ft	5.83
Shear, k	0.15
Moment, k-ft M =	8.74
Deflection, in D =	-0.25
Δ/Span	L/584

Beam Properties	
E (ksi)	1800
b (in)	5.5
d (in)	10.5
I (in <sup>4</sup> )	530.58
S (in <sup>3</sup> )	101.06
A (in <sup>2</sup> )	57.75
I (Override)	
S (Override)	
A (Override)	

Steel Beam Section NONE



Span	V <sub>L</sub> (kips)	V <sub>R</sub> (kips)	M(-) (k-ft)	M(+) (k-ft)	Δ <sub>TL</sub> (in)	@ x = L/	Δ <sub>TL</sub> (in)	@ x = L/
Span 1	4.03	-2.02	-	8.84	-0.375 (↑)	5.8	-0.171 (↑)	5.3



Jaffe Residence - Permit Correction #1

PROJECT Gravity Design - Floor

04-05-2023

DATE 00043-2022-03

PROJ. # ETC

DESIGN 17

SHEET

Beam: FB17		Dead	Live	Roof Live	Seismic	Factored	Location
Distributed (k/ft)	w <sub>1</sub>	0.072	0.240			0.252	
	w <sub>2</sub>	0.104		0.173		0.233	
	w <sub>3</sub>	0.034	0.170	0.071		0.215	
	w <sub>4</sub>					0.000	
	w <sub>5</sub>					0.000	
	w <sub>6</sub>					0.000	
	w <sub>7</sub>					0.000	
	w <sub>8</sub>					0.000	
	w <sub>9</sub>					0.000	
	w <sub>10</sub>	0				0.000	
	Trapezoidal (k/ft/ft)	t <sub>1</sub>					0.000
t <sub>2</sub>						0.000	
t <sub>3</sub>						0.000	
t <sub>4</sub>						0.000	
t <sub>5</sub>						0.000	
t <sub>6</sub>						0.000	
Point (k)	P <sub>1</sub>				2.21	0.000	7.42
	P <sub>2</sub>					0.000	
	P <sub>3</sub>					0.000	
	P <sub>4</sub>					0.000	
	P <sub>5</sub>					0.000	
	P <sub>6</sub>					0.000	
	P <sub>7</sub>					0.000	
	P <sub>8</sub>					0.000	
	P <sub>9</sub>					0.000	
	P <sub>10</sub>					0.000	

FLOOR  
ROOF  
DECK  
  
SW  
  
OT

Support Locations and Reactions		
# of Supports		2
Total Beam Length		13.75
Left End Condition		Pinned
Right End Condition		Pinned
R <sub>1</sub>	4.814	0.00
R <sub>2</sub>	4.814	13.75
R <sub>3</sub>	0.000	13.75
R <sub>4</sub>	0.000	13.75
R <sub>5</sub>	0.000	13.75
R <sub>6</sub>	0.000	13.75
R <sub>7</sub>	0.000	13.75
R <sub>8</sub>	0.000	13.75
R <sub>9</sub>	0.000	13.75
R <sub>10</sub>	0.000	13.75

Load Factors	
Dead	1.00
Live	0.75
Roof Live	0.75
Seismic	0.00


Stresses @ Input Location	
f <sub>v</sub> (psi)	-9
f <sub>b</sub> (psi)	1495

Max/Min Stresses	
f <sub>v</sub> _MAX (psi)	112
f <sub>v</sub> _MIN (psi)	-112
f <sub>b</sub> _MAX (psi)	1536
f <sub>b</sub> _MIN (psi)	0


Demand Output	
Location, ft	7.41
Shear, k	-0.38
Moment, k-ft M =	16.45
Deflection, in D =	-0.39
Δ/Span	L/421

Beam Properties	
E (ksi)	1800
b (in)	5.5
d (in)	12
I (in <sup>4</sup> )	792
S (in <sup>3</sup> )	132
A (in <sup>2</sup> )	66
I (Override)	
S (Override)	
A (Override)	

Steel Beam Section NONE



Span	V <sub>L</sub> (kips)	V <sub>R</sub> (kips)	M(-) (k-ft)	M(+) (k-ft)	Δ <sub>TL</sub> (in)	@ x =	L/	Δ <sub>LL</sub> (in)	@ x =	L/
Span 1	4.92	-4.92	-	16.9	-0.655 (+)	6.9	L/252	-0.237 (+)	6.9	L/696



Jaffe Residence - Permit Correction #1

PROJECT  
Gravity Design - Floor

04-05-2023

DATE  
00043-2022-03

PROJ. #  
ETC

DESIGN  
18

SHEET

Beam: FB18		Dead	Live	Roof Live	Seismic	Factored	Location
Distributed (k/ft)	w <sub>1</sub>	0.058	0.193			0.203	
	w <sub>2</sub>	0.087		0.18125		0.223	
	w <sub>3</sub>	0.075	0.375	0.156		0.473	
	w <sub>4</sub>					0.000	
	w <sub>5</sub>					0.000	
	w <sub>6</sub>					0.000	
	w <sub>7</sub>					0.000	
	w <sub>8</sub>					0.000	
	w <sub>9</sub>					0.000	
	w <sub>10</sub>	0.02206				0.022	
Trapezoidal (k/ft/ft)	t <sub>1</sub>					0.000	
	t <sub>2</sub>					0.000	
	t <sub>3</sub>					0.000	
	t <sub>4</sub>					0.000	
	t <sub>5</sub>					0.000	
	t <sub>6</sub>					0.000	
Point (k)	P <sub>1</sub>					0.000	
	P <sub>2</sub>					0.000	
	P <sub>3</sub>					0.000	
	P <sub>4</sub>					0.000	
	P <sub>5</sub>					0.000	
	P <sub>6</sub>					0.000	
	P <sub>7</sub>					0.000	
	P <sub>8</sub>					0.000	
	P <sub>9</sub>					0.000	
	P <sub>10</sub>					0.000	

FLOOR  
ROOF  
DECK  
  
SW  
  
RF

Support Locations and Reactions	
# of Supports	2
Total Beam Length	18.50
Left End Condition	Pinned
Right End Condition	Pinned
R <sub>1</sub>	8.524 0.00
R <sub>2</sub>	8.524 18.50
R <sub>3</sub>	0.000 18.50
R <sub>4</sub>	0.000 18.50
R <sub>5</sub>	0.000 18.50
R <sub>6</sub>	0.000 18.50
R <sub>7</sub>	0.000 18.50
R <sub>8</sub>	0.000 18.50
R <sub>9</sub>	0.000 18.50
R <sub>10</sub>	0.000 18.50

Load Factors	
Dead	1.00
Live	0.75
Roof Live	0.75
Seismic	1.00


Stresses @ Input Location	
f <sub>v</sub> (psi)	70
f <sub>t</sub> (psi)	1422

Max/Min Stresses	
f <sub>v</sub> MAX (psi)	104
f <sub>v</sub> MIN (psi)	-104
f <sub>t</sub> MAX (psi)	1399
f <sub>t</sub> MIN (psi)	0


Demand Output	
Location, ft	4.63
Shear, k	4.26
Moment, k-ft M =	29.57
Deflection, in D =	-0.47
Δ/Span	L/475

Beam Properties	
E (ksi)	1800
b (in)	5.5
d (in)	16.5
I (in <sup>4</sup> )	2058.9
S (in <sup>3</sup> )	249.56
A (in <sup>2</sup> )	90.75
I (Override)	
S (Override)	
A (Override)	

Steel Beam Section NONE



Span	V <sub>L</sub> (kips)	V <sub>R</sub> (kips)	M(-) (k-ft)	M(+) (k-ft)	Δ <sub>TL</sub> (in)	@ x =	L/	Δ <sub>LL</sub> (in)	@ x =	L/
Span 1	6.28	-6.28	-	29.1	-0.86 (+)	9.3	L/258	-0.425 (+)	9.3	L/522



Jaffe Residence - Permit Correction #1  
 PROJECT Gravity Design - Floor

04-05-2023  
 DATE 00043-2022-03  
 PROJ. # ETC  
 DESIGN 19  
 SHEET

Beam:		FB19					
Load	Dead	Live	Roof Live	Seismic	Factored	Location	
Distributed (k/ft)	w <sub>1</sub>	0.090	0.300		0.315		
	w <sub>2</sub>	0.079		0.13125	0.177		
	w <sub>3</sub>	0.033	0.165	0.069	0.208		
	w <sub>4</sub>				0.000		
	w <sub>5</sub>				0.000		
	w <sub>6</sub>				0.000		
	w <sub>7</sub>				0.000		
	w <sub>8</sub>				0.000		
	w <sub>9</sub>				0.000		
	w <sub>10</sub>				0.000		
Trapezoidal (k/ft/ft)	t <sub>1</sub>				0.000		
	t <sub>2</sub>				0.000		
	t <sub>3</sub>				0.000		
	t <sub>4</sub>				0.000		
	t <sub>5</sub>				0.000		
	t <sub>6</sub>				0.000		
Point (k)	P <sub>1</sub>	1.648			1.648	3.33	
	P <sub>2</sub>	1			1.000	5.50	
	P <sub>3</sub>				0.000		
	P <sub>4</sub>				0.000		
	P <sub>5</sub>				0.000		
	P <sub>6</sub>				0.000		
	P <sub>7</sub>				0.000		
	P <sub>8</sub>				0.000		
	P <sub>9</sub>				0.000		
	P <sub>10</sub>				0.000		

FLOOR  
ROOF  
DECK  
  
  
  
  
  
  
  
  
  
SW  
  
  
  
FB1\*  
Coffee

Support Locations and Reactions		
# of Supports		2
Total Beam Length		6.50
Left End Condition		Pinned
Right End Condition		Pinned
R <sub>1</sub>	3.232	0.00
R <sub>2</sub>	3.967	6.50
R <sub>3</sub>	0.000	6.50
R <sub>4</sub>	0.000	6.50
R <sub>5</sub>	0.000	6.50
R <sub>6</sub>	0.000	6.50
R <sub>7</sub>	0.000	6.50
R <sub>8</sub>	0.000	6.50
R <sub>9</sub>	0.000	6.50
R <sub>10</sub>	0.000	6.50

Load Factors	
Dead	1.00
Live	0.75
Roof Live	0.75
Seismic	1.00


Stresses @ Input Location	
f <sub>v</sub> (psi)	38
f <sub>b</sub> (psi)	1278

Max/Min Stresses	
f <sub>v</sub> _MAX (psi)	132
f <sub>v</sub> _MIN (psi)	-162
f <sub>b</sub> _MAX (psi)	1284
f <sub>b</sub> _MIN (psi)	0


Demand Output	
Location, ft	3.29
Shear, k	0.92
Moment, k-ft M =	6.85
Deflection, in D =	-0.08
Δ/Span	L/972

Beam Properties	
E (ksi)	1800
b (in)	3.5
d (in)	10.5
I (in <sup>4</sup> )	337.64
S (in <sup>3</sup> )	64.313
A (in <sup>2</sup> )	36.75
I (Override)	
S (Override)	
A (Override)	

Steel Beam Section NONE



Span	V <sub>L</sub> (kips)	V <sub>R</sub> (kips)	M(-) (k-ft)	M(+) (k-ft)	Δ <sub>T</sub> (in)	@ x =	L/	Δ <sub>L</sub> (in)	@ x =	L/
Span 1	3.23	-3.97	-	6.88	-0.078 (+)	3.3	L/1000	-0.026 (+)	3.2	L/2999



Jaffe Residence - Permit Correction #1

PROJECT  
Gravity Design - Floor

04-05-2023

DATE  
00043-2022-03

PROJ. #  
ETC

DESIGN  
20

SHEET

Beam: FB21 - OVERSTRENGTH							
Load	Dead	Live	Roof Live	Seismic	Factored	Location	
Distributed (k/ft)	w <sub>1</sub>	0.044	0.145			0.044	FLOOR DECK
	w <sub>2</sub>	0.050	0.248			0.050	
	w <sub>3</sub>					0.000	
	w <sub>4</sub>					0.000	
	w <sub>5</sub>					0.000	
	w <sub>6</sub>					0.000	
	w <sub>7</sub>					0.000	
	w <sub>8</sub>					0.000	
	w <sub>9</sub>					0.000	
	w <sub>10</sub>					0.000	
Trapezoidal (k/ft/ft)	t <sub>1</sub>					0.000	SW
	t <sub>2</sub>					0.000	
	t <sub>3</sub>					0.000	
	t <sub>4</sub>					0.000	
	t <sub>5</sub>					0.000	
	t <sub>6</sub>					0.000	
Point (k)	P <sub>1</sub>	0.863		1.44		0.863	RF OTOS
	P <sub>2</sub>				2.21	5.525	
	P <sub>3</sub>					0.000	
	P <sub>4</sub>					0.000	
	P <sub>5</sub>					0.000	
	P <sub>6</sub>					0.000	
	P <sub>7</sub>					0.000	
	P <sub>8</sub>					0.000	
	P <sub>9</sub>					0.000	
	P <sub>10</sub>					0.000	

Support Locations and Reactions		
# of Supports		2
Total Beam Length		14.08
Left End Condition		Pinned
Right End Condition		Pinned
R <sub>1</sub>	6.136	0.00
R <sub>2</sub>	1.562	14.08
R <sub>3</sub>	0.000	14.08
R <sub>4</sub>	0.000	14.08
R <sub>5</sub>	0.000	14.08
R <sub>6</sub>	0.000	14.08
R <sub>7</sub>	0.000	14.08
R <sub>8</sub>	0.000	14.08
R <sub>9</sub>	0.000	14.08
R <sub>10</sub>	0.000	14.08

Load Factors	
Dead	1.00
Live	0.00
Roof Live	0.00
Seismic	2.50


Stresses @ Input Location	
f <sub>v</sub> (psi)	-32
f <sub>b</sub> (psi)	1292

Max/Min Stresses	
f <sub>v</sub> _MAX (psi)	222
f <sub>v</sub> _MIN (psi)	-56
f <sub>b</sub> _MAX (psi)	1765
f <sub>b</sub> _MIN (psi)	0


Demand Output	
Location, ft	6.86
Shear, k	-0.89
Moment, k-ft M =	8.86
Deflection, in D =	-0.33
Δ/Span	L/518

Beam Properties	
E (ksi)	2200
b (in)	3.5
d (in)	11.875
I (in <sup>4</sup> )	488.41
S (in <sup>3</sup> )	82.259
A (in <sup>2</sup> )	41.563
I (Override)	
S (Override)	
A (Override)	

Steel Beam Section NONE



Span	V <sub>L</sub> (kips)	V <sub>R</sub> (kips)	M(-) (k-ft)	M(+) (k-ft)	Δ <sub>TL</sub> (in)	@ x =	L/	Δ <sub>LL</sub> (in)	@ x =	L/
Span 1	6.14	-1.56	-	12.1	-0.576 (+)	6.8	L/293	-0.323 (+)	7	L/523



Jaffe Residence - Permit Correction #1

PROJECT  
Gravity Design - Floor

DATE  
00043-2022-03

PROJ. #  
ETC

DESIGN  
21

SHEET

Beam: FB23						
Load	Dead	Live	Roof Live	Seismic	Factored	Location
Distributed (k/ft)	w <sub>1</sub>	0.120	0.600		0.720	
	w <sub>2</sub>				0.000	
	w <sub>3</sub>				0.000	
	w <sub>4</sub>				0.000	
	w <sub>5</sub>				0.000	
	w <sub>6</sub>				0.000	
	w <sub>7</sub>				0.000	
	w <sub>8</sub>				0.000	
	w <sub>9</sub>				0.000	
	w <sub>10</sub>				0.000	
Trapezoidal (k/ft/ft)	t <sub>1</sub>				0.000	
	t <sub>2</sub>				0.000	
	t <sub>3</sub>				0.000	
	t <sub>4</sub>				0.000	
	t <sub>5</sub>				0.000	
	t <sub>6</sub>				0.000	
Point (k)	P <sub>1</sub>				0.000	
	P <sub>2</sub>				0.000	
	P <sub>3</sub>				0.000	
	P <sub>4</sub>				0.000	
	P <sub>5</sub>				0.000	
	P <sub>6</sub>				0.000	
	P <sub>7</sub>				0.000	
	P <sub>8</sub>				0.000	
	P <sub>9</sub>				0.000	
	P <sub>10</sub>				0.000	

DECK

Support Locations and Reactions		
# of Supports		2
Total Beam Length		9.33
Left End Condition		Pinned
Right End Condition		Pinned
R <sub>1</sub>	3.359	0.00
R <sub>2</sub>	3.359	9.33
R <sub>3</sub>	0.000	9.33
R <sub>4</sub>	0.000	9.33
R <sub>5</sub>	0.000	9.33
R <sub>6</sub>	0.000	9.33
R <sub>7</sub>	0.000	9.33
R <sub>8</sub>	0.000	9.33
R <sub>9</sub>	0.000	9.33
R <sub>10</sub>	0.000	9.33

Load Factors	
Dead	1.00
Live	1.00
Roof Live	0.75
Seismic	1.00


Stresses @ Input Location	
f <sub>v</sub> (psi)	0
f <sub>b</sub> (psi)	1199

Max/Min Stresses	
f <sub>v_MAX</sub> (psi)	99
f <sub>v_MIN</sub> (psi)	-99
f <sub>b_MAX</sub> (psi)	1198
f <sub>b_MIN</sub> (psi)	0


Demand Output	
Location, ft	4.66
Shear, k	0.00
Moment, k-ft M =	7.83
Deflection, in D =	-0.26
Δ/Span	L/430

Beam Properties	
E (ksi)	1300
b (in)	5.5
d (in)	9.25
I (in <sup>4</sup> )	362.75
S (in <sup>3</sup> )	78.432
A (in <sup>2</sup> )	50.875
I (Override)	
S (Override)	
A (Override)	

Steel Beam Section NONE



Span	V <sub>L</sub> (kips)	V <sub>R</sub> (kips)	M(-) (k-ft)	M(+) (k-ft)	Δ <sub>TL</sub> (in)	@ x =	L/	Δ <sub>LL</sub> (in)	@ x =	L/
Span 1	3.36	-3.36	-	7.83	-0.26 (+)	4.7	L/431	-0.217 (+)	4.7	L/516



Jaffe Residence - Permit Correction #1

PROJECT Gravity Design - Floor

04-05-2023

DATE 00043-2022-03

PROJ. # ETC

DESIGN 22

SHEET

Beam:		FB24					
Load	Dead	Live	Roof Live	Seismic	Factored	Location	
Distributed (k/ft)	w <sub>1</sub>	0.016	0.053			0.056	FLOOR
	w <sub>2</sub>					0.000	
	w <sub>3</sub>					0.000	
	w <sub>4</sub>					0.000	
	w <sub>5</sub>					0.000	
	w <sub>6</sub>					0.000	
	w <sub>7</sub>					0.000	
	w <sub>8</sub>					0.000	
	w <sub>9</sub>					0.000	
	w <sub>10</sub>	0.01237				0.012	
Trapezoidal (k/ft/ft)	t <sub>1</sub>					0.000	SW
	t <sub>2</sub>					0.000	
	t <sub>3</sub>					0.000	
	t <sub>4</sub>					0.000	
	t <sub>5</sub>					0.000	
	t <sub>6</sub>					0.000	
Point (k)	P <sub>1</sub>	0.9		1.5		2.025	RF
	P <sub>2</sub>					0.000	
	P <sub>3</sub>					0.000	
	P <sub>4</sub>					0.000	
	P <sub>5</sub>					0.000	
	P <sub>6</sub>					0.000	
	P <sub>7</sub>					0.000	
	P <sub>8</sub>					0.000	
	P <sub>9</sub>					0.000	
	P <sub>10</sub>					0.000	

Support Locations and Reactions	
# of Supports	2
Total Beam Length	8.25
Left End Condition	Pinned
Right End Condition	Pinned
R <sub>1</sub>	1.981 0.00
R <sub>2</sub>	0.608 8.25
R <sub>3</sub>	0.000 8.25
R <sub>4</sub>	0.000 8.25
R <sub>5</sub>	0.000 8.25
R <sub>6</sub>	0.000 8.25
R <sub>7</sub>	0.000 8.25
R <sub>8</sub>	0.000 8.25
R <sub>9</sub>	0.000 8.25
R <sub>10</sub>	0.000 8.25

Load Factors	
Dead	1.00
Live	0.75
Roof Live	0.75
Seismic	1.00


Stresses @ Input Location	
f <sub>v</sub> (psi)	-4
f <sub>b</sub> (psi)	394

Max/Min Stresses	
f <sub>v</sub> _MAX (psi)	58
f <sub>v</sub> _MIN (psi)	-18
f <sub>b</sub> _MAX (psi)	393
f <sub>b</sub> _MIN (psi)	0


Demand Output	
Location, ft	1.34
Shear, k	-0.14
Moment, k-ft M =	2.57
Deflection, in D =	-0.03
Δ/Span	L/3929

Beam Properties	
E (ksi)	1700
b (in)	5.5
d (in)	9.25
I (in <sup>4</sup> )	362.75
S (in <sup>3</sup> )	78.432
A (in <sup>2</sup> )	50.875
I (Override)	
S (Override)	
A (Override)	

Steel Beam Section NONE



Span	V <sub>L</sub> (kips)	V <sub>R</sub> (kips)	M(-) (k-ft)	M(+) (k-ft)	Δ <sub>T,L</sub> (in)	@ x =	L/	Δ <sub>L</sub> (in)	@ x =	L/
Span 1	1.98	-0.608	-	2.57	-0.051 (↑)	3.7	L/1941	-0.009 (↑)	4.1	L/11000



Jaffe Residence - Permit Correction #1

PROJECT Gravity Design - Floor

04-05-2023

DATE 00043-2022-03

PROJ. # ETC

DESIGN 23

SHEET