

LOT COVERAGE	
Lot Area	16,710
Allowed	35%
Allowed sf	5,849

New	
Main Structure Roof Area	3,991
Driveway	997
New sf	4,988

Existing	
Main Structure Roof Area	2,070
Driveway	2,377
Auxiliary Bldg	38
Total Existing	4,485
Existing Removed	(4,485)
Total New and Existing	4,988
	% 29.9%

PARKING	
Covered	3 ea
Driveway	3 ea.

Gross Floor Area	
Lot Size	16,710
Main Floor Living	2,191 sf
Garage	702 sf
Second Floor Living	2,649 sf
Less Second Floor Stairs	-122 sf
Total	5,420 sf

Max Allowed: 40% 6,684 sf
 This Proposal 32.4%


PROPERTY OWNER
 Erik and Katie Spring
STREET ADDRESS
 4740 West Mercer Way
PARCEL#
 4045100055
LEGAL DESCRIPTION
 LOTS 11, 12 AND 13 OF A PORTION OF LAKE ISLE,
 ACCORDING TO THE PLAT THEREOF, VOL. 28, P13
 BOOK OF PLATS, KING COUNTY, WA
ZONE: R-15
SETBACKS:
 Front Yard - 20'
 Rear Yard - 25'
 Side Yards - 7.5'/15'
HEIGHT LIMIT; 30' above ABE to roof peak
MAXIMUM LOT COVERAGE: 35%
MAXIMUM HARDSCAPE: 9%
MAXIMUM FAR: 40%
PARKING SPACES PROVIDED: 3 GARAGE 3DRIVEWAY

4740 West Mercer Way TREE INVENTORY														
Tree ID	Common Name	DBH	Multi	Health	Structural Condition	Drillpipe				Exceptions		Retain?		
						N	E	S	W	Threshold	Above 24'			
377	Bigleaf Maple	34.7	24,29	Good	Good	26.4	26.4	33.4	31.4	30'	Size	Yes	Yes	
378	Lodgepole Pine	11.5		Good	Fair	0.5	13.5	24.5	12.5	6	Size	No	Yes	
379	Austrian Black Pine	26.7		Good	Fair	17.1	9.1	26.1	21.1	24	Size	Yes	Yes	
380	Austrian Black Pine	28.3		Good	Fair	19.2	21.2	27.2	9.2	24	Size	Yes	Yes	
381	Western Red Cedar	12.9		Good	Good	14.5	14.5	14.5	14.5	30	No	No	Yes	
382	Western Red Cedar	32.5		Good	Good	21.4	21.4	21.4	21.4	30	Size	Yes	Yes	
383	Flowering Cherry	10.2	6,5,7,1,3,3	Good	Good	16.4	8.4	12.4	16.4	23	No	No	No	
384	Western Red Cedar	45.4		Good	Good	31.9	21.9	26.9	21.9	30	Size	Yes	Yes	
385	Doug-Fir	20.3		Good	Good	15.8	15.8	15.8	15.8	30	No	No	No	
386	Doug-Fir	42		Good	Excellent	25.8	25.8	25.8	25.8	30	Size	Yes	Yes	
10	TOTALS											7	6	9

4740 W Mercer Way Height Table				
Wall Segment	Midpoint Elevation	Length	Product	
A	115.2	76.5	8,812.8	
B	114.3	45	5,143.5	
C	114.2	18.75	2,141.3	
D	114.3	2.75	314.3	
E	114.1	18	2,053.8	
F	113.9	2.75	313.2	
G	112	18	2,016.0	
H	112.2	3.1	347.8	
I	114	8.7	991.8	
J	113	3.1	350.3	
K	112.1	31.6	3,542.4	
L	112.1	24	2,690.4	
M	113	19.5	2,203.5	
N	114.5	20.6	2,358.7	
Sub Totals	292.4		33,279.8	
ABE			113.8	
Max Height			30.0	
Max Elevation			143.84	

Lot Slope Calculations	
High Point	130 ft
Low Point	110 ft
Elevation Difference	20 ft
Distance	112.6 ft
Slope%	17.8%

Hardscape	
Lot Size	16,710
EXISTING	
Uncovered Patio	1420
Walkways	140
Stairs	0
Rockery/Retaining Walls	251
Total Existing	1811
Existing Removed	1560
Net Existing Retained	251
NEW	
Uncovered Patio	
Walk	131
Total New	131
Total Project	382
Project %	2.30%



Hatch denotes landslide and Steep Slope mapped area

JayMarc Homes, LLC
 7525 SE 24th St, #487
 Mercer Island, WA 98040
 425 281 2706

Spring Residence
 4740 W Mercer Way

Drawn by
 Gary Upper

12/8/22

12/19/22

1/11/232

A2.0

Issue	Issue Date	By	Description

Spring Residence
4740 W. Mercer Way
Mercer Island, WA.
Job Number: Spring
JMC011

plan name: -
marketing name: -
plan number: -
mark sys. number: -

Conditions not specifically represented graphically or in writing or which conflict with the current International Residential Code (IRC.) or those of the local municipality then the current standards and requirements of each respectively shall govern.

The drawings in this set are instruments of service and shall remain the property of JayMarc Homes, LLC.

© 2017 JayMarc Homes, LLC; All rights reserved.

12.19.22
Submission Date

Sheet Title/Description


JAYMARC HOMES
Design Firm

R.K.N.
Drawn by:

S.K.
Checked by:

Primary Scale

A3
of .



4x10 DROPPED CONT. BEAM (TYP. U.N.O.)

TYP. CRAWLSPACE POSTS:
4x4 P.T. POST W/2x4 CLEATS EA. SIDE + (2) A35 CLIPS @ BASE OF POST W/O.131"x1-1/2" LONG REDHEAD NAILS (4'-0" MAX. POST HEIGHT) ON ASPHALT SHINGLE ON 24"x24"x8" PLAIN CONC. FTG. (TYP. U.N.O.)

FOUNDATION VENTILATION

Aw/Space Area:	2197 s.f.	
Installation Required:	2197 s.f. / 300 =	1054 s.i. Req'd
Size:	14" x 7" Foundation Vents	
Net Area =	98 s.i. - 25% reduct., 1/4" mesh =	73.5 s.i.
Units Required =	1054 s.i. / Vent Area =	14.34 s.i.
Provide:	15 14" x 7" Vents, Area =	1103 s.i.
Installation Provided =	1103.00 s.i. is Greater than	1054 s.i. Req'd
Size:	15 14" x 7" Foundation Vents	

FOUNDATION VENTS SHALL NOT INTERFERE WITH DIRECT LOAD PATH OF COLUMNS
INSTALL 6 MIL BLACK POLYETHYLENE VAPOR RETARDER GROUND COVER
LOCATE ONE VENT WITHIN 3 FEET OF EACH CORNER OF THE BUILDING, EXCEPT ONE SIDE IF THE BUILDING SHALL BE PERMITTED TO HAVE NO VENTS.

LEGEND

- INTERIOR BEARING WALL
- EXTERIOR WALL ABOVE
- JL METAL HANGER
- * INDICATES POST ABOVE. PROVIDE SOLID BLOCKING UNDER POST OR JAMB ABOVE.
- ▲ INDICATES HOLD-DOWN.

REFER TO S-O FOR TYPICAL STRUCTURAL NOTES & SCHEDULES

HOLD-DOWN SCHEDULE

SYMBOL	SPECIFICATION
HD-1	SIMPSON STHD14 (RJ) HOLD-DOWN
HD-5	SIMPSON CS16 STRAP TIE (14" END LENGTH)
HD-6	SIMPSON MSTC40 STRAP TIE (12" END LENGTH)
HD-7	SIMPSON MSTC66 STRAP TIE (24" END LENGTH)

FOUNDATION PLAN

1/4" = 1'-0"

Sheet Title/Description

Issue	Issue Date	By	Description

Spring Residence
4740 W. Mercer Way
Mercer Island, WA.
Job Number: Spring JMC011

plan name: -
marking name: -
plan number: -
mark sys. number: -

Conditions not specifically represented graphically or in writing or which conflict with the current International Residential Code (IRC.) or those of the local municipality then the current standards and requirements of each respectively shall govern.

The drawings in this set are instruments of service and shall remain the property of JayMarc Homes, LLC.

© 2017 JayMarc Homes, LLC; All rights reserved.

12.19.22
Submission Date


Sheet Title/Description
JAYMARC HOMES
Design Firm

R.K.N.
Drawn by:

S.K.
Checked by:

Primary Scale

A4
of .



B35 4x10 DROPPED CONT. BEAM (TYP. U.N.O.)

TYP. CRAWLSPACE POSTS:
4x4 P.T. POST W/2x4 CLEATS EA. SIDE + (2) A35 CLIPS ON EA. SIDE @ BASE OF POST W/O.131"x1-1/2" LONG REDHEAD NAILS (4'-0" MAX. POST HEIGHT) ON ASPHALT SHINGLE ON 24"x24"x8" PLAIN CONC. FTG. (TYP. U.N.O.)

INDICATES 11-7/8" TJI FLOOR JOISTS @ 16" O.C. (TYP. U.N.O.)

REFER TO S-O FOR TYPICAL STRUCTURAL NOTES & SCHEDULES

LEGEND

- INTERIOR BEARING WALL
- BEARING WALL ABOVE (B.W.A.), OR SHEARWALL ABOVE (S.W.A.)
- BEAM / HEADER
- INTERIOR SHEAR WALL PANEL OR EXTERIOR SHEAR WALL w/ 3" o.c. EDGE NAILING
- AREA OF FLOOR SYSTEM DESIGNED FOR TILE
- JL METAL HANGER
- INDICATES POST ABOVE. PROVIDE SOLID BLOCKING UNDER POST OR JAMB ABOVE.
- INDICATES HOLD-DOWN.

HOLD-DOWN SCHEDULE

SYMBOL	SPECIFICATION
HD-1	SIMPSON STHD14 (R.J.) HOLD-DOWN
HD-5	SIMPSON CS16 STRAP TIE (14" END LENGTH)
HD-6	SIMPSON MSTC40 STRAP TIE (12" END LENGTH)
HD-7	SIMPSON MSTC66 STRAP TIE (24" END LENGTH)

SQUARE FOOTAGE SUMMARY

LOWER FLOOR AREA	0 S.F.
MAIN FLOOR AREA	2,141 S.F.
UPPER FLOOR AREA	2,644 S.F.
TOTAL CONDITIONED AREA	4840 S.F.
2 CAR GARAGE	702 S.F.
COVID PATIO	815 S.F.
COVID PORCH	97 S.F.
TOTAL AREA UNDER ROOF	6,414 S.F.
OVERALL WIDTH	45'-0"
OVERALL DEPTH	44'-8"

Updated: 12.03.20
Method for Calculating Square Footage - ANSI Z165-2013 except, no separate distribution of above-grade or below-grade areas and each level is measured to the outside of studs not the exterior finished surface.
Square Footage calculations for this house were made based on plan dimensions only and may vary from the finished square footage of the house as built.
See sheet CODES for additional zoning required Area Calculations

MAIN FLOOR FRAMING PLAN

1/4" = 1'-0"

Sheet Title/Description

Issue	Issue Date	By	Description

Spring Residence
4740 W. Mercer Way
Mercer Island, WA.
Job Number: Spring JMC011

plan name: _____
marketing name: _____
plan number: _____
mark sys. number: _____

Conditions not specifically represented graphically or in writing or which conflict with the current International Residential Code (IRC), or those of the local municipality then the current standards and requirements of each respectively shall govern.

The drawings in this set are instruments of service and shall remain the property of JayMarc Homes, LLC.

© 2017 JayMarc Homes, LLC; All rights reserved.

12.19.22
Submittal Date


Sheet Title/Description
JAYMARC HOMES
Design Firm

R.K.N.
Drawn by:

S.K.
Checked by:

Primary Scale

A5
of .



WHOLE HOUSE VENTILATION

PROVIDE WHOLE HOUSE VENTILATION per 2015 IRC, M507 and IMC R403.8 USING LAUNDRY ROOM EXHAUST FAN INTEGRATED INTO FORCED AIR SYSTEM (FAU) PROVIDE OUTDOOR FRESH AIR W/DUCTS CONNECTED TO THE RETURN SIDE OF THE AIR HANDLER.

SYMBOL	LOCATION	MIN. FAN REQUIREMENTS (ALL FANS VENT TO OUTSIDE)
	BATH & POWDER	Min. 50cfm, INTERMITTENT at .025kg per TABLE M507.4
	KITCHEN	Min. 100cfm, INTERMITTENT at .025kg per TBL. M507.4
	LAUNDRY ROOM	MIN. 180cfm, INTERMITTENT at .025kg to FUNCTION AS WHOLE HOUSE FAN (WHF)

MECHANICAL CONTRACTOR TO SIZE WHF, FAN AND SET OPERATING TIMER per TABLE M507.3(3) FOR A 3,001-4,500sf. DWELLING w/4-5 BEDRMS. TO OPERATE INTERMITTENTLY and CONTINUOUSLY per TABLE M507.3(3)(2)

PROVIDE CONTROLS FOR WHF, per M507.3.2 AFFIX LABEL TO CONTROLS THAT READS "WHOLE HOUSE VENTILATION - SEE OPERATING INSTRUCTIONS"

MAIN FLOOR PLAN NOTES

PLAN SPECIFIC 2018 WSEC. SECTION R06

R406.2 ADDITIONAL ENERGY EFFICIENCY REQUIREMENTS (MANDATORY). THIS RESIDENTIAL DWELLING SHALL COMPLY w/SUFFICIENT OPTIONS FROM TABLE R406.2 TO ACHIEVE THE FOLLOWING MIN. NUMBER OF CREDITS: 35 FOR a 1501sf to 4999sf HOME.

CREDITS PROVIDED IN THIS HOME AS FOLLOWS:

EFFICIENT BUILDING ENVELOPE (a) .05 CREDITS

PRESCRIPTIVE COMPLIANCE IS BASED ON TABLE R402.1.1 WITH FOLLOWING MODIFICATIONS:

VERTICAL PENETRATION U = 0.28 WINDOWS

FLOORS TO BE R-38 and SLAB ON GRADE TO BE R-10 PERIMETER and UNDER ENTIRE SLAB BELOW GRADE.

HIGH EFFICIENCY HVAC EQUIPMENT 3a) 1.0 CREDITS

GAS FURNACE WITH MINIMUM AFUE OF 94%

EFFICIENT WATER HEATING 5a) .05 CREDITS

ALL SHOWERHEAD AND KITCHEN SINK FAUCETS INSTALLED IN THE HOUSE SHALL BE RATED AT 1.75 GPM or LESS.

ALL OTHER LAVATORY FAUCETS SHALL BE RATED AT 1.0 GPM or LESS.

EFFICIENT WATER HEATING 5c) 1.5 CREDITS

WATER HEATING SYSTEM SHALL BE GAS WATER HEATER WITH A MINIMUM EF OF 0.91

SUMMARY

SQUARE FOOTAGE SUMMARY	
LOWER FLOOR AREA	0 S.F.
MAIN FLOOR AREA	2,141 S.F.
UPPER FLOOR AREA	2,644 S.F.
TOTAL CONDITIONED AREA	4840 S.F.
2 CAR GARAGE	702 S.F.
COVERED PATIO	815 S.F.
COVERED PORCH	97 S.F.
TOTAL AREA UNDER ROOF	6,414 S.F.
OVERALL WIDTH	95'-0"
OVERALL DEPTH	44'-8"

Method for Calculating Square Footage - ANSI Z165-2019 except, no separate distinction of "above-grade or below-grade" areas and each level is measured to the outside of studs not the exterior finished surface.

Square Footage calculations for this house were made based on plan dimensions only and may vary from the finished square footage of the house as built.

See Sheet "CODES" for additional Zoning required Area Calculations

MAIN FLOOR PLAN

1/4" = 1'-0"

Sheet Title/Description

Issue	Issue Date	By	Description

Spring Residence
4740 W. Mercer Way
Mercer Island, WA.
Job Number: Spring JMC011

plan name: -
marketing name: -
plan number: -
mark sys. number: -

Conditions not specifically represented graphically or in writing or which conflict with the current International Residential Code (IRC), or those of the local municipality then the current standards and requirements of each respectively shall govern.

The drawings in this set are instruments of service and shall remain the property of JayMarc Homes, LLC.

© 2017 JayMarc Homes, LLC; All rights reserved.

12.19.22
Submittal Date

Sheet Title/Description
JAYMARC HOMES
Design Firm


R.K.N.
Drawn by:

S.K.
Checked by:

Primary Scale

A6
of .

Sheet Title/Description



NOTE #1:
PROVIDE 3/16" OSB OR PLYWOOD FASTENED PER 3" O.C. EDGE NAILING (SEE S-O.O)

REFER TO S-O FOR TYPICAL STRUCTURAL NOTES & SCHEDULES

4x10 HDR @ ALL EXT. B33 WINDOWS/DOORS (TYP. U.N.O.)

LEGEND

- ▨ INTERIOR BEARING WALL
- ▤ BEAM/HEADER
- ▧ FLOOR TRUSS @ 24" O.C. (U.N.O.)
- ▩ INTERIOR SHEAR WALL PANEL OR EXTERIOR SHEAR WALL w/ 3" o.c. EDGE NAILING
- JL METAL HANGER
- * INDICATES POST ABOVE. PROVIDE SOLID BLOCKING UNDER POST OR JAMB ABOVE.
- ◁ INDICATES HOLD-DOWN.

HOLD-DOWN SCHEDULE

SYMBOL	SPECIFICATION
HD-1	SIMPSON STD14 (R.J) HOLD-DOWN
HD-5	SIMPSON C516 STRAP TIE (14" END LENGTH)
HD-6	SIMPSON MSTC40 STRAP TIE (12" END LENGTH)
HD-7	SIMPSON MSTC66 STRAP TIE (24" END LENGTH)

UPPER FLOOR & LOWER ROOF FRAMING PLAN

1/4" = 1'-0"

Issue	Issue Date	By	Description

Spring Residence
4740 W. Mercer Way
Mercer Island, WA.
Job Number: Spring JMC011

plan name: -
marketing name: -
plan number: -
mark sys. number: -

Conditions not specifically represented graphically or in writing or which conflict with the current International Residential Code (IRC), or those of the local municipality then the current standards and requirements of each respectively shall govern.

The drawings in this set are instruments of service and shall remain the property of JayMarc Homes, LLC.

© 2017 JayMarc Homes, LLC; All rights reserved.

12.19.22
Submittal Date


Sheet Title/Description
JAYMARC HOMES
Design Firm

R.K.N.
Drawn by:

S.K.
Checked by:

Primary Scale

A7
of: .



WHOLE HOUSE VENTILATION
PROVIDE WHOLE HOUSE VENTILATION per 2015 IRC, M507 and IMC R409.8 USING LAUNDRY ROOM EXHAUST FAN INTEGRATED INTO FORCED AIR SYSTEM (FAU) PROVIDE OUTDOOR FRESH AIR W/DUCTS CONNECTED TO THE RETURN SIDE OF THE AIR HANDLER.

SYMBOL	LOCATION	MIN. FAN REQUIREMENTS (ALL FANS VENT TO OUTSIDE)
	BATH & POWDER	Min. 50cfm, INTERMITTENT at .025mg per TABLE M507.4
	KITCHEN	Min. 100cfm, INTERMITTENT at .025mg per TBL. M507.4 RANGE HOOD or DOWN DRAFT EXHAUST FAN RATED at min. 100cfm, at 600mg MAY BE USED FOR EXHAUST FAN REQ. EXHAUST HOODS IN EXCESS OF 400cfm SHALL BE INTERLOCKED AND PROVIDE MAKE UP AIR per M507.4
	LAUNDRY ROOM	MIN. 180cfm, INTERMITTENT at .025mg TO FUNCTION AS WHOLE HOUSE FAN (WHF.)

MECHANICAL CONTRACTOR TO SIZE WHF, FAN and SET OPERATING TIMER per TABLE M507.3(B) FOR A 3,000-4500cfm DWELLING w/4-5 BEDRMS, TO OPERATE INTERMITTENTLY and CONTINUOUSLY per TABLE M507.3(B)
PROVIDE CONTROLS FOR WHF, per M507.3.2 AFFIX LABEL TO CONTROLS THAT READS "WHOLE HOUSE VENTILATION - SEE OPERATING INSTRUCTIONS"

UPPER FLOOR PLAN NOTES:








PLAN SPECIFIC 2018 WSEC. SECTION R406
R406.2 ADDITIONAL ENERGY EFFICIENCY REQUIREMENTS (MANDATORY). THIS RESIDENTIAL DWELLING SHALL COMPLY w/SUFFICIENT OPTIONS FROM TABLE R406.2 TO ACHIEVE THE FOLLOWING MIN. NUMBER OF CREDITS: 3.5 FOR a 1500sf to 4,999sf HOME.
CREDITS PROVIDED IN THIS HOME AS FOLLOWS:
EFFICIENT BUILDING ENVELOPE (a) 0.5 CREDITS
PRESCRIPTIVE COMPLIANCE IS BASED ON TABLE R402.1.1 WITH FOLLOWING MODIFICATIONS:
VERTICAL PENETRATION U = 0.28 WINDOWS
FLOORS TO BE R-38 and SLAB ON GRADE TO BE R-10 PERIMETER and UNDER ENTIRE SLAB BELOW GRADE.
EFFICIENT WATER HEATING (b) 1.0 CREDITS
R406.2 ADDITIONAL ENERGY EFFICIENCY REQUIREMENTS (MANDATORY).
HIGH EFFICIENCY HVAC EQUIPMENT 3a: 1.0 CREDITS
GAS FURNACE WITH MINIMUM AFUE OF 94%
EFFICIENT WATER HEATING 5a: 0.5 CREDITS
ALL SHOWERHEAD and KITCHEN SINK FAUCETS INSTALLED IN THE HOUSE SHALL BE RATED AT 1.75 GPM or LESS.
ALL OTHER LAVATORY FAUCETS SHALL BE RATED AT 1.0 GPM or LESS.
EFFICIENT WATER HEATING 5c: 1.5 CREDITS
WATER HEATING SYSTEM SHALL BE:
GAS WATER HEATER WITH A MINIMUM EF OF 0.91

SUMMARY

SQUARE FOOTAGE SUMMARY	
LOWER FLOOR AREA	0 S.F.
MAIN FLOOR AREA	2,191 S.F.
UPPER FLOOR AREA	2,644 S.F.
TOTAL CONDITIONED AREA	4840 S.F.
2 CAR GARAGE	702 S.F.
COVID PATIO	815 S.F.
COVID PORCH	57 S.F.
TOTAL AREA UNDER ROOF	6,414 S.F.
OVERALL WIDTH	45'-0"
OVERALL DEPTH	44'-8"

Updated: 12.09.20
Method for Calculating Square Footage - ANSI Z765-2019 excludes no separate distinction of above-grade or below-grade areas and each level is measured to the outside of studs not the exterior finished surface.
Square footage calculations for this house were made based on plan dimensions only and may vary from square footage measurements on the house site.

Sheet Title/Description



JM
JAYMARC
 HOMES

7525 SE 24th St., 487
 Mercer Island, WA
 98040
 425.266.9100

Issue	Issue Date	By	Description

Spring Residence
 4740 W. Mercer Way
 Mercer Island, WA.
 Job Number: Spring JMC011

plan name: -
 marketing name: -
 plan number: -
 mark sys. number: -

Conditions not specifically represented graphically or in writing or which conflict with the current International Residential Code (IRC.) or those of the local municipality then the current standards and requirements of each respectively shall govern.

The drawings in this set are instruments of service and shall remain the property of JayMarc Homes, LLC.

© 2017 JayMarc Homes, LLC; All rights reserved.

12.19.22
 Submittal Date

Sheet Title/Description
 JAYMARC HOMES
 Design Firm

R.K.N.
 Drawn by:

S.K.
 Checked by:

Primary Scale


A8
 of .

Sheet Title/Description

ROOF PLAN
 1/4" = 1'-0"

LOWER ROOF VENTILATION @ GARAGE	
Standard Truss / Scissor Truss Roof Framing Assembly:	ZONE 1
Roof Area = 443 s.f.	
Ventilation Required: 443 s.f. x 144 s.i. / s.f. / 300 =	212.64 s.i. Req'd
Provide between 40% & 50% of the total required ventilation no more than 3 ft below the ridge or the highest point of the space. Remainder to be installed at eave vents.	
Ridge Ventilation: 50% of ventilation	50.16
Continuous Ridge Vent =	18.00 s.i. per l.f.
Upper Ventilation MIN. Req'd = 106.32 s.i. x 0.4 / s.i. per linear foot =	5 l.f.
Upper Ventilation MAX. Req'd = 106.32 s.i. x 0.5 / s.i. per linear foot =	5 l.f.
Provide: 0 l.f. ridge vent. Ventilation =	0.00 s.i.
Ventilation area remainder for AF50 vents =	50.16 s.i.
Upper Roof Ventilation: as needed to achieve 50% of ventilation	
AF50 Roof Jack (10" x 7") =	50.00 s.i. each.
Upper Ventilation Req'd TO GET 50% = 50.16 s.i. / s.i. of each vent =	2 vents
Provide: 3 -10"x7" roof jacks. Ventilation =	150.00 s.i.
Eave Ventilation:	
Birdblocking: (3/2" dia holes per bay = 4.71 s.i. / l.f. - 25% reduction =	3.53 s.i. / l.f.
Eave Ventilation Req'd = 106.32 s.i. / s.i. per l.f. =	92.62 l.f.
Provide Minimum: 20 l.f. birdblocking. Ventilation =	70.85 s.i.
Minimum Ventilation Provided =	220.65 s.i. IS GREATER THAN : 212.64 s.i. Req'd

LOWER ROOF VENTILATION @ KITCHEN & DINING	
Standard Truss / Scissor Truss Roof Framing Assembly:	ZONE 1
Roof Area = 209 s.f.	
Ventilation Required: 209 s.f. x 144 s.i. / s.f. / 300 =	100.32 s.i. Req'd
Provide between 40% & 50% of the total required ventilation no more than 3 ft below the ridge or the highest point of the space. Remainder to be installed at eave vents.	
Ridge Ventilation: 50% of ventilation	50.16
Continuous Ridge Vent =	18.00 s.i. per l.f.
Upper Ventilation MIN. Req'd = 50.16 s.i. x 0.4 / s.i. per linear foot =	3 l.f.
Upper Ventilation MAX. Req'd = 50.16 s.i. x 0.5 / s.i. per linear foot =	2 l.f.
Provide: 0 l.f. ridge vent. Ventilation =	0.00 s.i.
Ventilation area remainder for AF50 vents =	50.16 s.i.
Upper Roof Ventilation: as needed to achieve 50% of ventilation	
AF50 Roof Jack (10" x 7") =	50.00 s.i. each.
Upper Ventilation Req'd TO GET 50% = 50.16 s.i. / s.i. of each vent =	2 vents
Provide: 2 -10"x7" roof jacks. Ventilation =	100.00 s.i.
Eave Ventilation:	
Birdblocking: (3/2" dia holes per bay = 4.71 s.i. / l.f. - 25% reduction =	3.53 s.i. / l.f.
Eave Ventilation Req'd = 106.32 s.i. / s.i. per l.f. =	78.47 l.f.
Provide Minimum: 15 l.f. birdblocking. Ventilation =	52.99 s.i.
Minimum Ventilation Provided =	152.99 s.i. IS GREATER THAN : 100.32 s.i. Req'd



Upper Roof Ventilation: as needed to achieve 50% of ventilation	
Standard Truss / Scissor Truss Roof Framing Assembly:	ZONE 1
Roof Area = 2477 s.f.	
Ventilation Required: 2477 s.f. x 144 s.i. / s.f. / 300 =	1189 s.i. Req'd
Provide between 40% & 50% of the total required ventilation no more than 3 ft below the ridge or the highest point of the space. Remainder to be installed at eave vents.	
Ridge Ventilation: 50% of ventilation	50.16
Continuous Ridge Vent =	18.00 s.i. per l.f.
Upper Ventilation MIN. Req'd = 594.48 s.i. x 0.4 / s.i. per linear foot =	27 l.f.
Upper Ventilation MAX. Req'd = 594.48 s.i. x 0.5 / s.i. per linear foot =	33 l.f.
Provide: 0 l.f. ridge vent. Ventilation =	0.00 s.i.
Ventilation area remainder for AF50 vents =	50.16 s.i.
Upper Roof Ventilation: as needed to achieve 50% of ventilation	
AF50 Roof Jack (10" x 7") =	50.00 s.i. each.
Upper Ventilation Req'd TO GET 50% = 50.16 s.i. / s.i. of each vent =	2 vents
Provide: 13 -10"x7" roof jacks. Ventilation =	650.00 s.i.
Eave Ventilation:	
Birdblocking: (3/2" dia holes per bay = 4.71 s.i. / l.f. - 25% reduction =	3.53 s.i. / l.f.
Eave Ventilation Req'd = 594.48 s.i. / s.i. per l.f. =	234.17 l.f.
Provide Minimum: 153 l.f. birdblocking. Ventilation =	540.47 s.i.
Minimum Ventilation Provided =	1190.47 s.i. IS GREATER THAN : 1189 s.i. Req'd

NOTE #2:
 PROVIDE SIMPSON CSI6 STRAP FROM DBL. TOP PLATE (13" END LENGTH) TO UNDERSIDE OF 2X BLOCKING BETWEEN TRUSS BOT. CHORDS FOR (3) TRUSS BAYS (6'-0" MIN.) PROVIDE 2X BLOCKING @ TOP CHORDS OF TRUSSES + SHTG. BETWEEN TOP CHORD @ BOT. CHORD BLOCKING FASTENED W/ 2 1/2"x0.131" NAILS @ 6" O.C. @ SHTG. EDGES. FASTEN ROOF SHTG. TO BLOCKING W/ 2 1/2"x0.131" NAILS @ 6" O.C.

REFER TO S-O FOR TYPICAL STRUCTURAL NOTES & SCHEDULES

PROVIDE CONT. EXT. SHEATHING BEHIND LOW TRUSSES DOWN TO SECOND FLOOR SOLE PLATE (TYP. @ LOW ROOF)

NOTE #1:
 PROVIDE 3/8" OSB OR PLYWOOD FASTENED PER 3" O.C. EDGE NAILING (SEE S-O)

4x8 HDR @ ALL EXT. WINDOWS/DOORS (TYP. U.N.O.)

LEGEND	
	INTERIOR BEARING WALL
	BEAM / HEADER
	ROOF TRUSS @ 24" O.C. (U.N.O.)
	GIRDER TRUSS
	INTERIOR SHEAR WALL PANEL OR EXTERIOR SHEAR WALL W/ 3" O.C. EDGE NAILING
	J.L. METAL HANGER
	INDICATES OVER FRAMED TRUSS AREA

JAYMARC HOMES
 7525 SE 24th St., 487
 Mercer Island, WA
 98040
 425.266.9100

Spring Residence
 4740 W. Mercer Way
 Mercer Island, WA.
 Job Number: Spring JMC011

plan name: ---
 marking name: ---
 plan number: ---
 mark sys. number: ---

Conditions not specifically represented graphically or in writing or which conflict with the current International Residential Code (I.R.C.) or those of the local municipality then the current standards and requirements of each respectively shall govern.

The drawings in this set are instruments of service and shall remain the property of JayMarc Homes, LLC.

© 2017 JayMarc Homes, LLC. All rights reserved.

12.19.22
 Submittal Date

Sheet Title/Description
 JAYMARC HOMES
 Design Firm

R.K.N.
 Drawn by:

S.K.
 Checked by:

Primary Scale

A9
 of .

ROOF FRAMING PLAN

1/4" = 1'-0"

Sheet Title/Description

Issue	Issue Date	By	Description

Spring Residence
 4740 W. Mercer Way
 Mercer Island, WA.
 Job Number: Spring JMC011

plan name:	-
marketing name:	-
plan number:	-
mark sys. number:	-

Conditions not specifically represented graphically or in writing or which conflict with the current International Residential Code (IRC) or those of the local municipality then the current standards and requirements of each respectively shall govern.

The drawings in this set are instruments of service and shall remain the property of JayMarc Homes, LLC.

© 2017 JayMarc Homes, LLC; All rights reserved.

12.09.22
 Submittal Date

Sheet Title/Description

JAYMARC HOMES
 Design Firm

R.K.N.
 Drawn by:

S.K.
 Checked by:


Primary Scale

A10
 of .


Sheet Title/Description



FRONT ELEVATION
 1/4" = 1'-0"



LEFT ELEVATION
 1/4" = 1'-0"



PARTIAL FRONT ELEVATION
 1/4" = 1'-0"

Issue	Issue Date	By	Description
△			
△			

Spring Residence
 4740 W. Mercer Way
 Mercer Island, WA.
 Job Number: Spring
 JMC011

plan name: -
 marketing name: -
 plan number: -
 mark sys. number: -

Conditions not specifically represented graphically or in writing or which conflict with the current International Residential Code (IRC), or those of the local municipality then the current standards and requirements of each respectively shall govern.

The drawings in this set are instruments of service and shall remain the property of JayMarc Homes, LLC.

© 2017 JayMarc Homes, LLC; All rights reserved.

12.09.22
 Submittal Date

Sheet Title/Description
 JAYMARC HOMES
 Design Firm

R.K.N.
 Drawn by:

S.K.
 Checked by:


Primary Scale

A11
 of .



REAR ELEVATION

1/4" = 1'-0"




RIGHT ELEVATION


1/4" = 1'-0"

Sheet Title/Description

NOTES:



A BUILDING SECTION
 1/4" = 1'-0"



B BUILDING SECTION
 1/4" = 1'-0"

Issue	Issue Date	By	Description

Spring Residence
 4740 W. Mercer Way
 Mercer Island, WA.
 Job Number: Spring
 JMC011

plan name:	-
marketing name:	-
plan number:	-
mark sys. number:	-

Conditions not specifically represented graphically or in writing or which conflict with the current international Residential Code (IRC.) or those of the local municipality then the current standards and requirements of each respectively shall govern.

The drawings in this set are instruments of service and shall remain the property of JayMarc Homes, LLC.

© 2017 JayMarc Homes, LLC; All rights reserved.

12.19.22
 Submittal Date

Sheet Title/Description
 JAYMARC HOMES
 Design Firm

R.K.N.
 Drawn by:

S.K.
 Checked by:

Primary Scale

A12
 of .

Sheet Title/Description



7525 SE 24th St., 487
Mercer Island, WA
98040
425.266.9100

Issue	Issue Date	By	Description
△			

Spring Residence
4740 W. Mercer Way
Mercer Island, WA.
Job Number: Spring JMC011

plan name: -
marketing name: -
plan number: -
mark sys. number: -

Conditions not specifically represented graphically or in writing or which conflict with the current international Residential Code (IRC.) or those of the local municipality then the current standards and requirements of each respectively shall govern.

The drawings in this set are instruments of service and shall remain the property of JayMarc Homes, LLC.

© 2017 JayMarc Homes, LLC; All rights reserved.

12.19.22
Submittal Date


Sheet Title/Description
JAYMARC HOMES
Design Firm

R.K.N.
Drawn by:

S.K.
Checked by:

Primary Scale

A13
of .



C STAIR SECTION
1/4" = 1'-0"

SECTION SHEET 2
1/4" = 1'-0"

Sheet Title/Description

BASEMENT SLAB

4" CONC. SLAB ON 6 MIL VAPOR BARRIER ON 4" MIN. GRANULAR FILL ON 95% COMPACTED FILL/VIRGIN SOIL

GARAGE SLAB

4" CONC. SLAB ON 6 MIL VAPOR BARRIER ON 4" MIN. GRANULAR FILL ON 95% COMPACTED FILL/VIRGIN SOIL

PORCH SLAB

4" CONC. SLAB ON GRADE ON 6 MIL VAPOR BARRIER ON 4" MIN. GRANULAR FILL ON 95% COMPACTED FILL/VIRGIN SOIL

GENERAL STRUCTURAL NOTES

FOUNDATION

DESIGN IS BASED ON 2018 INTERNATIONAL RESIDENTIAL CODE & 2018 INTERNATIONAL BUILDING CODE... DESIGN LOADS: SOIL 1500 PSF ALLOWABLE BEARING PRESSURE... CONCRETE SHALL ATTAIN THE FOLLOWING MINIMUM COMPRESSIVE STRENGTHS IN 28 DAYS, UNO... UTILIZE 5# SACK 2500 PSI CONCRETE MIXES THAT ARE EQUIVALENT TO 3000 PSI CONCRETE FOR WEATHERING POTENTIAL... FOUNDATION WALL DESIGN IS BASED ON BACKFILL SOIL CLASSIFICATIONS OF SC, ML-CL, OR CL (60 PCF) SOIL...

LOADING AND DESIGN PARAMETERS

GRAVITY DESIGN LOADS: DEAD LOAD (PSF): ROOF TRUSS TOP CHORD 10, ROOF TRUSS BOTTOM CHORD 7, FLOOR (TRUSSES) 15, ROOF / FLOOR / DECK (JOISTS) 10, FEDESTAL PAVERS 10, TILE FLOORS 15, STUCCO 10... LIVE LOAD (PSF): ROOF 20, RESIDENTIAL LIVING AREAS 40, RESIDENTIAL SLEEPING AREAS 30, RESIDENTIAL WOOD DECKS 40, GARAGE 50... SNOW LOAD: GROUND SNOW LOAD (P) (PSF) 25, FLAT ROOF SNOW LOAD (P) (PSF) 25... LATERAL DESIGN LOADS: WIND LOAD: (IBC 1609) SPEED (Va) (MPH) 100, WIND RISK CATEGORY 11, IMPORTANCE FACTOR (Iw) 1.0, EXPOSURE CATEGORY 10, INTERNAL PRESSURE COEFF. (GC) 0.0, TOPOGRAPHIC FACTOR (Kz) 1.6...

LATERAL BRACING NOTES

THIS HOME HAS BEEN ENGINEERED TO RESIST LATERAL FORCES RESULTING FROM: 100 MPH WIND SPEED, EXP. C (ASCE 7-16 WIND MAP, PER IRC R301.2.1.1) RISK CAT. 2 & SEISMIC CAT. D2. 110 MPH WIND IN 2018 IRC MAP ENGINEERED DESIGN WAS COMPLETED PER 2018 IBC (SECTION 1604 & 1613) & ASCE 7-16, AS PERMITTED BY R301.1.3 OF THE 2018 IRC. ACCORDINGLY, THIS HOME, AS DOCUMENTED AND DETAILED HEREWITIN, IS ADEQUATE TO RESIST THE CODE REQUIRED LATERAL FORCES, AND DOES NOT NEED TO CONFORM TO THE PRESCRIPTIVE PROVISIONS OF R602.10.

STANDARD EXTERIOR WALL SHEATHING SPECIFICATIONS

3/8" OSB OR 1/2" PLYWOOD: FASTEN SHEATHING W/ 2 1/2"x0.131" NAILS @ 6" O.C. AT ALL SUPPORTED PANEL EDGES AND 12" O.C. IN THE PANEL FIELD. ALL SHEATHING SHEET PANEL EDGES SHALL OCCUR OVER WALL FRAMING MEMBERS OR 2x HORIZONTAL BLOCKING SHALL BE PROVIDED TO SUPPORT PANEL EDGE. ALL EXTERIOR WALLS SHALL BE CONSTRUCTED PER THIS SPECIFICATION UNO. ON PLANS.


3" O.C. EDGE NAILING (WHERE NOTED ON PLANS)

3/8" OSB OR 1/2" PLYWOOD: ONLY AT LOCATIONS INDICATED ON PLANS - SHEATHE WALL SHOWN WITH 3/8" OSB. FASTEN SHEATHING W/ 2 1/2"x0.131" NAILS @ 3" O.C. AT EDGES AND 12" O.C. AT CENTER. ALL SHEATHING SHEET PANEL EDGES SHALL OCCUR OVER WALL FRAMING MEMBERS OR 2x HORIZONTAL BLOCKING SHALL BE PROVIDED TO SUPPORT PANEL EDGE AND 3" O.C. FASTENING.

- NOTES: 1. LATERAL ANALYSIS ASSUMES STUD SPACING @ 16" O.C. 2. ALL SHEAR WALLS SHALL HAVE DOUBLE TOP PLATES FASTENED TOGETHER W/ 3"x0.131" NAILS @ 8" O.C. USE (2) 2 1/2"x0.131" NAILS AT EACH LAP SPLICE. (6) EACH SIDE OF JOINT (TYP. UNO.) 3. ALL EXTERIOR WALLS ARE CONTINUOUSLY SHEATHED. 4. ALL INTERIOR SHEAR WALLS AND EXTERIOR WALLS ARE SHEATHED ABOVE AND BELOW OPENINGS.

LEGEND

Interior bearing wall, Bearing wall above (B.W.A.), Shearwall above (S.W.A.), Beam / Header, Interior shear wall panel or exterior shear wall w/ 3" o.c. edge nailing, Area of overframing, Metal hanger, Indicates post above, provide solid blocking under post or jamb above, Indicates hold-down.



HOLD-DOWN SCHEDULE

Table with 2 columns: Symbol, Specification. HD-1: SIMPSON STDH14 (R.J) HOLD-DOWN. HD-5: SIMPSON CS16 STRAP TIE (14" END LENGTH). HD-6: SIMPSON MSTC40 STRAP TIE (CENTER STRAP ON FLOOR SYSTEM UNO.). HD-7: SIMPSON MSTC66 STRAP TIE (CENTER STRAP ON FLOOR SYSTEM UNO.).

MEANS & METHODS NOTES

THE STRUCTURE IS DESIGNED TO BE SELF SUPPORTING AND STABLE AFTER THE BUILDING IS FINISHED AND ALL PLAN, DETAIL, AND NOTE SPECIFICATIONS HAVE BEEN COMPLETED. IT IS THE CONTRACTOR'S SOLE RESPONSIBILITY TO DETERMINE THE ERECTION PROCEDURES AND SEQUENCE TO INSURE THE SAFETY OF THE BUILDING AND ITS COMPONENTS DURING CONSTRUCTION. THIS INCLUDES, BUT IS NOT LIMITED TO, THE ADDITION OF NECESSARY SHORINGS, SHEETING, TEMPORARY BRACING, GUYS, AND TIE-DOWNS. CONTRACTOR SHALL BE RESPONSIBLE FOR ALL SHORING AND BRACING REQUIRED TO STABILIZE AND PROTECT EXISTING AND ADJACENT STRUCTURES AND SYSTEMS DURING COURSE OF DEMOLITION AND CONSTRUCTION OF THE PROJECT.

STRUCTURAL DESIGN AND SPECIFICATIONS ASSUME THAT ALL SUPPORTING AND NON-SUPPORTING ELEMENTS IN CONTACT WITH FLOOR FRAMING ARE LEVEL, INCLUDING, BUT NOT LIMITED TO: FOUNDATIONS, SLABS ON GRADE, BEAMS, WALLS, AND NON-BEARING ELEMENTS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY LEVELNESS AND MAKE ADJUSTMENTS AS NECESSARY, INCLUDING CONSIDERATION OF THOSE AREAS THAT MAY BE WITHIN CONTRACTUAL, INDUSTRY, OR WARRANTY TOLERANCES.

ADDITIONAL NOTES FOR TRUSS & I-JOIST MANUFACTURER

ROOF TRUSS, FLOOR TRUSS AND ENGINEERED JOISTS SHALL BE DESIGNED TO MEET THE DIFFERENTIAL DEFLECTION CRITERIA BELOW UNLESS NOTED OTHERWISE ON PLAN. MULHERN + KULP CANNOT BE HELD RESPONSIBLE FOR ANY STRUCTURAL ISSUES RELATED TO ANY BUILDING COMPONENT IF COMPONENT SHOP DRAWINGS ARE NOT SUBMITTED TO MKF FOR REVIEW PRIOR TO FABRICATION, DELIVERY, OR INSTALLATION. TRUSSES SHALL BE DESIGNED SO THAT DIFFERENTIAL DEFLECTION BETWEEN ADJACENT PARALLEL TRUSSES OR GIRDER TRUSSES DOES NOT EXCEED THE FOLLOWING: A. ROOF TRUSSES: 1/4" DEAD LOAD. B. FLOOR TRUSSES, ATTIC TRUSSES, & I-JOISTS: 1/8" DEAD LOAD. C. FLOOR TRUSSES & ATTIC TRUSSES ADJACENT TO FLOOR FRAMING BY OTHERS: LIMIT ABSOLUTE TRUSS DEFLECTION TO 3/16" DEAD LOAD. (NOT DIFFERENTIAL DEFLECTION)

GENERAL STRUCTURAL NOTES

DESIGN PARAMETERS

DESIGN IS BASED ON 2018 INTERNATIONAL RESIDENTIAL CODE & 2018 INTERNATIONAL BUILDING CODE... WOOD FRAME ENGINEERING IS BASED ON NDS, NATIONAL DESIGN SPECIFICATION FOR WOOD CONSTRUCTION - LATEST EDITION.

GENERAL FRAMING

EXTERIOR BEARING WALLS SHALL BE 2x4 OR 2x6 (AS SHOWN ON PLANS) @ 16" O.C. (W/ DOUBLE TOP PLATE) HEM FIR (HF) "STUD" GRADE LUMBER, OR BETTER, UNO. INTERIOR BEARING WALLS SHALL BE 2x4 OR 2x6 (AS SHOWN ON PLANS) @ 16" O.C. (W/ DOUBLE TOP PLATE) HEM FIR (HF) "STUD" GRADE LUMBER, OR BETTER, UNO. ALL NON-BEARING INTERIOR STUD WALLS SHALL BE CONSTRUCTED WITH 2x "STUD" GRADE MEMBERS SPACED @ 24" O.C. (MAX.) ALL WALLS TALLER THAN TYP. PLATE HEIGHT SHALL BE CONSIDERED BALLOON FRAMED & SHALL BE CONSTRUCTED FROM FLOOR TO UNDERSIDE OF FRAMING AT NEXT LEVEL. BF. WALLS SHALL BE 2x4 OR 2x6 (AS SHOWN ON PLANS) HEM FIR (HF) #2 GRADE LUMBER, OR BETTER. ALL HEADERS SHALL BE SUPPORTED BY (1)2x JACK STUD & (1)2x KING STUD, MINIMUM... BUILD-UP POSTS SHALL BE 2x4 OR 2x6 HEM FIR (HF) "STUD" GRADE LUMBER, OR BETTER, UNO. & SOLID WOOD COLUMN SHALL BE SPRUCE PINE FIR (SPF) #2 GRADE LUMBER, OR BETTER, UNO. ALL 2x6 AND LARGER SOLID SAWN BEAMS/HEADERS SHALL BE HEM FIR #2 (HF #2) OR BETTER. ALL 4x6 AND LARGER SOLID SAWN LUMBER SHALL BE DOUG FIR #2 (DF #2) OR BETTER. ALL FRAMING LUMBER SHALL BE KILN DRIED TO 15% MC (KD-15). ALL TYP. NAIL FASTENER REQUIREMENTS ARE NOTED IN GENERAL NOTES, IN DETAILS, OR ON PLANS. ALL NAILS SPECIFIED ARE MIN DIAMETER AND LENGTH REQUIRED FOR CONNECTION. ALL HANGER NAILS SHALL BE INSTALLED PER MANUFACTURER'S REQUIREMENTS FOR MAX CHARTED CAPACITY. NOTE: HANGERS USE COMMON NAIL DIAMETERS NOT TYPICAL FRAMING GUN NAILS. FASTEN ALL BEAMS TO COLUMN, OR FLUSH BEAMS TO SUPPORTING BEAMS, W/ (4) 3"x0.131" TOENAILS (MN), TYP. UNO. PROVIDE SOLID BLOCKING IN FLOOR SYSTEM UNDER ALL POSTS & HOLD-DOWNS CONTINUOUS TO FOUNDATION/BEARING. BLOCKING TO MATCH POST ABOVE. ENGINEERED LUMBER TO MEET OR EXCEED THE FOLLOWING: LVL MEMBERS - Fb=2525 PSI, Fv=910 PSI, E=155x10^6 PSI... FACE NAIL MULTI-PLY 2x BEAMS & HEADERS W/ 3-RINGS OF 3"x0.131" NAILS (MN) @ 12" O.C. STAGGERED. APPLY NAILING FROM BOTH FACES @ 3-PLY OR MORE CONDITIONS. UTILIZE 2 RINGS OF NAILS FOR 2x6 & 2x8 MEMBERS. ALL MEMBERS SPECIFIED AS MULTI-PLY (B*) SHALL BE FASTENED TOGETHER PER MANUFACTURER. EQUIVALENT WIDTH SOLID MATERIAL MAY BE USED AS EQUAL. FASTEN 2x WOOD PLATES TO TOP FLANGE OF STEEL BEAMS W/ PAFs (HILT) X-U PINS OR EQUAL (0.151" DIA. x 2" LONG MIN) @ 16" O.C. STAGGERED, OR 1/2" DIA. BOLTS @ 48" O.C. STAGGERED. REFER TO IRC FASTENING SCHEDULE TABLE R602.3(i) FOR ALL CONNECTIONS, TYP. UNO.

FLOOR FRAMING

I-JOISTS/TRUSSES SHALL BE DESIGNED BY MANUF. TO MEET OR EXCEED L/480 LIVE LOAD DEFLECTION CRITERIA AND SHALL RUN CONTINUOUS OVER SUPPORTS WHEREVER POSSIBLE. ALL LOADS SHOWN ON PLAN FOR MANUF. DESIGN ARE ASS LEVEL LOADS, UNO. (EXCLUDES STONE/MARBLE OR NET BED CONSTRUCTED FLOORS - CONTACT MKF FOR EXCLUDED DESIGN). ALL METAL I-JOIST/TRUSS HANGERS SHALL BE SPECIFIED BY I-JOIST/TRUSS MANUFACTURER, UNLESS OTHERWISE NOTED. I-JOIST/TRUSS SHOP DRAWINGS SHALL BE SUBMITTED TO ARCHITECT AND ENGINEER FOR REVIEW AND APPROVAL PRIOR TO FABRICATION OR DELIVERY. 2x FLOOR JOISTS HAVE BEEN DESIGNED TO MEET OR EXCEED L/240 LIVE LOAD DEFLECTION CRITERIA. TYPICAL 2x JOIST HANGERS (UNO. ON PLANS): SINGLE PLY: SIMPSON LUS20 DOUBLES: SIMPSON LUS20-2 FLOOR SHEATHING SHALL BE 23/32" A.P.A. RATED "STURD"-FLOOR" 24" O.C. EXPOSURE 1 (OR APPROVED EQUAL) WITH TONGUE AND GROOVE EDGES. FASTEN TO FRAMING MEMBERS W/ GLUE AND 2 1/2" x 0.131" NAILS @ 6" O.C. @ PANEL EDGES & @ 12" O.C. FIELD. ALL FLUSH CONNECTIONS SHALL BE CONNECTED WITH HANGER APPROPRIATE FOR MEMBER SIZE, UNO. FASTEN HANGERS TO SINGLE PLY FLUSH BEAMS W/ 1/2" LONG NAILS.

ROOF FRAMING

FASTEN EACH ROOF TRUSS TO TOP PLATE W/ (4) 3"x0.131" TOENAILS (MN) & (1) SIMPSON SDNKG15600 SCREW @ ALL BEARING POINTS. PROVIDE (2) SIMPSON SDNKG15600 SCREWS AT 2-PLY GIRDER TRUSSES, (3) SIMPSON SDNKG15600 SCREWS AT 3-PLY GIRDER TRUSSES AT ALL BEARING POINTS. FASTEN EACH ROOF RAFTER TO TOP PLATE WITH (1) SIMPSON SDNKG15600 SCREW PROVIDE (2) SIMPSON SDNKG15600 SCREWS AT FLUSH BEAMS IN THE ROOF - AT ALL BEARING POINTS. ROOF SHEATHING SHALL BE 7/16" A.P.A. RATED SHEATHING 24/16 EXPOSURE 1 (OR APPROVED EQUAL). FASTEN TO FRAMING MEMBERS W/ 2 1/2" x 0.131" NAILS @ 6" O.C. AT PANEL EDGES & @ 12" O.C. AT INTERMEDIATE SUPPORTS. ROOF SHEATHING SHALL EXTEND BELOW ALL INSTANCES OF OVERFRAMING. BLOCKING SHALL BE INSTALLED AS REQUIRED TO LIMIT ROOF SHEATHING SPANS TO 24" MAX. WITHIN 48" OF ALL ROOF EDGES, RIDGES, & HIPs FASTEN ROOF SHEATHING FIELDS PER EDGE NAILING SPEC. ALL METAL HANGERS SHALL BE SPECIFIED BY THE TRUSS MANUFACTURER, UNLESS OTHERWISE NOTED. ROOF TRUSS SHOP DRAWINGS SHALL BE SUBMITTED TO ARCHITECT AND ENGINEER FOR REVIEW AND APPROVAL PRIOR TO FABRICATION OR DELIVERY. ROOF TRUSS SHOP DRAWINGS & CALCULATIONS SHALL BE PREPARED BY A WASHINGTON STATE LICENSED ENGINEER AND SHALL BE DESIGNED FOR UNBALANCED SNOW LOADING PER ASCE 7-16, SECTION 7.6. ERECT AND INSTALL ROOF TRUSSES PER WTCA & TP15 BCS1 I-08 GUIDE TO GOOD PRACTICE FOR HANDLING, INSTALLING & BRACING OF METAL PLATE CONNECTED WOOD TRUSSES. FASTEN OVER-FRAMED TRUSS SETS TO TRUSSES BELOW W/ (2) 3"x0.131" TOENAILS AT EA TRUSS. SUPPORT PORCH & SHORT SPAN ROOF TRUSSES (UP TO 6' TRIB.) W/ 2x6 LEDGER FASTENED TO FRAMING W/ (3) 3"x0.131" NAILS @ 16" O.C. FASTEN ALL INTERIOR NON-BEARING PARTITION WALLS TO TRUSS BOTTOM CHORD ABOVE WITH SIMPSON STC CLIPS AT 24" O.C. MAX. PROVIDE BLOCKING BETWEEN THE TRUSS BOTTOM CHORDS AS REQUIRED FOR THE PARALLEL CONDITIONS.

MULHERN+KULP RESIDENTIAL STRUCTURAL ENGINEERING 7720 Trade Street, Suite 350, San Diego, CA 92171 619-660-0010 mulhern+kulp.com

M&K project number: 154-22026 project mgr: R.JZ draw by: JCL issue date: 11-07-22

REVISIONS: date: initial:

JAYMARC HOMES

STRUCTURAL NOTES SPRING RESIDENCE MERCER ISLAND, WASHINGTON

seal: S-O.O



© copyright: MULHERN + KULP Structural Engineering, Inc.

MULHERN+KULP
RESIDENTIAL STRUCTURAL ENGINEERING
7220 Trade Street, Suite 350, San Diego, CA 92121
p 619-560-0010 • mulhernkulp.com




M&K project number:
154-22026
project mgr: **RJZ**
drawn by: **JCL**
issue date: **11-07-22**

REVISIONS:
date: _____ initial: _____




STRUCTURAL DETAILS
SPRING RESIDENCE
MERCER ISLAND, WASHINGTON


sheet:
LB-1




1 TYPICAL SHEAR TRANSFER DETAIL @ ROOF
SCALE: 3/4"=1'-0" HEEL HEIGHT LESS THAN 4"




2 TYPICAL SHEAR TRANSFER DETAIL @ RAISED HEEL DETAIL
SCALE: 3/4"=1'-0" HEEL HEIGHT UP TO 24" MAX.




3 TYPICAL GABLE END DETAIL
SCALE: 3/4"=1'-0"




4 TYPICAL SHEAR TRANSFER DETAIL BETWEEN FLOORS @ EXTERIOR WALL
SCALE: 3/4"=1'-0" PERPENDICULAR FRAMING




5 TYPICAL SHEAR TRANSFER DETAIL BETWEEN FLOORS @ EXTERIOR WALL
SCALE: 3/4"=1'-0" PARALLEL FRAMING




6 TYPICAL SHEAR TRANSFER DETAIL @ ROOF
SCALE: 3/4"=1'-0" HEEL HEIGHT BETWEEN 4" - 11 1/2"




7 TYPICAL SHEAR TRANSFER DETAIL @ ROOF & EXTERIOR WALL
SCALE: 3/4"=1'-0"




8 TYPICAL SHEAR TRANSFER DETAIL @ SHEAR WALL BELOW
SCALE: 3/4"=1'-0"




9 SHEAR TRANSFER DETAIL @ SHEAR WALL BELOW
SCALE: 3/4"=1'-0"




10 TYPICAL SHEAR TRANSFER DETAIL BETWEEN FLOORS @ EXTERIOR WALL
SCALE: 3/4"=1'-0"



11 TYPICAL SHEAR TRANSFER DETAIL BETWEEN FLOORS @ EXTERIOR WALL
SCALE: 3/4"=1'-0"



12 SHEAR TRANSFER DETAIL @ EXTERIOR SHEARWALL ABOVE
SCALE: 3/4"=1'-0"



© copyright: MULHERN + KULP Structural Engineering, Inc.

MULHERN+KULP
RESIDENTIAL STRUCTURAL ENGINEERING
7720 Trade Street, Suite 350, San Diego, CA 92121
p 619-550-0010 • mulhernkulp.com



M&K project number:
154-22026

project mgr: R.JZ
drawn by: JCL
issue date: 11-07-22


REVISIONS:
date: initial:




STRUCTURAL DETAILS
SPRING RESIDENCE
MERCER ISLAND, WASHINGTON

sheet:


LB-2




35 SHEAR TRANSFER DETAIL @ EXTERIOR SHEARWALL ABOVE
SCALE: 3/4"=1'-0"




36 SECTION
SCALE: 3/4"=1'-0"




37 TYPICAL SHEAR TRANSFER DETAIL BETWEEN FLOORS @ EXTERIOR WALL
SCALE: 3/4"=1'-0"




38 SHEAR TRANSFER DETAIL @ EXTERIOR SHEARWALL ABOVE
SCALE: 3/4"=1'-0"




39 SHEAR TRANSFER DETAIL @ EXTERIOR SHEARWALL ABOVE
SCALE: 3/4"=1'-0"




40 SHEAR TRANSFER DETAIL @ EXTERIOR SHEARWALL ABOVE
SCALE: 3/4"=1'-0"




41 SHEAR TRANSFER DETAIL @ EXTERIOR SHEARWALL ABOVE
SCALE: 3/4"=1'-0"




42 TYPICAL SHEAR TRANSFER DETAIL @ ROOF & EXTERIOR WALL
SCALE: 3/4"=1'-0"




43 TYPICAL SHEAR TRANSFER DETAIL BETWEEN FLOORS @ EXTERIOR WALL
SCALE: 3/4"=1'-0"




42 EXT. WALL & INT. SHEARWALL OPENING ELEVATION
SCALE: NTS




43 EXT. WALL & INT. SHEARWALL OPENING ELEVATION
SCALE: NTS




44 EXT. WALL & INT. SHEARWALL OPENING ELEVATION
SCALE: NTS




99 SHEAR TRANSFER DETAIL @ INTERSECTING INT. SHEARWALL
 SCALE: 3/4"=1'-0" SHTS. OPPOSITE PAGES




100 SHEAR TRANSFER DETAIL @ EXTERIOR SHEARWALL ABOVE
 SCALE: 3/4"=1'-0"




117 STRAP DETAIL
 SCALE: 3/4"=1'-0"




A TYPICAL HOLD-DOWN INSTALLATION
 NOT TO SCALE





B TYPICAL HOLD-DOWN INSTALLATION
 NOT TO SCALE



C TYPICAL HOLD-DOWN INSTALLATION
 NOT TO SCALE



D STL BM TO WOOD FRMG CONNECTION
 SCALE: 3/4"=1'-0"




MULHERN+KULP
 RESIDENTIAL STRUCTURAL ENGINEERING
 7720 Trade Street, Suite 350, San Diego, CA 92121
 p 619-560-0010 > mulhernkulp.com

M&K project number:
 154-22026
 project mgr: R.JZ
 draw by: JCL
 issue date: 11-07-22

REVISIONS:	
date:	initial:



STRUCTURAL DETAILS
 SPRING RESIDENCE
 MERCER ISLAND, WASHINGTON



© copyright: MULHERN & KULP Structural Engineering, Inc.

MULHERN+KULP
RESIDENTIAL STRUCTURAL ENGINEERING
7220 Trade Street, Suite 350, San Diego, CA 92121
p 619-550-0010 > mulhernkulp.com

M&K project number:
154-22026









project mgr: R.JZ
drawn by: JCL
issue date: 11-07-22

REVISIONS:
date: initial:



STRUCTURAL DETAILS
SPRING RESIDENCE
MERCER ISLAND, WASHINGTON

sheet:
SD.01






4 TYPICAL CRAWLSPACE FOUNDATION @ GARAGE
SCALE: 3/4"=1'-0"

5 TYPICAL CONCRETE FOOTING @ GARAGE DOOR OPENING
SCALE: 3/4"=1'-0"

6 TYPICAL EXT. GARAGE FOUNDATION
SCALE: 3/4"=1'-0"

6A TYPICAL EXT. GARAGE FOUNDATION
SCALE: 3/4"=1'-0"



7 TYPICAL CRAWLSPACE FOOTING DETAIL
SCALE: 3/4"=1'-0"

8 TYPICAL FOOTING @ PORCH SLAB
SCALE: 3/4"=1'-0"

9 SITE FOUNDATION WALL
SCALE: 3/4"=1'-0"



2018 WSEC COMPLIANCE NOTES - SHEET 1

2018 WASH. STATE ENERGY CODE (WSEC)

HEAT CONTROLS SHALL INDICATE WHEN SUPPLEMENTAL HEATING IS BEING USED THROUGH VISUAL MEANS (E.G., LED INDICATORS). HEAT PUMPS EQUIPPED WITH SUPPLEMENTARY HEATERS SHALL BE INSTALLED WITH CONTROLS THAT PREVENT SUPPLEMENTAL HEATER OPERATION ABOVE 40°F. AT FINAL INSPECTION THE AUXILIARY HEAT LOCK-OUT CONTROL SHALL BE SET TO 35°F OR LESS.

R403.2 HOT WATER BOILER OUTDOOR TEMPERATURE SETBACK.
HOT WATER BOILERS THAT SUPPLY HEAT TO THE BUILDING THROUGH ONE- OR TWO-PIPE HEATING SYSTEMS SHALL HAVE AN OUTDOOR TEMPERATURE SETBACK CONTROL THAT LOWERS THE BOILER WATER TEMPERATURE BASED ON THE OUTDOOR TEMPERATURE.

R403.3 DUCTS.
DUCTS AND AIR HANDLERS SHALL BE IN ACCORDANCE WITH SECTIONS R403.3.1 THROUGH R403.3.5.

R403.3.1 INSULATION (PRESCRIPTIVE).
DUCTS OUTSIDE THE BUILDING THERMAL ENVELOPE SHALL BE INSULATED TO A MINIMUM OF R-6. DUCTS WITHIN A CONCRETE SLAB OR IN THE GROUND SHALL BE INSULATED TO R-10 WITH INSULATION DESIGNED TO BE USED BELOW GRADE.

EXCEPTION: DUCTS OR PORTIONS THEREOF LOCATED COMPLETELY INSIDE THE BUILDING THERMAL ENVELOPE. DUCTS LOCATED IN CRANL SPACES DO NOT QUALIFY FOR THIS EXCEPTION.

R403.3.2 SEALING (MANDATORY).
DUCTS, AIR HANDLERS, AND FILTER BOXES SHALL BE SEALED. JOINTS AND SEAMS SHALL COMPLY WITH EITHER THE INTERNATIONAL MECHANICAL CODE OR INTERNATIONAL RESIDENTIAL CODE, AS APPLICABLE.

EXCEPTIONS:
1. AIR-IMPERMEABLE SPRAY FOAM PRODUCTS SHALL BE PERMITTED TO BE APPLIED WITHOUT ADDITIONAL JOINT SEALS.
2. FOR DUCTS HAVING A STATIC PRESSURE CLASSIFICATION OF LESS THAN 2 INCHES OF WATER COLUMN (500 PA), ADDITIONAL CLOSURE SYSTEMS SHALL NOT BE REQUIRED FOR CONTINUOUSLY WELDED JOINTS AND SEAMS, AND LOCKING-TYPE JOINTS AND SEAMS OF OTHER THAN THE SNAP-LOCK AND BUTT-LOCK TYPES.

R403.3.2.1 SEALED AIR HANDLERS.
AIR HANDLERS SHALL HAVE A MANUFACTURER'S DESIGNATION FOR AN AIR LEAKAGE OF NO MORE THAN 2 PERCENT OF THE DESIGN AIR FLOW RATE WHEN TESTED IN ACCORDANCE WITH ASHRAE 183.

R403.3.3 DUCT TESTING (MANDATORY).
DUCTS SHALL BE LEAK TESTED IN ACCORDANCE WITH 95.9 R-33, USING THE MAXIMUM DUCT LEAKAGE RATES SPECIFIED.

EXCEPTION: THE TOTAL LEAKAGE TEST OR LEAKAGE TO THE OUTDOORS IS FOR DUCTS AND AIR HANDLERS LOCATED ENTIRELY WITHIN THE BUILDING THERMAL ENVELOPE. FOR FORCED AIR DUCTS, A MAXIMUM OF 10 LINEAR FEET OF RETURN DUCTS AND 5 LINEAR FEET OF SUPPLY DUCTS MAY BE LOCATED OUTSIDE THE CONDITIONED SPACE. ALL METALLIC DUCTS LOCATED OUTSIDE THE CONDITIONED SPACE MUST HAVE BOTH TRANSVERSE AND LONGITUDINAL JOINTS SEALED WITH MASTIC. IF FLEX DUCTS ARE USED, THEY CANNOT CONTAIN SEAMS. FLEX DUCT CONNECTIONS MUST BE MADE WITH NYLON STRAPS AND INSTALLED USING A PLASTIC STRAPPING TENSIONING TOOL. DUCTS LOCATED IN CRANL SPACES DO NOT QUALIFY FOR THIS EXCEPTION.

A WRITTEN REPORT OF THE RESULTS SHALL BE SIGNED BY THE PARTY CONDUCTING THE TEST AND PROVIDED TO THE CODE OFFICIAL.

R403.3.4 DUCT LEAKAGE (MANDATORY).
THE TOTAL LEAKAGE OF THE DUCTS, WHERE MEASURED IN ACCORDANCE WITH SECTION R403.3.3, SHALL BE AS FOLLOWS:

1. RIM-TO-RIM TEST: TOTAL LEAKAGE SHALL BE LESS THAN OR EQUAL TO 4 CFM (103 L/MIN) PER 100 SQUARE FEET (9.29 M²) OF CONDITIONED FLOOR AREA WHEN TESTED AT A PRESSURE DIFFERENTIAL OF 0.1 INCHES HG. (25 PA) ACROSS THE SYSTEM, INCLUDING THE MANUFACTURER'S AIR HANDLER ENCLOSURE. ALL REGISTER SHALL BE TAPED OR OTHERWISE SEALED DURING THE TEST. IF THE AIR HANDLER IS NOT INSTALLED AT THE TIME OF THE TEST, TOTAL LEAKAGE SHALL BE LESS THAN OR EQUAL TO 3 CFM (76 L/MIN) PER 100 SQUARE FEET (9.29 M²) OF CONDITIONED FLOOR AREA.
2. POST-CONSTRUCTION TEST: LEAKAGE TO OUTDOORS SHALL BE LESS THAN OR EQUAL TO 0.4 CFM (103 L/MIN) PER 100 SQUARE FEET (9.29 M²) OF CONDITIONED FLOOR AREA OR TOTAL LEAKAGE SHALL BE LESS THAN OR EQUAL TO 4 CFM (103 L/MIN) PER 100 SQUARE FEET (9.29 M²) OF CONDITIONED FLOOR AREA WHEN TESTED AT A PRESSURE DIFFERENTIAL OF 0.1 INCHES HG. (25 PA) ACROSS THE ENTIRE SYSTEM, INCLUDING THE MANUFACTURER'S AIR HANDLER ENCLOSURE. ALL REGISTER BOOTS SHALL BE TAPED OR OTHERWISE SEALED DURING THE TEST.

R403.3.5 BUILDING CAVITIES (MANDATORY).
BUILDING FRAMING CAVITIES SHALL NOT BE USED AS DUCTS OR PLENUMS. INSTALLATION OF DUCTS IN EXTERIOR WALLS, FLOORS OR CEILING SHALL NOT DISPLACE REQUIRED ENVELOPE INSULATION.

R403.4 MECHANICAL SYSTEM PIPING INSULATION (MANDATORY).
MECHANICAL SYSTEM PIPING CAPABLE OF CARRYING FLUIDS ABOVE 105°F (41°C) OR BELOW 55°F (13°C) SHALL BE INSULATED TO A MINIMUM OF R-6.

EXCEPTION: UP TO 200 FEET OF HYDRONIC SYSTEM PIPING INSTALLED WITHIN THE CONDITIONED SPACE MAY BE INSULATED WITH A MINIMUM OF 1/2 INCH INSULATION WITH A R VALUE OF 0.28.

R403.4.1 PROTECTION OF PIPING INSULATION.
PIPING INSULATION EXPOSED TO WEATHER SHALL BE PROTECTED FROM DAMAGE, INCLUDING THAT CAUSED BY SUNLIGHT, MOISTURE, EQUIPMENT MAINTENANCE, AND WIND. INSULATION SHALL PROVIDE SHIELDING FROM SOLAR RADIATION THAT CAN CAUSE DEGRADATION OF THE MATERIAL. ADHESIVE TAPE SHALL NOT BE PERMITTED.

R403.5 SERVICE HOT WATER SYSTEMS.
ENERGY CONSERVATION MEASURES FOR SERVICE HOT WATER SYSTEMS SHALL BE IN ACCORDANCE WITH SECTIONS R403.5.1 THROUGH R403.5.5.

R403.5.1 HEATED WATER CIRCULATION AND TEMPERATURE MAINTENANCE SYSTEM (MANDATORY).
HEATED WATER CIRCULATION SYSTEMS SHALL BE IN ACCORDANCE WITH SECTION R403.5.1.2.

HEAT TRACE TEMPERATURE MAINTENANCE SYSTEMS SHALL BE IN ACCORDANCE WITH SECTION R403.5.1.2. AUTOMATIC CONTROLS, TEMPERATURE SENSORS AND PUMPS SHALL BE ACCESSIBLE. MANUAL CONTROLS SHALL BE READILY ACCESSIBLE.

R403.5.1.1 CIRCULATION SYSTEMS.
HEATED WATER CIRCULATION SYSTEMS SHALL BE PROVIDED WITH A CIRCULATION PUMP. THE SYSTEM RETURN PIPE SHALL BE A DEDICATED RETURN PIPE OR A COLD WATER SUPPLY PIPE. GRAVITY AND THERMO-SYTHON CIRCULATION SYSTEMS SHALL BE PROHIBITED. CONTROLS FO R403.5.1.2 HEAT TRACE SYSTEMS.
ELECTRIC HEAT TRACE SYSTEMS SHALL COMPLY WITH IEEE 551 OR IEC 515. CONTROLS FOR SUCH SYSTEMS SHALL AUTOMATICALLY ADJUST THE ENERGY INPUT TO THE HEAT TRACING TO MAINTAIN THE DESIRED WATER TEMPERATURE IN THE PIPING IN ACCORDANCE WITH THE WHEN HEATED WATER IS USED IN THE OCCUPANCY.

R403.5.2 DEMAND RECIRCULATION SYSTEMS.
A WATER DISTRIBUTION SYSTEM HAVING ONE OR MORE RECIRCULATION PUMPS THAT PUMP WATER FROM A HEATED WATER SUPPLY PIPE BACK TO THE HEATED WATER SOURCE THROUGH A COLD WATER SUPPLY PIPE SHALL BE A DEMAND RECIRCULATION WATER SYSTEM. PUMPS SHALL HAVE CONTROLS THAT COMPLY WITH BOTH OF THE FOLLOWING:

1. THE CONTROL SHALL START THE PUMP UPON RECEIVING A SIGNAL FROM THE ACTION OF A USER OF A FIXTURE OR APPLIANCE, SENSING THE PRESENCE OF A USER OF A FIXTURE OR SENSING THE FLOW OF HOT OR TEMPERED WATER TO A FIXTURE FITTING OR APPLIANCE.
2. THE CONTROL SHALL LIMIT THE TEMPERATURE OF THE WATER ENTERING THE COLD WATER PIPE TO 104°F (40°C).

R403.5.3 HOT WATER PIPE INSULATION (PRESCRIPTIVE).
INSULATION FOR HOT WATER PIPE, BOTH WITHIN AND OUTSIDE THE CONDITIONED SPACE, SHALL HAVE A MINIMUM THERMAL RESISTANCE (R-VALUE) OF R-3.

EXCEPTION: PIPE INSULATION IS PERMITTED TO BE DISCONTINUOUS WHERE IT PASSES THROUGH STUDS, JOISTS OR OTHER STRUCTURAL MEMBERS AND WHERE THE INSULATED PIPES PASS OTHER PIPING, CONDUIIT OR VENTS, PROVIDED THE INSULATION IS INSTALLED TIGHT TO EACH OBSTRUCTION.

R403.5.4 DRAIN WATER HEAT RECOVERY UNITS.
DRAIN WATER HEAT RECOVERY UNITS SHALL COMPLY WITH CSA 55.2. DRAIN WATER HEAT RECOVERY UNITS SHALL BE IN ACCORDANCE WITH CSA 55.1. POTABLE WATER-SIDE PRESSURE LOSS OF DRAIN WATER HEAT RECOVERY UNITS SHALL BE LESS THAN 3 PSI (20.7 KPA) FOR INDIVIDUAL UNITS CONNECTED TO ONE OR TWO SHOWERS. POTABLE WATER-SIDE PRESSURE LOSS OF DRAIN WATER HEAT RECOVERY UNITS SHALL BE LESS THAN 2 PSI (13.8 KPA) FOR INDIVIDUAL UNITS CONNECTED TO THREE OR MORE SHOWERS.

R403.5.5 ELECTRIC WATER HEATER INSULATION.
ALL ELECTRIC WATER HEATERS IN UNHEATED SPACES OR ON CONCRETE FLOORS SHALL BE PLACED ON AN IMPERMEABLE, INSULATED SURFACE WITH A MINIMUM THERMAL RESISTANCE OF R-10.

R403.6 MECHANICAL VENTILATION (MANDATORY).
BUILDINGS SHALL BE PROVIDED WITH VENTILATION THAT MEETS THE REQUIREMENTS OF THE INTERNATIONAL RESIDENTIAL CODE OR INTERNATIONAL MECHANICAL CODE, AS APPLICABLE, OR WITH OTHER APPROVED MEANS OF VENTILATION. OUTDOOR AIR INTAKES AND EXHAUSTS SHALL HAVE AUTOMATIC OR GRAVITY DAMPERS THAT CLOSE WHEN THE VENTILATION SYSTEM IS NOT OPERATING.

R403.6.1 WHOLE-HOUSE MECHANICAL VENTILATION SYSTEM FAN EFFICACY.
MECHANICAL VENTILATION SYSTEM FANS SHALL MEET THE EFFICACY REQUIREMENTS OF TABLE R403.6.1.

EXCEPTION: WHERE MECHANICAL VENTILATION FANS ARE INTEGRAL TO TESTED AND LISTED HVAC EQUIPMENT, THEY SHALL BE POWERED BY AN ELECTRONICALLY COMMUTATED MOTOR.

Issue	Issue Date By
△	Description

△	
---	--

--	--

--	--

--	--

--	--

--	--

--	--

--	--

--	--

--	--

--	--

--	--

--	--

AND LISTED FOR THE FIREPLACE, WHEN USING TIGHT-FITTING DOORS ON MASONRY FIREPLACES, THE DOORS SHALL BE LISTED AND LABELED IN ACCORDANCE WITH UL 907.

R402.4.3 AIR LEAKAGE OF PENETRATION.
WINDOWS, SKYLIGHTS AND SLIDING GLASS DOORS SHALL HAVE AN AIR INFILTRATION RATE OF NO MORE THAN 0.3 CFM PER SQUARE FOOT (1.5 L/S/M²) AND SHINGING DOORS NO MORE THAN 0.3 CFM PER SQUARE FOOT (2.6 L/S/M²), WHEN TESTED ACCORDINGS TO NFRC 400 OR AIAA/NIDA/CSA 101/1.52/4440 BY AN ACCREDITED, INDEPENDENT LABORATORY AND LISTED AND LABELED BY THE MANUFACTURER. EXCEPTIONS:

1. FIELD-FABRICATED PENETRATION PRODUCTS (WINDOWS, SKYLIGHTS AND DOORS).
 2. CUSTOM EXTERIOR PENETRATION PRODUCTS MANUFACTURED BY A SMALL BUSINESS PROVIDED THEY MEET THE APPLICABLE PROVISIONS OF CHAPTER 24 OF THE INTERNATIONAL BUILDING CODE. ONCE VISUAL INSPECTION HAS CONFIRMED THE PRESENCE OF A GASKET, OPERABLE WINDOWS AND DOORS MANUFACTURED BY SMALL BUSINESS SHALL BE PERMITTED TO BE SEALED OFF AT THE FRAME PRIOR TO THE TEST.
- R402.4.4 COMBUSTION AIR OPENINGS.
WHERE OPEN COMBUSTION AIR DUCTS PROVIDE COMBUSTION AIR TO OPEN COMBUSTION SPACE CONDITIONING FUEL BURNING APPLIANCES, THE APPLIANCES AND COMBUSTION AIR OPENINGS SHALL BE LOCATED OUTSIDE OF THE BUILDING THERMAL ENVELOPE, OR ENCLOSED IN A ROOM ISOLATED FROM INSIDE THE THERMAL ENVELOPE. SUCH ROOMS SHALL BE SEALED AND INSULATED IN ACCORDANCE WITH THE ENVELOPE REQUIREMENTS OF TABLE R402.1.1 WHERE THE WALLS, FLOORS AND CEILING SHALL MEET THE MINIMUM OF THE BELOW-GRADE R-VALUE REQUIREMENT. THE DOOR INTO THE ROOM SHALL BE FULLY GASKETED AND ANY WATER LINES AND DUCTS IN THE ROOM INSULATED IN ACCORDANCE WITH SECTION R403. THE COMBUSTION AIR DUCT SHALL BE INSULATED WHERE IT PASSES THROUGH CONDITIONED SPACE TO A MINIMUM OF R-6.

EXCEPTIONS:
1. DIRECT VENT APPLIANCES WITH BOTH INTAKE AND EXHAUST PIPES INSTALLED CONTINUOUS TO THE OUTSIDE.
2. FIREPLACES AND STOVES COMPLYING WITH SECTION R402.4.2 AND SECTION R1006 OF THE INTERNATIONAL RESIDENTIAL CODE.

R402.4.5 RECESSED LIGHTING.
RECESSED LUMINAIRES INSTALLED IN THE BUILDING THERMAL ENVELOPE SHALL BE TYPE I-C RATED AND CERTIFIED UNDER ASTM E283 AS HAVING AN AIR LEAKAGE RATE NOT MORE THAN 2.0 CFM (0.444 L/S) WHEN TESTED AT A 1.51 PSF (75 PA) PRESSURE DIFFERENTIAL AND SHALL HAVE A LABEL ATTACHED SHOWING COMPLIANCE WITH THIS TEST METHOD. ALL RECESSED LUMINAIRES SHALL BE SEALED WITH A GASKET OR CAULK BETWEEN THE HOUSING AND THE INTERIOR WALL OR CEILING COVERING.

R402.5 MAXIMUM PENETRATION U-FACTOR (MANDATORY).
THE AREA-WEIGHTED AVERAGE MAXIMUM PENETRATION U-FACTOR PERMITTED USING TRADEOFFS FROM SECTION R402.1.4 OR R405 SHALL BE 0.49 FOR VERTICAL PENETRATION AND 0.15 FOR SKYLIGHTS.

TABLE R402.4.1.1 AIR BARRIER AND INSULATION INSTALLATION		
COMPONENT	AIR BARRIER CRITERIA	INSULATION CRITERIA
GENERAL REQUIREMENTS	A CONTINUOUS AIR BARRIER SHALL BE INSTALLED IN THE BUILDING ENVELOPE. EXTERIOR THERMAL ENVELOPE CONTAINS A CONTINUOUS AIR BARRIER. BREAKS OR JOINTS IN THE AIR BARRIER SHALL BE SEALED.	AIR-PERMEABLE INSULATION SHALL NOT BE USED AS A SEALING MATERIAL.
CAVITY INSULATION INSTALLATION		ALL CAVITIES IN THE THERMAL ENVELOPE SHALL BE FILLED WITH INSULATION. THE DENSITY OF THE INSULATION SHALL BE AT THE MANUFACTURERS' PRODUCT RECOMMENDATION AND SAID DENSITY SHALL BE MAINTAINED FOR ALL VOLUME OF EACH CAVITY. BATT TYPE INSULATION SHALL SHOW NO VOIDS OR GAPS AND MAINTAIN AN EVEN DENSITY FOR THE ENTIRE CAVITY. BATT INSULATION SHALL BE INSTALLED IN THE RECOMMENDED CAVITY DEPTH. WHERE AN OBSTRUCTION IN THE CAVITY DUE TO SERVICES, BLOCKING, BRACING OR OTHER OBSTRUCTION EXISTS, THE BATT PRODUCT WILL BE CUT TO FIT THE REMAINING DEPTH OF THE CAVITY. WHERE THE BATT IS CUT AROUND OBSTRUCTIONS, LOOSE FILL INSULATION SHALL BE PLACED TO FILL ANY SURFACE OR CONCEALED VOIDS, AND AT THE MANUFACTURERS' SPECIFIED DENSITY. WHERE FACED BATT IS USED, THE INSTALLATION TABS MUST BE STAPLED TO THE FACE OF THE STUD. THERE SHALL BE NO COMPRESSION TO THE BATT AT THE EDGES OF THE CAVITY DUE TO INSET STAPLING INSTALLATION TABS. INSULATION THAT UPON INSTALLATION READILY CONFORMS TO AVAILABLE SPACE SHALL BE INSTALLED FILLING THE ENTIRE CAVITY AND WITHIN THE MANUFACTURERS' DENSITY RECOMMENDATION.
CEILING/ATTIC	THE AIR BARRIER IN ANY DROPPED CEILING/SOFFIT SHALL BE ALIGNED WITH THE INSULATION AND ANY GAPS IN THE AIR BARRIER SEALED. ACCESS OPENINGS, DROP DOWN STAIR OR ELEVATOR SHAFTS TO UNCONDITIONED ATTIC SPACES SHALL BE SEALED.	THE INSULATION IN ANY DROPPED CEILING/SOFFIT SHALL BE ALIGNED WITH THE AIR BARRIER. BATT INSULATION INSTALLED IN ATTIC ROOF ASSEMBLIES MAY BE COMPRESSED AT EXTERIOR WALL TURNS TO ALLOW FOR REQUIRED ATTIC VENTILATION.
WALLS	THE JUNCTION OF THE FOUNDATION AND SILL PLATE SHALL BE SEALED. THE JUNCTION OF THE TOP PLATE AND TOP OF EXTERIOR WALLS SHALL BE SEALED. KNEE WALLS SHALL BE SEALED.	CAVITIES WITHIN CORNERS AND HEADERS OF FRAME WALLS SHALL BE INSULATED BY COMPLETELY FILLING THE CAVITY WITH A MATERIAL HAVING A THERMAL RESISTANCE OF R-3 PER INCH MINIMUM. EXTERIOR THERMAL ENVELOPE INSULATION FOR FRAMED WALLS SHALL BE INSTALLED IN SUBSTANTIAL CONTACT AND CONTINUOUS ALIGNMENT WITH THE AIR BARRIER.
WINDOWS, SKYLIGHTS AND DOORS	THE SPACE BETWEEN WINDOW/DOWN JAMBS AND FRAMING AND SKYLIGHTS AND FRAMING SHALL BE SEALED.	
RIM JOISTS	RIM JOISTS SHALL INCLUDE THE AIR BARRIER.	RIM JOISTS SHALL BE INSULATED.
FLOORS (INCLUDING ABOVE GARAGE AND CANTILEVERED FLOORS)	THE AIR BARRIER SHALL BE INSTALLED AT ANY EXPOSED EDGE OF INSULATION.	FLOOR FRAMING CAVITY INSULATION SHALL BE INSTALLED TO MAINTAIN PERMANENT CONTACT WITH THE UNDERSIDE OF SUBFLOOR DECKING OR FLOOR FRAMING GAVITY INSULATION SHALL BE PERMITTED TO BE IN CONTACT WITH THE TOPSIDE OF SHEATHING OR CONTINUOUS INSULATION INSTALLED ON THE UNDERSIDE OF FLOOR FRAMING AND EXTEND FROM THE BOTTOM TO THE TOP OF ALL PERIMETER FLOOR FRAMING MEMBERS.
CRANL SPACE WALLS	EXPOSED EARTH IN UNVENTED CRANL SPACES SHALL BE COVERED WITH A CLASS I, BLACK VAPOR RETARDER WITH OVERLAPPING JOINTS TAPED.	WHERE PROVIDED INSTEAD OF FLOOR INSULATION, INSULATION SHALL BE PERMANENTLY ATTACHED TO THE CRANLSPACE WALLS.
SHAFTS, PENETRATIONS	DUCT/ SHAFTS, UTILITY PENETRATIONS, AND RIM SHAFTS OPENING TO EXTERIOR OR UNCONDITIONED SPACE SHALL BE SEALED.	BATTS IN NARROW CAVITIES SHALL BE CUT TO FIT AND INSTALLED TO THE CORRECT DENSITY WITHOUT ANY VOIDS OR GAPS OR COMPRESSION, OR NARROW CAVITIES SHALL BE FILLED BY INSULATION THAT ON INSTALLATION READILY CONFORMS TO THE AVAILABLE CAVITY SPACE.
NARROW CAVITIES		
GARAGE SEPARATION	AIR SEALING SHALL BE PROVIDED BETWEEN THE GARAGE AND THE CONDITIONED SPACE.	RECESSED LIGHT FIXTURES INSTALLED IN THE BUILDING THERMAL ENVELOPE SHALL BE SEALED TO THE DRYWALL.
RECESSED LIGHTING		RECESSED LIGHT FIXTURES INSTALLED IN THE BUILDING THERMAL ENVELOPE SHALL BE AIR TIGHT AND IG RATED.
PLUMBING AND WIRING		BATT INSULATION SHALL BE CUT NEATLY TO FIT AROUND WIRING AND PLUMBING IN EXTERIOR WALLS. THERE SHALL BE NO VOIDS OR GAPS OR COMPRESSION WHERE CUT TO FIT. INSULATION THAT ON INSTALLATION READILY CONFORMS TO AVAILABLE SPACE SHALL EXTEND BEHIND PIPING AND WIRING.
SHOWER/TUB ON EXTERIOR WALL	THE AIR BARRIER INSTALLED AT EXTERIOR WALLS ADJACENT TO SHOWERS AND TUBS SHALL SEPARATE THEM FROM THE SHOWERS AND TUBS.	EXTERIOR WALLS ADJACENT TO SHOWERS AND TUBS SHALL BE INSULATED.
ELECTRICAL/PHONE BOX ON EXTERIOR WALL	THE AIR BARRIER SHALL BE INSTALLED BEHIND ELECTRICAL OR COMMUNICATION BOXES OR AIR SEALED BOXES SHALL BE INSTALLED.	
HVAC REGISTER BOOTS	HVAC REGISTER BOOTS THAT PENETRATE BUILDING THERMAL ENVELOPE SHALL BE SEALED TO THE SUBFLOOR OR DRYWALL.	
CONCEALED SPRINKLERS	WHEN REQUIRED TO BE SEALED, CONCEALED FIRE SPRINKLERS SHALL ONLY BE SEALED IN A MANNER THAT IS RECOMMENDED BY THE MANUFACTURER. CAULKING OR OTHER ADHESIVE SEALANTS SHALL NOT BE USED TO FILL VOIDS BETWEEN SPRINKLER COVER PLATES AND WALLS OR CEILING.	

SECTION R403 SYSTEMS

R403.1 CONTROLS (MANDATORY).
AT LEAST ONE THERMOSTAT SHALL BE PROVIDED FOR EACH SEPARATE HEATING AND COOLING SYSTEM.

R403.1.1 PROGRAMMABLE THERMOSTAT.
WHERE THE PRIMARY HEATING SYSTEM IS A FORCED-AIR FURNACE, AT LEAST ONE THERMOSTAT PER DWELLING UNIT SHALL BE CAPABLE OF CONTROLLING THE HEATING AND COOLING SYSTEM ON A DAILY SCHEDULE TO MAINTAIN DIFFERENT TEMPERATURE SET POINTS AT DIFFERENT TIMES OF THE DAY. THE THERMOSTAT SHALL ALLOW FOR, AT A MINIMUM, A 5-2 PROGRAMMABLE SCHEDULE (WEEKDAYS/WEEKENDS) AND BE CAPABLE OF PROVIDING AT LEAST TWO PROGRAMMABLE SETBACK PERIODS PER DAY. THIS THERMOSTAT SHALL INCLUDE THE CAPABILITY TO SET BACK OR TEMPORARILY OPERATE THE SYSTEM TO MAINTAIN ZONE TEMPERATURES DOWN TO 55°F (13°C) OR UP TO 85°F (24°C). THE THERMOSTAT SHALL INITIALLY BE PROGRAMMED BY THE MANUFACTURER WITH A HEATING TEMPERATURE SET POINT NO HIGHER THAN 70°F (21°C) AND A COOLING TEMPERATURE SET POINT NO LOWER THAN 78°F (26°C). THE THERMOSTAT AND/OR CONTROL SYSTEM SHALL HAVE AN ADJUSTABLE DEADBAND OF NOT LESS THAN 10°F.

EXCEPTIONS:
1. SYSTEMS CONTROLLED BY AN OCCUPANT SENSOR THAT IS CAPABLE OF SHUTTING THE SYSTEM OFF WHEN NO OCCUPANT IS SENSED FOR A PERIOD OF UP TO 30 MINUTES.
2. SYSTEMS CONTROLLED SOLELY BY A MANUALLY OPERATED TIMER CAPABLE OF OPERATING THE SYSTEM FOR NO MORE THAN TWO HOURS.

R403.1.2 HEAT PUMP SUPPLEMENTARY HEAT (MANDATORY).

INCLUDED IN APPENDIX A IN CHAPTER 5-I-1C. THESE VALUES SHALL BE USED FOR ALL CALCULATIONS, WHERE PROPOSED CONSTRUCTION ASSEMBLIES ARE NOT REPRESENTED IN APPENDIX A, VALUES SHALL BE CALCULATED IN ACCORDANCE WITH THE ASHRAE HANDBOOK OF FUNDAMENTALS USING THE FRAMING FACTORS LISTED IN APPENDIX A WHERE APPLICABLE AND SHALL INCLUDE THE THERMAL BRIDGING EFFECTS OF FRAMING MATERIALS. THE SHGC REQUIREMENTS SHALL BE MET IN ADDITION TO U/A COMPLIANCE, WHEN USING RESCHECK, THE U-FACTORS CALCULATED BY THE SOFTWARE BASED ON COMPONENT R-VALUE DESCRIPTIONS ARE ACCEPTABLE. FOR THE BASE BUILDING U/A CALCULATION, THE MAXIMUM GLAZING AREA IS 15% OF THE FLOOR AREA.

R402.1.5 VAPOR RETARDER.
WALL ASSEMBLIES IN THE BUILDING THERMAL ENVELOPE SHALL COMPLY WITH THE VAPOR RETARDER REQUIREMENTS OF SECTION R102.7 OF THE INTERNATIONAL RESIDENTIAL CODE OR SECTION 1405.3 OF THE INTERNATIONAL BUILDING CODE, AS APPLICABLE.

R402.2 SPECIFIC INSULATION REQUIREMENTS (PRESCRIPTIVE).
IN ADDITION TO THE REQUIREMENTS OF SECTION R402.1, INSULATION SHALL MEET THE SPECIFIC REQUIREMENTS OF SECTIONS R402.2.1 THROUGH R402.2.11.

R402.2.1 CEILING/6 WITH ATTIC SPACES.
WHERE SECTION R402.1.1 WOULD REQUIRE R-4 IN THE CEILING, INSTALLING R-38 OVER 100 PERCENT OF THE CEILING AREA REQUIRING INSULATION SHALL BE DEEMED TO SATISFY THE REQUIREMENT FOR R-4. WHERE THE FULL HEIGHT OF UNCOMPLETED R-38 INSULATION EXTENDS OVER THE WALL, TOP PLATE AT THE EAVES, THIS REDUCTION SHALL NOT APPLY TO THE U-FACTOR ALTERNATIVE APPROACH IN SECTION R402.1.3 AND THE TOTAL U/A ALTERNATIVE IN SECTION R402.1.4.

R402.2.1.1 LOOSE INSULATION IN ATTIC SPACES.
OPEN-BLOWN OR POURED LOOSE FILL INSULATION MAY BE USED IN ATTIC SPACES WHERE THE SLOPE OF THE CEILING IS NOT MORE THAN 3 FEET IN 12 INCHES AND THERE IS AT LEAST 30 INCHES OF CLEAR DISTANCE FROM THE TOP OF THE BOTTOM CHORD OF THE TRUSS OR CEILING JOIST TO THE UNDERSIDE OF THE SHEATHING AT THE ROOF RIDGE.

R402.2.2 RESERVED.

R402.2.3 EAVE Baffle.
FOR AIR PERMEABLE INSULATIONS IN VENTED ATTICS, A Baffle SHALL BE INSTALLED ADJACENT TO SOFFIT AND EAVE VENTS. Baffles SHALL MAINTAIN AN OPENING EQUAL OR GREATER THAN THE SIZE OF THE VENT. THE Baffle SHALL EXTEND OVER THE TOP OF THE ATTIC INSULATION. THE Baffle SHALL BE PERMITTED TO BE ANY SOLID MATERIAL.

R402.2.4 ACCESS HATCHES AND DOORS.
ACCESS DOORS FROM CONDITIONED SPACES TO UNCONDITIONED SPACES (E.G., ATTICS AND CRANL SPACES) SHALL BE WEATHERSTRIPPED AND INSULATED TO A LEVEL EQUIVALENT TO THE INSULATION ON THE SURROUNDING SURFACES. ACCESS SHALL BE PROVIDED TO ALL EQUIPMENT THAT PREVENTS DAMAGING OR COMPRESSING THE INSULATION. A WOOD FRAMED OR EQUIVALENT Baffle OR RESTAINER IS REQUIRED TO BE PROVIDED WHEN LOOSE FILL INSULATION IS INSTALLED, THE PURPOSE OF WHICH IS TO PREVENT THE LOOSE FILL INSULATION FROM SPRILLING INTO THE LIVING SPACE WHEN THE ATTIC ACCESS IS OPENED, AND TO PROVIDE A PERMANENT MEANS OF MAINTAINING THE INSTALLED INSULATION TO THE LOOSE FILL INSULATION.

EXCEPTION: VERTICAL DOORS THAT PROVIDE ACCESS FROM CONDITIONED TO UNCONDITIONED SPACES SHALL BE PERMITTED TO MEET THE PENETRATION REQUIREMENTS OF TABLE R402.1.1.

R402.2.5 MASS WALLS.
MASS WALLS FOR THE PURPOSES OF THIS CHAPTER SHALL BE CONSIDERED ABOVE-GRADE WALLS OF CONCRETE BLOCK, CONCRETE, INSULATED CONCRETE FORM (ICF), MASONRY BRICK, BRICK (OTHER THAN BRICK VENEER), EARTH (ADOB, COMPRESSED EARTH BLOCK, RAMMED EARTH) AND SOLID TIMBER LOGS, OR ANY OTHER WALLS HAVING A HEAT CAPACITY GREATER THAN OR EQUAL TO 8 BTU/FT² x FT³ (23 KJ/M³ x X³).

R402.2.6 STEEL-FRAME CEILING, WALLS, AND FLOORS.
STEEL-FRAME CEILING, WALLS, AND FLOORS SHALL MEET THE U-FACTOR REQUIREMENTS OF TABLE R402.

R402.2.7 FLOORS.
FLOOR FRAMING GAVITY INSULATION SHALL BE INSTALLED TO MAINTAIN PERMANENT CONTACT WITH THE UNDERSIDE OF THE SUBFLOOR DECKING. INSULATION SHALL BE INSTALLED 50 SPACING IS NO MORE THAN 24 INCHES ON CENTER. FOUNDATION VENTS SHALL BE PLACED SO THAT THE TOP OF THE VENT IS BELOW THE LOWER SURFACE OF THE FLOOR INSULATION.

EXCEPTIONS:
1. THE FLOOR FRAMING GAVITY INSULATION SHALL BE PERMITTED TO BE IN CONTACT WITH THE TOPSIDE OF SHEATHING OR CONTINUOUS INSULATION INSTALLED ON THE BOTTOM SIDE OF FLOOR FRAMING WHERE COHESIVE WITH INSULATION THAT MEETS OR EXCEEDS THE MINIMUM WOOD FRAME BELLOW VALUE IN TABLE R402.1.1 AND EXTENDS FROM THE BOTTOM TO THE TOP OF ALL PERIMETER FLOOR FRAMING MEMBERS.
2. WHEN FOUNDATION VENTS ARE NOT PLACED SO THAT THE TOP OF THE VENT IS BELOW THE LOWER SURFACE OF THE FLOOR INSULATION, A PERMANENTLY ATTACHED Baffle SHALL BE INSTALLED AT AN ANGLE OF 30° FROM HORIZONTAL, TO DIVERT AIR FLOW BELOW THE LOWER SURFACE OF THE FLOOR INSULATION.
3. SUBSTANTIAL CONTACT WITH THE SURFACE BEING INSULATED IS NOT REQUIRED IN ENCLOSED FLOOR/CEILING ASSEMBLIES CONTAINING DUCTS WHERE FULL R-VALUE INSULATION IS INSTALLED BETWEEN THE DUCT AND THE EXTERIOR SURFACE.

R402.2.8 BELOW-GRADE WALLS.
BELOW-GRADE EXTERIOR WALL INSULATION USED ON THE EXTERIOR (COLD) SIDE OF THE WALL SHALL EXTEND FROM THE TOP OF THE BELOW-GRADE WALL TO THE TOP OF THE FOOTING AND SHALL BE APPROVED FOR BELOW-GRADE USE. ABOVE-GRADE INSULATION SHALL BE PROTECTED. INSULATION USED ON THE INTERIOR (WARM) SIDE OF THE WALL SHALL EXTEND FROM THE TOP OF THE BELOW-GRADE WALL TO THE BELOW-GRADE FLOOR LEVEL AND SHALL INCLUDE R-5 RIGID BOARD PROVIDING A THERMAL BREAK BETWEEN THE CONCRETE WALL AND THE SLAB.

R402.2.9 SLAB-ON-GRADE FLOORS.
THE MINIMUM THERMAL RESISTANCE (R-VALUE) OF THE INSULATION AROUND THE PERIMETER OF UNHEATED OR HEATED SLAB-ON-GRADE FLOORS SHALL BE AS SPECIFIED IN TABLE R402.1.1. THE INSULATION SHALL BE PLACED ON THE OUTSIDE OF THE FOUNDATION OR ON THE INSIDE OF THE FOUNDATION WALL. THE INSULATION SHALL EXTEND DOWNWARD FROM THE TOP OF THE SLAB FOR A MINIMUM DISTANCE AS SHOWN IN THE TABLE. THE TOP OF THE FOOTING, WHICH IS 15 LESS, OR DOWNWARD TO AT LEAST THE BOTTOM OF THE SLAB AND THEN HORIZONTALLY TO THE INTERIOR OR EXTERIOR FOR THE TOTAL DISTANCE SHOWN IN THE TABLE. A TWO-INCH (MAXIMUM) PRESSURE TREATED WALKER MAY BE PLACED AT THE FINISHED FLOOR ELEVATION FOR ATTACHMENT OF INTERIOR FINISH MATERIALS. INSULATION EXTENDING AWAY FROM THE BUILDING SHALL BE PROTECTED BY PAVEMENT OR BY A MINIMUM OF 10 INCHES (254 MM) OF SOIL.

R402.2.10 RESERVED.

R402.2.11 HEATED SLAB-ON-GRADE FLOORS (MANDATORY).
THE ENTIRE AREA OF A HEATED SLAB-ON-GRADE FLOOR SHALL BE THERMALLY ISOLATED FROM THE SOIL WITH A MINIMUM OF R-10 INSULATION. THE INSULATION SHALL BE AN APPROVED PRODUCT FOR ITS INTENDED USE. IF A SOIL GAS CONTROL SYSTEM IS PRESENT BELOW THE HEATED SLAB-ON-GRADE FLOOR, WHICH RESULTS IN INCREASED CONVECTIVE FLOW BELOW THE HEATED SLAB-ON-GRADE FLOOR, THE HEATED SLAB-ON-GRADE FLOOR SHALL BE THERMALLY ISOLATED FROM THE SUB-SLAB GRAVEL LAYER. R-10 HEATED SLAB-ON-GRADE FLOOR INSULATION IS REQUIRED FOR ALL COMPLIANCE PATHS.

R402.2.12 RESERVED.

R402.2.13 MASONRY VENEER.
INSULATION SHALL NOT BE REQUIRED ON THE HORIZONTAL PORTION OF THE FOUNDATION THAT SUPPORTS A MASONRY VENEER.

R402.3 PENETRATION (PRESCRIPTIVE).
IN ADDITION TO THE REQUIREMENTS OF SECTION R402, INSULATION SHALL COMPLY WITH SECTIONS R402.3.1 THROUGH R402.3.5.

R402.3.1 U-FACTOR.
AN AREA-WEIGHTED AVERAGE OF PENETRATION PRODUCTS SHALL BE PERMITTED TO SATISFY THE U-FACTOR REQUIREMENTS.

R402.3.2 GLAZED PENETRATION SHGC.
AN AREA-WEIGHTED AVERAGE OF PENETRATION PRODUCTS MORE THAN 50 PERCENT GLAZED SHALL BE PERMITTED TO SATISFY THE SHGC REQUIREMENTS.

R402.3.3 GLAZED PENETRATION EXEMPTION.
UP TO 15 SQUARE FEET (1.4 M²) OF GLAZED PENETRATION PER DWELLING UNIT SHALL BE PERMITTED TO BE EXEMPT FROM U-FACTOR AND SHGC REQUIREMENTS IN SECTION R402.1.1. THIS EXEMPTION SHALL NOT APPLY TO THE U-FACTOR ALTERNATIVE APPROACH IN SECTION R402.1.3 AND THE TOTAL U/A ALTERNATIVE IN SECTION R402.1.4.

R402.3.4 OPAQUE DOOR EXEMPTION.
ONE SINGLE-HINGED OPAQUE DOOR ASSEMBLY UP TO 24 SQUARE FEET (2.22 M²) AREA IS EXEMPTED FROM THE U-FACTOR REQUIREMENT IN SECTION R402.1.1. THIS EXEMPTION SHALL NOT APPLY TO THE U-FACTOR ALTERNATIVE APPROACH IN SECTION R402.1.3 AND THE TOTAL U/A ALTERNATIVE IN SECTION R402.1.4.

R402.3.5 RESERVED.

R402.4 AIR LEAKAGE (MANDATORY).
THE BUILDING THERMAL ENVELOPE SHALL BE CONSTRUCTED TO LIMIT AIR LEAKAGE IN ACCORDANCE WITH THE REQUIREMENTS OF SECTIONS R402.4.1 THROUGH R402.4.4.

R402.4.1 BUILDING THERMAL ENVELOPE.
THE BUILDING THERMAL ENVELOPE SHALL COMPLY WITH SECTIONS R402.4.1.1 AND R402.4.1.2. THE SEALING METHODS BETWEEN DISSIMILAR MATERIALS SHALL ALLOW FOR DIFFERENTIAL EXPANSION AND CONTRACTION.

R402.4.1.1 INSTALLATION.
THE COMPONENTS OF THE BUILDING THERMAL ENVELOPE AS LISTED IN TABLE R402.4.1.1 SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS AND THE CRITERIA LISTED IN TABLE R402.4.1.1, AS APPLICABLE TO THE METHOD OF CONSTRUCTION, WHERE REQUIRED BY THE CODE OFFICIAL, AN APPROVED THIRD PARTY SHALL INSPECT ALL COMPONENTS AND VERIFY COMPLIANCE.

R402.4.1.2 TESTING.
THE BUILDING OR DWELLING UNIT SHALL BE TESTED AND VERIFIED AS HAVING AN AIR LEAKAGE RATE OF NOT EXCEEDING 5 AIR CHANGES PER HOUR. TESTING SHALL BE CONDUCTED WITH A GLOWER DOOR AT A PRESSURE OF 0.2 INCHES WATER (50 PASCALS), WHERE REQUIRED BY THE CODE OFFICIAL. TESTING SHALL BE CONDUCTED BY AN APPROVED THIRD PARTY, A WRITTEN REPORT OF THE RESULTS OF THE TEST SHALL BE SIGNED BY THE PARTY CONDUCTING THE TEST AND PROVIDED TO THE CODE OFFICIAL. TESTING SHALL BE PERFORMED AT ANY TIME AFTER CREATION OF ALL PENETRATIONS OF THE BUILDING THERMAL ENVELOPE. ONCE VISUAL INSPECTION HAS CONFIRMED SEALING (SEE TABLE R402.4.1.1), OPERABLE WINDOWS AND DOORS MANUFACTURED BY SMALL BUSINESS SHALL BE PERMITTED TO BE SEALED OFF AT THE FRAME PRIOR TO THE TEST.

DURING TESTING:
1. EXTERIOR WINDOWS AND DOORS, FIREPLACE AND STOVE DOORS SHALL BE CLOSED, BUT NOT SEALED, BEHIND THE INTENDED WEATHERSTRIPPING OR OTHER INFILTRATION CONTROL MEASURES.
2. DAMPERS INCLUDING EXHAUST, INTAKE, MAKEUP AIR, BACKDRIFT AND FLUE DAMPERS SHALL BE CLOSED, BUT NOT SEALED BEYOND INTENDED INFILTRATION CONTROL MEASURES.
3. INTERIOR DOORS, IF INSTALLED AT THE TIME OF THE TEST, SHALL BE OPEN. ACCESS HATCHES TO CONDITIONED CRANL SPACES AND CONDITIONED ATTICS SHALL BE OPEN.
4. EXTERIOR OPENINGS FOR CONTINUOUS VENTILATION SYSTEMS AND HEAT RECOVERY VENTILATORS SHALL BE CLOSED AND SEALED.
5. HEATING AND COOLING SYSTEMS, IF INSTALLED AT THE TIME OF THE TEST, SHALL BE TURNED OFF, and
6. SUPPLY AND RETURN REGISTERS, IF INSTALLED AT THE TIME OF THE TEST, SHALL BE FULLY OPEN.

EXCEPTIONS:
1. ADDITIONS LESS THAN 500 SQUARE FEET OF CONDITIONED FLOOR AREA.
2. ADDITIONS TESTED WITH THE EXISTING HOME HAVING A COMBINED MAXIMUM AIR LEAKAGE RATE OF 1 AIR CHANGES PER HOUR. TO QUALIFY FOR THIS EXCEPTION, THE DATE OF CONSTRUCTION OF THE EXISTING HOUSE MUST BE PRIOR TO THE 2004 WASHINGTON STATE ENERGY CODE.

R402.4.2 FIREPLACES.
NEW EXISTING BUILDING CODES SHALL HAVE TIGHT-FITTING DOORS AND MASONRY FIREPLACES, THE DOORS SHALL BE LISTED AND LABELED IN ACCORDANCE WITH UL 907.

2018 WSEC COMPLIANCE NOTES:

CHAPTER 3 GENERAL REQUIREMENTS
SECTION R303 MATERIALS, SYSTEMS AND EQUIPMENT

R303.1 IDENTIFICATION.
MATERIALS, SYSTEMS AND EQUIPMENT SHALL BE IDENTIFIED IN A MANNER THAT WILL ALLOW A DETERMINATION

2018 WSEC COMPLIANCE NOTES
- SHEET 3

2018 WASH. STATE ENERGY CODE (WSEC)

(CONTINUED FROM PREVIOUS SHEET)

R403.6 MECHANICAL VENTILATION (MANDATORY). BUILDING SHALL BE PROVIDED WITH VENTILATION THAT MEETS THE REQUIREMENTS OF THE INTERNATIONAL RESIDENTIAL CODE OR INTERNATIONAL MECHANICAL CODE, AS APPLICABLE, OR WITH OTHER APPROVED MEANS OF VENTILATION. OUTDOOR AIR INTAKES AND EXHAUSTS SHALL HAVE AUTOMATIC OR GRAVITY DAMPERS THAT CLOSE WHEN THE VENTILATION SYSTEM IS NOT OPERATING.

R403.6.1 WHOLE-HOUSE MECHANICAL VENTILATION SYSTEM FAN EFFICACY. MECHANICAL VENTILATION SYSTEM FANS SHALL MEET THE EFFICACY REQUIREMENTS OF TABLE R403.6.1. EXCEPTION: WHERE MECHANICAL VENTILATION FANS ARE INTEGRAL TO TESTED AND LISTED HVAC EQUIPMENT, THEY SHALL BE POWERED BY AN ELECTRONICALLY COMMUTATED MOTOR.

FAN LOCATION	AIR FLOW RATE (MINIMUM CFM)	MINIMUM EFFICACY (CFM/WATT)	AIR FLOW RATE MAXIMUM (CFM)
RANGE HOODS	ANY	2.0 CFM/WATT	ANY
IN-LINE FAN	ANY	2.0 CFM/WATT	ANY
BATHROOM, UTILITY ROOM	10	1.4 CFM/WATT	< 10
BATHROOM, UTILITY ROOM	40	2.0 CFM/WATT	ANY

R403.1 EQUIPMENT SIZING AND EFFICIENCY RATING (MANDATORY). HEATING AND COOLING EQUIPMENT SHALL BE SIZED IN ACCORDANCE WITH ACCA MANUAL 5 BASED ON BUILDING LOADS CALCULATED IN ACCORDANCE WITH ACCA MANUAL J OR OTHER APPROVED HEATING AND COOLING CALCULATION METHODOLOGIES. THE OUTPUT CAPACITY OF HEATING AND COOLING EQUIPMENT SHALL NOT BE GREATER THAN THAT OF THE SMALLEST AVAILABLE EQUIPMENT SIZE THAT EXCEEDS THE LOADS CALCULATED, INCLUDING ALLOWABLE OVERSIZING LIMITS. NEW OR REPLACEMENT HEATING AND COOLING EQUIPMENT SHALL HAVE AN EFFICIENCY RATING EQUAL TO OR GREATER THAN THE MINIMUM REQUIRED BY FEDERAL LAW FOR THE GEOGRAPHIC LOCATION WHERE THE EQUIPMENT IS INSTALLED.

R403.1.1 ELECTRIC RESISTANCE ZONE HEATED UNITS. ALL DETACHED ONE- AND TWO-FAMILY DWELLINGS AND MULTIPLE SINGLE-FAMILY DWELLINGS (TOWNHOUSES) UP TO THREE STORIES IN HEIGHT ABOVE GRADE PLAN USING ELECTRIC ZONAL HEATING AS THE PRIMARY HEAT SOURCE SHALL INSTALL AN INVERTER-DRIVEN DUCTLESS MINI-SPLIT HEAT PUMP IN THE LARGEST ZONE IN THE DWELLING. BUILDING PERMIT DRAWINGS SHALL SPECIFY THE HEATING EQUIPMENT TYPE AND LOCATION OF THE HEATING SYSTEM.

EXCEPTION: TOTAL INSTALLED HEATING CAPACITY OF 2KH PER DWELLING OR LESS.

R403.2 SYSTEMS SERVING MULTIPLE DWELLING UNITS (MANDATORY). SYSTEMS SERVING MULTIPLE DWELLING UNITS SHALL COMPLY WITH SECTIONS C403 AND C404 OF THE WSEC--COMMERICAL PROVISIONS IN LIEU OF SECTION R403.

R403.9 SNOW MELT SYSTEM CONTROLS (MANDATORY). SNOW AND ICE-MELTING SYSTEMS, SUPPLIED THROUGH ENERGY SERVICE TO THE BUILDING, SHALL INCLUDE AUTOMATIC CONTROLS CAPABLE OF SHUTTING OFF THE SYSTEM WHEN THE PAVEMENT TEMPERATURE IS ABOVE 50°F, AND NO PRECIPITATION IS FALLING AND AN AUTOMATIC OR MANUAL CONTROL THAT WILL ALLOW SHUTOFF WHEN THE OUTDOOR TEMPERATURE IS ABOVE 40°F.

R403.10 POOL AND PERMANENT SPA ENERGY CONSUMPTION (MANDATORY). POOLS AND PERMANENT SPAS SHALL COMPLY WITH SECTIONS R403.10.1 THROUGH R403.10.4.2.

R403.10.1 HEATERS. THE ELECTRIC POWER TO HEATERS SHALL BE CONTROLLED BY A READILY ACCESSIBLE ON-OFF SWITCH THAT IS AN INTEGRAL PART OF THE HEATER MOUNTED ON THE EXTERIOR OF THE HEATER, OR EXTERNAL TO AND WITHIN 5 FEET (1.5 M) OF THE HEATER. OPERATION OF SUCH SWITCH SHALL NOT CHANGE THE SETTINGS OF THE HEATER THERMOSTAT. SUCH SWITCHES SHALL BE IN ADDITION TO A CIRCUIT BREAKER FOR THE POWER TO THE HEATER. GAS-FIRED HEATERS SHALL NOT BE EQUIPPED WITH CONSTANT BURNING PILOT LIGHTS.

R403.10.2 TIME SWITCHES. TIME SWITCHES OR OTHER CONTROL METHOD THAT CAN AUTOMATICALLY TURN OFF AND ON ACCORDING TO A PRESET SCHEDULE SHALL BE INSTALLED FOR HEATERS AND PUMP MOTORS. HEATERS AND PUMP MOTORS THAT HAVE BUILT IN TIME SWITCHES SHALL BE DEEMED IN COMPLIANCE WITH THIS REQUIREMENT.

EXCEPTIONS:
1. WHERE PUBLIC HEALTH STANDARDS REQUIRE 24-HOUR PUMP OPERATION.
2. PUMPS THAT OPERATE SOLAR- AND WASTE-HEAT-RECOVERY POOL HEATING SYSTEMS.

R403.10.3 COVERS. OUTDOOR HEATED POOLS AND OUTDOOR PERMANENT SPAS SHALL BE PROVIDED WITH A VAPOR-RETARDANT COVER, OR OTHER APPROVED VAPOR RETARDANT MEANS.

EXCEPTION: WHERE MORE THAN 10 PERCENT OF THE ENERGY FOR HEATING, COMPUTED OVER AN OPERATING SEASON, IS FROM SITE-RECOVERED ENERGY, SUCH AS FROM A HEAT PUMP OR SOLAR ENERGY SOURCE, COVERS OR OTHER VAPOR-RETARDANT MEANS SHALL NOT BE REQUIRED.

R403.10.4 RESIDENTIAL POOL PUMPS. POOL PUMP MOTORS MAY NOT BE SPLIT-PHASE OR CAPACITOR START-INDUCTION RUN TYPE.

R403.10.4.1 TWO-SPEED CAPABILITY.
1. PUMP MOTORS: POOL PUMP MOTORS WITH A CAPACITY OF 1 HP OR MORE SHALL HAVE THE CAPABILITY OF OPERATING AT TWO OR MORE SPEEDS WITH LOW SPEED HAVING A ROTATION RATE THAT IS NO MORE THAN ONE-HALF OF THE MOTOR'S MAXIMUM ROTATION RATE.
2. PUMP CONTROLS: POOL PUMP MOTOR CONTROLS SHALL HAVE THE CAPABILITY OF OPERATING THE POOL PUMP WITH AT LEAST TWO SPEEDS. THE DEFAULT CIRCULATION SPEED SHALL BE THE LOWEST SPEED, WITH A HIGH SPEED OVERRIDE CAPABILITY BEING FOR A TEMPORARY PERIOD NOT TO EXCEED ONE NORMAL CYCLE.

R403.10.4.2 PUMP OPERATION. CIRCULATING WATER SYSTEMS SHALL BE CONTROLLED SO THAT THE CIRCULATION PUMPS CAN BE CONVENIENTLY TURNED OFF, AUTOMATICALLY OR MANUALLY, WHEN THE WATER SYSTEM IS NOT IN OPERATION.

R403.11 PORTABLE SPAS (MANDATORY). THE ENERGY CONSUMPTION OF ELECTRIC-POWERED PORTABLE SPAS SHALL BE CONTROLLED BY THE REQUIREMENTS OF APSP-14.

R403.12 RESIDENTIAL POOLS AND PERMANENT RESIDENTIAL SPAS. RESIDENTIAL SWIMMING POOLS AND PERMANENT RESIDENTIAL SPAS THAT ARE ACCESSORY TO DETACHED ONE- AND TWO-FAMILY DWELLINGS AND TOWNHOUSES THREE STORIES OR LESS IN HEIGHT ABOVE GRADE PLANE AND THAT ARE AVAILABLE ONLY TO THE HOUSEHOLD AND ITS GUESTS SHALL BE IN ACCORDANCE WITH APSP-15.

FENESTRATION U-FACTOR	SKYLIGHT U-FACTOR	GLAZED FENESTRATION SHGC	CEILING R-VALUE	WOOD FRAMED WALL R-VALUE	FLOOR R-VALUE	BELOW GRADE WALL R-VALUE	SLAB R-VALUE & DEPTH
0.30	0.50	NR	R-49 R-30 VAULTED	R-21	R-30	10/15 R-21 + TB	R-10 2 FEET

SECTION R404. ELECTRICAL POWER AND LIGHTING SYSTEMS

R404.1 LIGHTING EQUIPMENT (MANDATORY). A MINIMUM OF 75 PERCENT OF LAMPS IN PERMANENTLY INSTALLED LIGHTING FIXTURES SHALL BE HIGH-EFFICACY LAMPS. HIGH-EFFICACY LAMPS, COMPACT FLUORESCENT LAMPS, T-8 OR SMALLER DIAMETER LINEAR FLUORESCENT LAMPS, OR LAMPS WITH A MINIMUM EFFICACY OF:
1. 60 LUMENS PER WATT FOR LAMPS OVER 40 WATTS;
2. 50 LUMENS PER WATT FOR LAMPS OVER 15 WATTS TO 40 WATTS; AND
3. 40 LUMENS PER WATT FOR LAMPS 15 WATTS OR LESS.

R404.1.1 LIGHTING EQUIPMENT (MANDATORY). FUEL GAS LIGHTING SYSTEMS SHALL NOT HAVE CONTINUOUSLY BURNING PILOT LIGHTS.

SECTION R406. ADDITIONAL ENERGY EFFICIENCY REQUIREMENTS

R406.1 SCOPE. THIS SECTION ESTABLISHES OPTIONS FOR ADDITIONAL CRITERIA TO BE MET FOR ONE- AND TWO-FAMILY DWELLINGS AND TOWNHOUSES, AS DEFINED IN SECTION 101.2 OF THE INTERNATIONAL RESIDENTIAL CODE TO DEMONSTRATE COMPLIANCE WITH THIS CODE.


R406.2 ADDITIONAL ENERGY EFFICIENCY REQUIREMENTS (MANDATORY). EACH DWELLING UNIT IN A RESIDENTIAL BUILDING SHALL COMPLY WITH SUFFICIENT OPTIONS FROM TABLE R406.2.50 AS TO ACHIEVE THE FOLLOWING MINIMUM NUMBER OF CREDITS:

- SMALL DWELLING UNIT: 15 CREDITS
DWELLING UNITS LESS THAN 1500 SQUARE FEET IN CONDITIONED FLOOR AREA WITH LESS THAN 300 SQUARE FEET OF FENESTRATION AREA. ADDITIONS TO EXISTING BUILDING GREATER THAN 500 SQUARE FEET OF HEATED FLOOR AREA BUT LESS THAN 1500 SQUARE FEET.
- MEDIUM DWELLING UNIT: 3.5 CREDITS
ALL DWELLING UNITS THAT ARE NOT INCLUDED IN #1 OR #3.
EXCEPTION: DWELLING UNITS SERVING R-2 OCCUPANCIES SHALL REQUIRE 2.5 CREDITS.
- LARGE DWELLING UNIT: 4.5 CREDITS
DWELLING UNITS GREATER THAN 1500 SQUARE FEET OF CONDITIONED FLOOR AREA.

OPTION	DESCRIPTION	CREDITS
1a	EFFICIENT BUILDING ENVELOPE 1a: PRESCRIPTIVE COMPLIANCE IS BASED ON TABLE R402.1.1 WITH THE FOLLOWING MODIFICATIONS: VERTICAL FENESTRATION U = 0.28 FLOOR R-30 SLAB ON GRADE R-10 PERIMETER AND UNDER ENTIRE SLAB BELOW GRADE SLAB R-10 PERIMETER AND UNDER ENTIRE SLAB OR COMPLIANCE BASED ON SECTION R402.1.4. REDUCE THE TOTAL UA BY 5%.	0.5
1b	EFFICIENT BUILDING ENVELOPE 1b: PRESCRIPTIVE COMPLIANCE IS BASED ON TABLE R402.1.1 WITH THE FOLLOWING MODIFICATIONS: VERTICAL FENESTRATION U = 0.25 WALL R-21 PLUS R-4 FLOOR R-30 BASEMENT WALL R-21 INT PLUS R-5 C1 SLAB ON GRADE R-10 PERIMETER AND UNDER ENTIRE SLAB BELOW GRADE SLAB R-10 PERIMETER AND UNDER ENTIRE SLAB OR COMPLIANCE BASED ON SECTION R402.1.4. REDUCE THE TOTAL UA BY 15%.	1.0
1c	EFFICIENT BUILDING ENVELOPE 1c: PRESCRIPTIVE COMPLIANCE IS BASED ON TABLE R402.1.1 WITH THE FOLLOWING MODIFICATIONS: VERTICAL FENESTRATION U = 0.22 CEILING AND SINGLE-RAFTER OR JOIST-VAULTED R-44 ADVANCED WOOD FRAME WALL R-21 INT PLUS R-12 C1 FLOOR R-30 BASEMENT WALL R-21 INT PLUS R-12 C1 SLAB ON GRADE R-10 PERIMETER AND UNDER ENTIRE SLAB BELOW GRADE SLAB R-10 PERIMETER AND UNDER ENTIRE SLAB OR COMPLIANCE BASED ON SECTION R402.1.4. REDUCE THE TOTAL UA BY 30%.	2.0
1d	EFFICIENT BUILDING ENVELOPE 1d: PRESCRIPTIVE COMPLIANCE IS BASED ON TABLE R402.1.1 WITH THE FOLLOWING MODIFICATIONS: VERTICAL FENESTRATION U = 0.24	0.5
2a	AIR LEAKAGE CONTROL AND EFFICIENT VENTILATION 2a: COMPLIANCE BASED ON R402.4.1.2. REDUCE THE TESTED AIR LEAKAGE TO 3.0 AIR CHANGES PER HOUR MAXIMUM AND ALL WHOLE HOUSE VENTILATION REQUIREMENTS AS DETERMINED BY SECTION M507.3 OF THE INTERNATIONAL RESIDENTIAL CODE SHALL BE MET WITH A HIGH EFFICIENCY FAN (MAXIMUM 0.35 WATTS/CFM), NOT INTERLOCKED WITH THE FURNACE FAN. VENTILATION SYSTEMS USING A FURNACE INCLUDING AN ECM MOTOR ARE ALLOWED, PROVIDED THAT THEY ARE CONTROLLED TO OPERATE AT LOW SPEED IN VENTILATION ONLY MODE. TO QUALIFY TO CLAIM THIS CREDIT, THE BUILDING PERMIT DRAWINGS SHALL SPECIFY THE OPTION BEING SELECTED AND SHALL SPECIFY THE MAXIMUM TESTED BUILDING AIR LEAKAGE AND SHALL SHOW THE QUALIFYING VENTILATION SYSTEM.	0.5
2b	AIR LEAKAGE CONTROL AND EFFICIENT VENTILATION 2b: COMPLIANCE BASED ON SECTION R402.4.1.2. REDUCE THE TESTED AIR LEAKAGE TO 2.0 AIR CHANGES PER HOUR MAXIMUM AND ALL WHOLE HOUSE VENTILATION REQUIREMENTS AS DETERMINED BY SECTION M507.3 OF THE INTERNATIONAL RESIDENTIAL CODE SHALL BE MET WITH A HEAT RECOVERY VENTILATION SYSTEM WITH MINIMUM SENSIBLE HEAT RECOVERY EFFICIENCY OF 0.10. TO QUALIFY TO CLAIM THIS CREDIT, THE BUILDING PERMIT DRAWINGS SHALL SPECIFY THE OPTION BEING SELECTED AND SHALL SPECIFY THE MAXIMUM TESTED BUILDING AIR LEAKAGE AND SHALL SHOW THE HEAT RECOVERY VENTILATION SYSTEM.	1.0
2c	AIR LEAKAGE CONTROL AND EFFICIENT VENTILATION 2c: COMPLIANCE BASED ON SECTION R402.4.1.2. REDUCE THE TESTED AIR LEAKAGE TO 1.5 AIR CHANGES PER HOUR MAXIMUM AND ALL WHOLE HOUSE VENTILATION REQUIREMENTS AS DETERMINED BY SECTION M507.3 OF THE INTERNATIONAL RESIDENTIAL CODE SHALL BE MET WITH A HEAT RECOVERY VENTILATION SYSTEM WITH MINIMUM SENSIBLE HEAT RECOVERY EFFICIENCY OF 0.25. TO QUALIFY TO CLAIM THIS CREDIT, THE BUILDING PERMIT DRAWINGS SHALL SPECIFY THE OPTION BEING SELECTED AND SHALL SPECIFY THE MAXIMUM TESTED BUILDING AIR LEAKAGE AND SHALL SHOW THE HEAT RECOVERY VENTILATION SYSTEM.	1.5
3a	HIGH EFFICIENCY HVAC EQUIPMENT 3a: GAS, PROPANE OR OIL-FIRED FURNACE WITH MINIMUM AFUE OF 94%, OR GAS, PROPANE OR OIL-FIRED BOILER WITH MINIMUM AFUE OF 92% TO QUALIFY TO CLAIM THIS CREDIT, THE BUILDING PERMIT DRAWINGS SHALL SPECIFY THE OPTION BEING SELECTED AND SHALL SPECIFY THE HEATING EQUIPMENT TYPE AND THE MINIMUM EQUIPMENT EFFICIENCY.	1.0
3b	HIGH EFFICIENCY HVAC EQUIPMENT 3b: AIR-SOURCE HEAT PUMP WITH MINIMUM SEER OF 14.0 TO QUALIFY TO CLAIM THIS CREDIT, THE BUILDING PERMIT DRAWINGS SHALL SPECIFY THE OPTION BEING SELECTED AND SHALL SPECIFY THE HEATING EQUIPMENT TYPE AND THE MINIMUM EQUIPMENT EFFICIENCY.	1.0
3c	HIGH EFFICIENCY HVAC EQUIPMENT 3c: CLOSED-LOOP GROUND SOURCE HEAT PUMP, WITH A MINIMUM COP OF 3.3 OR OPEN LOOP WATER SOURCE HEAT PUMP WITH A MAXIMUM PUMPING HYDRAULIC HEAD OF 150 FEET AND MINIMUM COP OF 3.6 TO QUALIFY TO CLAIM THIS CREDIT, THE BUILDING PERMIT DRAWINGS SHALL SPECIFY THE OPTION BEING SELECTED AND SHALL SPECIFY THE HEATING EQUIPMENT TYPE AND THE MINIMUM EQUIPMENT EFFICIENCY.	1.5
3d	HIGH EFFICIENCY HVAC EQUIPMENT 3d: DUCTLESS SPLIT SYSTEM HEAT PUMPS, ZONAL CONTROL. IN HOMES WHERE THE PRIMARY SPACE HEATING SYSTEM IS ZONAL ELECTRIC HEATING, A DUCTLESS HEAT PUMP SYSTEM SHALL BE INSTALLED AND PROVIDE HEATING TO THE LARGEST ZONE OF THE HOUSING UNIT. TO QUALIFY TO CLAIM THIS CREDIT, THE BUILDING PERMIT DRAWINGS SHALL SPECIFY THE OPTION BEING SELECTED AND SHALL SPECIFY THE HEATING EQUIPMENT TYPE AND THE MINIMUM EQUIPMENT EFFICIENCY.	1.0

OPTION	DESCRIPTION	CREDITS
4	HIGH EFFICIENCY HVAC DISTRIBUTION SYSTEM: ALL HEATING AND COOLING SYSTEM COMPONENTS INSTALLED INSIDE THE CONDITIONED SPACE. THIS INCLUDES ALL EQUIPMENT AND DISTRIBUTION SYSTEM COMPONENTS SUCH AS FORCED AIR DUCTS, HYDRONIC PIPING, HYDRONIC FLOOR HEATING LOOP, CONVECTORS AND RADIATORS. ALL COMBUSTION EQUIPMENT SHALL BE DIRECT VENT OR SEALED COMBUSTION. FOR FORCED AIR DUCTS: A MAXIMUM OF 10 LINEAR FEET OF RETURN DUCTS AND 5 LINEAR FEET OF SUPPLY DUCTS MAY BE LOCATED OUTSIDE THE CONDITIONED SPACE. ALL METALLIC DUCTS LOCATED OUTSIDE THE CONDITIONED SPACE MUST HAVE BOTH TRANSVERSE AND LONGITUDINAL JOINTS SEALED WITH MASTIC. IF FLEX DUCTS ARE USED, THEY CANNOT CONTAIN SPLICES. FLEX DUCT CONNECTIONS MUST BE MADE WITH NYLON STRAPS AND INSTALLED USING A PLASTIC STRAPPING-TENSIONING TOOL. DUCTS LOCATED OUTSIDE THE CONDITIONED SPACE MUST BE INSULATED TO A MINIMUM OF R-8. LOCATING SYSTEM COMPONENTS IN CONDITIONED GRABLL SPACES IS NOT PERMITTED UNDER THIS OPTION. ELECTRIC RESISTANCE HEAT AND DUCTLESS HEAT PUMPS ARE NOT PERMITTED UNDER THIS OPTION. DIRECT COMBUSTION HEATING EQUIPMENT WITH AFUE LESS THAN 90% IS NOT PERMITTED UNDER THIS OPTION. TO QUALIFY TO CLAIM THIS CREDIT, THE BUILDING PERMIT DRAWINGS SHALL SPECIFY THE OPTION BEING SELECTED AND SHALL SPECIFY THE HEATING EQUIPMENT TYPE AND SHALL SHOW THE LOCATION OF THE HEATING AND COOLING EQUIPMENT AND ALL THE DUCTWORK.	1.0
5a	EFFICIENT WATER HEATING 5a: ALL SHOWERHEAD AND KITCHEN SINK FAUCETS INSTALLED IN THE HOUSE SHALL BE RATED AT 1.75 GPM OR LESS. ALL OTHER LAVATORY FAUCETS SHALL BE RATED AT 1.0 GPM OR LESS. TO QUALIFY TO CLAIM THIS CREDIT, THE BUILDING PERMIT DRAWINGS SHALL SPECIFY THE OPTION BEING SELECTED AND SHALL SPECIFY THE MAXIMUM FLOW RATES FOR ALL SHOWERHEADS, KITCHEN SINK FAUCETS, AND OTHER LAVATORY FAUCETS.	0.5
5b	EFFICIENT WATER HEATING 5b: WATER HEATING SYSTEM SHALL INCLUDE ONE OF THE FOLLOWING: GAS, PROPANE OR OIL WATER HEATER WITH A MINIMUM EF OF 0.14 OR WATER HEATER HEATED BY GROUND SOURCE HEAT PUMP MEETING THE REQUIREMENTS OF OPTION 3c. OR FOR R-2 OCCUPANCY, A CENTRAL HEAT PUMP WATER HEATER WITH AN EF GREATER THAN 2.0 THAT WOULD SUPPLY DHW TO ALL THE UNITS THROUGH A CENTRAL WATER LOOP INSULATED WITH R-8 MINIMUM PIPE INSULATION. TO QUALIFY TO CLAIM THIS CREDIT, THE BUILDING PERMIT DRAWINGS SHALL SPECIFY THE OPTION BEING SELECTED AND SHALL SPECIFY THE WATER HEATER EQUIPMENT TYPE AND THE MINIMUM EQUIPMENT EFFICIENCY.	1.0
5c	EFFICIENT WATER HEATING 5c: WATER HEATING SYSTEM SHALL INCLUDE ONE OF THE FOLLOWING: GAS, PROPANE OR OIL WATER HEATER WITH A MINIMUM EF OF 0.91 OR SOLAR WATER HEATING SUPPLEMENTING A MINIMUM STANDARD WATER HEATER. SOLAR WATER HEATING WILL PROVIDE A RATED MINIMUM SAVINGS OF 85 THERMS OR 2000 KWH BASED ON THE SOLAR RATING AND CERTIFICATION CORPORATION (SRCO) ANNUAL PERFORMANCE OF 06-300 CERTIFIED SOLAR WATER HEATING SYSTEMS. OR ELECTRIC HEAT PUMP WATER HEATER WITH A MINIMUM EF OF 2.0 AND MEETING THE STANDARDS OF NEEA'S NORTHERN CLIMATE SPECIFICATIONS FOR HEAT PUMP WATER HEATERS. TO QUALIFY TO CLAIM THIS CREDIT, THE BUILDING PERMIT DRAWINGS SHALL SPECIFY THE OPTION BEING SELECTED AND SHALL SPECIFY THE WATER HEATER EQUIPMENT TYPE AND THE MINIMUM EQUIPMENT EFFICIENCY AND, FOR SOLAR WATER HEATING SYSTEMS, THE CALCULATION OF THE MINIMUM ENERGY SAVINGS.	1.5
5d	EFFICIENT WATER HEATING 5d: A DRAIN WATER HEAT RECOVERY (DWH) UNIT SHALL BE INSTALLED, WHICH CAPTURES WASTE WATER HEAT FROM ALL THE SHOWERS, AND HAS A MINIMUM EFFICIENCY OF 40%. IF INSTALLED FOR EQUAL FLOW OR A MINIMUM EFFICIENCY OF 52% IF INSTALLED FOR UNEQUAL FLOW, SUCH UNITS SHALL BE RATED IN ACCORDANCE WITH CSA B951 AND BE SO LABELED. TO QUALIFY TO CLAIM THIS CREDIT, THE BUILDING PERMIT DRAWINGS SHALL INCLUDE A PLUMBING DIAGRAM THAT SPECIFIES THE DRAIN WATER HEAT RECOVERY UNITS AND THE PLUMBING LAYOUT NEEDED TO INSTALL IT AND LABELS OR OTHER DOCUMENTATION SHALL BE PROVIDED THAT DEMONSTRATES THAT THE UNIT COMPLIES WITH THE STANDARD.	0.5
6	RENEWABLE ELECTRIC ENERGY: FOR EACH 1200 KWH OF ELECTRICAL GENERATION PER HOUSING UNIT PROVIDED ANNUALLY BY ON-SITE WIND OR SOLAR EQUIPMENT A 0.5 CREDIT SHALL BE ALLOWED, UP TO 3 CREDITS. GENERATION SHALL BE CALCULATED AS FOLLOWS: FOR SOLAR ELECTRIC SYSTEMS, THE DESIGN SHALL BE DEMONSTRATED TO MEET THIS REQUIREMENT USING THE NATIONAL RENEWABLE ENERGY LABORATORY CALCULATOR PVWATTS. DOCUMENTATION NOTING SOLAR ACCESS SHALL BE INCLUDED ON THE PLANS. FOR WIND GENERATION PROJECTS DESIGNS SHALL DOCUMENT ANNUAL POWER GENERATION BASED ON THE FOLLOWING FACTORS: THE WIND TURBINE POWER CURVE; AVERAGE ANNUAL WIND SPEED AT THE SITE; FREQUENCY DISTRIBUTION OF THE WIND SPEED AT THE SITE AND HEIGHT OF THE TOWER. TO QUALIFY TO CLAIM THIS CREDIT, THE BUILDING PERMIT DRAWINGS SHALL SPECIFY THE OPTION BEING SELECTED AND SHALL SHOW THE PHOTOVOLTAIC OR WIND TURBINE EQUIPMENT TYPE, PROVIDE DOCUMENTATION OF SOLAR AND WIND ACCESS, AND INCLUDE A CALCULATION OF THE MINIMUM ANNUAL ENERGY POWER PRODUCTION.	0.5

- A. PROJECTS USING THIS OPTION MAY NOT USE OPTION 1a, 1b or 1c.
B. PROJECTS MAY ONLY INCLUDE CREDIT FROM ONE SPACE HEATING OPTION 3a, 3b, 3c or 3d, WHEN A HOUSING UNIT HAS TWO PIECES OF EQUIPMENT (I.E., TWO FURNACES) BOTH MUST MEET THE STANDARD TO RECEIVE THE CREDIT.
C. PLUMBING FIXTURES FLOW RATINGS, LOW FLOW PLUMBING FIXTURES (WATER CLOSETS AND URINALS) AND FITTINGS (FAUCETS AND SHOWERHEADS) SHALL COMPLY WITH THE FOLLOWING REQUIREMENTS:
1. RESIDENTIAL BATHROOM LAVATORY SINK FAUCETS: MAXIMUM FLOW RATE - 3.0 L/MIN (1.0 GAL/MIN) WHEN TESTED IN ACCORDANCE WITH ASME A112.18.1/CSA B125.1.
2. RESIDENTIAL KITCHEN FAUCETS: MAXIMUM FLOW RATE - 6.6 L/MIN (1.75 GAL/MIN) WHEN TESTED IN ACCORDANCE WITH ASME A112.18.1/CSA B125.1.
3. RESIDENTIAL SHOWERHEADS: MAXIMUM FLOW RATE - 6.6 L/MIN (1.75 GAL/MIN) WHEN TESTED IN ACCORDANCE WITH ASME A112.18.1/CSA B125.1.



Issue Issue Date By
Description

Spring Residence
4740 W. Mercer Way
Mercer Island, WA.
Job Number: Spring JMC011

plan name: -
marketing name: -
plan number: -
mark sys. number: -

Conditions not specifically represented graphically or in writing or which conflict with the current International Residential Code (IRC.) or those of the local municipality then the current standards and requirements of each respectively shall govern.

The drawings in this set are instruments of service and shall remain the property of JayMarc Homes, LLC.

© 2017 JayMarc Homes, LLC; All rights reserved.

12.09.22
Submittal Date

Sheet Title/Description
JAYMARC HOMES
Design Firm

R.K.N.
Drawn by:

S.K.
Checked by:

Primary Scale


EN2
of .

Sheet Title/Description

SE 1/4 OF THE SE 1/4 OF SECTION 13, TOWNSHIP 24 NORTH, RANGE 4 EAST, W.M., KING COUNTY, WA.

NOTE: THE LAWN AND LANDSCAPE AREAS ARE REQUIRED TO PROVIDE POST-CONSTRUCTION SOIL QUALITY AND DEPTH IN ACCORDANCE WITH BMP T5.13. THE PROJECT CIVIL ENGINEER MUST PROVIDE A LETTER OF CERTIFICATION TO ENSURE THAT THE LAWN AND LANDSCAPE AREAS ARE MEETING THE POST-CONSTRUCTION SOIL QUALITY AND DEPTH REQUIREMENTS SPECIFIED ON THE APPROVED PLAN SET PRIOR TO FINAL INSPECTION OF THE PROJECT.

EXISTING UTILITY LOCATIONS SHOWN HEREON ARE APPROXIMATE ONLY. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE EXACT VERTICAL AND HORIZONTAL LOCATION OF ALL EXISTING UNDERGROUND UTILITIES PRIOR TO COMMENCING CONSTRUCTION. NO REPRESENTATION IS MADE THAT ALL EXISTING UTILITIES ARE SHOWN HEREON. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR UTILITIES NOT SHOWN OR UTILITIES NOT SHOWN IN THEIR PROPER LOCATION.
CALL BEFORE YOU DIG: 811



LEGEND

- ASPHALT SURFACE
- BRICK SURFACE
- BUILDING
- CENTERLINE ROW
- CLEANOUT
- CULVERT PIPE
- CONCRETE SURFACE
- RETAINING WALL
- DECK
- FENCE LINE (CHAIN LINK)
- FENCE LINE (WOOD)
- GAS METER
- GRAVEL SURFACE
- HEDGE FOLIAGE LINE
- INLET (TYPE 1)
- MAILBOX (RESIDENTIAL)
- EXISTING SPOT ELEVATIONS
- MONUMENT IN CASE (FOUND)
- POWER METER
- POWER (OVERHEAD)
- POWER POLE
- REBAR AS NOTED (FOUND)
- REBAR & CAP (SET)
- ROCKERY
- SEWER LINE
- SEWER MANHOLE
- STORM DRAIN LINE
- TELEPHONE (OVERHEAD)
- TEL SENTRY
- TELEPHONE SENTRY
- WATER METER
- POWER TRANSFORMER POLE
- TREE (AS NOTED)

NOTES:

- (A) 4" FOUNDATION DRAIN
- (B) INSTALL NEW WATER SERVICE & METER BOX PER CITY OF MERCER ISLAND STANDARD PLAN #W-17.
- (C) CB#2. CONTROL STRUCTURE, TYPE II-54"Ø W/SOLID LOCKING LID RIM=111.60 OVERFLOW=109.55, 6"(TOP OF TEE) IE=109.00, 6"(E) IE=106.05, 36"(N), 6"(SW) ELEV.=104.05, 6"(BOTTOM OF TEE) INSIDE BOTTOM=102.05
- (D) CB#1, TYPE 1 W/SOLID LOCKING LID RIM=108.10 IE=105.78, 6"(W,N,E)
- (E) 20' SLOT DRAIN GRATE=110.00 ((DO NOT INSTALL LOWER THAN ELEV. 110.00)) IE=108.00, 4"(S)

NOTE: A TV INSPECTION OF THE EXISTING SIDE SEWER TO THE CITY SEWER MAIN IN WEST MERCER WAY IS REQUIRED PRIOR TO ANY WORK RELATED TO THE SIDE SEWER. IF THE RESULT OF THE TV INSPECTION IS NOT IN SATISFACTORY CONDITION, AS DETERMINED BY THE CITY OF MERCER ISLAND INSPECTOR, THE REPLACEMENT OF THE EXISTING SIDE SEWER IS REQUIRED TO THE SEWER MAIN.

ABANDON EXISTING WATER METER AND SERVICE

6-8 inches of arborist wood chips and plywood as soil protection between TP fencing and house

Limit of Excavation Exploratory Air Excavation Required With arborist.

Tree ID	Common Name	DSH	Multi	Health	Structural Condition	Dripline				Exceptional I Threshold	Exceptional I Above 24"	Retain?		
						N	E	S	W					
377	Bigleaf Maple	34.7	24,25	Good	Good	26.4	26.4	33.4	31.4	30"	Size	Yes	Yes	
378	Lodgepole Pine	11.5		Good	Fair	0.5	13.5	24.5	12.5	6	Size	No	Yes	
379	Austrian Black Pine	26.7		Good	Fair	17.1	9.1	26.1	21.1	24	Size	Yes	Yes	
380	Austrian Black Pine	28.3		Good	Fair	19.2	21.2	27.2	9.2	24	Size	Yes	Yes	
381	Western Red Cedar	12.9		Good	Good	14.5	14.5	14.5	14.5	30	No	No	Yes	
382	Western Red Cedar	32.5		Good	Good	21.4	21.4	21.4	21.4	30	Size	Yes	Yes	
383	Flowering Cherry	10.2	6,5,7,1,3,3	Good	Good	16.4	8.4	12.4	16.4	23	No	No	No	
384	Western Red Cedar	45.4		Good	Good	31.9	21.9	26.9	21.9	30	Size	Yes	Yes	
385	Doug-Fir	20.3		Good	Good	15.8	15.8	15.8	15.8	30	No	No	No	
386	Doug-Fir	42		Good	Excellent	25.8	25.8	25.8	23.8	30	Size	Yes	Yes	
10	TOTALS											7	6	9

Tree ID	Common Name	DSH	Multi	Health	Structural Condition	N	E	S	W	Exceptional I Threshold	Exceptional I Above 24"	Retain?
A	Red Alder	12		Poor	Fair	15.5	17.5	10.5	16.5		No	

SIDE SEWER NOTES

- (S1) APPROXIMATE LOCATION OF EXISTING SANITARY SIDE SEWER.
- (S2) INSTALL 32LF., 4" PVC SIDE SEWER @ MIN. 2% SLOPE

STORM PIPE TABLE

- ① 9LF., 6" D.I. @ S=2.00%
- ② 12LF., 6" PVC SDR-35 @ S=2.00%
- ③ 16LF., 6" PVC SDR-35 @ S=3.13%
- ④ 14LF., 4" PVC SDR-35 @ S=24.3%
- ⑤ 24LF., 4" PVC SDR-35 @ S=2.00%
- ⑥ 18LF., 4" PVC SDR-35 @ S=2.00%
- ⑦ 21LF., 4" PVC SDR-35 @ S=2.00%
- ⑧ 24LF., 4" PVC SDR-35 @ S=2.71%
- ⑨ 21LF., 4" PVC SDR-35 @ S=15.87%
- ⑩ 19LF., 4" PVC SDR-35 @ S=2.00%
- ⑪ 23LF., 4" PVC SDR-35 @ S=2.61%
- ⑫ 32LF., 4" PVC SDR-35 @ S=2.00%
- ⑬ 18LF., 4" PVC SDR-35 @ S=2.00%
- ⑭ 49LF., 48" CMP @S=0.00% (LEVEL)
- ⑮ 8LF., 4" CMP @S=8.75%

DOWNSPOUT TABLE


- DS#1 CONCRETE=116.00 DOWNSPOUT LINE=112.90, 4"
- DS#2 CONCRETE=116.00 DOWNSPOUT LINE=113.40, 4"
- DS#3 GROUND=114.50 DOWNSPOUT LINE=113.80, 4"
- DS#4 GROUND=115.00 DOWNSPOUT LINE=114.25, 4"
- DS#5 GROUND=115.50 DOWNSPOUT LINE=114.90, 4"
- DS#6 GROUND=115.50 DOWNSPOUT LINE=114.90, 4"
- DS#7 GROUND=112.40 DOWNSPOUT LINE=111.50, 4"
- DS#8 GROUND=112.40 DOWNSPOUT LINE=111.10, 4"
- DS#9 GROUND=112.40 DOWNSPOUT LINE=110.50, 4"
- DS#10 GROUND=114.00 DOWNSPOUT LINE=109.86, 4"

STORM PIPE PVC SHALL BE SDR-35 PVC AT SLOPE=2.00% MINIMUM (TYPICAL) UNLESS OTHERWISE NOTED

IMPERVIOUS SURFACES:
ROOF AREA (UNDER EAVES) = 3,992 SQ. FEET
UNCOVERED DRIVEWAY AREA = 1,002 SQ. FEET
TOTAL IMPERVIOUS AREAS = 4,994 SQ. FEET

LANDSCAPE AREAS NOTE:


DISTURBED LANDSCAPE AREAS SHALL BE TREATED AS AMENDED SOILS PER DOE FIGURE V-5.3.3, TYPICAL




GRAPHIC SCALE

1 inch = 10 feet

PERMIT #: 22xx-xx





OFFE ENGINEERS
13902 SOUTHEAST 159TH PLACE
RENTON, WASHINGTON 98058
PHONE: 425-260-3412
CONTACT: DARRELL OFFE, P.E.




PROJECT: 4740 West Mercer Way
CLIENT: JayMarc Custom Homes - Spring Residence
SHEET CONTENT: Utility & Tree Plan

DATE: 11/21/2022
JOB NO.:
DWG NO.: 2 OF 4
SHEET: 4



DESIGNED BY	DRAWN BY	CHECKED BY	DATE	DESCRIPTION
DLO	SLM	DLO	11/21/2022	



OFFE ENGINEERS
 13902 SOUTHEAST 159TH PLACE
 RENTON, WASHINGTON 98058
 PHONE: 425-260-3412
 CONTACT: DARRELL OFFE, P.E.



CATCH BASIN TYPE 1
STANDARD PLAN B-5.20-03
 SHEET 1 OF 1 SHEET
 APPROVED FOR PUBLICATION
Roark, Steve Digitally signed by Roark, Steve
 STATE DESIGN LICENSED
 Washington State Department of Transportation






4740 West Mercer Way
JayMarc Custom Homes - Spring Residence
Utility Details



PROJECT: _____ CLIENT: _____ SHEET CONTENT: _____
 DATE: 11/23/2022
 JOB NO.: _____
 DWG NO.: _____
 SHEET 3 OF 4

PERMIT #: 22xx-xx

SE 1/4 OF THE SE 1/4 OF SECTION 13, TOWNSHIP 24 NORTH., RANGE 4 EAST, W.M., KING COUNTY, WA.



		11/22/2022 REV. NO. DATE DESCRIPTION
OFFE ENGINEERS 13902 SOUTHEAST 159TH PLACE RENTON, WASHINGTON 98058 PHONE: 425-260-3412 CONTACT: DARRELL OFFE, P.E.		CHECKED BY DLO
		DRAWN BY SLM
4740 West Mercer Way JayMarc Custom Homes - Spring Residence Amended Soil Map & Detail		DESIGNED BY DLO
PROJECT	CLIENT JayMarc Custom Homes - Spring Residence	SHEET CONTENT 4 OF 4
DATE 11/22/2022	JOB NO.	DWG NO.
PERMIT #: 22xx-xx		



- GENERAL NOTES**
1. INSTRUMENTATION FOR THIS SURVEY WAS A 3-SECOND LEICA VIVA TS15 SMART POLE TOTAL STATION/RTK GPS.
 2. PROCEDURES USED IN THIS SURVEY MEET OR EXCEED STANDARDS SET BY WAC 332-130-090. SURVEY WAS COMPLETED BY A FIELD TRAVERSE.
 3. UTILITIES SHOWN ON THIS SURVEY ARE BASED UPON ABOVE GROUND OBSERVATIONS, UTILITY LOCATES BY THIRD PARTIES, AND AS-BUILT PLANS WHERE AVAILABLE. ACTUAL LOCATIONS OF UNDERGROUND UTILITIES MAY VARY AND UTILITIES NOT SHOWN ON THIS SURVEY MAY EXIST ON THIS SITE.
 4. ALL MONUMENTS WERE LOCATED DURING THIS SURVEY UNLESS OTHERWISE NOTED.
 5. CONTOURS SHOWN ARE BASED ON A FIELD SURVEY.
 6. TREE IDENTIFICATION WAS PERFORMED BY SURVEY FIELD PERSONNEL AND SHOULD BE CONSIDERED A BEST GUESS. AN ARBORIST SHOULD BE RELIED UPON FOR MORE ACCURATE AND DETAILED IDENTIFICATION OF TREE SPECIES AND HEALTH.

PROJECT INFORMATION

SURVEYOR: PLOG ENGINEERING, PLLC
P.O. BOX 412
RAVENSDALE, WA 98051
PH: (206) 420-7130

PROPERTY OWNER: ERIC & KATIE SPRING
4740 WEST MERCER WAY
MERCER ISLAND, WA 98040

TAX PARCEL NUMBER: 404510-0055

PROJECT ADDRESS: 4740 WEST MERCER WAY
MERCER ISLAND, WA 98040

PARCEL AREA: 16,710 S.F. (0.384 ACRES ±)
AS SURVEYED

SYMBOL LEGEND

MONUMENT AS NOTED	FIBER OPTIC MAINTENANCE HOLE
SECTION CORNER	TELEPHONE MAINTENANCE HOLE
QUARTER SECTION CORNER	TRAFFIC SIGNAL MAINTENANCE HOLE
FOUND REBAR AS NOTED	PAD MOUNTED TRANSFORMER
SET REBAR AND CAP LS 31976	HAND HOLE
FOUND SURFACE MARKER/DISK	A/C COMPRESSOR
SET SURFACE MARKER/DISK LS 31976	YARD LIGHT
SEWER MAINTENANCE HOLE	POWER POLE
SEPTIC MAINTENANCE HOLE	GUY WIRE
SEWER CLEAN OUT	STREET LIGHT
SEWER LINE	O-HU—OVERHEAD UTILITIES (GENERAL/MIXED)
STORM DRAIN MAINTENANCE HOLE	O-HE—OVERHEAD ELECTRICAL
CATCH BASIN (TYPE 2)	O-HC—OVERHEAD CABLE
CATCH BASIN (TYPE 1)	O-HT—OVERHEAD TELEPHONE
STORM DRAIN CLEAN OUT	U-GU—UNDERGROUND UTILITIES (GENERAL/MIXED)
ROUND YARD DRAIN	U-GE—UNDERGROUND ELECTRICAL
SQUARE YARD DRAIN	U-GC—UNDERGROUND CABLE
SD—STORM DRAIN LINE	U-GT—UNDERGROUND TELEPHONE
WATER MAINTENANCE HOLE	U-FO—UNDERGROUND FIBER OPTIC
WATER VALVE	BOLLARD
WATER METER	M MAILBOX
FIRE HYDRANT	S SIGN
BLOW OFF VALVE	WF WETLAND FLAG
IRRIGATION VALVE/JUNCTION	SNAG
W—WATER LINE	DECIDUOUS MULTI—TRUNK
G V GAS VALVE	DECIDUOUS
G M GAS METER	CONIFER MULTI—TRUNK
G—GAS LINE	CONIFER
CABLE RISER	
CTV CABLE BOX	
CABLE MAINTENANCE HOLE	

REFERENCE SURVEYS

P1 - REPLAT OF LAKE ISLE, VOL 26, PG 13
R1 - AF# 20061023900004
SP1 - AF# 9809099001 SP# M.J. 98-0179

VERTICAL DATUM & CONTOUR INTERVAL

ELEVATIONS SHOWN ON THIS DRAWING ARE BASE ON THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD88) AND WERE ESTABLISHED USING RTK GPS.

2.0' CONTOUR INTERVAL - THE EXPECTED VERTICAL ACCURACY IS EQUAL TO 1/2 THE CONTOUR INTERVAL OR ± 1.0' FOR THIS PROJECT.

LEGAL DESCRIPTION

LOTS 11, 12 AND 13, REPLAT OF A PORTION OF LAKE ISLE, ACCORDING TO THE PLAT THEREOF RECORDED IN VOLUME 26 OF PLATS, PAGE 13, RECORDS OF KING COUNTY, WASHINGTON.

SITUATE IN THE COUNTY OF KING, STATE OF WASHINGTON.

BASIS OF BEARINGS

PER THE REPLAT OF A PORTION OF LAKE ISLE, ACCORDING TO THE PLAT THEREOF RECORDED IN VOLUME 26 OF PLATS, PAGE 13, RECORDS OF KING COUNTY, WASHINGTON.

ACCEPTED THE BEARING OF N 0°05'56" W FOR 84TH AVE SE BASED ON FOUND MONUMENTS IN CASE.

ABBREVIATION LEGEND

MON = MONUMENT
DN = DOWN
SP = SHORT PLAT
BLA = BOUNDARY LINE ADJUSTMENT
DBH = DIAMETER AT BREAST HEIGHT (FT)
DLR = DRIP LINE RADIUS (FT)
APN = ASSESSORS' PARCEL NUMBER
AF# = AUDITOR'S FILE NUMBER
(M) = AS MEASURED
(C) = AS CALCULATED
(P) = PER PLAT
(D) = PER DEED
(R#) = PER REFERENCE SURVEY
(H) = HELD



PLOG ENGINEERING
Surveyors & Civil Engineers

P.O. Box 412
Ravensdale, WA 98051
(206) 420-7130
www.PlogEngineering.com

SE1/4, SE1/4, SEC 13, TWP 24N, RNG 4E, W.M.			
BOUNDARY & TOPOGRAPHIC SURVEY			
ERIC & KATIE SPRING			
4740 WEST MERCER WAY			
MERCER ISLAND, WA 98040			
PROJECT NO.:	REVISION DATE:	REVISION NO.:	SHEET
174-21	10/12/2021	0	1 OF 1