

# DRAINAGE REPORT


for

## WELLMON RESIDENCE

6333 77<sup>th</sup> Ave SE

Mercer Island, Washington 98040

Parcel No. 4097100010



---

**DRS Project No. 22109**

**Mercer Island File No. \_\_\_\_\_**

*Owner/Applicant*

Nick & Lindsey Wellmon  
6333 77<sup>th</sup> Ave SE  
Mercer Island WA 98040

*Report Prepared by*



D. R. STRONG Consulting Engineers, Inc.  
620 7<sup>th</sup> Ave.  
Kirkland WA 98033  
(425) 827-3063

**Issue Date:**

**May 12, 2023**

# TABLE OF CONTENTS

<b>MR 1 - STORMWATER SITE PLANNING .....</b>	<b>1</b>
PROJECT OVERVIEW .....	1
PREDEVELOPED SITE CONDITIONS.....	1
DEVELOPED SITE CONDITIONS.....	1
THRESHOLD DETERMINATION .....	2
OFFSITE ANALYSIS AND MITIGATION .....	2
UPSTREAM ANALYSIS.....	2
DOWNSTREAM ANALYSIS .....	2
ADJUSTMENTS, DEVIATIONS AND EXEMPTIONS .....	3
<b>MR 2 - SWPPP NARRATIVE .....</b>	<b>6</b>
<b>MR 3 - WATER POLLUTION SOURCE CONTROL FOR NEW DEVELOPMENT .....</b>	<b>8</b>
<b>MR 4 - PRESERVATION OF NATURAL DRAINAGE SYSTEMS AND OUTFALLS, AND PROVISIONS OF OFF-SITE MITIGATION.....</b>	<b>9</b>
<b>MR 5 - ON-SITE STORMWATER MANAGEMENT .....</b>	<b>16</b>
GENERAL PARAMETERS .....	16
SOIL MANAGEMENT PLAN .....	16
CONVEYANCE SYSTEM .....	17
SITE DISCHARGE .....	16
<b>MR 6 - RUNOFF TREATMENT REQUIREMENTS .....</b>	<b>18</b>
<b>MR 7 - FLOW CONTROL.....</b>	<b>19</b>
<b>MR 8 - DETENTION OR TREATMENT IN WETLAND AND WETLAND BUFFERS .....</b>	<b>20</b>
<b>MR 9 - INSPECTION, OPERATION AND MAINTENANCE REQUIREMENTS .....</b>	<b>21</b>

## List of Figures

Figure 1 Vicinity Map.....	4
Figure 2 Downstream Map .....	5
Figure 3 Existing Site Conditions Map.....	10
Figure 4 Proposed Site Conditions Map.....	11
Figure 5 USDA Soil Survey Map .....	12
Figure 6 Drainage SubBasins Map.....	15

## Appendix

Appendix A DOE Flow Chart.....	22
Appendix B Mercer Island Small Project Stormwater Report .....	23
Appendix C WWHM2012 Report.....	24
Appendix D Geotech Report .....	25

# MR 1 - STORMWATER SITE PLANNING

## PROJECT OVERVIEW

The Site is located at 6333 77<sup>th</sup> Ave SE in the City of Mercer Island, Washington, also known as Tax Parcel Number 4097100010 (Site). The applicant is proposing to demolish the existing residence and construct a single-family home, driveway, landscaping and associated utilities. The Site is approximately 19,982 SF (0.458 AC). The Project will meet the requirements of MICC 15.09.050, and the 2014 Washington State Department of Ecology (DOE) Stormwater Management Manual for Western Washington (Manual).

## PREDEVELOPED SITE CONDITIONS

The existing Site is currently developed with a single-family residence, detached garage, brick paved driveway and walkways, concrete patio, boat dock and rockeries. The remainder of the Site consists of lawn, trees, and shrubs

The Site is contained within one Threshold Discharge Area (TDA). The topography slopes from east to west at slopes ranging from 10-30%. Surface runoff generated onsite travels westerly across the Site and sheet-flows into Lake Washington. Driveway and roof runoff collected onsite is discharged to Lake Washington via a 4" outlet at the bulkhead.

According to the City of Mercer Island GIS portal sensitive areas maps, the contains erosion, and seismic hazard areas.

The USDA Web Soil Survey describes the soil on Site as Kitsap silt loam (KpB), 2-8% slopes.

## DEVELOPED SITE CONDITIONS

The applicant is seeking approval to demolish the existing residence, and construct a new single-family residence. The total Project area is assumed to be the Site area, which is approximately 19,882 SF (0.456 AC). The impervious surface estimates are based on the architectural site plan, provided by Lochwood Lozier, dated March 6, 2023. An upstream area of 600 SF (0.014 AC) of road area is included in the flow rate calculations (see section MR 5). The Project is proposing 6,633 SF of new or replaced impervious area. The remainder of the Project area will consist of residential landscaping and other pervious surfaces. See the table below for a breakdown of the contributing surfaces.

Site is proposing to utilize the existing 4" discharge pipe. Because the Project is discharging directly to Lake Washington, which is a designated receiving water, no control facilities are required. See Section IV for a full description of the drainage calculations.

Total new or replaced Pollution Generating Impervious Surface (PGIS) for the project will include a concrete driveway to the single-family residence. Per Section 1.2.8.1 of the Manual, the project is exempt from providing a water quality facility (less than 5,000 SF of new plus replaced PGIS being added and less than  $\frac{3}{4}$  of an acre of new PGPS being added). See the table below for proposed surface area breakdown.

Developed Site Area Breakdown				
Land Cover	Roof	Walkways	Driveway (PGIS)	Grass/Landscape (PGPS)
S.F.	4,496	338	*1,799	13,322
Acres	0.103	0.008	0.041	0.306

\*For flow calculations, an additional 600 SF of road is included (total = 2,399 SF) for the upstream area.

### THRESHOLD DETERMINATION

Existing Site hard surface area coverage is approximately 39%. The remainder of the Site is vegetated. Greater than 35% of the existing Site is existing hard surface coverage and therefore the thresholds for redevelopment projects apply.

The Project will create over 5,000 SF (6,560 SF) of new, replaced, or new plus replaced hard surfaces and the value of the proposed improvements exceeds 50% of the assessed value of the existing Site improvements. Per DOE Figure I-2.4.2 *Flow Chart for Determining Requirements for Redevelopment Minimum Requirements*, MR #1 - 9 apply to new and replaced hard surfaces and the land disturbed (see Appendix A). No adverse drainage impacts are anticipated as a result of the proposed Project improvements.

### OFFSITE ANALYSIS AND MITIGATION

The Project will discharge all collected runoff directly to Lake Washington. Since Lake Washington is a designated receiving water no flow control facilities are required or proposed. On-site Flow Control BMPs were evaluated and found to be unsuitable for this Site. See Section MR 5 for complete BMP analysis. No adverse drainage impacts are anticipated as a result of the proposed Project improvements.

### UPSTREAM ANALYSIS

The upstream area consists of approximately 600 SF (0.014 AC) of area within the 77<sup>th</sup> Ave SE ROW to the east of the Site. Due to existing asphalt berms, most of the runoff generated on 77<sup>th</sup> Ave SE is directed south, away from the Site. Runoff generated on parcels to the east is collected by the conveyance system in 77<sup>th</sup> Ave SE. Existing topography keeps runoff from the developed adjacent parcels to the north and south contained on their own parcels.

See Figure 5 for the limits of the upstream basin area.


### DOWNSTREAM ANALYSIS

Site runoff currently is discharged via sheet flow and a 4" pipe outfall to Lake Washington, which is a designated receiving water. The Natural Discharge Location of the Site will remain unchanged. No adverse drainage impacts are anticipated as a result of the proposed Project.


## **ADJUSTMENTS, DEVIATIONS AND EXEMPTIONS**

There are no Adjustments, Deviations or Exemptions that have been requested or apply to this Project.

# FIGURE 1 VICINITY MAP




**FIGURE 2  
DOWNSTREAM MAP**



NATURAL DISCHARGE LOCATION 1  
COLLECTED RUNOFF LEAVES AS  
PIPE FLOW OVER WESTERN  
PROPERTY LINE INTO LAKE

CULV 24" PVC E  
IE = 18.85'

NATURAL DISCHARGE LOCATION 1  
RUNOFF LEAVES AS SHEET FLOW  
OVER WESTERN PROPERTY LINE  
INTO LAKE



**DRS**

D.R. STRONG  
CONSULTING ENGINEERS

ENGINEERS PLANNERS SURVEYORS  
620 - 7th AVENUE KIRKLAND, WA 98033  
O 425.827.3063 F 425.827.2423

**FIGURE 2**  
**DOWNSTREAM MAP**  
**WELLMON RESIDENCE**

DRAFTED BY: PHB  
DESIGNED BY: NBM  
PROJECT ENGINEER: LRJ  
DATE: 5/12/2023  
PROJECT NO.: 22109



## **MR 2 - SWPPP NARRATIVE**

A Construction Stormwater Pollution Prevention Plan has been prepared for this Site and is enclosed. Each of the 13 construction SWPPP elements has been considered and discussed below.

Element 1: Mark clearing limits: Prior to beginning land disturbing activities, including clearing and grading, all clearing limits, sensitive areas and their buffers (if any), and trees that are to be preserved within the construction area shall be clearly marked in the field to prevent damage and offsite impacts.

Element 2: Establish construction access: Construction vehicle access and exit shall be limited to the one route shown on the CSWPPP. Sediment tracked off Site shall be cleaned up at the end of each day.

Element 3: Control flow rates: Not applicable – no detention required.

Element 4: Install sediment controls: Prior to leaving the construction site, stormwater runoff from disturbed areas shall pass through a double silt fence.

Element 5: Stabilize soils: All exposed and unworked soils shall be stabilized by application of straw mulch such that the soil is protected from the erosive forces of raindrop impacts and flowing water, and wind erosion. Soils shall be stabilized at the end of the shift before a holiday or weekend if needed based on the weather forecast. Soil stockpiles must be stabilized from erosion, protected with sediment trapping measures, and when possible, be located away from storm drain inlets, waterways and drainage channels.

Element 6: Protect slopes: Cut and fill slopes will be protected from erosion by covering worked soils with mulching, matting, and compost blankets. If necessary, plastic covering can be used to protect slopes.

Element 7: Protect drain inlets: All storm drain inlets made operable during construction and existing inlets affected by runoff shall be protected so that stormwater runoff shall not enter the public conveyance system without first being filtered or treated to remove sediment. Inlets should be inspected weekly at a minimum and daily during storm events. Inlet protection devices should be cleaned or removed and replaced when sediment has filled one-third of the available storage.

Element 8: Stabilize channels and outlets: The existing outlet is above the ordinary high water mark of Lake Washington and discharge directly to the lake surface.

Element 9: Control pollutants: All pollutants, including waste materials and demolition debris that occur on-site, shall be handled and disposed of in a manner that does not cause contamination of stormwater. Woody debris may be chopped and spread on site. Cover, containment, and protection from vandalism shall be provided for all chemicals, liquid products, petroleum products, and non-inert wastes present on the site (see chapter 173-304 WAC for the definition of inert waste). On-site fueling tanks shall include secondary containment.

Element 10: Control de-watering: If dewatering is required a temporary sediment trap may be utilized.

Element 11: Maintain BMPs: All temporary and permanent erosion and sediment control BMPs shall be maintained and repaired as needed to assure continued performance of their intended function. All maintenance and repair shall be conducted in accordance with BMP specifications. All temporary erosion and sediment control BMPs shall be removed within 30 days after final Site stabilization is achieved or after the temporary BMPs are no longer needed. Trapped sediment shall be removed or stabilized on site. Disturbed soil areas resulting from removal of BMPs or vegetation shall be permanently stabilized.

Element 12: Manage the project: All BMPs shall be inspected, maintained, and repaired as needed to assure continued performance of their intended function. The CSWPPP shall be modified whenever there is a significant change in the design, construction, operation, or maintenance at the construction site that has, or could have, a significant effect on the discharge of pollutants to waters of the state.

Element 13: Protect LID BMPs: No LID BMPs are proposed at this time. Due to Site constraints, including high groundwater and steep slopes, no LID BMPs are feasible.


### **MR 3 - WATER POLLUTION SOURCE CONTROL FOR NEW DEVELOPMENT**

Not applicable for this Project. There will be no activities during or after construction that are listed in Volume IV of the Drainage Manual.

#### **MR 4 - PRESERVATION OF NATURAL DRAINAGE SYSTEMS AND OUTFALLS, AND PROVISIONS OF OFF-SITE MITIGATION.**

Under existing conditions, runoff collected onsite is discharged to Lake Washington via a 4" outlet at the bulkhead. Any runoff generated onsite that is not collected, sheet flows in a westerly direction into Lake Washington. The proposed development will discharge at the natural location along the western property line (Lake Washington). No adverse drainage impacts are anticipated as a result of the proposed Project.

**FIGURE 3  
EXISTING SITE CONDITIONS MAP**









**PREDEV. AREA BREAKDOWN**


- SITE & TDA BOUNDARY
- - - PROJECT BOUNDARY

WVHM INPUTS:

TDA AREA (SITE+UPSTREAM): 20,482 SF (0.470 AC)

-  MODERATE LAWN/LANDSCAPE AREA  
C, LAWN, MOD: 5,487 SF (0.127 AC)
-  STEEP LAWN/LANDSCAPE AREA  
C, LAWN, STEEP: 6,504 SF (0.149 AC)









-  ROOF AREA  
C, ROOF, FLAT: 4,811 SF (0.110 AC)
-  WALKWAY/PATIO AREA  
SIDEWALK, FLAT: 2,320 SF (0.053 AC)
-  DRIVEWAY AREA  
ROAD, MOD: 760 SF (0.017 AC)
-  UPSTREAM AREA  
ROAD, MOD: 600 SF (0.014 AC)





**FIGURE 3**  
**PRE-DEVELOPED CONDITIONS**  
**WELLMON RESIDENCE**

**FIGURE 4  
PROPOSED SITE CONDITIONS MAP**

**PREDEV. AREA BREAKDOWN**

	SITE & TDA BOUNDARY
	PROJECT BOUNDARY
WWHM INPUTS:	
TDA AREA (SITE+UPSTREAM): 20,482 SF (0.470 AC)	
	TREE PROTECTION AREA C, PASTURE, FLAT: 2,021 SF (0.046 AC) C, PASTURE, MOD: 2,048 SF (0.047 AC) C, PASTURE, STEEP: 650 SF (0.015 AC)
	LAWN/LANDSCAPE AREA C, PASTURE, FLAT: 4,107 SF (0.094 AC) C, PASTURE, MOD: 2,048 SF (0.047 AC) C, PASTURE, STEEP: 2,375 SF (0.055 AC)
	ROOF AREA C, ROOF, FLAT: 4,496 SF (0.103 AC)
	WALKWAY/PATIO/DECK AREA SIDEWALK, FLAT: 338 SF (0.008 AC)
	DRIVEWAY AREA ROAD, FLAT: 2,399 SF (0.055 AC)
	UPSTREAM AREA ROAD, FLAT: 600 SF (0.014 AC)



**FIGURE 4**  
 DEVELOPED CONDITIONS  
 WELLMON RESIDENCE

DRAFTED BY: PHB  
 DESIGNED BY: NBM  
 PROJECT ENGINEER: LRJ  
 DATE: 1/19/2023  
 PROJECT NO.: 22109



# FIGURE 5 USDA SOIL SURVEY MAP



## Map Unit Legend

Map Unit Symbol	Map Unit Name	Acres in AOI	Percent of AOI
KpB	Kitsap silt loam, 2 to 8 percent slopes	0.4	100.0%
<b>Totals for Area of Interest</b>		<b>0.4</b>	<b>100.0%</b>

## King County Area, Washington

### KpB—Kitsap silt loam, 2 to 8 percent slopes

- **Map Unit Setting**

- *National map unit symbol:* 1hmt9
- *Elevation:* 0 to 590 feet
- *Mean annual precipitation:* 37 inches
- *Mean annual air temperature:* 50 degrees F
- *Frost-free period:* 160 to 200 days
- *Farmland classification:* All areas are prime farmland

- **Map Unit Composition**

- *Kitsap and similar soils:* 85 percent
- *Minor components:* 15 percent
- *Estimates are based on observations, descriptions, and transects of the mapunit.*

- **Description of Kitsap**

- **Setting**

- *Landform:* Terraces
- *Parent material:* Lacustrine deposits with a minor amount of volcanic ash

- **Typical profile**

- *H1 - 0 to 5 inches:* silt loam
- *H2 - 5 to 24 inches:* silt loam
- *H3 - 24 to 60 inches:* stratified silt to silty clay loam

- **Properties and qualities**

- *Slope:* 2 to 8 percent
- *Depth to restrictive feature:* More than 80 inches
- *Natural drainage class:* Moderately well drained
- *Capacity of the most limiting layer to transmit water (Ksat):* Moderately low to moderately high (0.06 to 0.20 in/hr)
- *Depth to water table:* About 18 to 36 inches
- *Frequency of flooding:* None
- *Frequency of ponding:* None
- *Available water supply, 0 to 60 inches:* High (about 11.4 inches)

- **Interpretive groups**

- *Land capability classification (irrigated):* None specified
- *Land capability classification (nonirrigated):* 3w

- *Hydrologic Soil Group: C*
- *Ecological site: F002XA004WA – Puget Lowlands Forest*
- *Forage suitability group: Soils with Few Limitations (G002XN502WA)*
- *Other vegetative classification: Soils with Few Limitations (G002XN502WA)*
- *Hydric soil rating: No*

- **Minor Components**
- **Alderwood**

- *Percent of map unit: 10 percent*
- *Hydric soil rating: No*

- **Bellingham**

- *Percent of map unit: 3 percent*
- *Landform: Depressions*
- *Other vegetative classification: Wet Soils (G002XN102WA)*
- *Hydric soil rating: Yes*

- **Tukwila**

- *Percent of map unit: 1 percent*
- *Landform: Depressions*
- *Other vegetative classification: Wet Soils (G002XN102WA)*
- *Hydric soil rating: Yes*

- **Seattle**


- *Percent of map unit: 1 percent*
- *Landform: Depressions*
- *Other vegetative classifications: Wet Soils (G002XN102WA)*
- *Hydric soil rating: Yes*

**FIGURE 6  
DRAINAGE SUBBASINS MAP**



**FIGURE 6**  
**DRAINAGE BASINS, SUBBASINS, AND SITE CHARACTERISTICS**  
**WELLMON RESIDENCE**

DRAFTED BY: PHB  
DESIGNED BY: NBM  
PROJECT ENGINEER: LRJ  
DATE: 1/19/2023  
PROJECT NO.: 22109



## MR 5 - ON-SITE STORMWATER MANAGEMENT

### GENERAL PARAMETERS

- The Project will implement the following BMP's: BMP T5.13 Post-Construction Soil Quality and Depth.
- Infiltration and dispersion Flow Control BMPs are not feasible due to the presence of high ground water, erosion hazard areas, seismic hazard areas, and steep slopes.

All runoff from roof and hard surfaces will be collected and directly discharged to Lake Washington.

### SOIL MANAGEMENT PLAN

Within the limits of Site disturbance, duff and topsoil will be retained in an undisturbed state and stockpiled for later use to stabilize and amend soils throughout the Site. Post-construction soil amendment will meet the requirements of BMP T5.13 Post-Construction Soil Quality and Depth.

### SITE DISCHARGE

The following table represents the Project areas breakdown of existing and post developed conditions used for WWHM modeling. Pasture is used to model the pervious area in the developed conditions because the Project is proposing Amended Soils BMP T5.13 (Manual, Vol. III Appendix C.9). The 600 SF (0.014 AC) of upstream road area is included in both the Predeveloped and Developed conditions.

<b>Predeveloped</b>	<b>S.F.</b>	<b>Acres</b>
Impervious (Rooftops/Flat)	4,811	0.110
Impervious (Roads/Mod)	1,360	0.031
Impervious (Sidewalks/Flat)	2,320	0.053
Pervious (C, Lawn, Mod)	5,487	0.126
Pervious (C, Lawn, Steep)	6,504	0.149
<b>Basin Total</b>	<b>20,482</b>	<b>0.470</b>

<b>Developed</b>	<b>SF</b>	<b>Acres</b>
Impervious (Rooftops/Flat)	4,496	0.103
Impervious (Roads/Flat)	2,399	0.055
Impervious (Sidewalks/Flat)	338	0.008
Pervious (C, Pasture, Flat.)	6,128	0.141
Pervious (C, Pasture, Mod)	4,096	0.095
Pervious (C, Pasture, Steep)	3,025	0.069
<b>Basin Total</b>	<b>20,482</b>	<b>0.470</b>

The 100-year, pre-developed runoff flowrate resulting from this WWHM analysis was 0.2670 CFS and the mitigated, developed runoff was 0.1609 CFS, as shown in the results below. Point of Compliance #1 (POC #1) is the existing 4" pipe outfall at the bulkhead.

**Flow Frequency Return Periods for Predeveloped. POC #1**

<u>Return Period</u>	<u>Flow(cfs)</u>
2 year	0.101509
5 year	0.139560
10 year	0.167152
25 year	0.204825
50 year	0.234983
100 year	0.266981

**Flow Frequency Return Periods for Mitigated. POC #1**

<u>Return Period</u>	<u>Flow(cfs)</u>
2 year	0.070817
5 year	0.092460
10 year	0.107856
25 year	0.128569
50 year	0.144941
100 year	0.162144

The full WWHM report used to model the scenarios has been included as Appendix C.

**CONVEYANCE SYSTEM**

Conveyance criteria for the Project require that all new pipes be designed to convey and contain (at minimum) the 25-year peak flow. This system has been designed to convey and contain the 100-year peak flow. To simplify calculations and provide a safety factor, each of the pipes is assumed to convey the runoff generated from the entire Project area.

Onsite and upstream runoff from all target surfaces, will be collected by catch basins, surface drains , or roof gutters, and conveyed to the existing 4 IN pipe outfall at the bulkhead. The conveyance system consists of 4 IN diameter PVC pipes, and type-1 catch basins. Manning’s Equation for flow in a circular channel was used to estimate the capacity of the pipes upstream of the detention tank. The WWHM2012 condition, included as Appendix C, was used to estimate the developed 100-year flow entering the tank for the on-site target surfaces.

Per the WWHM model, the developed 100-year flow is 0.1621 CFS. The 4 IN pipe that connects to the existing 4 IN outfall has the flattest slope, at 1.5%. The pipe capacity of this 4 IN with 1.5% slope is 0.2761 CFS. Therefore, all pipes meet flow capacity requirements. The complete analysis is shown below.

**Pipe P1 Capacity Estimate:**

## **MR 6 - RUNOFF TREATMENT REQUIREMENTS**

Not required for this Project. Total new/ replaced P.G.H.S. is less than 5,000 SF and P.G.P.S. is less than  $\frac{3}{4}$  of an acre. A spill control device will be provided for collected driveway runoff.



## **MR 7 - FLOW CONTROL**

Not required for this Project. The Site directly discharges to Lake Washington, which is a designated receiving water.

**MR 8 - DETENTION OR TREATMENT IN WETLAND AND WETLAND  
BUFFERS**

Not required for this Project. No known wetlands exist on or adjacent to the Site.

## **MR 9 - INSPECTION, OPERATION AND MAINTENANCE REQUIREMENTS**

### **Catch Basins:**

Catch basins have a one foot deep sump for sediment accumulation. This sump should be periodically checked and the sediment removed when accumulated to more than 1/3 of the depth from the bottom of the basin to the invert of the lowest pipe into or out of the basin. Grates should be cleaned when trash or debris of more than ½ cubic foot is located immediately in front of the basin opening, or is blocking capacity of the basin by more than 10%. Additional details are provided at the end of this section.

### **Conveyance Pipes and Channels:**


Conveyance pipes and channels should be periodically checked and cleaned when more than 20% of the pipe diameter or channel depth is obstructed by accumulated sediment or debris.

### **Inspections:**

Perform inspections of all components quarterly during the first year of operation, then annually thereafter.

**APPENDIX A  
DOE FLOW CHART**

**Figure I-2.4.2 Flow Chart for Determining Requirements for Redevelopment**



**Figure I-2.4.2  
Flow Chart for Determining Requirements for  
Redevelopment**

Revised June 2015

Please see <http://www.ecy.wa.gov/copyright.html> for copyright notice including permissions, limitation of liability, and disclaimer.

**APPENDIX B**  
**MERCER ISLAND SMALL PROJECT STORMWATER REPORT**

Mercer Island small project stormwater report will be included with next submittal, if required.

**APPENDIX C  
WWHM2012 REPORT**

**WWHM2012**  
**PROJECT REPORT**



## General Model Information

WWHM2012 Project Name: 22109\_WELLMON FLOW CALCS\_230323

Site Name: WELLMON  
Site Address: 6333 77TH AVE SE  
City: MERCER ISLAND  
Report Date: 5/12/2023  
Gage: Seatac  
Data Start: 1948/10/01  
Data End: 2009/09/30  
Timestep: 15 Minute  
Precip Scale: 1.000  
Version Date: 2023/01/27  
Version: 4.2.19

## POC Thresholds

---

Low Flow Threshold for POC1:	50 Percent of the 2 Year
High Flow Threshold for POC1:	50 Year

---

## Landuse Basin Data

### Predeveloped Land Use

#### PREDEV

Bypass:	No
GroundWater:	No
Pervious Land Use	acre
C, Lawn, Mod	0.127
C, Lawn, Steep	0.149
Pervious Total	0.276
Impervious Land Use	acre
ROADS MOD	0.031
ROOF TOPS FLAT	0.11
SIDEWALKS FLAT	0.053
Impervious Total	0.194
Basin Total	0.47

## *Mitigated Land Use*

### DEVELOPED



Bypass:	No
GroundWater:	No
Pervious Land Use	acre
C, Pasture, Flat	0.14
C, Pasture, Mod	0.095
C, Pasture, Steep	0.069
Pervious Total	0.304
Impervious Land Use	acre
ROADS FLAT	0.055
ROOF TOPS FLAT	0.103
SIDEWALKS FLAT	0.008
Impervious Total	0.166
Basin Total	0.47

*Routing Elements*  
*Predeveloped Routing*

## *Mitigated Routing*

# Analysis Results

## POC 1



+ Predeveloped x Mitigated

### Predeveloped Landuse Totals for POC #1

Total Pervious Area: 0.276  
Total Impervious Area: 0.194

### Mitigated Landuse Totals for POC #1

Total Pervious Area: 0.304  
Total Impervious Area: 0.166

Flow Frequency Method: Log Pearson Type III 17B

### Flow Frequency Return Periods for Predeveloped. POC #1

Return Period	Flow(cfs)
2 year	0.101509
5 year	0.13956
10 year	0.167152
25 year	0.204825
50 year	0.234983
100 year	0.266981

### Flow Frequency Return Periods for Mitigated. POC #1

Return Period	Flow(cfs)
2 year	0.070817
5 year	0.09246
10 year	0.107856
25 year	0.128569
50 year	0.144941
100 year	0.162144

## Annual Peaks

### Annual Peaks for Predeveloped and Mitigated. POC #1

Year	Predeveloped	Mitigated
1949	0.157	0.100
1950	0.142	0.089
1951	0.092	0.066
1952	0.062	0.048
1953	0.065	0.049
1954	0.084	0.059
1955	0.090	0.064
1956	0.085	0.062
1957	0.113	0.077
1958	0.077	0.057

1959	0.066	0.054
1960	0.098	0.072
1961	0.088	0.064
1962	0.066	0.050
1963	0.093	0.062
1964	0.078	0.056
1965	0.118	0.076
1966	0.068	0.052
1967	0.141	0.089
1968	0.143	0.089
1969	0.109	0.067
1970	0.097	0.068
1971	0.115	0.078
1972	0.140	0.087
1973	0.058	0.047
1974	0.112	0.071
1975	0.117	0.080
1976	0.086	0.060
1977	0.081	0.054
1978	0.098	0.068
1979	0.119	0.090
1980	0.173	0.110
1981	0.102	0.073
1982	0.165	0.110
1983	0.106	0.076
1984	0.073	0.053
1985	0.101	0.068
1986	0.094	0.070
1987	0.118	0.088
1988	0.064	0.054
1989	0.085	0.067
1990	0.251	0.173
1991	0.188	0.116
1992	0.075	0.053
1993	0.057	0.043
1994	0.054	0.045
1995	0.087	0.064
1996	0.128	0.087
1997	0.105	0.074
1998	0.089	0.063
1999	0.230	0.128
2000	0.105	0.071
2001	0.094	0.069
2002	0.144	0.093
2003	0.127	0.082
2004	0.210	0.129
2005	0.092	0.067
2006	0.086	0.060
2007	0.228	0.149
2008	0.181	0.119
2009	0.116	0.082

### Ranked Annual Peaks

Ranked Annual Peaks for Predeveloped and Mitigated. POC #1

Rank	Predeveloped	Mitigated
1	0.2512	0.1732
2	0.2297	0.1492
3	0.2284	0.1287

4	0.2102	0.1283
5	0.1880	0.1186
6	0.1814	0.1163
7	0.1731	0.1105
8	0.1650	0.1100
9	0.1573	0.0999
10	0.1440	0.0929
11	0.1433	0.0902
12	0.1418	0.0890
13	0.1414	0.0890
14	0.1405	0.0887
15	0.1280	0.0883
16	0.1267	0.0867
17	0.1186	0.0867
18	0.1180	0.0824
19	0.1178	0.0819
20	0.1166	0.0801
21	0.1157	0.0776
22	0.1154	0.0773
23	0.1128	0.0764
24	0.1117	0.0763
25	0.1086	0.0741
26	0.1056	0.0734
27	0.1050	0.0718
28	0.1048	0.0714
29	0.1020	0.0705
30	0.1007	0.0700
31	0.0981	0.0688
32	0.0980	0.0682
33	0.0972	0.0678
34	0.0938	0.0678
35	0.0936	0.0675
36	0.0932	0.0670
37	0.0920	0.0667
38	0.0919	0.0659
39	0.0896	0.0642
40	0.0889	0.0638
41	0.0883	0.0637
42	0.0871	0.0631
43	0.0863	0.0623
44	0.0862	0.0622
45	0.0852	0.0604
46	0.0848	0.0599
47	0.0842	0.0591
48	0.0814	0.0571
49	0.0781	0.0565
50	0.0768	0.0539
51	0.0747	0.0538
52	0.0728	0.0536
53	0.0678	0.0534
54	0.0662	0.0527
55	0.0658	0.0516
56	0.0647	0.0504
57	0.0636	0.0492
58	0.0615	0.0477
59	0.0584	0.0467
60	0.0567	0.0447
61	0.0544	0.0430





## Duration Flows

The Facility PASSED

Flow(cfs)	Predev	Mit	Percentage	Pass/Fail
0.0508	1349	586	43	Pass
0.0526	1196	496	41	Pass
0.0545	1042	427	40	Pass
0.0563	928	371	39	Pass
0.0582	838	325	38	Pass
0.0601	748	284	37	Pass
0.0619	670	246	36	Pass
0.0638	608	215	35	Pass
0.0656	549	192	34	Pass
0.0675	494	173	35	Pass
0.0694	448	148	33	Pass
0.0712	424	134	31	Pass
0.0731	389	122	31	Pass
0.0749	356	111	31	Pass
0.0768	332	104	31	Pass
0.0787	305	93	30	Pass
0.0805	289	88	30	Pass
0.0824	270	81	30	Pass
0.0843	254	66	25	Pass
0.0861	234	57	24	Pass
0.0880	203	50	24	Pass
0.0898	187	45	24	Pass
0.0917	174	42	24	Pass
0.0936	160	38	23	Pass
0.0954	147	34	23	Pass
0.0973	140	28	20	Pass
0.0991	131	25	19	Pass
0.1010	124	22	17	Pass
0.1029	119	21	17	Pass
0.1047	110	20	18	Pass
0.1066	102	20	19	Pass
0.1084	97	19	19	Pass
0.1103	94	18	19	Pass
0.1122	90	16	17	Pass
0.1140	88	15	17	Pass
0.1159	85	12	14	Pass
0.1177	79	9	11	Pass
0.1196	71	7	9	Pass
0.1215	68	6	8	Pass
0.1233	64	6	9	Pass
0.1252	59	6	10	Pass
0.1271	54	5	9	Pass
0.1289	49	3	6	Pass
0.1308	46	2	4	Pass
0.1326	44	2	4	Pass
0.1345	43	2	4	Pass
0.1364	43	2	4	Pass
0.1382	41	2	4	Pass
0.1401	39	2	5	Pass
0.1419	35	2	5	Pass
0.1438	30	2	6	Pass
0.1457	29	2	6	Pass
0.1475	27	2	7	Pass

0.1494	27	1	3	Pass
0.1512	26	1	3	Pass
0.1531	25	1	4	Pass
0.1550	25	1	4	Pass
0.1568	23	1	4	Pass
0.1587	20	1	5	Pass
0.1605	19	1	5	Pass
0.1624	19	1	5	Pass
0.1643	19	1	5	Pass
0.1661	18	1	5	Pass
0.1680	18	1	5	Pass
0.1699	17	1	5	Pass
0.1717	17	1	5	Pass
0.1736	15	0	0	Pass
0.1754	15	0	0	Pass
0.1773	13	0	0	Pass
0.1792	13	0	0	Pass
0.1810	13	0	0	Pass
0.1829	12	0	0	Pass
0.1847	10	0	0	Pass
0.1866	9	0	0	Pass
0.1885	8	0	0	Pass
0.1903	8	0	0	Pass
0.1922	7	0	0	Pass
0.1940	7	0	0	Pass
0.1959	6	0	0	Pass
0.1978	5	0	0	Pass
0.1996	5	0	0	Pass
0.2015	5	0	0	Pass
0.2033	4	0	0	Pass
0.2052	4	0	0	Pass
0.2071	4	0	0	Pass
0.2089	4	0	0	Pass
0.2108	3	0	0	Pass
0.2127	3	0	0	Pass
0.2145	3	0	0	Pass
0.2164	3	0	0	Pass
0.2182	3	0	0	Pass
0.2201	3	0	0	Pass
0.2220	3	0	0	Pass
0.2238	3	0	0	Pass
0.2257	3	0	0	Pass
0.2275	3	0	0	Pass
0.2294	2	0	0	Pass
0.2313	1	0	0	Pass
0.2331	1	0	0	Pass
0.2350	1	0	0	Pass

## Water Quality

Water Quality BMP Flow and Volume for POC #1

On-line facility volume: 0 acre-feet

On-line facility target flow: 0 cfs.

Adjusted for 15 min: 0 cfs.

Off-line facility target flow: 0 cfs.

Adjusted for 15 min: 0 cfs.

# LID Report

LID Technique	Used for Treatment ?	Total Volume Needs Treatment (ac-ft)	Volume Through Facility (ac-ft)	Infiltration Volume (ac-ft)	Cumulative Volume Infiltration Credit	Percent Volume Infiltrated	Water Quality	Percent Water Quality Treated	Comment
Total Volume Infiltrated		0.00	0.00	0.00		0.00	0.00	0%	No Treat. Credit
Compliance with LID Standard 8% of 2-yr to 50% of 2-yr									Duration Analysis Result = Passed

## *Model Default Modifications*

Total of 0 changes have been made.


### *PERLND Changes*

No PERLND changes have been made.


### *IMPLND Changes*

No IMPLND changes have been made.

*Appendix*  
*Predeveloped Schematic*



Mitigated Schematic





# Predeveloped UCI File

RUN

GLOBAL

WVHM4 model simulation  
START 1948 10 01 END 2009 09 30  
RUN INTERP OUTPUT LEVEL 3 0  
RESUME 0 RUN 1 UNIT SYSTEM 1  
END GLOBAL

FILES

<File>	<Un#>	<-----File Name----->	***
<-ID->			***
WDM	26	22109_WELLMON FLOW CALCS_230323.wdm	
MESSU	25	Pre22109_WELLMON FLOW CALCS_230323.MES	
	27	Pre22109_WELLMON FLOW CALCS_230323.L61	
	28	Pre22109_WELLMON FLOW CALCS_230323.L62	
	30	POC22109_WELLMON FLOW CALCS_2303231.dat	

END FILES

OPN SEQUENCE

INGRP INDELT 00:15  
PERLND 17  
PERLND 18  
IMPLND 2  
IMPLND 4  
IMPLND 8  
COPY 501  
DISPLY 1  
END INGRP

END OPN SEQUENCE

DISPLY

DISPLY-INFO1

#	-	#	<-----Title----->	***	TRAN	PIVL	DIG1	FIL1	PYR	DIG2	FIL2	YRND
1			PREDEV		MAX				1	2	30	9

END DISPLY-INFO1

END DISPLY

COPY

TIMESERIES

#	-	#	NPT	NMN	***
1			1	1	
501			1	1	

END TIMESERIES

END COPY

GENER

OPCODE

#	#	OPCD	***

END OPCODE

PARM

#	#	K	***

END PARM

END GENER

PERLND

GEN-INFO

<PLS >	<-----Name----->	NBLKS	Unit-systems	Printer	***	
#	-	#	User	t-series	Engl Metr	***
			in	out		***
17	C, Lawn, Mod	1	1	1	27	0
18	C, Lawn, Steep	1	1	1	27	0

END GEN-INFO

\*\*\* Section PWATER\*\*\*

ACTIVITY

<PLS >	***** Active Sections *****													***	
#	-	#	ATMP	SNOW	PWAT	SED	PST	PWG	PQAL	MSTL	PEST	NITR	PHOS	TRAC	***
17			0	0	1	0	0	0	0	0	0	0	0	0	
18			0	0	1	0	0	0	0	0	0	0	0	0	

END ACTIVITY

```

PRINT-INFO
<PLS > ***** Print-flags ***** PIVL  PYR
# - # ATMP SNOW PWAT  SED  PST  PWG  PQAL MSTL PEST NITR PHOS TRAC  *****
17   0   0   4   0   0   0   0   0   0   0   0   0   0   1   9
18   0   0   4   0   0   0   0   0   0   0   0   0   0   1   9
END PRINT-INFO

```

```

PWAT-PARM1
<PLS > PWATER variable monthly parameter value flags ***
# - # CSNO RTOP UZFG  VCS  VUZ  VNN VIFW VIRC  VLE INFC  HWT ***
17   0   0   0   0   0   0   0   0   0   0   0   0
18   0   0   0   0   0   0   0   0   0   0   0   0
END PWAT-PARM1

```

```

PWAT-PARM2
<PLS > PWATER input info: Part 2          ***
# - # ***FOREST  LZSN  INFILT  LRSUR  SLSUR  KVARY  AGWRC
17   0           4.5   0.03   400    0.1    0.5    0.996
18   0           4.5   0.03   400    0.15   0.5    0.996
END PWAT-PARM2

```

```

PWAT-PARM3
<PLS > PWATER input info: Part 3          ***
# - # ***PETMAX  PETMIN  INFEXP  INFILD  DEEPFR  BASETP  AGWETP
17   0           0       2       2       0       0       0
18   0           0       2       2       0       0       0
END PWAT-PARM3

```

```

PWAT-PARM4
<PLS > PWATER input info: Part 4          ***
# - # CEPSC  UZSN  NSUR  INTFW  IRC  LZETP ***
17   0.1    0.25  0.25  6      0.5  0.25
18   0.1    0.15  0.25  6      0.3  0.25
END PWAT-PARM4

```

```

PWAT-STATE1
<PLS > *** Initial conditions at start of simulation
ran from 1990 to end of 1992 (pat 1-11-95) RUN 21 ***
# - # *** CEPS  SURS  UZS  IFWS  LZS  AGWS  GWVS
17   0       0     0     0     2.5  1     0
18   0       0     0     0     2.5  1     0
END PWAT-STATE1

```

END PERLND

IMPLND

```

GEN-INFO
<PLS ><-----Name----->  Unit-systems  Printer ***
# - # User t-series Engl Metr ***
in out
2   ROADS/MOD  1  1  1  27  0
4   ROOF TOPS/FLAT  1  1  1  27  0
8   SIDEWALKS/FLAT  1  1  1  27  0
END GEN-INFO
*** Section IWATER***

```

```

ACTIVITY
<PLS > ***** Active Sections *****
# - # ATMP SNOW IWAT  SLD  IWG IQAL  ***
2   0   0   1   0   0   0
4   0   0   1   0   0   0
8   0   0   1   0   0   0
END ACTIVITY

```

```

PRINT-INFO
<ILS > ***** Print-flags ***** PIVL  PYR
# - # ATMP SNOW IWAT  SLD  IWG IQAL  *****
2   0   0   4   0   0   4   1   9
4   0   0   4   0   0   0   1   9
8   0   0   4   0   0   0   1   9
END PRINT-INFO

```

```

IWAT-PARM1
<PLS > IWATER variable monthly parameter value flags ***
# - # CSNO RTOP VRS VNN RTLI ***
2 0 0 0 0 0
4 0 0 0 0 0
8 0 0 0 0 0
END IWAT-PARM1

```

```

IWAT-PARM2
<PLS > IWATER input info: Part 2 ***
# - # *** LSUR SLSUR NSUR RETSC
2 400 0.05 0.1 0.08
4 400 0.01 0.1 0.1
8 400 0.01 0.1 0.1
END IWAT-PARM2

```

```

IWAT-PARM3
<PLS > IWATER input info: Part 3 ***
# - # ***PETMAX PETMIN
2 0 0
4 0 0
8 0 0
END IWAT-PARM3

```

```

IWAT-STATE1
<PLS > *** Initial conditions at start of simulation
# - # *** RETS SURS
2 0 0
4 0 0
8 0 0
END IWAT-STATE1

```

END IMPLND

```

SCHEMATIC
<-Source-> <--Area--> <-Target-> MBLK ***
<Name> # <-factor-> <Name> # Tbl# ***
PREDEV***
PERLND 17 0.127 COPY 501 12
PERLND 17 0.127 COPY 501 13
PERLND 18 0.149 COPY 501 12
PERLND 18 0.149 COPY 501 13
IMPLND 2 0.031 COPY 501 15
IMPLND 4 0.11 COPY 501 15
IMPLND 8 0.053 COPY 501 15

```

\*\*\*\*\*Routing\*\*\*\*\*  
END SCHEMATIC

```

NETWORK
<-Volume-> <-Grp> <-Member-><--Mult-->Tran <-Target vols> <-Grp> <-Member-> ***
<Name> # <Name> # #<-factor->strg <Name> # # <Name> # # ***
COPY 501 OUTPUT MEAN 1 1 48.4 DISPLY 1 INPUT TIMSER 1

```

```

<-Volume-> <-Grp> <-Member-><--Mult-->Tran <-Target vols> <-Grp> <-Member-> ***
<Name> # <Name> # #<-factor->strg <Name> # # <Name> # # ***
END NETWORK

```

```

RCHRES
GEN-INFO
RCHRES Name Nexits Unit Systems Printer ***
# - #<-----><----> User T-series Engl Metr LKFG ***
in out ***
END GEN-INFO
*** Section RCHRES***

```

ACTIVITY

```

<PLS > ***** Active Sections *****
# - # HYFG ADFG CNFG HTFG SDFG GQFG OXFG NUFG PKFG PHFG ***
END ACTIVITY

PRINT-INFO
<PLS > ***** Print-flags ***** PIVL  PYR
# - # HYDR ADCA CONS HEAT  SED  GQL  OXRX NUTR PLNK PHCB PIVL  PYR  *****
END PRINT-INFO

HYDR-PARM1
RCHRES  Flags for each HYDR Section ***
# - # VC A1 A2 A3  ODFVFG for each *** ODGTFG for each  FUNCT for each
      FG FG FG FG  possible exit *** possible exit  possible exit
      * * * * * * * * * * * * * * * * * * * * * * * * * * * * * * * * * * *
END HYDR-PARM1

HYDR-PARM2
# - # FTABNO          LEN          DELTH          STCOR          KS          DB50          ***
<-----><-----><-----><-----><-----><-----><-----><-----> ***
END HYDR-PARM2

HYDR-INIT
RCHRES  Initial conditions for each HYDR section ***
# - # *** VOL          Initial value of COLIND          Initial value of OUTDGT
      *** ac-ft          for each possible exit          for each possible exit
<-----><----->          <-----><-----><-----><-----> *** <-----><-----><-----><----->
END HYDR-INIT
END RCHRES

SPEC-ACTIONS
END SPEC-ACTIONS
FTABLES
END FTABLES

EXT SOURCES
<-Volume-> <Member> SsysSgap<--Mult-->Tran <-Target vols> <-Grp> <-Member-> ***
<Name> # <Name> # tem strg<-factor->strg <Name> # # <Name> # # ***
WDM      2 PREC      ENGL      1          PERLND  1 999 EXTNL  PREC
WDM      2 PREC      ENGL      1          IMPLND  1 999 EXTNL  PREC
WDM      1 EVAP      ENGL      0.76     PERLND  1 999 EXTNL  PETINP
WDM      1 EVAP      ENGL      0.76     IMPLND  1 999 EXTNL  PETINP
END EXT SOURCES

EXT TARGETS
<-Volume-> <-Grp> <-Member-><--Mult-->Tran <-Volume-> <Member> Tsys Tgap Amd ***
<Name> #          <Name> # #<-factor->strg <Name> # <Name> tem strg strg***
COPY  501 OUTPUT MEAN  1 1          48.4     WDM  501 FLOW      ENGL      REPL
END EXT TARGETS

MASS-LINK
<Volume> <-Grp> <-Member-><--Mult-->          <Target>          <-Grp> <-Member->***
<Name> #          <Name> # #<-factor->          <Name>          <Name> # #***
MASS-LINK          12
PERLND  PWATER SURO          0.083333  COPY          INPUT  MEAN
END MASS-LINK          12

MASS-LINK          13
PERLND  PWATER IFWO          0.083333  COPY          INPUT  MEAN
END MASS-LINK          13

MASS-LINK          15
IMPLND  IWATER SURO          0.083333  COPY          INPUT  MEAN
END MASS-LINK          15

END MASS-LINK

END RUN

```

# Mitigated UCI File

RUN

GLOBAL

WVHM4 model simulation  
START 1948 10 01 END 2009 09 30  
RUN INTERP OUTPUT LEVEL 3 0  
RESUME 0 RUN 1 UNIT SYSTEM 1  
END GLOBAL

FILES

```
<File> <Un#> <-----File Name----->***  
<-ID-> ***  
WDM 26 22109_WELLMON FLOW CALCS_230323.wdm  
MESSU 25 Mit22109_WELLMON FLOW CALCS_230323.MES  
27 Mit22109_WELLMON FLOW CALCS_230323.L61  
28 Mit22109_WELLMON FLOW CALCS_230323.L62  
30 POC22109_WELLMON FLOW CALCS_2303231.dat
```

END FILES

OPN SEQUENCE

INGRP INDELT 00:15  
PERLND 13  
PERLND 14  
PERLND 15  
IMPLND 1  
IMPLND 4  
IMPLND 8  
COPY 501  
DISPLY 1

END INGRP

END OPN SEQUENCE

DISPLY

DISPLY-INFO1

```
# - #<-----Title----->***TRAN PIVL DIG1 FIL1 PYR DIG2 FIL2 YRND  
1 DEVELOPED MAX 1 2 30 9
```

END DISPLY-INFO1

END DISPLY

COPY

TIMESERIES

```
# - # NPT NMN ***  
1 1 1  
501 1 1
```

END TIMESERIES

END COPY

GENER

OPCODE

```
# # OPCD ***
```

END OPCODE

PARM

```
# # K ***
```

END PARM

END GENER

PERLND

GEN-INFO

```
<PLS ><-----Name----->NBLKS Unit-systems Printer ***  
# - # User t-series Engl Metr ***  
in out ***  
13 C, Pasture, Flat 1 1 1 1 27 0  
14 C, Pasture, Mod 1 1 1 1 27 0  
15 C, Pasture, Steep 1 1 1 1 27 0
```

END GEN-INFO

\*\*\* Section PWATER\*\*\*

ACTIVITY

```
<PLS > ***** Active Sections *****  
# - # ATMP SNOW PWAT SED PST PWG PQAL MSTL PEST NITR PHOS TRAC ***  
13 0 0 1 0 0 0 0 0 0 0 0 0  
14 0 0 1 0 0 0 0 0 0 0 0 0
```

15 0 0 1 0 0 0 0 0 0 0 0 0  
 END ACTIVITY

PRINT-INFO

<PLS > \*\*\*\*\* Print-flags \*\*\*\*\* PIVL PYR  
 # - # ATMP SNOW PWAT SED PST PWG PQAL MSTL PEST NITR PHOS TRAC \*\*\*\*\*  
 13 0 0 4 0 0 0 0 0 0 0 0 0 1 9  
 14 0 0 4 0 0 0 0 0 0 0 0 0 0 1 9  
 15 0 0 4 0 0 0 0 0 0 0 0 0 0 1 9  
 END PRINT-INFO

PWAT-PARM1

<PLS > PWATER variable monthly parameter value flags \*\*\*  
 # - # CSNO RTOP UZFG VCS VUZ VNN VIFW VIRC VLE INFC HWT \*\*\*  
 13 0 0 0 0 0 0 0 0 0 0 0  
 14 0 0 0 0 0 0 0 0 0 0 0  
 15 0 0 0 0 0 0 0 0 0 0 0  
 END PWAT-PARM1

PWAT-PARM2

<PLS > PWATER input info: Part 2 \*\*\*  
 # - # \*\*\*FOREST LZSN INFILT LSUR SLSUR KVARY AGWRC  
 13 0 4.5 0.06 400 0.05 0.5 0.996  
 14 0 4.5 0.06 400 0.1 0.5 0.996  
 15 0 4.5 0.06 400 0.15 0.5 0.996  
 END PWAT-PARM2

PWAT-PARM3

<PLS > PWATER input info: Part 3 \*\*\*  
 # - # \*\*\*PETMAX PETMIN INFEXP INFILD DEEPFR BASETP AGWETP  
 13 0 0 2 2 0 0 0  
 14 0 0 2 2 0 0 0  
 15 0 0 2 2 0 0 0  
 END PWAT-PARM3

PWAT-PARM4

<PLS > PWATER input info: Part 4 \*\*\*  
 # - # CEPSC UZSN NSUR INTFW IRC LZETP \*\*\*  
 13 0.15 0.4 0.3 6 0.5 0.4  
 14 0.15 0.4 0.3 6 0.5 0.4  
 15 0.15 0.25 0.3 6 0.3 0.4  
 END PWAT-PARM4

PWAT-STATE1

<PLS > \*\*\* Initial conditions at start of simulation  
 ran from 1990 to end of 1992 (pat 1-11-95) RUN 21 \*\*\*  
 # - # \*\*\* CEPS SURS UZS IFWS LZS AGWS GWVS  
 13 0 0 0 0 2.5 1 0  
 14 0 0 0 0 2.5 1 0  
 15 0 0 0 0 2.5 1 0  
 END PWAT-STATE1

END PERLND

IMPLND

GEN-INFO

<PLS ><-----Name-----> Unit-systems Printer \*\*\*  
 # - # User t-series Engl Metr \*\*\*  
 in out \*\*\*  
 1 ROADS/FLAT 1 1 1 27 0  
 4 ROOF TOPS/FLAT 1 1 1 27 0  
 8 SIDEWALKS/FLAT 1 1 1 27 0  
 END GEN-INFO

\*\*\* Section IWATER\*\*\*

ACTIVITY

<PLS > \*\*\*\*\* Active Sections \*\*\*\*\*  
 # - # ATMP SNOW IWAT SLD IWG IQAL \*\*\*  
 1 0 0 1 0 0 0  
 4 0 0 1 0 0 0  
 8 0 0 1 0 0 0

END ACTIVITY

PRINT-INFO

<ILS > ***** Print-flags ***** PIVL PYR										
#	-	#	ATMP	SNOW	IWAT	SLD	IWG	IQAL	*****	
1			0	0	4	0	0	4	1	9
4			0	0	4	0	0	0	1	9
8			0	0	4	0	0	0	1	9

END PRINT-INFO

IWAT-PARM1

<PLS > IWATER variable monthly parameter value flags ***								
#	-	#	CSNO	RTOP	VRS	VNN	RTL1	***
1			0	0	0	0	0	
4			0	0	0	0	0	
8			0	0	0	0	0	

END IWAT-PARM1

IWAT-PARM2

<PLS > IWATER input info: Part 2 ***							
#	-	#	***	LSUR	SLSUR	NSUR	RETSC
1				400	0.01	0.1	0.1
4				400	0.01	0.1	0.1
8				400	0.01	0.1	0.1

END IWAT-PARM2

IWAT-PARM3

<PLS > IWATER input info: Part 3 ***					
#	-	#	***	PETMAX	PETMIN
1				0	0
4				0	0
8				0	0

END IWAT-PARM3

IWAT-STATE1

<PLS > *** Initial conditions at start of simulation					
#	-	#	***	RETS	SURS
1				0	0
4				0	0
8				0	0

END IWAT-STATE1

END IMPLND

SCHEMATIC

<-Source->		<--Area-->		<-Target->	MBLK	***
<Name>	#	<-factor->		<Name>	#	Tbl#
DEVELOPED***						
PERLND	13		0.14	COPY	501	12
PERLND	13		0.14	COPY	501	13
PERLND	14		0.095	COPY	501	12
PERLND	14		0.095	COPY	501	13
PERLND	15		0.069	COPY	501	12
PERLND	15		0.069	COPY	501	13
IMPLND	1		0.055	COPY	501	15
IMPLND	4		0.103	COPY	501	15
IMPLND	8		0.008	COPY	501	15

\*\*\*\*\*Routing\*\*\*\*\*

END SCHEMATIC

NETWORK

<-Volume->	<-Grp>	<-Member->	<--Mult-->	Tran	<-Target	vols>	<-Grp>	<-Member->	***			
<Name>	#	<Name>	#	<-factor->	strg	<Name>	#	<Name>	#			
COPY	501	OUTPUT	MEAN	1	1	48.4		DISPLY	1	INPUT	TIMSER	1

<-Volume->	<-Grp>	<-Member->	<--Mult-->	Tran	<-Target	vols>	<-Grp>	<-Member->	***
<Name>	#	<Name>	#	<-factor->	strg	<Name>	#	<Name>	#

END NETWORK

RCHRES

GEN-INFO

RCHRES	Name	Nexits	Unit Systems	Printer	***
# - #	<-----><---->	User T-series	Engl Metr	LKFG	***
		in out			***

END GEN-INFO

\*\*\* Section RCHRES\*\*\*

ACTIVITY

<PLS > \*\*\*\*\* Active Sections \*\*\*\*\*

# - #	HYFG	ADFG	CNFG	HTFG	SDFG	GQFG	OXFG	NUFG	PKFG	PHFG	***
-------	------	------	------	------	------	------	------	------	------	------	-----

END ACTIVITY

PRINT-INFO

<PLS > \*\*\*\*\* Print-flags \*\*\*\*\* PIVL PYR

# - #	HYDR	ADCA	CONS	HEAT	SED	GQL	OXRX	NUTR	PLNK	PHCB	PIVL	PYR	*****
-------	------	------	------	------	-----	-----	------	------	------	------	------	-----	-------

END PRINT-INFO

HYDR-PARM1

RCHRES Flags for each HYDR Section \*\*\*

# - #	VC	A1	A2	A3	ODFVFG	for each	***	ODGTFG	for each	FUNCT	for each
	FG	FG	FG	FG	possible	exit	***	possible	exit	possible	exit
	*	*	*	*	*	*	*	*	*	*	*

END HYDR-PARM1

HYDR-PARM2

# - #	FTABNO	LEN	DELTH	STCOR	KS	DB50	***
<-----><-----><-----><-----><-----><-----><----->							***

END HYDR-PARM2

HYDR-INIT

RCHRES Initial conditions for each HYDR section \*\*\*

# - #	***	VOL	Initial value of	COLIND	Initial value of	OUTDGT
	***	ac-ft	for each possible	exit	for each possible	exit

END HYDR-INIT

END RCHRES

SPEC-ACTIONS

END SPEC-ACTIONS

FTABLES

END FTABLES

EXT SOURCES

<-Volume->	<Member>	SsysSgap	<--Mult-->	Tran	<-Target vols>	<-Grp>	<-Member->	***
<Name>	#	<Name>	#	tem strg	<-factor->	strg	<Name>	# # ***
WDM	2	PREC	ENGL	1	PERLND	1 999	EXTNL	PREC
WDM	2	PREC	ENGL	1	IMPLND	1 999	EXTNL	PREC
WDM	1	EVAP	ENGL	0.76	PERLND	1 999	EXTNL	PETINP
WDM	1	EVAP	ENGL	0.76	IMPLND	1 999	EXTNL	PETINP

END EXT SOURCES

EXT TARGETS

<-Volume->	<-Grp>	<-Member->	<--Mult-->	Tran	<-Volume->	<Member>	Tsys	Tgap	Amd	***
<Name>	#	<Name>	#	#<-factor->	strg	<Name>	#	<Name>	tem strg	strg***
COPY	1	OUTPUT	MEAN	1 1	48.4	WDM	701	FLOW	ENGL	REPL
COPY	501	OUTPUT	MEAN	1 1	48.4	WDM	801	FLOW	ENGL	REPL

END EXT TARGETS

MASS-LINK

<Volume>	<-Grp>	<-Member->	<--Mult-->	<Target>	<-Grp>	<-Member->	***
<Name>		<Name>	#	#<-factor->	<Name>	<Name>	# #***
MASS-LINK			12				
PERLND	PWATER	SURO	0.083333	COPY	INPUT	MEAN	

END MASS-LINK

MASS-LINK

PERLND	PWATER	IFWO	0.083333	COPY	INPUT	MEAN
--------	--------	------	----------	------	-------	------



END MASS-LINK 13  
MASS-LINK 15  
IMPLND IWATER SURO 0.083333 COPY INPUT MEAN  
END MASS-LINK 15

END MASS-LINK

END RUN

*Predeveloped HSPF Message File*

*Mitigated HSPF Message File*

## *Disclaimer*

### *Legal Notice*

This program and accompanying documentation are provided 'as-is' without warranty of any kind. The entire risk regarding the performance and results of this program is assumed by End User. Clear Creek Solutions Inc. and the governmental licensee or sublicensees disclaim all warranties, either expressed or implied, including but not limited to implied warranties of program and accompanying documentation. In no event shall Clear Creek Solutions Inc. be liable for any damages whatsoever (including without limitation to damages for loss of business profits, loss of business information, business interruption, and the like) arising out of the use of, or inability to use this program even if Clear Creek Solutions Inc. or their authorized representatives have been advised of the possibility of such damages. Software Copyright © by : Clear Creek Solutions, Inc. 2005-2023; All Rights Reserved.

Clear Creek Solutions, Inc.  
6200 Capitol Blvd. Ste F  
Olympia, WA. 98501  
Toll Free 1(866)943-0304  
Local (360)943-0304

[www.clearcreeksolutions.com](http://www.clearcreeksolutions.com)

## **APPENDIX D GEOTECH REPORT**

Geotechnical Report provided by Cobalt Geosciences, dated December 16, 2022.



December 16, 2022

Nick and Lindsey Wellmon  
C/O Matt Mamiya  
Lochwood Lozier

**RE: Geotechnical Evaluation**  
Proposed Residence  
6333 77<sup>th</sup> Avenue SE  
Mercer Island, Washington

In accordance with your authorization, Cobalt Geosciences, LLC has prepared this letter to discuss the results of our geotechnical evaluation at the referenced site.

The purpose of our evaluation was to provide recommendations for foundation design, grading, and earthwork.

### **Site Description**

The site is located at 6333 77<sup>th</sup> Avenue SE in Mercer Island, Washington. The site consists of one nearly rectangular parcel (No. 4097100010) with an area of about 21,100 square feet.

The east-central portion of the site is developed with a residence with daylight basement areas and driveway. There are local rockery walls along and near the north and west property lines. These walls are about 2 to 8 feet in height and are locally terraced on the north side of the property to the west. The north wall faces south and the west walls face west.

The site is vegetated with grasses, bushes, and variable diameter evergreen and deciduous trees. The site slopes downward from east to west at magnitudes of 10 to 30 percent and relief of about 42 feet. There are numerous block and cobble/rockery walls west of the residence. These walls are mostly 1 to 3 feet in height and are located at grade breaks. There is a 2 to 3 feet tall cobble with mortar wall at the shoreline.

The site is bordered to the north and south by residential properties, to the west by Lake Washington, and to the east by 77<sup>th</sup> Avenue SE.

The proposed development includes a new residence and driveway. Stormwater will include infiltration or other systems depending on feasibility.

Site grading may include cuts and fills of 10 feet or less for basement placement and foundation loads are expected to be light. We should be provided with the final plans to verify that our recommendations remain valid and do not require updating.

### **Area Geology**

The Geologic Map of Mercer Island, indicates that the site is near the contacts between Pre-Olympia Glacial Drift and Lake Deposits.

The drift typically includes silty-sands with minor gravel. These deposits generally become denser with depth below a weathered zone. Lake deposits include loose or soft silts near margins of larger bodies of water, where erosion and deposition often occur.

## Soil & Groundwater Conditions

As part of our evaluation, we excavated two hand borings within the property, where accessible.

The explorations encountered approximately 6 inches of grass and topsoil underlain by approximately 3.5 to 4.5 feet of loose to medium dense, silty-fine to medium grained sand trace gravel (Weathered Pre-Olympia Glacial Drift). These materials were underlain by medium dense to dense, silty-fine to medium grained sand trace gravel (Pre-Olympia Glacial Drift) which continued to the termination depths of the explorations.

Groundwater was observed approximately 4 feet below grade in HB-2. Groundwater was not encountered in HB-1. We anticipate that groundwater would be present at or just above lake elevations.

We reviewed numerous explorations from the property to the north. These explorations encountered fill, weathered drift/till, and unweathered drift/till approximately 5 to 8 feet below grade. Groundwater was noted at shallow depths in their explorations closer to the lake.

Water table elevations often fluctuate over time. The groundwater level will depend on a variety of factors that may include seasonal precipitation, irrigation, land use, climatic conditions and soil permeability. Water levels at the time of the field investigation may be different from those encountered during the construction phase of the project.

## City of Mercer Island GIS Mapped Hazards

The City of Mercer Island GIS maps indicate that the site contains erosion hazard areas. There are local seismic hazard areas mapped in the western quarter of the property.

The erosion hazard designation is likely due to the presence of slopes with magnitudes over 15 percent. The liquefaction/seismic hazard designation is likely due to the possible presence of lake deposits near the shoreline. We did not observe evidence of lake deposits except for at the shoreline, where development is not proposed.

Overall, the site areas appear stable at this time with no evidence of recent or ongoing erosion or landslide activity. It is our opinion that the proposed development can be completed without adversely affecting erosion or seismic hazards on the property or adjacent areas.

## Statement of Risk

Per Section 19.07.160B3 of the Mercer Island City Code, development within geologic hazard areas require that a Geotechnical Engineer licensed within the State of Washington provide a statement of risk with supporting documentation indicating that one of the following conditions can be met:

- a. The geologic hazard area will be modified, or the development has been designed so that the risk to the lot and adjacent property is eliminated or mitigated such that the site is determined to be safe; or
- b. An evaluation of site specific subsurface conditions demonstrates that the proposed development is not located in a geologic hazard area; or
- c. Development practices are proposed for the alteration that would render the development as safe as if it were not located in a geologic hazard area; or
- d. The alteration is so minor as not to pose a threat to the public health, safety and welfare.

The project meets the criteria of b and c from above.

The site soil and topographic conditions are not consistent with the mapped geologic hazards. The risk of erosion is very low at this site and will remain low with installation of proper temporary erosion control systems followed by permanent landscaping.

### Erosion Hazard

The Natural Resources Conservation Services (NRCS) maps for King County indicate that the site is underlain by Kitsap silt loam (2 to 8 percent slopes). These soils would have a slight to moderate erosion potential in a disturbed state depending on the slope magnitude.

It is our opinion that soil erosion potential at this project site can be reduced through landscaping and surface water runoff control. Typically, erosion of exposed soils will be most noticeable during periods of rainfall and may be controlled by the use of normal temporary erosion control measures, such as silt fences, hay bales, mulching, control ditches and diversion trenches. The typical wet weather season, with regard to site grading, is from October 31<sup>st</sup> to April 1<sup>st</sup>. Erosion control measures should be in place before the onset of wet weather.

### Seismic Hazard

The overall subsurface profile corresponds to a Site Class *D* as defined by Table 1613.5.2 of the International Building Code (IBC). A Site Class *D* applies to an overall profile consisting of stiff/medium dense soils within the upper 100 feet.

We referenced the U.S. Geological Survey (USGS) Earthquake Hazards Program Website to obtain values for  $S_s$ ,  $S_t$ ,  $F_a$ , and  $F_v$ . The USGS website includes the most updated published data on seismic conditions. The following tables provide seismic parameters from the USGS web site with referenced parameters from ASCE 7-16.

Seismic Design Parameters (ASCE 7-16)

Site Class	Spectral Acceleration at 0.2 sec. (g)	Spectral Acceleration at 1.0 sec. (g)	Site Coefficients		Design Spectral Response Parameters		Design PGA
			$F_a$	$F_v$	$S_{DS}$	$S_{D1}$	
D	1.47	0.509	1.0	Null	0.98	Null	0.63

Additional seismic considerations include liquefaction potential and amplification of ground motions by soft/loose soil deposits. The liquefaction potential is highest for loose sand with a high groundwater table. The site has a relatively low likelihood of liquefaction. For items listed as “Null” see Section 11.4.8 of the ASCE.



## Conclusions and Recommendations

---

### General

The site is underlain by soils consistent with Pre-Olympia Glacial Drift. These soils become relatively dense below a thin weathered zone. The proposed residential structure may be supported on a shallow foundation system bearing on medium dense or firmer native soils or on structural fill placed on the native soils. Local overexcavation or recompaction of loose weathered native soils may be necessary depending on the proposed elevations and locations of the new footings.

Infiltration is not feasible due to the presence of dense, fine grained soils at shallow depths and shallow groundwater, particularly in the lower elevation portions of the site. In general, dispersion systems and permeable pavements are feasible in the upper, weathered drift above the groundwater. In general, we recommend direct or perforated connection of runoff devices to City infrastructure.

### Site Preparation

Trees, shrubs and other vegetation should be removed prior to stripping of surficial organic-rich soil and fill. Based on observations from the site investigation program, it is anticipated that the stripping depth will be 6 to 12 inches. Deeper excavations will be necessary below larger trees and in any areas where fill is present.

The native soils consist of silty-sand with gravel. Most of the native soils may be used as structural fill provided they achieve compaction requirements and are within 3 percent of the optimum moisture. Some of these soils may only be suitable for use as fill during the summer months, as they will be above the optimum moisture levels in their current state. These soils are variably moisture sensitive and may degrade during periods of wet weather and under equipment traffic.

Imported structural fill should consist of a sand and gravel mixture with a maximum grain size of 3 inches and less than 5 percent fines (material passing the U.S. Standard No. 200 Sieve). Structural fill should be placed in maximum lift thicknesses of 12 inches and should be compacted to a minimum of 95 percent of the modified proctor maximum dry density, as determined by the ASTM D 1557 test method.

### Temporary Excavations

Based on our understanding of the project, we anticipate that the grading could include local cuts on the order of approximately 10 feet or less for foundation and utility placement. Temporary excavations should be sloped no steeper than 1.5H:1V (Horizontal:Vertical) in loose native soils and fill, 1H:1V in medium dense native soils and 3/4H:1V in dense to very dense native soils (if encountered at greater depths). If an excavation is subject to heavy vibration or surcharge loads, we recommend that the excavations be sloped no steeper than 2H:1V, where room permits.

Temporary cuts should be in accordance with the Washington Administrative Code (WAC) Part N, Excavation, Trenching, and Shoring. Temporary slopes should be visually inspected daily by a qualified person during construction activities and the inspections should be documented in daily reports. The contractor is responsible for maintaining the stability of the temporary cut slopes and reducing slope erosion during construction.

Temporary cut slopes should be covered with visqueen to help reduce erosion during wet weather, and the slopes should be closely monitored until the permanent retaining systems or slope configurations are complete. Materials should not be stored or equipment operated within 10 feet of the top of any temporary cut slope.

Soil conditions may not be completely known from the geotechnical investigation. In the case of temporary cuts, the existing soil conditions may not be completely revealed until the excavation work exposes the soil. Typically, as excavation work progresses the maximum inclination of temporary slopes will need to be re-evaluated by the geotechnical engineer so that supplemental recommendations can be made. Soil and groundwater conditions can be highly variable. Scheduling for soil work will need to be adjustable, to deal with unanticipated conditions, so that the project can proceed and required deadlines can be met.

If any variations or undesirable conditions are encountered during construction, we should be notified so that supplemental recommendations can be made. If room constraints or groundwater conditions do not permit temporary slopes to be cut to the maximum angles allowed by the WAC, temporary shoring systems may be required. The contractor should be responsible for developing temporary shoring systems, if needed. We recommend that Cobalt Geosciences and the project structural engineer review temporary shoring designs prior to installation, to verify the suitability of the proposed systems.

### **Foundation Design**

The proposed residence may be supported on a shallow spread footing foundation system bearing on undisturbed medium dense or firmer native soils or on properly compacted structural fill placed on the suitable native soils. Any undocumented fill and/or loose native soils should be removed and replaced with structural fill below foundation elements. Structural fill below footings should consist of clean angular rock 5/8 to 4 inches in size. We should verify soil conditions during foundation excavation work.

For shallow foundation support, we recommend widths of at least 16 and 24 inches, respectively, for continuous wall and isolated column footings supporting the proposed structure. Provided that the footings are supported as recommended above, a net allowable bearing pressure of 2,500 pounds per square foot (psf) may be used for design.

A 1/3 increase in the above value may be used for short duration loads, such as those imposed by wind and seismic events. Structural fill placed on bearing, native subgrade should be compacted to at least 95 percent of the maximum dry density based on ASTM Test Method D1557. Footing excavations should be inspected to verify that the foundations will bear on suitable material.

Exterior footings should have a minimum depth of 18 inches below pad subgrade (soil grade) or adjacent exterior grade, whichever is lower. Interior footings should have a minimum depth of 12 inches below pad subgrade (soil grade) or adjacent exterior grade, whichever is lower.

If constructed as recommended, the total foundation settlement is not expected to exceed 1 inch. Differential settlement, along a 25-foot exterior wall footing, or between adjoining column footings, should be less than 1/2 inch. This translates to an angular distortion of 0.002. Most settlement is expected to occur during construction, as the loads are applied. However, additional post-construction settlement may occur if the foundation soils are flooded or saturated. All footing excavations should be observed by a qualified geotechnical consultant.

Resistance to lateral footing displacement can be determined using an allowable friction factor of 0.40 acting between the base of foundations and the supporting subgrades. Lateral resistance for footings can also be developed using an allowable equivalent fluid passive pressure of 250 pounds per cubic foot (pcf) acting against the appropriate vertical footing faces (neglect the upper 12 inches below grade in exterior areas). The frictional and passive resistance of the soil may be combined without reduction in determining the total lateral resistance.

Care should be taken to prevent wetting or drying of the bearing materials during construction. Any extremely wet or dry materials, or any loose or disturbed materials at the bottom of the footing excavations, should be removed prior to placing concrete. The potential for wetting or drying of the bearing materials can be reduced by pouring concrete as soon as possible after completing the footing excavation and evaluating the bearing surface by the geotechnical engineer or his representative.

### Concrete Retaining Walls

The following table, titled **Wall Design Criteria**, presents the recommended soil related design parameters for retaining walls with a level backslope. Contact Cobalt if an alternate retaining wall system is used. This has been included for new cast in place walls, if any are proposed.

<b>Wall Design Criteria</b>	
“At-rest” Conditions (Lateral Earth Pressure – EFD <sup>+</sup> )	55 pcf (Equivalent Fluid Density)
“Active” Conditions (Lateral Earth Pressure – EFD <sup>+</sup> )	35 pcf (Equivalent Fluid Density)
Seismic Increase for “At-rest” Conditions (Lateral Earth Pressure)	21H* (Uniform Distribution) 1 in 2,500 year event
Seismic Increase for “At-rest” Conditions (Lateral Earth Pressure)	14H* (Uniform Distribution) 1 in 500 year event
Seismic Increase for “Active” Conditions (Lateral Earth Pressure)	7H* (Uniform Distribution)
Passive Earth Pressure on Low Side of Wall (Allowable, includes F.S. = 1.5)	Neglect upper 2 feet, then 275 pcf EFD <sup>+</sup>
Soil-Footing Coefficient of Sliding Friction (Allowable; includes F.S. = 1.5)	0.40

\*H is the height of the wall; Increase based on one in 500 year seismic event (10 percent probability of being exceeded in 50 years),

+EFD – Equivalent Fluid Density

The stated lateral earth pressures do not include the effects of hydrostatic pressure generated by water accumulation behind the retaining walls. Uniform horizontal lateral active and at-rest pressures on the retaining walls from vertical surcharges behind the wall may be calculated using active and at-rest lateral earth pressure coefficients of 0.3 and 0.5, respectively. A soil unit weight of 125 pcf may be used to calculate vertical earth surcharges.

To reduce the potential for the buildup of water pressure against the walls, continuous footing drains (with cleanouts) should be provided at the bases of the walls. The footing drains should consist of a minimum 4-inch diameter perforated pipe, sloped to drain, with perforations placed down and enveloped by a minimum 6 inches of pea gravel in all directions.

The backfill adjacent to and extending a lateral distance behind the walls at least 2 feet should consist of free-draining granular material. All free draining backfill should contain less than 3 percent fines (passing the U.S. Standard No. 200 Sieve) based upon the fraction passing the U.S. Standard No. 4 Sieve with at least 30 percent of the material being retained on the U.S. Standard No. 4 Sieve. The primary purpose of the free-draining material is the reduction of hydrostatic pressure. Some potential for the moisture to contact the back face of the wall may exist, even with treatment, which may require that more extensive waterproofing be specified for walls, which require interior moisture sensitive finishes.

We recommend that the backfill be compacted to at least 90 percent of the maximum dry density based on ASTM Test Method D1557. In place density tests should be performed to verify adequate compaction. Soil compactors place transient surcharges on the backfill. Consequently, only light hand operated equipment is recommended within 3 feet of walls so that excessive stress is not imposed on the walls.

### **Stormwater Management Feasibility**

The site is underlain by weathered to unweathered glacial drift or till which becomes denser with depth. These soils were mottled and we observed groundwater at shallow depths near Lake Washington. Infiltration is not feasible or recommended in these areas. There is inadequate clearance above the groundwater table. Based on nearby explorations by others, groundwater could be within 2 feet of the ground surface in lower elevation areas.

Dispersion trenches and permeable pavements are generally feasible depending on their locations and elevations. In general, we recommend direct or perforated connection of runoff collection devices to City infrastructure. If allowed, it may be possible to disperse or overflow into Lake Washington.

We should be provided with final plans for review to determine if the intent of our recommendations has been incorporated or if additional modifications are needed.

### **Slab-on-Grade**

We recommend that the upper 18 inches of the existing native soils within slab areas be re-compacted to at least 95 percent of the modified proctor (ASTM D1557 Test Method).

Often, a vapor barrier is considered below concrete slab areas. However, the usage of a vapor barrier could result in curling of the concrete slab at joints. Floor covers sensitive to moisture typically requires the usage of a vapor barrier. A materials or structural engineer should be consulted regarding the detailing of the vapor barrier below concrete slabs. Exterior slabs typically do not utilize vapor barriers.

The American Concrete Institutes ACI 360R-06 Design of Slabs on Grade and ACI 302.1R-04 Guide for Concrete Floor and Slab Construction are recommended references for vapor barrier selection and floor slab detailing.

Slabs on grade may be designed using a coefficient of subgrade reaction of 210 pounds per cubic inch (pci) assuming the slab-on-grade base course is underlain by structural fill placed and compacted as outlined above. A 4- to 6-inch-thick capillary break layer should be placed over the prepared subgrade. This material should consist of pea gravel or 5/8 inch clean angular rock.

A perimeter drainage system is recommended unless interior slab areas are elevated a minimum of 12 inches above adjacent exterior grades. If installed, a perimeter drainage system should consist of a 4-inch diameter perforated drain pipe surrounded by a minimum 6 inches of drain rock wrapped in a non-woven geosynthetic filter fabric to reduce migration of soil particles into the drainage system. The perimeter drainage system should discharge by gravity flow to a suitable stormwater system.

Exterior grades surrounding buildings should be sloped at a minimum of one percent to facilitate surface water flow away from the building and preferably with a relatively impermeable surface cover immediately adjacent to the building.

### **Erosion and Sediment Control**

Erosion and sediment control (ESC) is used to reduce the transportation of eroded sediment to wetlands, streams, lakes, drainage systems, and adjacent properties. Erosion and sediment control measures should be implemented, and these measures should be in general accordance with local regulations. At a minimum, the following basic recommendations should be incorporated into the design of the erosion and sediment control features for the site:

- Schedule the soil, foundation, utility, and other work requiring excavation or the disturbance of the site soils, to take place during the dry season (generally May through September). However, provided precautions are taken using Best Management Practices (BMP's), grading activities can be completed during the wet season (generally October through April).
- All site work should be completed and stabilized as quickly as possible.
- Additional perimeter erosion and sediment control features may be required to reduce the possibility of sediment entering the surface water. This may include additional silt fences, silt fences with a higher Apparent Opening Size (AOS), construction of a berm, or other filtration systems.
- Any runoff generated by dewatering discharge should be treated through construction of a sediment trap if there is sufficient space. If space is limited other filtration methods will need to be incorporated.

### **Utilities**

Utility trenches should be excavated according to accepted engineering practices following OSHA (Occupational Safety and Health Administration) standards, by a contractor experienced in such work. The contractor is responsible for the safety of open trenches. Traffic and vibration adjacent to trench walls should be reduced; cyclic wetting and drying of excavation side slopes should be avoided. Depending upon the location and depth of some utility trenches, groundwater flow into open excavations could be experienced, especially during or shortly following periods of precipitation.

In general, sandy soils were encountered at shallow depths in the explorations at this site. These soils have low cohesion and density and will have a tendency to cave or slough in excavations. Shoring or sloping back trench sidewalls is required within these soils in excavations greater than 4 feet deep.

All utility trench backfill should consist of imported structural fill or suitable on site soils. Utility trench backfill placed in or adjacent to buildings and exterior slabs should be compacted to at least 95 percent of the maximum dry density based on ASTM Test Method D1557. The upper 5 feet of utility trench backfill placed in pavement areas should be compacted to at least 95 percent of the maximum dry density based on ASTM Test Method D1557. Below 5 feet, utility trench backfill in pavement areas should be compacted to at least 90 percent of the maximum dry density based on ASTM Test Method D1557. Pipe bedding should be in accordance with the pipe manufacturer's recommendations.

The contractor is responsible for removing all water-sensitive soils from the trenches regardless of the backfill location and compaction requirements. Depending on the depth and location of the proposed utilities, we anticipate the need to re-compact existing fill soils below the utility structures and pipes. The contractor should use appropriate equipment and methods to avoid damage to the utilities and/or structures during fill placement and compaction procedures.

### **CONSTRUCTION FIELD REVIEWS**

Cobalt Geosciences should be retained to provide part time field review during construction in order to verify that the soil conditions encountered are consistent with our design assumptions and that the intent of our recommendations is being met. This will require field and engineering review to:

- Monitor and test structural fill placement and soil compaction
- Observe bearing capacity at foundation locations
- Observe slab-on-grade preparation
- Monitor foundation drainage placement
- Observe excavation stability

Geotechnical design services should also be anticipated during the subsequent final design phase to support the structural design and address specific issues arising during this phase. Field and engineering review services will also be required during the construction phase in order to provide a Final Letter for the project.

### **CLOSURE**

This report was prepared for the exclusive use of Nick and Lindsey Wellmon and their appointed consultants. Any use of this report or the material contained herein by third parties, or for other than the intended purpose, should first be approved in writing by Cobalt Geosciences, LLC.

The recommendations contained in this report are based on assumed continuity of soils with those of our test holes and assumed structural loads. Cobalt Geosciences should be provided with final architectural and civil drawings when they become available in order that we may review our design recommendations and advise of any revisions, if necessary.

Use of this report is subject to the Statement of General Conditions provided in Appendix A. It is the responsibility of Nick and Lindsey Wellmon who is identified as "the Client" within the Statement of General Conditions, and its agents to review the conditions and to notify Cobalt Geosciences should any of these not be satisfied.

Sincerely,

**Cobalt Geosciences, LLC**



12/16/2022  
Phil Haberman, PE, LG, LEG  
Principal

### **Statement of General Conditions**

**USE OF THIS REPORT:** This report has been prepared for the sole benefit of the Client or its agent and may not be used by any third party without the express written consent of Cobalt Geosciences and the Client. Any use which a third party makes of this report is the responsibility of such third party.

**BASIS OF THE REPORT:** The information, opinions, and/or recommendations made in this report are in accordance with Cobalt Geosciences present understanding of the site specific project as described by the Client. The applicability of these is restricted to the site conditions encountered at the time of the investigation or study. If the proposed site specific project differs or is modified from what is described in this report or if the site conditions are altered, this report is no longer valid unless Cobalt Geosciences is requested by the Client to review and revise the report to reflect the differing or modified project specifics and/or the altered site conditions.


**STANDARD OF CARE:** Preparation of this report, and all associated work, was carried out in accordance with the normally accepted standard of care in the state of execution for the specific professional service provided to the Client. No other warranty is made.

**INTERPRETATION OF SITE CONDITIONS:** Soil, rock, or other material descriptions, and statements regarding their condition, made in this report are based on site conditions encountered by Cobalt Geosciences at the time of the work and at the specific testing and/or sampling locations. Classifications and statements of condition have been made in accordance with normally accepted practices which are judgmental in nature; no specific description should be considered exact, but rather reflective of the anticipated material behavior. Extrapolation of in situ conditions can only be made to some limited extent beyond the sampling or test points. The extent depends on variability of the soil, rock and groundwater conditions as influenced by geological processes, construction activity, and site use.

**VARYING OR UNEXPECTED CONDITIONS:** Should any site or subsurface conditions be encountered that are different from those described in this report or encountered at the test locations, Cobalt Geosciences must be notified immediately to assess if the varying or unexpected conditions are substantial and if reassessments of the report conclusions or recommendations are required. Cobalt Geosciences will not be responsible to any party for damages incurred as a result of failing to notify Cobalt Geosciences that differing site or sub-surface conditions are present upon becoming aware of such conditions.

**PLANNING, DESIGN, OR CONSTRUCTION:** Development or design plans and specifications should be reviewed by Cobalt Geosciences, sufficiently ahead of initiating the next project stage (property acquisition, tender, construction, etc), to confirm that this report completely addresses the elaborated project specifics and that the contents of this report have been properly interpreted. Specialty quality assurance services (field observations and testing) during construction are a necessary part of the evaluation of sub-subsurface conditions and site preparation works. Site work relating to the recommendations included in this report should only be carried out in the presence of a qualified geotechnical engineer; Cobalt Geosciences cannot be responsible for site work carried out without being present.





**HB-1** Approximate Hand Boring Location



**King County Imap**


Not to Scale



Proposed Residence  
6333 77th Avenue SE  
Mercer Island, Washington

**SITE MAPS**  
**FIGURE 1**

Cobalt Geosciences, LLC  
P.O. Box 82243  
Kenmore, WA 98028  
(206) 331-1097  
[www.cobaltgeo.com](http://www.cobaltgeo.com)  
[cobaltgeo@gmail.com](mailto:cobaltgeo@gmail.com)



Not to Scale



Typical Foundation Drain Detail

Attachment

Cobalt Geosciences, LLC  
 PO Box 1792  
 North Bend, WA 98045  
 (206) 331-1097  
[www.cobaltgeo.com](http://www.cobaltgeo.com)  
[phil@cobaltgeo.com](mailto:phil@cobaltgeo.com)

## Unified Soil Classification System (USCS)

MAJOR DIVISIONS			SYMBOL	TYPICAL DESCRIPTION		
<b>COARSE GRAINED SOILS</b> (more than 50% retained on No. 200 sieve)	Gravels (more than 50% of coarse fraction retained on No. 4 sieve)	Clean Gravels (less than 5% fines)	GW	Well-graded gravels, gravels, gravel-sand mixtures, little or no fines		
		Gravels with Fines (more than 12% fines)	GP	Poorly graded gravels, gravel-sand mixtures, little or no fines		
		Gravels with Fines (more than 12% fines)	GM	Silty gravels, gravel-sand-silt mixtures		
		Gravels with Fines (more than 12% fines)	GC	Clayey gravels, gravel-sand-clay mixtures		
	Sands (50% or more of coarse fraction passes the No. 4 sieve)	Clean Sands (less than 5% fines)	SW	Well-graded sands, gravelly sands, little or no fines		
		Sands with Fines (more than 12% fines)	SP	Poorly graded sand, gravelly sands, little or no fines		
		Sands with Fines (more than 12% fines)	SM	Silty sands, sand-silt mixtures		
		Sands with Fines (more than 12% fines)	SC	Clayey sands, sand-clay mixtures		
		<b>FINE GRAINED SOILS</b> (50% or more passes the No. 200 sieve)	Silts and Clays (liquid limit less than 50)	Inorganic	ML	Inorganic silts of low to medium plasticity, sandy silts, gravelly silts, or clayey silts with slight plasticity
				Inorganic	CL	Inorganic clays of low to medium plasticity, gravelly clays, sandy clays, silty clays, lean clays
Silts and Clays (liquid limit 50 or more)	Organic		OL	Organic silts and organic silty clays of low plasticity		
	Inorganic		MH	Inorganic silts, micaceous or diatomaceous fine sands or silty soils, elastic silt		
	Inorganic		CH	Inorganic clays of medium to high plasticity, sandy fat clay, or gravelly fat clay		
Organic	OH	Organic clays of medium to high plasticity, organic silts				
<b>HIGHLY ORGANIC SOILS</b>	Primarily organic matter, dark in color, and organic odor	PT	Peat, humus, swamp soils with high organic content (ASTM D4427)			

Classification of Soil Constituents
<p>MAJOR constituents compose more than 50 percent, by weight, of the soil. Major constituents are capitalized (i.e., SAND).</p> <p>Minor constituents compose 12 to 50 percent of the soil and precede the major constituents (i.e., silty SAND). Minor constituents preceded by "slightly" compose 5 to 12 percent of the soil (i.e., slightly silty SAND).</p> <p>Trace constituents compose 0 to 5 percent of the soil (i.e., slightly silty SAND, trace gravel).</p>

Grain Size Definitions	
Description	Sieve Number and/or Size
Fines	< #200 (0.08 mm)
Sand	#200 to #40 (0.08 to 0.4 mm)
-Fine	#40 to #10 (0.4 to 2 mm)
-Medium	#10 to #4 (2 to 5 mm)
-Coarse	
Gravel	#4 to 3/4 inch (5 to 19 mm)
-Fine	3/4 to 3 inches (19 to 76 mm)
-Coarse	
Cobbles	3 to 12 inches (75 to 305 mm)
Boulders	>12 inches (305 mm)

Relative Density (Coarse Grained Soils)		Consistency (Fine Grained Soils)	
N, SPT, Blows/FT	Relative Density	N, SPT, Blows/FT	Relative Consistency
0 - 4	Very loose	Under 2	Very soft
4 - 10	Loose	2 - 4	Soft
10 - 30	Medium dense	4 - 8	Medium stiff
30 - 50	Dense	8 - 15	Stiff
Over 50	Very dense	15 - 30	Very stiff
		Over 30	Hard

Moisture Content Definitions	
Dry	Absence of moisture, dusty, dry to the touch
Moist	Damp but no visible water
Wet	Visible free water, from below water table





Cobalt Geosciences, LLC  
 P.O. Box 82243  
 Kenmore, WA 98028  
 (206) 331-1097  
[www.cobaltgeo.com](http://www.cobaltgeo.com)  
[cobaltgeo@gmail.com](mailto:cobaltgeo@gmail.com)



Soil Classification Chart

Figure C1

# Hand Boring HB-1

Date: December 2022		Depth: 6'		Groundwater: None		
Contractor:		Elevation:		Logged By: PH      Checked By: SC		
Depth (Feet)	Interval	Graphic Log	USCS Symbol	Material Description	Groundwater	Moisture Content (%)
						Plastic Limit  -----●-----  Liquid Limit
						DCP Equivalent N-Value
						0    10    20    30    40    50
1			SM	Topsail/Grass Loose to medium dense, silty-fine to medium grained sand with gravel, dark yellowish brown, moist. (Weathered Glacial Drift)		
2				Locally mottled		
3	■					
4			SM	Dense to very dense, silty-fine to medium grained sand with gravel, mottled yellowish brown to grayish brown, moist. (Glacial Drift)		
5						
6	■			End of Hand Boring 6'		
7						
8						
9						
10						

# Hand Boring HB-2

Date: December 2022		Depth: 6'		Groundwater: 3'		
Contractor:		Elevation:		Logged By: PH      Checked By: SC		
Depth (Feet)	Interval	Graphic Log	USCS Symbol	Material Description	Groundwater	Moisture Content (%)
						Plastic Limit  -----●-----  Liquid Limit
						DCP Equivalent N-Value
						0    10    20    30    40    50
1			SM	Topsail/Grass Loose to medium dense, silty-fine to medium grained sand with gravel, dark yellowish brown, moist. (Weathered Glacial Drift)		
2	■			Mottled below 20"		
3					▼	
4						
5			SM	Dense to very dense, silty-fine to medium grained sand with gravel, mottled yellowish brown to grayish brown, moist. (Glacial Drift)		
6	■			End of Hand Boring 6'		
7						
8						
9						
10						





Proposed Residence  
6333 77th Avenue SE  
Mercer Island, Washington

**Hand Boring  
Logs**

Cobalt Geosciences, LLC  
P.O. Box 82243  
Kenmore, WA 98028  
(206) 331-1097  
[www.cobaltgeo.com](http://www.cobaltgeo.com)  
[cobaltgeo@gmail.com](mailto:cobaltgeo@gmail.com)

NORTH



**Legend:**

 Test Boring Location



**GEOTECH**  
CONSULTANTS, INC.


**SITE EXPLORATION PLAN**  
6323 - 77th Avenue Southeast  
Mercer Island, Washington

Job No: 15031	Date: Feb. 2015	No Scale	Plate: 2
------------------	--------------------	----------	-------------

# BORING 1

Depth (ft.)  
Moisture  
Water  
Table  
Blows  
per Foot  
Sample  
USCS

Description



\* Test boring was terminated on February 9, 2015 at 25.9 feet.

\* Perched groundwater seepage was observed at 3 feet during drilling.




**TEST BORING LOG**  
6323 - 77th Avenue Southeast  
Mercer Island, Washington

<b>Job</b> 15031	<b>Date:</b> Feb. 2015	<b>Logged by:</b> TRC	<b>Plate:</b> 3
---------------------	---------------------------	--------------------------	--------------------

# BORING 2

Depth (ft.)  
Moisture  
Water  
Table  
Blows  
per Foot  
Sample  
USCS

Description



\* Test boring was terminated on February 9, 2015 at 20.9 feet.  
\* Groundwater seepage was not observed during drilling.




**TEST BORING LOG**  
6323 - 77th Avenue Southeast  
Mercer Island, Washington

Job	Date:	Logged by:	Plate:
15031	Feb. 2015	TRC	4

# BORING 3

Depth (ft.)  
Moisture  
Water  
Table  
Blows  
per Foot  
Sample  
USCS

Description



- \* Test boring was terminated on February 9, 2015 at 11.5 feet.
- \* Groundwater seepage was observed at 3 feet during drilling.



**TEST BORING LOG**  
6323 - 77th Avenue Southeast  
Mercer Island, Washington

<b>Job</b> 15031	<b>Date:</b> Feb. 2015	<b>Logged by:</b> TRC	<b>Plate:</b> 5
---------------------	---------------------------	--------------------------	-----------------