

CITY OF MERCER ISLAND

Fire Marshal's Office

3030 78th Ave SE | MERCER ISLAND, WA 98040

PHONE: 206.275.7966 | www.mercerisland.gov



2024 FIRE AREA AND VALUATION FORM

Project Type: <input type="checkbox"/> New Single Family		<input checked="" type="checkbox"/> Alteration	<input checked="" type="checkbox"/> Addition	<input checked="" type="checkbox"/> ADU/DADU
Project Address: 3413 72nd Pl SE Mercer Is WA 98040				
Contact Name: Laura Hafermann		Phone No. 206-948-2104		
Owner Name: Jane Eckels and Hans Andersen		206-412-4557		

Gross floor area shall be that area in square feet under the roof line of the structure including all usable area whether heated or not, above and below grade. This includes the garage and any unheated storage rooms or attachments including covered decks. If it is *usable space*, then it is included in the **Gross** square footage calculation. *This is not the same calculation for floor area ratio.*

For all construction types, add all the interior wall measurements of each floor and the basement and total that figure.

CONSTRUCTION VALUATION TYPE (verified with permit application)

Good \$209.91 sq/ft	*Very Good (most common) \$268.22 sq/ft	Very Good Custom \$326.52 sq/ft	Luxury Custom \$443.14 sq/ft
Select One: Very Good (268.22) sq/ft			<i>* Hit enter when done</i>

NEW CONSTRUCTION (**ONLY FOR NEW CONSTRUCTION**- otherwise "N/A")

<input type="checkbox"/> N/A	<table border="1"> <thead> <tr> <th>Measurements</th> <th>Square Footage</th> </tr> </thead> <tbody> <tr> <td>Main Floor interior</td> <td>305</td> </tr> <tr> <td>Lower Floor Interior</td> <td></td> </tr> <tr> <td>Other Floors interior</td> <td>364</td> </tr> <tr> <td>Basement interior</td> <td></td> </tr> <tr> <td>Attached Garage interior</td> <td>388</td> </tr> <tr> <td>Covered Decks interior</td> <td></td> </tr> <tr> <td>Other interior</td> <td></td> </tr> <tr> <td>TOTALS</td> <td>1,057.00</td> </tr> </tbody> </table>	Measurements	Square Footage	Main Floor interior	305	Lower Floor Interior		Other Floors interior	364	Basement interior		Attached Garage interior	388	Covered Decks interior		Other interior		TOTALS	1,057.00
Measurements	Square Footage																		
Main Floor interior	305																		
Lower Floor Interior																			
Other Floors interior	364																		
Basement interior																			
Attached Garage interior	388																		
Covered Decks interior																			
Other interior																			
TOTALS	1,057.00																		

ADDITION or ALTERATION

Does this house have an existing **Fire Sprinkler System?** Yes No / **NFPA 72 Alarm System** Yes No

Current Square Footage	Existing Square Footage	Standardized Value	Addition/Final Square Footage
Main Floor interior	1425	x \$ 268.22 sq/ft \$ 382,213.50	305
Lower Floor Interior	1229	x \$ 268.22 sq/ft \$ 329,642.38	0
Other Floors interior		x \$ 268.22 sq/ft \$ 268.22	364
Basement interior		x \$ 268.22 sq/ft \$ 268.22	
Attached Garage interior	388	x 43.99 sq/ft \$ 17,068.12	388
Covered Decks interior		x 43.99 sq/ft \$ 43.99	
Other interior		x \$ 268.22 sq/ft \$ 268.22	
TOTALS	3,042.00	\$729,772.65	1,057.00

Construction Cost \$ 465,575

Official Use

Verified Cost \$ _____

Higher of Verified or Cost \$ _____ / Value \$ 729,772.65 = % 0.00%

Valuation Ratio

Exempt structure – detached garage or similar structure less than 750 sf.

Less than 10% (fire review not required)

10 – 49% (monitored Household Fire Alarm System per NFPA 72 Chapter 29, if fire deficiency)

50% or greater (substantial alteration)

2018 INT'L FIRE CODE

901.4.4 Additional Fire Protection Systems. In occupancies of a hazardous nature, where special hazards exist in addition to the normal hazards of the occupancy, or where the fire code official determines that access for fire apparatus is unduly difficult, the fire code official shall have the authority to require additional safeguards. Such safeguards include, but shall not be limited to, the following:

- Automatic fire detection systems,
- Fire alarm systems,
- Automatic fire-extinguishing systems,
- Standpipe systems, or
- Portable or fixed extinguishers.

Fire protection equipment required under this section shall be installed in

accordance with this code and the applicable referenced standards.

2018 INT'L RESIDENTIAL CODE

AV107.1 Fire Sprinklers. An approved automatic fire sprinkler system shall be installed in new one-family and two-family dwellings and townhouses in accordance with Appendix U.

AV107.2 Fire Sprinklers in Existing Buildings. An approved automatic fire sprinkler system shall be installed throughout the residence in existing one-family and two-family dwellings (and townhouses) in accordance with Appendix U when undergoing a remodel or addition when the construction value of all additions, alterations or repairs performed within

a sixty-month period exceeds 50% of the value of the residence. Value shall be determined by a method approved by the fire code official.

AV107.3 Household Fire Alarm System. An approved household fire alarm system shall be installed throughout the residence in existing one-family and two-family dwellings (and townhouses) that have deficiencies in fire flow, hydrants or access. This system shall be installed in accordance with NFPA 72 Chapter 29 when undergoing a remodel or addition when the construction value of all additions, alterations or repairs performed within a sixty-month period is within 10% to 50% of the value of the residence. Value shall be determined by a method approved by the fire code official.