

Agreed Amended Conditions

Paragraph IV. PEDESTRIANS and TRAFFIC

A. The applicant shall comply with the traffic control plan attached to this permit. However, the contractor may submit a revised traffic control plan for City review.

E. One lane, two-way traffic control (see traffic control plan drawing E07-TMP002) may only ~~Work that impacts traffic flow must~~ be performed Monday – Friday 9:00 am – 3:30 pm and as needed on Saturdays 9:00 am – 3:30 pm , except legal holidays. Additional time restrictions may be added to this permit to mitigate one lane, flagger controlled construction impacts on traffic when frequent and significant traffic delays extend through intersections beyond the limits of the approved traffic control plan(s).

Paragraph VII. CONSTRUCTION and RESTORATION

H. Final asphalt restoration must be completed prior to substantial completion and inspection of each phase of construction in the traffic control plan(s). ~~within 30 days of excavation unless an extension has been granted in advance.~~ The limits of pavement restoration in the public right of way shall be limited to the approved permit plan set unless pavement has been clearly damaged beyond said limits. ~~determined by the City Engineer prior to final inspection of the project.~~

I. Class B hot mix asphalt or polymer-modified cold asphalt (EZ Street or equal) shall be used for temporary asphalt patches. MC250 cold mix is not allowed. Temporary asphalt patches shall be marked “TEMP” in white paint. ~~Permanent pavement restoration shall be completed within 30 calendar days.~~