

To:

Mr. William C. Summers

1840 Wilbur Avenue Vero Beach, FL 32960 Date: 01/21/19

Re:

Proposed Residence - Pipe Piling

5637 E. Mercer Way Mercer Island, WA

Dear Bill,

We understand that your engineer is planning on having approx. 20 – 25 each 4" dia. pipe piles for the construction of your single-family residence at the above address on Mercer Island. These piles will penetrate 15'-20' deep through the loose and unstable soil on this steep sloped site located on the West side of E Mercer Way. Versatile Drilling has over 35 years of experience in drilling and driving piling in the metropolitan Seattle area, including many project on Mercer Island.

We expect to use a hydraulic hammer mounted on a mini-excavator to complete this work. Driving small diameter piling does not produce any significant amount of vibration. There will, of course, be some noise generated by the pipe pile driving. This work should be completed in 1-3 days, but noise levels will not exceed 85 decibels – the maximum allowed by the City of Seattle standards.

Please advise me if we can be of further assistance.

Sincerely,

John C Marth

Versatile Drilling Contractors, Inc.