
CITY OF MERCER ISLAND

COMMUNITY PLANNING & DEVELOPMENT

9611 SE 36TH STREET | MERCER ISLAND, WA 98040

PHONE: 206.275.7605 | www.mercergov.org



STAFF REPORT

Critical Areas Determination

Project No.:	CAO19-008
Description:	Buffer averaging of a type 3 watercourse with a planting plan.
Applicant/ Owner:	Kevin Sutton (MZA Architects) / Timothy Paek
Site Address:	2215 80 th Ave SE Mercer Island, WA 98040 Identified by King County Assessor tax parcel number: 54523-02145
Zoning District	R-8.4
SEPA Compliance:	Exempt per WAC 197-11-800(6)(e)
Staff Contact:	Lauren Anderson, Planner
Exhibits:	<ol style="list-style-type: none">1. Plan Set received by the City on May 6, 2019.2. Project Narrative prepared by MZA Architecture received by the City on May 6, 2019.3. Critical Areas Study prepared by John Altmann, an Ecologist at Altmann Oliver Associates LLC received by the City on May 6, 2019.4. Development Application received by the City on May 6, 2019.5. ESA First Review Memo received by the City on August 8, 2019.6. Site Visit Photos from August 5, 2019.7. City's GIS watercourse map.

INTRODUCTION

1. Application Description:

The proposal is a significant remodel and story addition that involves the removal of the entry level walls down to the foundation and at the floor framing above the daylight basement below. The downhill side of the house will be three (3) stories. The existing house has a gross floor area of 3,352 square feet and the new proposed house will be 4,370 square feet. For the proposed development, the applicant has a building permit application under review, #1808-172.

2. Zoning & Adjacent Land Use:

The site gently slopes down to the west and has three existing trees within the 35-foot watercourse buffer. The lot and surrounding lots are zoned R-8.4 residential and are single-family residential. The existing home sits within the existing 35-foot buffer of an existing type 3 watercourse that is located on the western neighbor's property. The proposal is to do buffer averaging and reduce the buffer where the remodel and existing house exists.

3. SEPA Compliance:

The proposal is categorically exempt from SEPA (State Environmental Policy Act) review per WAC 197-11-800(6)(e).

4. Consistency with Land Use Code/Zoning Requirements:

A Critical Areas Determination for watercourse buffer averaging is a type III (3) land use review per MICC 19.15.030 Table A. The applicant has applied for a Critical Areas Determination to average the width of the watercourse buffer by removing 141 square feet from the southwest portion of the lot and relocating the 141 square feet of buffer to the northwest portion of the lot. The watercourse buffer enhancement area is 187 square feet and consists of native vegetation (red currant and snowberry).

The City's GIS map (Exhibit 7) indicated that the watercourse was a type 2 watercourse, however the City's peer reviewer (ESA) Ecologist and the applicant's Ecologist (AOA, LLC) have found that it is a type 3 watercourse with a 35-foot associated buffer. Please refer to Exhibit 3 and 5, and the analysis below in the Findings of Fact and Conclusions of Law #8.

Findings of Fact & Conclusions of Law

5. Application Date, Letter of Completion, Vesting:

The applicant applied on May 6, 2019 and the application was deemed complete on May 30, 2019. Due to the application being a type III land use review, per MICC 19.15.170(B) it vests on the date of completion.

6. NOA, Review Process, Comment Period:

Type III land use reviews per MICC 19.15.030(Table B) require public notice of application (NOA) which includes the following: weekly bulletin notice, 300-foot mailing, 30-day comment period and sign posted near the site. The public NOA was issued on June 3, 2019 and the 30-day comment period went until 5pm on July 3, 2019. The City received no public comments during this time or afterwards.

7. Site Visit Finding:

City Planner Lauren Anderson and Jessica Redman from ESA (Environmental Science Associates, peer reviewer) conducted a site visit on August 5, 2019. Refer to Exhibit 6 site visit photographs of the backyard (western portion) of the lot and looking over the fence. The watercourse looked to be a ditched channel and no flow was observed. Refer to Exhibit 5 for ESA's review memo with ESA's recommendations and findings.

8. SEPA Finding of Fact and Conclusions:

Categorical exemption finding pursuant to WAC 197-11-800(6)(e). In addition, the watercourse is located on the neighbor's property, thus the site is not considered lands covered by water.

9. Critical Areas:

MICC 19.07.070 has the watercourse requirements for typing, buffer size and buffer averaging. This code is copied below with staff analysis in italic text.

- A. Watercourses – Designation and Typing. Watercourses shall be designated as Type 1, Type 2, Type 3 and Restored according to the following criteria:
 1. Type 1 Watercourse. Watercourses or reaches of watercourses used by fish, or are downstream of areas used by fish.

2. Type 2 Watercourse. Watercourses or reaches of watercourses with year-round flow, not used by fish.
 3. Type 3 Watercourse. Watercourses or reaches of watercourses with intermittent or seasonal flow and not used by fish.
 4. Restored Watercourse. Any Type 1, 2 or 3 watercourses created from the opening of previously piped, channelized or culverted watercourses.
- B. Watercourse Buffers.
1. Watercourse Buffer Widths. Standard buffer widths shall be as follows, measured from the ordinary high water mark (OHW), or top of bank if the OHW cannot be determined through simple nontechnical observations.

Watercourse Type	Standard (Base) Buffer Width (feet)	Minimum Buffer Width with Enhancement (feet)
Type 1	75	37
Type 2	50	25
Type 3	35	25
Restored or Piped	25	Determined by the code official

Staff Analysis: The applicant’s Ecologist, Altmann Oliver Associates (AOA) found that “since Stream 1 does not contain fish habitat and conveys only seasonal or intermittent flows, it meets the criteria for a Type 3 watercourse per MICC 19.07.070.A (Exhibit 3, page 2).” In addition, the City’s peer reviewer, ESA agreed with AOA’s findings that it is a type 3 watercourse which has a 35-foot standard buffer. ESA stated the following: “ESA and City staff observed the watercourse from the project parcel during the August 5, 2019 site visit. The watercourse appeared to be a ditched channel that was dug to primarily convey stormwater. No flow was observed during the August site visit. Stream substrate was primarily soil and no fish habitat was observed. Based on the stream characteristics and the location of the parcel near the start of a deep ravine, we also agree that the stream would not support fish and therefore, is a Type 3 watercourse, which would be allotted a 35-foot buffer (Exhibit 5, page 2).”

.....

3. Averaging of Buffer Widths. The code official may allow the standard buffer width to be averaged if:
 - a. The proposal will result in a net improvement of critical area function;
 - b. The proposal will include replanting of the averaged buffer using native vegetation;
 - c. The total area contained in the averaged buffers on the development proposal site is not decreased below the total area that would be provided if the maximum width were not averaged
 - d. The standard buffer width is not reduced to a width that is less than the minimum buffer width at any location; and
 - e. That portion of the buffer that has been reduced in width shall not contain a steep slope.

Staff Analysis:

- a. *As shown in Exhibit 3 and Exhibit 5, ESA and AOA Ecologist’s both found that the proposal will result in a new improvement of watercourse function. The proposal includes permanent removal of*

impervious surface within the buffer and native vegetation plantings. ESA states the following: "Based on our review of the AOA Report and MICC, as well as the site visit, ESA concludes the proposed buffer addition and enhancement with native plantings will improve buffer conditions at the site and result in an ecological lift in functions [Exhibit 5, page 3]."

- b. As shown in Exhibit 1 page 11, eleven one-gallon red currant and eleven one-gallon snowberry will be planted within the enhancement area. MICC 19.16 defines native vegetation as "vegetation identified by the Washington Native Plant Society or the United States Department of Agriculture as being native to Washington State. Native vegetation does not include noxious weeds." Red currant and snowberry are identified by the United States Department of Agriculture as being native to Washington State.*
- c. As shown in Exhibit 1 page 10 and 11, the total area contained in the averaged buffers on the site is not decreased as 141 square feet (sf) buffer area is being reduced and 141 sf is being added.*
- d. As shown in Exhibit 1 page 10 and 11, the buffer width is not reduced to less than 25 feet (minimum buffer width) at any location.*
- e. As shown in Exhibit 1 page 5 Topographic Survey by Terrane, the reduced buffer area does not contain a steep slope.*

CONDITIONS OF APPROVAL

1. The following conditions shall be binding on the "Applicant," which shall include the owner or owners of the property, heirs, assign and successors.
2. Substantial conformance with the development plan set (Exhibit 1).
3. This permit approval shall expire three (3) years from the date of notice of decision if the activity approved by the permit is not exercised. This activity includes construction or substantial progress toward construction of a development proposal.
4. The mitigation plants shall be monitored twice (2) approximately one (1) year after plant installation (to determine survival and replacement) and five (5) years after the plant installation to ensure the mitigation actions of the project were a success.
5. The applicant shall install and have inspected full temporary erosion and sediment control measures prior to construction.

DECISION

Based upon the above noted Findings of Fact and Conclusions of Law, critical areas determination application CAO19-008, as depicted in Exhibit 1 and 3, is hereby preliminarily **APPROVED**. This decision is final, unless appealed in writing consistent with adopted appeal procedures, MICC 19.15.020(J), and all other applicable appeal regulations.

Approved this 19th day of August 2019



Lauren Anderson
Planner

**Community Planning & Development
City of Mercer Island**

If you desire to file an appeal, you must submit the appropriate form, available from the department of Community Planning and Development, and file it with the City Clerk within fourteen (14) days from the date after the notice of decision is made available to the public and applicant pursuant to MICC 19.15.120. Upon receipt of a timely complete appeal application and appeal fee, an appeal hearing will be scheduled. To reverse, modify or remand this decision, the appeal hearing body must find that there has been substantial error, the proceedings were materially affected by irregularities in procedure, the decision was unsupported by material and substantial evidence in view of the entire record, or the decision is in conflict with the city's applicable decision criteria.

Please note that the City will provide notice of this decision to the King County Department of Assessment, as required by State Law (RCW 36.70B.130). Pursuant to RCW 84.41.030(1), affected property owners may request a change in valuation for property tax purposes notwithstanding any program of revaluation by contacting the King County Department of Assessment at (206) 296-7300.


GENERAL NOTES

VICINITY MAP

SINGLE FAMILY ADDITION
PAEK RESIDENCE
2215 80TH AVE SE
MERCER ISLAND, WA 98040

PROJECT
PAEK RESIDENCE
ADDRESS
2215 80TH AVE SE
MERCER ISLAND, WA 98040
CLIENT
TIMOTHY PAEK

- A. ALL WORK SHALL BE PERFORMED IN STRICT ACCORDANCE WITH ALL GOVERNING BUILDING CODES AND REGULATIONS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL WORK THAT HAS BEEN PERFORMED WHICH DOES NOT MEET THESE CODES AND REGULATIONS.
B. ALL WORK SHALL BE PERFORMED IN STRICT ACCORDANCE TO THE ARCHITECT'S CONSTRUCTION DOCUMENTS. THE CONTRACTOR IS RESPONSIBLE FOR REPORTING IMMEDIATELY TO THE ARCHITECT ANY DISCREPANCIES OR DETAILS WHICH DO NOT MEET BUILDING CODES AND CONSTRUCTION STANDARDS.
C. THE CONTRACTOR SHALL VERIFY ALL CONDITIONS AND DIMENSIONS ON SITE PRIOR TO THE COMMENCEMENT OF CONSTRUCTION. IN THE EVENT OF CONFLICTS OR CHANGES BETWEEN DETAILS, OR BETWEEN THE PLANS AND SPECIFICATIONS, THE ARCHITECT SHALL BE NOTIFIED IMMEDIATELY.
D. THE CONTRACTOR SHALL VERIFY LOCATION OF ALL UTILITIES AND PIPING BEFORE BEGINNING WORK.
E. THE GC SHALL COORDINATE ALL OPERATIONS WITH THE OWNER, INCLUDING AREA FOR WORK, MATERIALS STORAGE, AND ACCESS TO AND FROM THE WORK. SPECIAL CONDITIONS OR NOISY WORK, TIMING OF WORK AND INTERRUPTION OF MECHANICAL AND ELECTRICAL SERVICES, NOISY OR DISRUPTIVE WORK SHALL BE SCHEDULED AT LEAST ONE (1) WEEK IN ADVANCE OF THE TIME WORK IS TO COMMENCE.
F. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE HIGHEST STANDARD OF WORKMANSHIP IN GENERAL AND WITH SUCH STANDARDS AS ARE SPECIFIED.
G. GC SHALL SUBMIT SAMPLES OF ALL FINISHES OF SUCH SIZE AND NUMBER THAT THEY REPRESENT A REASONABLE DISTRIBUTION OF COLOR RANGES AND PATTERN PRIOR TO INSTALLATION FOR ARCHITECT'S APPROVAL. GC SHALL PROVIDE SHOP DWGS AND PRODUCT DATA FOR ARCHITECT'S APPROVAL ON ALL SPECIAL ITEMS REQUIRING CUSTOM FABRICATION (SHALL INCLUDE RATED FIRE DOORS AND HARDWARE).
H. SURROUNDING AREAS MAY BE OCCUPIED DURING CONSTRUCTION. THE GC SHALL PROTECT ALL PERSONNEL, PASSENGERS OR VISITORS TO THE SITE FROM HARM AND INJURY. BARRIERS SHALL BE INSTALLED AS REQUIRED TO PROTECT EQUIPMENT INSTALLED DURING CONSTRUCTION, CAREFULLY MAINTAIN AND PROTECT MONUMENTS, BENCH MARKS AND THEIR REFERENCE POINT FROM BEING DESTROYED OR DISTURBED; REPLACE AS REQUIRED.
I. MATERIALS, ARTICLES, DEVICES AND PRODUCTS ARE SPECIFIED IN THE DOCUMENTS BY LISTING ACCEPTABLE MANUFACTURERS OR PRODUCTS, BY REQUIRING COMPLIANCE WITH REFERENCED STANDARDS, OR BY PERFORMANCE SPECIFICATIONS. FOR ITEMS SPECIFIED BY NAME, SELECT ANY PRODUCT NAMED. FOR THOSE SPECIFIED BY REFERENCE STANDARDS OR BY PERFORMANCE SPECIFICATIONS SELECT ANY PRODUCT MEETING OR EXCEEDING SPECIFIED CRITERIA. FOR APPROVAL OF AN ITEM NOT SPECIFIED, SUBMIT REQUIRED SUBMITTALS, PROVIDING COMPLETE BACK-UP INFORMATION FOR PURPOSES OF EVALUATION. WHERE BUILDING STANDARD ITEMS ARE CALLED FOR, NO SUBSTITUTE WILL BE ACCEPTED.
J. REFER TO STRUCTURAL PLANS FOR SPECIAL INSPECTION REQUIREMENTS.
K. SUBSTITUTIONS



SCOPE OF WORK

RESIDENTIAL ADDITION INVOLVING DEMO OF THE EXISTING ENTRY LEVEL AND RECONSTRUCTION OF THAT LEVEL PLUS A NEW UPPER LEVEL FLOOR. SOME MODIFICATION OF INTERIOR BASEMENT WALLS FOR NEW ACCESSORY DWELLING UNIT OF 330 SF.

DEFERRED SUBMITTALS

- MECHANICAL:
1. THE MECHANICAL WORK FOR THE PROJECT SHALL BE PERFORMED AS DESIGN-BUILD. THE GENERAL CONTRACTOR SHALL SUBMIT WITH THE BID A PROPOSED HVAC AND PLUMBING DRAWING THAT COORDINATES WITH THE ARCHITECTURAL DRAWINGS.
2. THE GENERAL CONTRACTOR'S MEP/FP SUBCONTRACTOR WILL BE RESPONSIBLE FOR APPLYING FOR AND SECURING ALL NECESSARY PERMITS.
3. ALL MEP/FP IS DESIGNED BY LICENSED PROFESSIONALS IN STATES & JURISDICTION FOR WORK. DESIGN CRITERIA IS PROVIDED BY OWNER/OR GENERAL CONTRACTORS.
4. REVIEW SET NOTES APPLICABLE TO MEP/FP D/B SUBCONTRACTORS & FOR COORDINATION W/ ARCHITECTURAL DRAWINGS.

DESIGN CODE

- 2015 INTERNATIONAL RESIDENTIAL CODE WITH WASHINGTON STATE AMENDMENTS
2015 INTERNATIONAL FIRE CODE
2015 INTERNATIONAL MECHANICAL CODE
2015 INTERNATIONAL FUEL GAS CODE
2015 UNIFORM PLUMBING CODE
2015 WASHINGTON STATE ENERGY CODE
WASHINGTON CITIES ELECTRICAL CODE

- HANDRAIL AND GUARDRAIL SYSTEMS:
1. THE HANDRAIL AND GUARDRAIL DESIGNS AND ENGINEERING FOR THE PROJECT SHALL BE PERFORMED AS DESIGN-BUILD. THE GENERAL CONTRACTOR SHALL SUBMIT WITH THE BID PROPOSED HANDRAIL AND GUARDRAIL DRAWINGS THAT COORDINATE WITH THE ARCHITECTURAL DRAWINGS AND INTENT.
2. THE GENERAL CONTRACTOR'S HANDRAIL & GUARDRAIL SUBCONTRACTOR WILL BE RESPONSIBLE FOR APPLYING FOR AND SECURING ALL ASSOCIATED AND NECESSARY PERMITS.

DOCUMENTS FOR DEFERRED SUBMITTAL ITEMS SHALL BE SUBMITTED TO THE REGISTERED DESIGN PROFESSIONAL IN RESPONSIBLE CHARGE WHO SHALL REVIEW THEM AND FORWARD THEM TO THE BUILDING OFFICIAL WITH A NOTATION INDICATING THAT THE DEFERRED SUBMITTAL DOCUMENTS HAVE BEEN REVIEWED AND BEEN FOUND TO BE IN GENERAL CONFORMANCE TO THE DESIGN OF THE BUILDING. THE DEFERRED SUBMITTAL ITEMS SHALL NOT BE INSTALLED UNTIL THE DESIGN AND SUBMITTAL DOCUMENTS HAVE BEEN APPROVED BY THE BUILDING OFFICIAL.

TEAM

CLIENT:
TIMOTHY & ELLEN PAEK
2215 80TH AVE SE
MERCER ISLAND, WA 98040
PHONE: 425.628.7165
CONTACT NAME: TIMOTHY PAEK
ARCHITECT OF RECORD:
MZA_PS
600 108TH AVE NE, SUITE 108
BELLEVUE, WA 98004
PHONE: 425-559-7888
CONTACT: KEVIN SUTTON

DATA

SITE ADDRESS: 2215 80TH AVE SE MERCER ISLAND, WA 98040
PARCEL DATA:
LEGAL DESCRIPTION: MERCER PARK, Plat Block: 21, Plat Lot: 3-4
PARCEL NUMBER: 545230-2145
JURISDICTION: CITY OF MERCER ISLAND
WATER & SEWER DISTRICT: CITY OF MERCER ISLAND
SECTION/TOWNSHIP/RANGE: SE-1-24-4
PROPERTY ZONING: R-8.5
TOTAL LOT AREA (RECORDED): 8,810 SF

Table with columns: STRUCTURE SETBACKS, REQ'D (ft), PROP. (ft). Rows include Front East Yard (20'), Rear West Yard (25'), Side Yard North (10' EA/15' TOTAL), Side Yard South (10' EA/15' TOTAL), Max. In Building Height Above Ave. Existing Grade (30').

BUILDING HEIGHT NOTES:
1. REFER TO SITE PLAN FOR AVERAGE GRADE CALCULATIONS
2. REFER TO BUILDING ELEVATIONS FOR GRADE DATUM POINTS AND ROOF PEAK...

Table with columns: MAXIMUM GROSS FLOOR AREA, MAX. LOT COV. BY STRUCT., MAX. HARDSCAPE. Rows show values for ADU (45), SF (3,964.5), SF (3,932).

STRUCTURAL:

Swenson Say Faget
2124 3rd Ave. Suite 100
Seattle, WA 98121
Telephone: 206-443-6212
Authorized Representative: Ryan Arderson

LANDSCAPE ARCHITECT:

ANR Landscape Design
22310 98th Ave W
Edmonds, WA 980120
Telephone: 206-818-3610
Authorized Representative: Anni Nozaka Rapelje

CIVIL:

ESM CONSULTING ENGINEERS, LLC
33400 8th Ave. S. Suite 205
Federal Way, WA 98003
Telephone: 253-838-6113

Envirmental:

Altman Oliver Associates, LLC
PO Box 578 Carnation, Wa 98014
Telephone: 425-333-4509
John Altman

SHEET INDEX

Table listing sheet numbers and titles: A0.0 COVER SHEET, A0.1 GENERAL CODE NOTES, A0.2 GENERAL & ENERGY CODE NOTES, A1.0 LAND USE CALCULATIONS, V1.0 SURVEY, C1.0 TESC & DEMO PLAN, C2.0 GRADING & DRAINAGE PLAN, C3.0 STORMWATER NOTES & DETAILS, L1.0 LANDSCAPE PLAN, W-1 BUFFER RESTORATION PLAN, W-2 PLANTING PLAN, W-3 SPECIFICATIONS & DETAILS, A1.1 SITE PLAN, A2.0 FLOOR PLANS, A2.1 BASEMENT & GROUND FLOOR PLANS, A2.2 UPPER LEVEL PLAN, A2.3 ROOF PLAN, A3.0 SECTION, A4.0 EAST & WEST ELEVATIONS, A4.1 NORTH & SOUTH ELEVATIONS, A5.0 VERTICAL CIRCULATION, A6.0 WALL SECTIONS & DETAILS, A6.1 WALL SECTIONS & DETAILS, A7.0 WINDOW & DOOD TYPE AND SCHEDULE, A7.1 WALL TYPES, A7.2 FLOOR & ROOF/CEILING TYPES, A8.0 BUILDING ENVELOPE DETAILS, S1.1 GENERAL STRUCTURAL NOTES, S1.2 GENERAL STRUCTURAL NOTES CONTINUED, S2.1 BASEMENT FOUNDATION PLAN, S2.2 MAIN FLOOR FRAMING PLAN, S2.3 UPPER FLOOR FRAMING PLAN, S2.4 ROOF FRAMING PLAN, S3.1 FOUNDATION SECTIONS & DETAILS, S4.1 TYPICAL WOOD SECTIONS & DETAILS, S4.2 WOOD FRAMING SECTIONS & DETAILS, S4.3 WOOD FRAMING SECTIONS & DETAILS, S4.4 WOOD FRAMING SECTIONS & DETAILS.

Table with columns: NO., ISSUED, DATE. Includes a REVISIONS section and a DRAWING STATUS section.






Discrepancies must be reported immediately to the Architect before proceeding. Only figured dimensions are to be used. Contractors must check all dimensions on site. This drawing is protected by copyright. ALL DIMENSIONS ARE SHOWN IN IMPERIAL.

ABBREVIATION



Table of abbreviations and symbols. Columns include SYMBOLS, AVERAGE BUILDING, AIR CONDITIONER, FLOOR DRAIN, FLOOR FINISH, ALUMINUM, APPROXIMATE, AUTOMATIC SPRINKLER, BELOW FINISH FLOOR, BUILDING STANDARD, BOTTOM OF, BETWEEN, CATCH BASIN, CAST IRON, CAST IN PLACE, CONTROL JOINT, CONSTRUCTION JOINT, CONCRETE MASONRY, COLUMN, CONCRETE, CONTINUOUS, CONSTRUCTION, CONTRACTOR, COVERAGE, CARPET, CERAMIC TILE, DRINKING FOUNTAIN, DOWNSPOUT, DRAWING, EACH, ELEVATION, ELEVATOR, ELECTRICAL, EXPANSION JOINT, EXISTING, EXPANSION JOINT, EXPANSION, EXTERIOR, FURNISH BY CONTRACTOR, FURNISH BY OWNER, FURNISHED BY OWNER, FLOOR DRAIN, FOUNDATION, FINISH FLOOR, FURNISHED BY OWNER, FIRE EXTINGUISHER CABINET, FURNISHED BY OWNER, FROST PROOF HOSE BIBB, FIBER REINFORCED PANEL(S), FOOTING, GAUGE, GALVANIZED, GENERAL CONTRACTOR, GYPSUM LATH & PLASTER, GYPSUM WALLBOARD, HIGH, HEIGHT, HOSE BIBB, HOLLOW METAL, HORIZONTAL, HORIZONTAL, HEATER, INSULATION, JOINT, JOINTS, LONG, LENGTH, LAMINATE, LAMINATED, LINEAR FOOT, LINEAL, LIGHT WEIGHT, LEVEL, MASONRY, MAXIMUM, METAL BUILDING, SUPPLIER, MARMOLEUM, COMPOSITE TILE, MECHANICAL, MEZZANINE, METAL, MANUFACTURING, MANUFACTURER, MANHOLE, MINIMUM, MISCELLANEOUS, MASONRY OPENING, MOISTURE RESISTANT, MOUNTED, MOUNTING, NOT IN CONTRACT, NOMINAL, NOT TO SCALE ON CENTER, OVERHEAD, OPPOSITE, OVER, PERPENDICULAR, PLATE, PLASTIC LAMINATE, PLUMBING, PANEL, PANELING, PROJECT, PROJECTED, PRESSURE REDUCING, POINT, QUARRY TILE, QUARTER, RADIUS, ROOF DRAIN, RAIN LEADER, RECEIVED, REFRIGERATOR, REINFORCING, REQUIRED, RUBBER FLOORING, RESTROOM, ROUGH OPENING, PUBLIC RIGHT OF WAY, SELF ADHESIVE, SCHEDULE, SOLID CORE, SQUARE FOOTAGE, SAFETY GLASS, SHEET, SIMILAR, SPECIFICATION, SQUARE, STAINLESS STEEL, SANITARY SEWER, STANDARD, STEEL, STRUCTURE, STRUCTURE, SUSPENDED SYSTEM, TEMPERED, TREAD, TOP, NOT IN CONTRACT, TELEPHONE, TEMPERED, TONGUE & GROOVE, TEMPERED GLASS, TOP OF, TYPICAL UTILITY, UNLESS OTHERWISE NOTED, VINYL COMPOSITION TILE, VERTICAL, VERT, WITH, WITHOUT, WALK OFF MAT, WATERPROOF, WATER RESISTANT, WATER RESISTANT, WEIGHT, WELDED WIRE MESH, WELDED WIRE FABRIC, YARD DRAIN.

LEGEND OF SYMBOLS






VIEW REFERENCES



EXTERIOR ELEVATIONS




OBJECT REFERENCES



MATERIAL REFERENCES



600 108th Ave NE
Suite 108
Bellevue WA 98004
425.559.7888
contact@mza.us



DRAWING TITLE
COVER SHEET

DRAWN: KNS
DESIGNED: Designer

DATE: 09/04/18

GRAPHIC SCALE: 1/4" = 1'-0"

PROJECT NO.: 18-009

DRAWING NO.: A0.0

PERMITS UNDER SEPERATE REVIEW
-ACCESSORY DWELLING UNIT (330 SF.)
-CRITICAL AREAS DETERMINATION

24"x36" Arch D - SHEET SIZE

FILE NAME:
PLOT DATE:

24"x36" ARCH D - SHEET SIZE

BUILDING PLANNING (CHAP. 3)

HABITABLE SPACE (IRC SECTION R202): A SPACE IN A BUILDING FOR LIVING, SLEEPING, EATING OR COOKING, BATHROOMS, TOILET ROOMS, CLOSETS, HALLS, STORAGE OR UTILITY SPACES AND SIMILAR AREAS ARE NOT CONSIDERED HABITABLE SPACES.

LIGHT, VENTILATION AND HEATING IN HABITABLE ROOMS (SECTION R303): ALL HABITABLE ROOMS SHALL HAVE AN AGGREGATE GLAZING AREA OF NOT LESS THAN 8 PERCENT OF THE FLOOR AREA OF SUCH ROOMS. NATURAL VENTILATION SHALL BE THROUGH WINDOWS, DOORS, LOUVERS OR OTHER APPROVED OPENINGS TO THE OUTDOOR AIR. SUCH OPENINGS SHALL BE PROVIDED WITH READY ACCESS OR SHALL OTHERWISE BE EASILY CONTROLLABLE BY THE BUILDING OCCUPANTS. THE MINIMUM OPENABLE AREA TO THE OUTDOORS SHALL BE 4 PERCENT OF THE FLOOR AREA BEING VENTILATED.

EXCEPTIONS:
1. THE GLAZED AREAS NEED NOT BE OPENABLE WHERE THE OPENING IS NOT REQUIRED BY SECTION R310 AND AN APPROVED MECHANICAL VENTILATION SYSTEM IS PROVIDED CAPABLE OF PRODUCING 0.35 AIR CHANGE PER HOUR IN THE ROOM OR A WHOLE-HOUSE MECHANICAL VENTILATION SYSTEM IS INSTALLED CAPABLE OF SUPPLYING OUTDOOR VENTILATION AIR OF 15 CUBIC FEET PER MINUTE (CFM) PER OCCUPANT COMPUTED ON THE BASIS OF TWO OCCUPANTS FOR THE FIRST BEDROOM AND ONE OCCUPANT FOR EACH ADDITIONAL BEDROOM.

2. THE GLAZED AREAS NEED NOT BE PROVIDED IN ROOMS WHERE EXCEPTION 1 ABOVE IS SATISFIED AND ARTIFICIAL LIGHT IS PROVIDED CAPABLE OF PRODUCING AN AVERAGE ILLUMINATION OF 6 FOOT-CANDELES OVER THE AREA OF THE ROOM AT A HEIGHT OF 30 INCHES ABOVE THE FLOOR LEVEL.

LIGHT, VENTILATION AND HEATING IN ADJOINING ROOMS (SECTION R303.2): FOR THE PURPOSE OF PERMITTING LIGHT AND HEATING THROUGH WALLS, A ROOM SHALL BE CONSIDERED AS A PORTION OF AN ADJOINING ROOM WHEN AT LEAST ONE-HALF OF THE AREA OF THE COMMON WALL IS OPEN AND UNOBSTRUCTED AND PROVIDES AN OPENING OF NOT LESS THAN ONE-TENTH OF THE FLOOR AREA OF THE INTERIOR ROOM BUT NOT LESS THAN 25 SQUARE FEET.

HANDRAILS AND VENTILATION IN ADJOINING ROOMS: HANDRAILS AND VENTILATION SHALL BE PERMITTED TO OPEN INTO A THERMALLY ISOLATED SUNROOM ADDITION OR PATIO COVER, PROVIDED THAT THERE IS AN OPENABLE AREA BETWEEN THE ADJOINING ROOM AND THE SUNROOM ADDITION OR PATIO COVER OF NOT LESS THAN ONE-TENTH OF THE FLOOR AREA OF THE INTERIOR ROOM BUT NOT LESS THAN 20 SQUARE FEET. THE MINIMUM OPENABLE AREA TO THE OUTDOORS SHALL BE BASED UPON THE TOTAL FLOOR AREA BEING VENTILATED.

LIGHT, VENTILATION AND HEATING IN BATHROOMS (SECTION R303.3): BATHROOMS, WATER CLOSET COMPARTMENTS AND OTHER SIMILAR ROOMS SHALL BE PROVIDED WITH AGGREGATE GLAZING AREA IN WINDOWS OF NOT LESS THAN 3 SQUARE FEET, ONE-HALF OF WHICH MUST BE OPENABLE. IN EXCEPTION THE GLAZED AREAS SHALL NOT BE REQUIRED WHERE ARTIFICIAL LIGHT AND A MECHANICAL VENTILATION SYSTEM ARE PROVIDED. THE MINIMUM VENTILATION RATES SHALL BE 50 CFM FOR INTERMITTENT VENTILATION OR 20 CFM FOR CONTINUOUS VENTILATION. VENTILATION AIR FROM THE SPACE SHALL BE EXHAUSTED DIRECTLY TO THE OUTSIDE.

CEILING HEIGHT (SECTION R305): HABITABLE SPACE, HALLWAYS, CORRIDORS, BATHROOMS, TOILET ROOMS, LAUNDRY ROOMS AND BASEMENTS SHALL HAVE A CEILING HEIGHT OF NOT LESS THAN 7 FEET. THE REQUIRED HEIGHT SHALL BE MEASURED FROM THE FINISH FLOOR TO THE LOWEST PROJECTION FROM THE CEILING.

EXCEPTIONS:
1. FOR ROOMS WITH SLOPED CEILINGS, AT LEAST 50 PERCENT OF THE REQUIRED AREA OF A ROOM MUST HAVE A CEILING HEIGHT OF AT LEAST 7 FEET AND NO PORTION OF THE REQUIRED FLOOR AREA MAY HAVE A CEILING HEIGHT OF LESS THAN 5 FEET.

2. BATHROOMS SHALL HAVE A MINIMUM CEILING HEIGHT OF 6 FEET 8 INCHES AT THE CENTER OF THE FRONT CLEARANCE AREA FOR FIXTURES AS SHOWN IN FIGURE R307.1. THE CEILING HEIGHT ABOVE FIXTURES SHALL BE SUCH THAT THE FIXTURE IS CAPABLE OF BEING USED FOR ITS INTENDED PURPOSE. A SHOWER OR TUB EQUIPPED WITH A SHOWERHEAD SHALL HAVE A MINIMUM CEILING HEIGHT OF 6 FEET 8 INCHES ABOVE 30 INCHES BY 30 INCHES AT THE SHOWERHEAD. BASEMENTS: PORTIONS OF BASEMENTS THAT DO NOT CONTAIN HABITABLE SPACE, HALLWAYS, BATHROOMS, TOILET ROOMS AND LAUNDRY ROOMS SHALL HAVE A CEILING HEIGHT OF NOT LESS THAN 6 FEET 8 INCHES.

EXCEPTIONS:
1. BEAMS, GIRDERS, DUCTS, OR OTHER OBSTRUCTIONS MAY PROJECT TO WITHIN 6 FEET 4 INCHES OF THE FINISHED FLOOR.
TOILET SPACES (SECTION R307): WATER CLOSET COMPARTMENTS ARE TO BE A MINIMUM 30 INCHES WIDE WITH A MINIMUM OF 21 CLEAR SPACE IN FRONT OF THE FIXTURE.

BATHS AND SHOWER SPACES (SECTION R307): BATHTUB AND SHOWER FLOORS AND WALLS ABOVE BATHTUBS WITH INSTALLED SHOWER HEADS AND IN SHOWER COMPARTMENTS SHALL BE FINISHED WITH A NONABSORBENT SURFACE. SUCH WALL SURFACES SHALL EXTEND TO A HEIGHT OF NOT LESS THAN 6 FEET ABOVE THE FLOOR.

CLOTHES DRYERS EXHAUST (SECTION M1502): DRYER EXHAUST SYSTEMS SHALL BE INDEPENDENT OF ALL OTHER SYSTEMS, SHALL CONVEY THE MOISTURE TO THE OUTDOORS AND SHALL TERMINATE ON THE OUTSIDE OF THE BUILDING. EXHAUST DUCT TERMINATIONS SHALL BE IN ACCORDANCE WITH THE DRYER MANUFACTURER'S INSTALLATION INSTRUCTIONS. SCREENS SHALL NOT BE INSTALLED AT THE DUCT TERMINATION. SCREENS SHALL NOT BE JOINED WITH SCREWS OR SIMILAR FASTENERS THAT PROTRUDE INTO THE SIDE OF THE DUCT. EXHAUST DUCTS SHALL BE EQUIPPED WITH A BACKDRAFT DAMPER. EXHAUST DUCTS SHALL BE CONSTRUCTED OF MINIMUM 4 INCHES NOMINAL DIAMETER AND 0.016-INCH-THICK RIGID METAL DUCTS, HAVING SMOOTH INTERIOR SURFACES WITH JOINTS RUNNING IN THE DIRECTION OF FLOW. FLEXIBLE DUCTS SHALL BE LIMITED TO A SINGLE LENGTH THAT IS LISTED AND LABELED IN ACCORDANCE WITH UL 2158A. TRANSITION DUCTS SHALL BE A MAXIMUM OF 8 FEET IN LENGTH. TRANSITION DUCTS SHALL NOT BE CONCEALED WITHIN CONSTRUCTION.

EXCEPTION: THIS SECTION DOES NOT APPLY TO LISTED AND LABELED CONDENSING (DUCTLESS) CLOTHES DRYERS.
CLOTHES DRYER LENGTH LIMITATION (SECTION M1502): THE MAXIMUM LENGTH OF A CLOTHES DRYER EXHAUST DUCT SHALL BE 35 FEET FROM THE DRYER CONNECTION TO THE OUTLET TERMINAL, WHERE FITTINGS ARE USED, THE MAXIMUM LENGTH OF THE EXHAUST DUCT SHALL BE REDUCED IN ACCORDANCE WITH IRC TABLE M1502.4.1. ALTERATION OF THE SIZE AND MAXIMUM LENGTH OF THE EXHAUST DUCT SHALL BE DETERMINED BY THE DRYER MANUFACTURER'S INSTALLATION INSTRUCTIONS. THE CODE OFFICIAL SHALL BE PROVIDED WITH A COPY OF THE INSTALLATION INSTRUCTIONS FOR THE MAKE AND MODEL OF THE DRYER AT THE CONCEALMENT INSPECTION.

RANGE HOODS (SECTION R303): RANGE HOODS SHALL DISCHARGE TO THE OUTDOORS THROUGH A SINGLE-WALL DUCT. THE DUCT SERVING THE HOOD SHALL HAVE A SMOOTH INTERIOR SURFACE, SHALL BE AIR-TIGHT, SHALL BE EQUIPPED WITH A BACKDRAFT DAMPER, AND SHALL BE INDEPENDENT OF ALL OTHER EXHAUST SYSTEMS. DUCTS SERVING RANGE HOODS SHALL NOT TERMINATE IN AN ATTIC OR CRAWL SPACE OR AREAS INSIDE THE BUILDING. EXCEPTION: WHEN INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S INSTALLATION INSTRUCTIONS, AND WHERE MECHANICAL OR NATURAL VENTILATION IS OTHERWISE PROVIDED, LISTED AND LABELED DUCTLESS RANGE HOODS SHALL NOT BE REQUIRED TO DISCHARGE TO THE OUTDOORS.

STAIRWAYS (SECTION R311.7): UNDER STAIR PROTECTION (SECTION 302.7): ENCLOSED ACCESSIBLE SPACE UNDER STAIRS SHALL HAVE WALLS, UNDER-STAIR SURFACE AND ANY SOFFITS PROTECTED ON THE ENCLOSED SIDE WITH 1/2-INCH GYPSUM BOARD.

WIDTHS (SECTION R302.1): STAIRWAYS SHALL BE 36 INCHES IN CLEAR WIDTH AT ALL POINTS ABOVE THE PERMITTED HANDRAIL HEIGHT AND BELOW THE REQUIRED HEADROOM HEIGHT. HANDRAILS SHALL NOT PROJECT MORE THAN 4.5 INCHES ON EITHER SIDE OF THE STAIRWAY AND THE MINIMUM CLEAR WIDTH OF THE STAIRWAY AT AND BELOW THE HANDRAIL HEIGHT, INCLUDING TREADS AND RISERS, SHALL NOT BE LESS THAN 31-1/2 INCHES WHERE A HANDRAIL IS INSTALLED ON ONE SIDE AND 27 INCHES WHERE HANDRAILS ARE PROVIDED ON BOTH SIDES. EXCEPTION: THE WIDTH OF SPIRAL STAIRWAYS SHALL BE IN ACCORDANCE WITH SECTION R311.7.10.1.

HEADROOM: THE MINIMUM HEADROOM IN ALL PARTS OF THE STAIRWAY SHALL NOT BE LESS THAN 6 FEET 8 INCHES MEASURED VERTICALLY FROM THE SLOPED LINE ADJOINING THE TREAD NOSING OR FROM THE FLOOR SURFACE OF THE LANDING OR PLATFORM ON THAT PORTION OF THE STAIRWAY. EXCEPTION: WHERE THE NOSINGS OF TREADS AT THE SIDE OF A FLIGHT EXTEND UNDER THE EDGE OF A FLOOR OR OPENING THROUGH WHICH THE STAIR PASSES, THE CLEAR OPENING SHALL BE AT LEAST 6 FEET 8 INCHES WHERE A HANDRAIL IS INSTALLED ON ONE SIDE AND 27 INCHES WHERE HANDRAILS ARE PROVIDED ON BOTH SIDES. EXCEPTION: THE WIDTH OF SPIRAL STAIRWAYS SHALL BE IN ACCORDANCE WITH SECTION R311.7.10.1.

TREAD DEPTH: THE MINIMUM TREAD DEPTH SHALL BE 10 INCHES. THE TREAD DEPTH SHALL BE MEASURED FROM THE POINT OF CONTACT OF THE VERTICAL PLANES OF THE FOREMOST PROJECTION OF ADJACENT TREADS AND AT A RIGHT ANGLE TO THE TREAD'S LEADING EDGE. THE GREATEST TREAD DEPTH WITH ANY FLIGHT OF STAIRS SHALL NOT EXCEED THE SMALLEST BY MORE THAN 3/8 INCH. CONSISTENTLY SHAPED WINDERS AT THE WALKLINE SHALL BE ALLOWED WITHIN THE SAME FLIGHT OF STAIRS AS RECTANGULAR TREADS AND DO NOT HAVE TO WITHIN 3/8 INCH OF THE RECTANGULAR TREAD DEPTH.

WINDER TREADS: SHALL HAVE A MINIMUM TREAD DEPTH OF 10 INCHES MEASURED BETWEEN THE VERTICAL PLANES OF THE FOREMOST PROJECTION OF ADJACENT TREADS AT THE INTERSECTIONS WITH THE WALKLINE. WINDER TREADS SHALL HAVE A MINIMUM TREAD DEPTH OF 6 INCHES AT ANY POINT WITHIN THE CLEAR WIDTH OF THE STAIRS WITHIN ANY FLIGHT OF STAIRS. THE LARGEST WINDER TREAD DEPTH AT THE WALKLINE SHALL NOT EXCEED THE SMALLEST WINDER TREAD BY MORE THAN 3/8 INCH.

NOSINGS: THE RADIUS OF CURVATURE AT THE NOSING SHALL BE NO GREATER THAN 9/16 INCH. A NOSING NOT LESS THAN 3/4 INCH BUT NOT MORE THAN 1-1/4 INCHES SHALL BE PROVIDED ON STAIRWAYS WITH SOLID RISERS. THE GREATEST NOSING PROJECTION SHALL NOT EXCEED THE SMALLEST NOSING PROJECTION BY MORE THAN 3/8 INCH BETWEEN TWO STORIES, INCLUDING THE NOSING AT THE LEVEL OF FLOORS AND LANDINGS. BEVELING OF NOSINGS SHALL NOT EXCEED 1/2 INCH. RISERS SHALL BE VERTICAL, OR SLOPED UNDER THE TREAD ABOVE FROM THE UNDERSIDE OF THE NOSING. IF AT AN ANGLE NOT MORE THAN 30 DEGREES FROM THE VERTICAL, OPEN RISERS ARE PERMITTED, PROVIDED THAT THE OPENING BETWEEN TREADS DOES NOT PERMIT THE PASSAGE OF A 4-INCH DIAMETER SPHERE.

EXCEPTIONS: A NOSING IS NOT REQUIRED WHERE THE TREAD DEPTH IS A MINIMUM OF 11 INCHES.

HANDRAILS: HANDRAILS SHALL BE PROVIDED ON AT LEAST ONE SIDE OF EACH CONTINUOUS RUN OF TREADS OR FLIGHT WITH FOUR OR MORE RISERS. HANDRAIL HEIGHT, MEASURED VERTICALLY FROM THE SLOPED PLANE ADJOINING THE TREAD NOSING, OR FINISH SURFACE OF RAMP SLOPE, SHALL BE NOT LESS THAN 34 INCHES AND NOT MORE THAN 38 INCHES.

EXCEPTIONS:
1. THE USE OF A VOLUTE, TURNOUT OR STARTING EASING SHALL BE ALLOWED OVER THE LOWEST RISE OF THE STAIRS.
2. WHEN HANDRAIL FITTINGS OR BENDINGS ARE USED TO PROVIDE CONTINUOUS TRANSITION BETWEEN FLIGHTS, THE TRANSITION FROM HANDRAIL TO GUARDRAIL, OR USED AT THE START OF A FLIGHT, THE HANDRAIL HEIGHT AT THE FITTINGS OR BENDINGS SHALL BE PERMITTED TO EXCEED THE MAXIMUM HEIGHT. CONTINUITY: HANDRAILS FOR STAIRWAYS SHALL BE CONTINUOUS FROM THE FULL LENGTH OF THE FLIGHT, FROM A POINT DIRECTLY ABOVE THE TOP RISER OF THE FLIGHT TO A POINT DIRECTLY ABOVE THE LOWEST RISER OF THE FLIGHT. HANDRAIL ENDS SHALL BE RETURNED OR SHALL TERMINATE IN NEWEL POSTS OR SAFETY TERMINALS. HANDRAILS ADJACENT TO A WALL SHALL HAVE A SPACE OF NOT LESS THAN 1-1/2 INCH BETWEEN THE WALL AND THE HANDRAILS.

EXCEPTIONS:
1. HANDRAILS SHALL BE PERMITTED TO BE INTERRUPTED BY A NEWEL POST AT THE TURN.
2. THE USE OF A VOLUTE, TURNOUT, STARTING EASING OR STARTING NEWEL SHALL BE ALLOWED OVER THE LOWEST TREAD.
GRIP-SIZE: ALL REQUIRED HANDRAILS SHALL BE ONE OF THE FOLLOWING TYPES OR PROVIDE EQUIVALENT GRASPABILITY.
1. TYPE I: HANDRAILS WITH A CIRCULAR CROSS SECTION SHALL HAVE AN OUTSIDE DIAMETER OF AT LEAST 1-1/4 INCHES AND NOT GREATER THAN 2 INCHES. IF THE HANDRAIL IS NOT CIRCULAR, IT SHALL HAVE A CIRCULAR DIMENSION OF AT LEAST 4 INCHES AND NOT GREATER THAN 6-1/4 INCHES WITH A MAXIMUM CROSS SECTION OF DIMENSION OF 2-1/4 INCHES. EDGES SHALL HAVE A MINIMUM RADIUS OF 0.01 INCH.
2. TYPE II: HANDRAILS WITH A PERIMETER GREATER THAN 6-1/4 INCHES SHALL HAVE A GRASPABLE FINGER RECESS ON BOTH SIDES OF THE PROFILE. THE FINGER RECESS SHALL BEGIN WITHIN A DISTANCE OF 3/4 INCH MEASURED VERTICALLY FROM THE TALLEST PORTION OF THE PROFILE AND ACHIEVE A DEPTH OF AT LEAST 9/16 INCH. THE USE OF A VOLUTE, TURNOUT, STARTING EASING OR STARTING NEWEL SHALL BE ALLOWED OVER THE LOWEST TREAD.
GRIP-SIZE: ALL REQUIRED HANDRAILS SHALL BE ONE OF THE FOLLOWING TYPES OR PROVIDE EQUIVALENT GRASPABILITY.
1. TYPE I: HANDRAILS WITH A CIRCULAR CROSS SECTION SHALL HAVE AN OUTSIDE DIAMETER OF AT LEAST 1-1/4 INCHES AND NOT GREATER THAN 2 INCHES. IF THE HANDRAIL IS NOT CIRCULAR, IT SHALL HAVE A CIRCULAR DIMENSION OF AT LEAST 4 INCHES AND NOT GREATER THAN 6-1/4 INCHES WITH A MAXIMUM CROSS SECTION OF DIMENSION OF 2-1/4 INCHES. EDGES SHALL HAVE A MINIMUM RADIUS OF 0.01 INCH.
2. TYPE II: HANDRAILS WITH A PERIMETER GREATER THAN 6-1/4 INCHES SHALL HAVE A GRASPABLE FINGER RECESS ON BOTH SIDES OF THE PROFILE. THE FINGER RECESS SHALL BEGIN WITHIN A DISTANCE OF 3/4 INCH MEASURED VERTICALLY FROM THE TALLEST PORTION OF THE PROFILE AND ACHIEVE A DEPTH OF AT LEAST 9/16 INCH. THE USE OF A VOLUTE, TURNOUT, STARTING EASING OR STARTING NEWEL SHALL BE ALLOWED OVER THE LOWEST TREAD.
GRIP-SIZE: ALL REQUIRED HANDRAILS SHALL BE ONE OF THE FOLLOWING TYPES OR PROVIDE EQUIVALENT GRASPABILITY.
1. TYPE I: HANDRAILS WITH A CIRCULAR CROSS SECTION SHALL HAVE AN OUTSIDE DIAMETER OF AT LEAST 1-1/4 INCHES AND NOT GREATER THAN 2 INCHES. IF THE HANDRAIL IS NOT CIRCULAR, IT SHALL HAVE A CIRCULAR DIMENSION OF AT LEAST 4 INCHES AND NOT GREATER THAN 6-1/4 INCHES WITH A MAXIMUM CROSS SECTION OF DIMENSION OF 2-1/4 INCHES. EDGES SHALL HAVE A MINIMUM RADIUS OF 0.01 INCH.
2. TYPE II: HANDRAILS WITH A PERIMETER GREATER THAN 6-1/4 INCHES SHALL HAVE A GRASPABLE FINGER RECESS ON BOTH SIDES OF THE PROFILE. THE FINGER RECESS SHALL BEGIN WITHIN A DISTANCE OF 3/4 INCH MEASURED VERTICALLY FROM THE TALLEST PORTION OF THE PROFILE AND ACHIEVE A DEPTH OF AT LEAST 9/16 INCH. THE USE OF A VOLUTE, TURNOUT, STARTING EASING OR STARTING NEWEL SHALL BE ALLOWED OVER THE LOWEST TREAD.
GRIP-SIZE: ALL REQUIRED HANDRAILS SHALL BE ONE OF THE FOLLOWING TYPES OR PROVIDE EQUIVALENT GRASPABILITY.
1. TYPE I: HANDRAILS WITH A CIRCULAR CROSS SECTION SHALL HAVE AN OUTSIDE DIAMETER OF AT LEAST 1-1/4 INCHES AND NOT GREATER THAN 2 INCHES. IF THE HANDRAIL IS NOT CIRCULAR, IT SHALL HAVE A CIRCULAR DIMENSION OF AT LEAST 4 INCHES AND NOT GREATER THAN 6-1/4 INCHES WITH A MAXIMUM CROSS SECTION OF DIMENSION OF 2-1/4 INCHES. EDGES SHALL HAVE A MINIMUM RADIUS OF 0.01 INCH.
2. TYPE II: HANDRAILS WITH A PERIMETER GREATER THAN 6-1/4 INCHES SHALL HAVE A GRASPABLE FINGER RECESS ON BOTH SIDES OF THE PROFILE. THE FINGER RECESS SHALL BEGIN WITHIN A DISTANCE OF 3/4 INCH MEASURED VERTICALLY FROM THE TALLEST PORTION OF THE PROFILE AND ACHIEVE A DEPTH OF AT LEAST 9/16 INCH. THE USE OF A VOLUTE, TURNOUT, STARTING EASING OR STARTING NEWEL SHALL BE ALLOWED OVER THE LOWEST TREAD.
GRIP-SIZE: ALL REQUIRED HANDRAILS SHALL BE ONE OF THE FOLLOWING TYPES OR PROVIDE EQUIVALENT GRASPABILITY.
1. TYPE I: HANDRAILS WITH A CIRCULAR CROSS SECTION SHALL HAVE AN OUTSIDE DIAMETER OF AT LEAST 1-1/4 INCHES AND NOT GREATER THAN 2 INCHES. IF THE HANDRAIL IS NOT CIRCULAR, IT SHALL HAVE A CIRCULAR DIMENSION OF AT LEAST 4 INCHES AND NOT GREATER THAN 6-1/4 INCHES WITH A MAXIMUM CROSS SECTION OF DIMENSION OF 2-1/4 INCHES. EDGES SHALL HAVE A MINIMUM RADIUS OF 0.01 INCH.
2. TYPE II: HANDRAILS WITH A PERIMETER GREATER THAN 6-1/4 INCHES SHALL HAVE A GRASPABLE FINGER RECESS ON BOTH SIDES OF THE PROFILE. THE FINGER RECESS SHALL BEGIN WITHIN A DISTANCE OF 3/4 INCH MEASURED VERTICALLY FROM THE TALLEST PORTION OF THE PROFILE AND ACHIEVE A DEPTH OF AT LEAST 9/16 INCH. THE USE OF A VOLUTE, TURNOUT, STARTING EASING OR STARTING NEWEL SHALL BE ALLOWED OVER THE LOWEST TREAD.
GRIP-SIZE: ALL REQUIRED HANDRAILS SHALL BE ONE OF THE FOLLOWING TYPES OR PROVIDE EQUIVALENT GRASPABILITY.
1. TYPE I: HANDRAILS WITH A CIRCULAR CROSS SECTION SHALL HAVE AN OUTSIDE DIAMETER OF AT LEAST 1-1/4 INCHES AND NOT GREATER THAN 2 INCHES. IF THE HANDRAIL IS NOT CIRCULAR, IT SHALL HAVE A CIRCULAR DIMENSION OF AT LEAST 4 INCHES AND NOT GREATER THAN 6-1/4 INCHES WITH A MAXIMUM CROSS SECTION OF DIMENSION OF 2-1/4 INCHES. EDGES SHALL HAVE A MINIMUM RADIUS OF 0.01 INCH.
2. TYPE II: HANDRAILS WITH A PERIMETER GREATER THAN 6-1/4 INCHES SHALL HAVE A GRASPABLE FINGER RECESS ON BOTH SIDES OF THE PROFILE. THE FINGER RECESS SHALL BEGIN WITHIN A DISTANCE OF 3/4 INCH MEASURED VERTICALLY FROM THE TALLEST PORTION OF THE PROFILE AND ACHIEVE A DEPTH OF AT LEAST 9/16 INCH. THE USE OF A VOLUTE, TURNOUT, STARTING EASING OR STARTING NEWEL SHALL BE ALLOWED OVER THE LOWEST TREAD.
GRIP-SIZE: ALL REQUIRED HANDRAILS SHALL BE ONE OF THE FOLLOWING TYPES OR PROVIDE EQUIVALENT GRASPABILITY.
1. TYPE I: HANDRAILS WITH A CIRCULAR CROSS SECTION SHALL HAVE AN OUTSIDE DIAMETER OF AT LEAST 1-1/4 INCHES AND NOT GREATER THAN 2 INCHES. IF THE HANDRAIL IS NOT CIRCULAR, IT SHALL HAVE A CIRCULAR DIMENSION OF AT LEAST 4 INCHES AND NOT GREATER THAN 6-1/4 INCHES WITH A MAXIMUM CROSS SECTION OF DIMENSION OF 2-1/4 INCHES. EDGES SHALL HAVE A MINIMUM RADIUS OF 0.01 INCH.
2. TYPE II: HANDRAILS WITH A PERIMETER GREATER THAN 6-1/4 INCHES SHALL HAVE A GRASPABLE FINGER RECESS ON BOTH SIDES OF THE PROFILE. THE FINGER RECESS SHALL BEGIN WITHIN A DISTANCE OF 3/4 INCH MEASURED VERTICALLY FROM THE TALLEST PORTION OF THE PROFILE AND ACHIEVE A DEPTH OF AT LEAST 9/16 INCH. THE USE OF A VOLUTE, TURNOUT, STARTING EASING OR STARTING NEWEL SHALL BE ALLOWED OVER THE LOWEST TREAD.
GRIP-SIZE: ALL REQUIRED HANDRAILS SHALL BE ONE OF THE FOLLOWING TYPES OR PROVIDE EQUIVALENT GRASPABILITY.
1. TYPE I: HANDRAILS WITH A CIRCULAR CROSS SECTION SHALL HAVE AN OUTSIDE DIAMETER OF AT LEAST 1-1/4 INCHES AND NOT GREATER THAN 2 INCHES. IF THE HANDRAIL IS NOT CIRCULAR, IT SHALL HAVE A CIRCULAR DIMENSION OF AT LEAST 4 INCHES AND NOT GREATER THAN 6-1/4 INCHES WITH A MAXIMUM CROSS SECTION OF DIMENSION OF 2-1/4 INCHES. EDGES SHALL HAVE A MINIMUM RADIUS OF 0.01 INCH.
2. TYPE II: HANDRAILS WITH A PERIMETER GREATER THAN 6-1/4 INCHES SHALL HAVE A GRASPABLE FINGER RECESS ON BOTH SIDES OF THE PROFILE. THE FINGER RECESS SHALL BEGIN WITHIN A DISTANCE OF 3/4 INCH MEASURED VERTICALLY FROM THE TALLEST PORTION OF THE PROFILE AND ACHIEVE A DEPTH OF AT LEAST 9/16 INCH. THE USE OF A VOLUTE, TURNOUT, STARTING EASING OR STARTING NEWEL SHALL BE ALLOWED OVER THE LOWEST TREAD.
GRIP-SIZE: ALL REQUIRED HANDRAILS SHALL BE ONE OF THE FOLLOWING TYPES OR PROVIDE EQUIVALENT GRASPABILITY.
1. TYPE I: HANDRAILS WITH A CIRCULAR CROSS SECTION SHALL HAVE AN OUTSIDE DIAMETER OF AT LEAST 1-1/4 INCHES AND NOT GREATER THAN 2 INCHES. IF THE HANDRAIL IS NOT CIRCULAR, IT SHALL HAVE A CIRCULAR DIMENSION OF AT LEAST 4 INCHES AND NOT GREATER THAN 6-1/4 INCHES WITH A MAXIMUM CROSS SECTION OF DIMENSION OF 2-1/4 INCHES. EDGES SHALL HAVE A MINIMUM RADIUS OF 0.01 INCH.
2. TYPE II: HANDRAILS WITH A PERIMETER GREATER THAN 6-1/4 INCHES SHALL HAVE A GRASPABLE FINGER RECESS ON BOTH SIDES OF THE PROFILE. THE FINGER RECESS SHALL BEGIN WITHIN A DISTANCE OF 3/4 INCH MEASURED VERTICALLY FROM THE TALLEST PORTION OF THE PROFILE AND ACHIEVE A DEPTH OF AT LEAST 9/16 INCH. THE USE OF A VOLUTE, TURNOUT, STARTING EASING OR STARTING NEWEL SHALL BE ALLOWED OVER THE LOWEST TREAD.
GRIP-SIZE: ALL REQUIRED HANDRAILS SHALL BE ONE OF THE FOLLOWING TYPES OR PROVIDE EQUIVALENT GRASPABILITY.
1. TYPE I: HANDRAILS WITH A CIRCULAR CROSS SECTION SHALL HAVE AN OUTSIDE DIAMETER OF AT LEAST 1-1/4 INCHES AND NOT GREATER THAN 2 INCHES. IF THE HANDRAIL IS NOT CIRCULAR, IT SHALL HAVE A CIRCULAR DIMENSION OF AT LEAST 4 INCHES AND NOT GREATER THAN 6-1/4 INCHES WITH A MAXIMUM CROSS SECTION OF DIMENSION OF 2-1/4 INCHES. EDGES SHALL HAVE A MINIMUM RADIUS OF 0.01 INCH.
2. TYPE II: HANDRAILS WITH A PERIMETER GREATER THAN 6-1/4 INCHES SHALL HAVE A GRASPABLE FINGER RECESS ON BOTH SIDES OF THE PROFILE. THE FINGER RECESS SHALL BEGIN WITHIN A DISTANCE OF 3/4 INCH MEASURED VERTICALLY FROM THE TALLEST PORTION OF THE PROFILE AND ACHIEVE A DEPTH OF AT LEAST 9/16 INCH. THE USE OF A VOLUTE, TURNOUT, STARTING EASING OR STARTING NEWEL SHALL BE ALLOWED OVER THE LOWEST TREAD.
GRIP-SIZE: ALL REQUIRED HANDRAILS SHALL BE ONE OF THE FOLLOWING TYPES OR PROVIDE EQUIVALENT GRASPABILITY.
1. TYPE I: HANDRAILS WITH A CIRCULAR CROSS SECTION SHALL HAVE AN OUTSIDE DIAMETER OF AT LEAST 1-1/4 INCHES AND NOT GREATER THAN 2 INCHES. IF THE HANDRAIL IS NOT CIRCULAR, IT SHALL HAVE A CIRCULAR DIMENSION OF AT LEAST 4 INCHES AND NOT GREATER THAN 6-1/4 INCHES WITH A MAXIMUM CROSS SECTION OF DIMENSION OF 2-1/4 INCHES. EDGES SHALL HAVE A MINIMUM RADIUS OF 0.01 INCH.
2. TYPE II: HANDRAILS WITH A PERIMETER GREATER THAN 6-1/4 INCHES SHALL HAVE A GRASPABLE FINGER RECESS ON BOTH SIDES OF THE PROFILE. THE FINGER RECESS SHALL BEGIN WITHIN A DISTANCE OF 3/4 INCH MEASURED VERTICALLY FROM THE TALLEST PORTION OF THE PROFILE AND ACHIEVE A DEPTH OF AT LEAST 9/16 INCH. THE USE OF A VOLUTE, TURNOUT, STARTING EASING OR STARTING NEWEL SHALL BE ALLOWED OVER THE LOWEST TREAD.
GRIP-SIZE: ALL REQUIRED HANDRAILS SHALL BE ONE OF THE FOLLOWING TYPES OR PROVIDE EQUIVALENT GRASPABILITY.
1. TYPE I: HANDRAILS WITH A CIRCULAR CROSS SECTION SHALL HAVE AN OUTSIDE DIAMETER OF AT LEAST 1-1/4 INCHES AND NOT GREATER THAN 2 INCHES. IF THE HANDRAIL IS NOT CIRCULAR, IT SHALL HAVE A CIRCULAR DIMENSION OF AT LEAST 4 INCHES AND NOT GREATER THAN 6-1/4 INCHES WITH A MAXIMUM CROSS SECTION OF DIMENSION OF 2-1/4 INCHES. EDGES SHALL HAVE A MINIMUM RADIUS OF 0.01 INCH.
2. TYPE II: HANDRAILS WITH A PERIMETER GREATER THAN 6-1/4 INCHES SHALL HAVE A GRASPABLE FINGER RECESS ON BOTH SIDES OF THE PROFILE. THE FINGER RECESS SHALL BEGIN WITHIN A DISTANCE OF 3/4 INCH MEASURED VERTICALLY FROM THE TALLEST PORTION OF THE PROFILE AND ACHIEVE A DEPTH OF AT LEAST 9/16 INCH. THE USE OF A VOLUTE, TURNOUT, STARTING EASING OR STARTING NEWEL SHALL BE ALLOWED OVER THE LOWEST TREAD.
GRIP-SIZE: ALL REQUIRED HANDRAILS SHALL BE ONE OF THE FOLLOWING TYPES OR PROVIDE EQUIVALENT GRASPABILITY.
1. TYPE I: HANDRAILS WITH A CIRCULAR CROSS SECTION SHALL HAVE AN OUTSIDE DIAMETER OF AT LEAST 1-1/4 INCHES AND NOT GREATER THAN 2 INCHES. IF THE HANDRAIL IS NOT CIRCULAR, IT SHALL HAVE A CIRCULAR DIMENSION OF AT LEAST 4 INCHES AND NOT GREATER THAN 6-1/4 INCHES WITH A MAXIMUM CROSS SECTION OF DIMENSION OF 2-1/4 INCHES. EDGES SHALL HAVE A MINIMUM RADIUS OF 0.01 INCH.
2. TYPE II: HANDRAILS WITH A PERIMETER GREATER THAN 6-1/4 INCHES SHALL HAVE A GRASPABLE FINGER RECESS ON BOTH SIDES OF THE PROFILE. THE FINGER RECESS SHALL BEGIN WITHIN A DISTANCE OF 3/4 INCH MEASURED VERTICALLY FROM THE TALLEST PORTION OF THE PROFILE AND ACHIEVE A DEPTH OF AT LEAST 9/16 INCH. THE USE OF A VOLUTE, TURNOUT, STARTING EASING OR STARTING NEWEL SHALL BE ALLOWED OVER THE LOWEST TREAD.
GRIP-SIZE: ALL REQUIRED HANDRAILS SHALL BE ONE OF THE FOLLOWING TYPES OR PROVIDE EQUIVALENT GRASPABILITY.
1. TYPE I: HANDRAILS WITH A CIRCULAR CROSS SECTION SHALL HAVE AN OUTSIDE DIAMETER OF AT LEAST 1-1/4 INCHES AND NOT GREATER THAN 2 INCHES. IF THE HANDRAIL IS NOT CIRCULAR, IT SHALL HAVE A CIRCULAR DIMENSION OF AT LEAST 4 INCHES AND NOT GREATER THAN 6-1/4 INCHES WITH A MAXIMUM CROSS SECTION OF DIMENSION OF 2-1/4 INCHES. EDGES SHALL HAVE A MINIMUM RADIUS OF 0.01 INCH.
2. TYPE II: HANDRAILS WITH A PERIMETER GREATER THAN 6-1/4 INCHES SHALL HAVE A GRASPABLE FINGER RECESS ON BOTH SIDES OF THE PROFILE. THE FINGER RECESS SHALL BEGIN WITHIN A DISTANCE OF 3/4 INCH MEASURED VERTICALLY FROM THE TALLEST PORTION OF THE PROFILE AND ACHIEVE A DEPTH OF AT LEAST 9/16 INCH. THE USE OF A VOLUTE, TURNOUT, STARTING EASING OR STARTING NEWEL SHALL BE ALLOWED OVER THE LOWEST TREAD.
GRIP-SIZE: ALL REQUIRED HANDRAILS SHALL BE ONE OF THE FOLLOWING TYPES OR PROVIDE EQUIVALENT GRASPABILITY.
1. TYPE I: HANDRAILS WITH A CIRCULAR CROSS SECTION SHALL HAVE AN OUTSIDE DIAMETER OF AT LEAST 1-1/4 INCHES AND NOT GREATER THAN 2 INCHES. IF THE HANDRAIL IS NOT CIRCULAR, IT SHALL HAVE A CIRCULAR DIMENSION OF AT LEAST 4 INCHES AND NOT GREATER THAN 6-1/4 INCHES WITH A MAXIMUM CROSS SECTION OF DIMENSION OF 2-1/4 INCHES. EDGES SHALL HAVE A MINIMUM RADIUS OF 0.01 INCH.
2. TYPE II: HANDRAILS WITH A PERIMETER GREATER THAN 6-1/4 INCHES SHALL HAVE A GRASPABLE FINGER RECESS ON BOTH SIDES OF THE PROFILE. THE FINGER RECESS SHALL BEGIN WITHIN A DISTANCE OF 3/4 INCH MEASURED VERTICALLY FROM THE TALLEST PORTION OF THE PROFILE AND ACHIEVE A DEPTH OF AT LEAST 9/16 INCH. THE USE OF A VOLUTE, TURNOUT, STARTING EASING OR STARTING NEWEL SHALL BE ALLOWED OVER THE LOWEST TREAD.
GRIP-SIZE: ALL REQUIRED HANDRAILS SHALL BE ONE OF THE FOLLOWING TYPES OR PROVIDE EQUIVALENT GRASPABILITY.
1. TYPE I: HANDRAILS WITH A CIRCULAR CROSS SECTION SHALL HAVE AN OUTSIDE DIAMETER OF AT LEAST 1-1/4 INCHES AND NOT GREATER THAN 2 INCHES. IF THE HANDRAIL IS NOT CIRCULAR, IT SHALL HAVE A CIRCULAR DIMENSION OF AT LEAST 4 INCHES AND NOT GREATER THAN 6-1/4 INCHES WITH A MAXIMUM CROSS SECTION OF DIMENSION OF 2-1/4 INCHES. EDGES SHALL HAVE A MINIMUM RADIUS OF 0.01 INCH.
2. TYPE II: HANDRAILS WITH A PERIMETER GREATER THAN 6-1/4 INCHES SHALL HAVE A GRASPABLE FINGER RECESS ON BOTH SIDES OF THE PROFILE. THE FINGER RECESS SHALL BEGIN WITHIN A DISTANCE OF 3/4 INCH MEASURED VERTICALLY FROM THE TALLEST PORTION OF THE PROFILE AND ACHIEVE A DEPTH OF AT LEAST 9/16 INCH. THE USE OF A VOLUTE, TURNOUT, STARTING EASING OR STARTING NEWEL SHALL BE ALLOWED OVER THE LOWEST TREAD.
GRIP-SIZE: ALL REQUIRED HANDRAILS SHALL BE ONE OF THE FOLLOWING TYPES OR PROVIDE EQUIVALENT GRASPABILITY.
1. TYPE I: HANDRAILS WITH A CIRCULAR CROSS SECTION SHALL HAVE AN OUTSIDE DIAMETER OF AT LEAST 1-1/4 INCHES AND NOT GREATER THAN 2 INCHES. IF THE HANDRAIL IS NOT CIRCULAR, IT SHALL HAVE A CIRCULAR DIMENSION OF AT LEAST 4 INCHES AND NOT GREATER THAN 6-1/4 INCHES WITH A MAXIMUM CROSS SECTION OF DIMENSION OF 2-1/4 INCHES. EDGES SHALL HAVE A MINIMUM RADIUS OF 0.01 INCH.
2. TYPE II: HANDRAILS WITH A PERIMETER GREATER THAN 6-1/4 INCHES SHALL HAVE A GRASPABLE FINGER RECESS ON BOTH SIDES OF THE PROFILE. THE FINGER RECESS SHALL BEGIN WITHIN A DISTANCE OF 3/4 INCH MEASURED VERTICALLY FROM THE TALLEST PORTION OF THE PROFILE AND ACHIEVE A DEPTH OF AT LEAST 9/16 INCH. THE USE OF A VOLUTE, TURNOUT, STARTING EASING OR STARTING NEWEL SHALL BE ALLOWED OVER THE LOWEST TREAD.
GRIP-SIZE: ALL REQUIRED HANDRAILS SHALL BE ONE OF THE FOLLOWING TYPES OR PROVIDE EQUIVALENT GRASPABILITY.
1. TYPE I: HANDRAILS WITH A CIRCULAR CROSS SECTION SHALL HAVE AN OUTSIDE DIAMETER OF AT LEAST 1-1/4 INCHES AND NOT GREATER THAN 2 INCHES. IF THE HANDRAIL IS NOT CIRCULAR, IT SHALL HAVE A CIRCULAR DIMENSION OF AT LEAST 4 INCHES AND NOT GREATER THAN 6-1/4 INCHES WITH A MAXIMUM CROSS SECTION OF DIMENSION OF 2-1/4 INCHES. EDGES SHALL HAVE A MINIMUM RADIUS OF 0.01 INCH.
2. TYPE II: HANDRAILS WITH A PERIMETER GREATER THAN 6-1/4 INCHES SHALL HAVE A GRASPABLE FINGER RECESS ON BOTH SIDES OF THE PROFILE. THE FINGER RECESS SHALL BEGIN WITHIN A DISTANCE OF 3/4 INCH MEASURED VERTICALLY FROM THE TALLEST PORTION OF THE PROFILE AND ACHIEVE A DEPTH OF AT LEAST 9/16 INCH. THE USE OF A VOLUTE, TURNOUT, STARTING EASING OR STARTING NEWEL SHALL BE ALLOWED OVER THE LOWEST TREAD.
GRIP-SIZE: ALL REQUIRED HANDRAILS SHALL BE ONE OF THE FOLLOWING TYPES OR PROVIDE EQUIVALENT GRASPABILITY.
1. TYPE I: HANDRAILS WITH A CIRCULAR CROSS SECTION SHALL HAVE AN OUTSIDE DIAMETER OF AT LEAST 1-1/4 INCHES AND NOT GREATER THAN 2 INCHES. IF THE HANDRAIL IS NOT CIRCULAR, IT SHALL HAVE A CIRCULAR DIMENSION OF AT LEAST 4 INCHES AND NOT GREATER THAN 6-1/4 INCHES WITH A MAXIMUM CROSS SECTION OF DIMENSION OF 2-1/4 INCHES. EDGES SHALL HAVE A MINIMUM RADIUS OF 0.01 INCH.
2. TYPE II: HANDRAILS WITH A PERIMETER GREATER THAN 6-1/4 INCHES SHALL HAVE A GRASPABLE FINGER RECESS ON BOTH SIDES OF THE PROFILE. THE FINGER RECESS SHALL BEGIN WITHIN A DISTANCE OF 3/4 INCH MEASURED VERTICALLY FROM THE TALLEST PORTION OF THE PROFILE AND ACHIEVE A DEPTH OF AT LEAST 9/16 INCH. THE USE OF A VOLUTE, TURNOUT, STARTING EASING OR STARTING NEWEL SHALL BE ALLOWED OVER THE LOWEST TREAD.
GRIP-SIZE: ALL REQUIRED HANDRAILS SHALL BE ONE OF THE FOLLOWING TYPES OR PROVIDE EQUIVALENT GRASPABILITY.
1. TYPE I: HANDRAILS WITH A CIRCULAR CROSS SECTION SHALL HAVE AN OUTSIDE DIAMETER OF AT LEAST 1-1/4 INCHES AND NOT GREATER THAN 2 INCHES. IF THE HANDRAIL IS NOT CIRCULAR, IT SHALL HAVE A CIRCULAR DIMENSION OF AT LEAST 4 INCHES AND NOT GREATER THAN 6-1/4 INCHES WITH A MAXIMUM CROSS SECTION OF DIMENSION OF 2-1/4 INCHES. EDGES SHALL HAVE A MINIMUM RADIUS OF 0.01 INCH.
2. TYPE II: HANDRAILS WITH A PERIMETER GREATER THAN 6-1/4 INCHES SHALL HAVE A GRASPABLE FINGER RECESS ON BOTH SIDES OF THE PROFILE. THE FINGER RECESS SHALL BEGIN WITHIN A DISTANCE OF 3/4 INCH MEASURED VERTICALLY FROM THE TALLEST PORTION OF THE PROFILE AND ACHIEVE A DEPTH OF AT LEAST 9/16 INCH. THE USE OF A VOLUTE, TURNOUT, STARTING EASING OR STARTING NEWEL SHALL BE ALLOWED OVER THE LOWEST TREAD.
GRIP-SIZE: ALL REQUIRED HANDRAILS SHALL BE ONE OF THE FOLLOWING TYPES OR PROVIDE EQUIVALENT GRASPABILITY.
1. TYPE I: HANDRAILS WITH A CIRCULAR CROSS SECTION SHALL HAVE AN OUTSIDE DIAMETER OF AT LEAST 1-1/4 INCHES AND NOT GREATER THAN 2 INCHES. IF THE HANDRAIL IS NOT CIRCULAR, IT SHALL HAVE A CIRCULAR DIMENSION OF AT LEAST 4 INCHES AND NOT GREATER THAN 6-1/4 INCHES WITH A MAXIMUM CROSS SECTION OF DIMENSION OF 2-1/4 INCHES. EDGES SHALL HAVE A MINIMUM RADIUS OF 0.01 INCH.
2. TYPE II: HANDRAILS WITH A PERIMETER GREATER THAN 6-1/4 INCHES SHALL HAVE A GRASPABLE FINGER RECESS ON BOTH SIDES OF THE PROFILE. THE FINGER RECESS SHALL BEGIN WITHIN A DISTANCE OF 3/4 INCH MEASURED VERTICALLY FROM THE TALLEST PORTION OF THE PROFILE AND ACHIEVE A DEPTH OF AT LEAST 9/16 INCH. THE USE OF A VOLUTE, TURNOUT, STARTING EASING OR STARTING NEWEL SHALL BE ALLOWED OVER THE LOWEST TREAD.
GRIP-SIZE: ALL REQUIRED HANDRAILS SHALL BE ONE OF THE FOLLOWING TYPES OR PROVIDE EQUIVALENT GRASPABILITY.
1. TYPE I: HANDRAILS WITH A CIRCULAR CROSS SECTION SHALL HAVE AN OUTSIDE DIAMETER OF AT LEAST 1-1/4 INCHES AND NOT GREATER THAN 2 INCHES. IF THE HANDRAIL IS NOT CIRCULAR, IT SHALL HAVE A CIRCULAR DIMENSION OF AT LEAST 4 INCHES AND NOT GREATER THAN 6-1/4 INCHES WITH A MAXIMUM CROSS SECTION OF DIMENSION OF 2-1/4 INCHES. EDGES SHALL HAVE A MINIMUM RADIUS OF 0.01 INCH.
2. TYPE II: HANDRAILS WITH A PERIMETER GREATER THAN 6-1/4 INCHES SHALL HAVE A GRASPABLE FINGER RECESS ON BOTH SIDES OF THE PROFILE. THE FINGER RECESS SHALL BEGIN WITHIN A DISTANCE OF 3/4 INCH MEASURED VERTICALLY FROM THE TALLEST PORTION OF THE PROFILE AND ACHIEVE A DEPTH OF AT LEAST 9/16 INCH. THE USE OF A VOLUTE, TURNOUT, STARTING EASING OR STARTING NEWEL SHALL BE ALLOWED OVER THE LOWEST TREAD.
GRIP-SIZE: ALL REQUIRED HANDRAILS SHALL BE ONE OF THE FOLLOWING TYPES OR PROVIDE EQUIVALENT GRASPABILITY.
1. TYPE I: HANDRAILS WITH A CIRCULAR CROSS SECTION SHALL HAVE AN OUTSIDE DIAMETER OF AT LEAST 1-1/4 INCHES AND NOT GREATER THAN 2 INCHES. IF THE HANDRAIL IS NOT CIRCULAR, IT SHALL HAVE A CIRCULAR DIMENSION OF AT LEAST 4 INCHES AND NOT GREATER THAN 6-1/4 INCHES WITH A MAXIMUM CROSS SECTION OF DIMENSION OF 2-1/4 INCHES. EDGES SHALL HAVE A MINIMUM RADIUS OF 0.01 INCH.
2. TYPE II: HANDRAILS WITH A PERIMETER GREATER THAN 6-1/4 INCHES SHALL HAVE A GRASPABLE FINGER RECESS ON BOTH SIDES OF THE PROFILE. THE FINGER RECESS SHALL BEGIN WITHIN A DISTANCE OF 3/4 INCH MEASURED VERTICALLY FROM THE TALLEST PORTION OF THE PROFILE AND ACHIEVE A DEPTH OF AT LEAST 9/16 INCH. THE USE OF A VOLUTE, TURNOUT, STARTING EASING OR STARTING NEWEL SHALL BE ALLOWED OVER THE LOWEST TREAD.
GRIP-SIZE: ALL REQUIRED HANDRAILS SHALL BE ONE OF THE FOLLOWING TYPES OR PROVIDE EQUIVALENT GRASPABILITY.
1. TYPE I: HANDRAILS WITH A CIRCULAR CROSS SECTION SHALL HAVE AN OUTSIDE DIAMETER OF AT LEAST 1-1/4 INCHES AND NOT GREATER THAN 2 INCHES. IF THE HANDRAIL IS NOT CIRCULAR, IT SHALL HAVE A CIRCULAR DIMENSION OF AT LEAST 4 INCHES AND NOT GREATER THAN 6-1/4 INCHES WITH A MAXIMUM CROSS SECTION OF DIMENSION OF 2-1/4 INCHES. EDGES SHALL HAVE A MINIMUM RADIUS OF 0.01 INCH.
2. TYPE II: HANDRAILS WITH A PERIMETER GREATER THAN 6-1/4 INCHES SHALL HAVE A GRASPABLE FINGER RECESS ON BOTH SIDES OF THE PROFILE. THE FINGER RECESS SHALL BEGIN WITHIN A DISTANCE OF 3/4 INCH MEASURED VERTICALLY FROM THE TALLEST PORTION OF THE PROFILE AND ACHIEVE A DEPTH OF AT LEAST 9/16 INCH. THE USE OF A VOLUTE, TURNOUT, STARTING EASING OR STARTING NEWEL SHALL BE ALLOWED OVER THE LOWEST TREAD.
GRIP-SIZE: ALL REQUIRED HANDRAILS SHALL BE ONE OF THE FOLLOWING TYPES OR PROVIDE EQUIVALENT GRASPABILITY.
1. TYPE I: HANDRAILS WITH A CIRCULAR CROSS SECTION SHALL HAVE AN OUTSIDE DIAMETER OF AT LEAST 1-1/4 INCHES AND NOT GREATER THAN 2 INCHES. IF THE HANDRAIL IS NOT CIRCULAR, IT SHALL HAVE A CIRCULAR DIMENSION OF AT LEAST 4 INCHES AND NOT GREATER THAN 6-1/4 INCHES WITH A MAXIMUM CROSS SECTION OF DIMENSION OF 2-1/4 INCHES. EDGES SHALL HAVE A MINIMUM RADIUS OF 0.01 INCH.
2. TYPE II: HANDRAILS WITH A PERIMETER GREATER THAN 6-1/4 INCHES SHALL HAVE A GRASPABLE FINGER RECESS ON BOTH SIDES OF THE PROFILE. THE FINGER RECESS SHALL BEGIN WITHIN A DISTANCE OF 3/4 INCH MEASURED VERTICALLY FROM THE TALLEST PORTION OF THE PROFILE AND ACHIEVE A DEPTH OF AT LEAST 9/16 INCH. THE USE OF A VOLUTE, TURNOUT, STARTING EASING OR STARTING NEWEL SHALL BE ALLOWED OVER THE LOWEST TREAD.
GRIP-SIZE: ALL REQUIRED HANDRAILS SHALL BE ONE OF THE FOLLOWING TYPES OR PROVIDE EQUIVALENT GRASPABILITY.
1. TYPE I: HANDRAILS WITH A CIRCULAR CROSS SECTION SHALL HAVE AN OUTSIDE DIAMETER OF AT LEAST 1-1/4 INCHES AND NOT GREATER THAN 2 INCHES. IF THE HANDRAIL IS NOT CIRCULAR, IT SHALL HAVE A CIRCULAR DIMENSION OF AT LEAST 4 INCHES AND NOT GREATER THAN 6-1/4 INCHES WITH A MAXIMUM CROSS SECTION OF DIMENSION OF 2-1/4 INCHES. EDGES SHALL HAVE A MINIMUM RADIUS OF 0.01 INCH.
2. TYPE II: HANDRAILS WITH A PERIMETER GREATER THAN 6-1/4 INCHES SHALL HAVE A GRASPABLE FINGER RECESS ON BOTH SIDES OF THE PROFILE. THE FINGER RECESS SHALL BEGIN WITHIN A DISTANCE OF 3/4 INCH MEASURED VERTICALLY FROM THE TALLEST PORTION OF THE PROFILE AND ACHIEVE A DEPTH OF AT LEAST 9/16 INCH. THE USE OF A VOLUTE, TURNOUT, STARTING EASING OR STARTING NEWEL SHALL BE ALLOWED OVER THE LOWEST TREAD.
GRIP-SIZE: ALL REQUIRED HANDRAILS SHALL BE ONE OF THE FOLLOWING TYPES OR PROVIDE EQUIVALENT GRASPABILITY.
1. TYPE I: HANDRAILS WITH A CIRCULAR CROSS SECTION SHALL HAVE AN OUTSIDE DIAMETER OF AT LEAST 1-1/4 INCHES AND NOT GREATER THAN 2 INCHES. IF THE HANDRAIL IS NOT CIRCULAR, IT SHALL HAVE A CIRCULAR DIMENSION OF AT LEAST 4 INCHES AND NOT GREATER THAN 6-1/4 INCHES WITH A MAXIMUM CROSS SECTION OF DIMENSION OF 2-1/4 INCHES. EDGES SHALL HAVE A MINIMUM RADIUS OF 0.01 INCH.
2. TYPE II: HANDRAILS WITH A PERIMETER GREATER THAN 6-1/4 INCHES SHALL HAVE A GRASPABLE FINGER RECESS ON BOTH SIDES OF THE PROFILE. THE FINGER RECESS SHALL BEGIN WITHIN A DISTANCE OF 3/4 INCH MEASURED VERTICALLY FROM THE TALLEST PORTION OF THE PROFILE AND ACHIEVE A DEPTH OF AT LEAST 9/16 INCH. THE USE OF A VOLUTE, TURNOUT, STARTING EASING OR STARTING NEWEL SHALL BE ALLOWED OVER THE LOWEST TREAD.
GRIP-SIZE: ALL REQUIRED HANDRAILS


A PORTION OF THE SE QUARTER OF SECTION 01, TOWNSHIP 24 N., RANGE 04 E., W.M.

EROSION CONTROL NOTES

- 1. PROVIDE AND MAINTAIN TEMPORARY SEDIMENTATION COLLECTION FACILITIES TO ENSURE THAT SEDIMENT OR OTHER HAZARDOUS MATERIALS DO NOT ENTER THE STORM DRAINAGE SYSTEM... 2. EXPOSED SOILS SHALL BE WORKED DURING THE WEEK UNTIL THEY HAVE BEEN STABILIZED... 3. ANY AND ALL POLLUTANTS, CHEMICALS, LIQUID PRODUCTS, AND OTHER MATERIALS THAT HAVE THE POTENTIAL TO POSE A THREAT TO HUMAN HEALTH... 4. BEST MANAGEMENT PRACTICES OR BMPs SHALL BE INSPECTED AND MAINTAINED DURING CONSTRUCTION...


SUGGESTED SWPPP SEQUENACE

- 1. MARK CLEARING LIMITS, CRITICAL AREAS, AND BUFFER. THE PERIMETER OF THE AREA TO BE CLEARED SHALL BE MARKED PRIOR TO CLEARING OPERATION WITH VISIBLE FLAGGING, ORANGE PLASTIC BARRIER FENCING AND/OR ORANGE SILT FENCING AS SHOWN ON THE SWPPP SITE MAP... 2. INSTALL STABILIZED CONSTRUCTION ENTRANCE WHERE NECESSARY... 3. INSTALL PROTECTION FOR EXISTING DRAINAGE SYSTEMS AND PERMANENT DRAIN INLETS... 4. ESTABLISH STAGING AREAS FOR STORAGE AND HANDLING POLLUTED MATERIAL AND BMPs... 5. INSTALL SEDIMENT CONTROL BMPs... 6. GRADE AND INSTALL STABILIZATION MEASURES FOR DISTURBED AREAS... 7. MAINTAIN BMPs UNTIL SITE STABILIZATION, AT WHICH TIME THEY MAY BE REMOVED



TYPICAL FILTER FENCE DETAIL

NOT TO SCALE



- Tree Protection Zone (TPZ)
- Extends from tree trunk to 1 foot for every inch of trunk diameter measured at 4.5 feet above grade or 6' whichever is greater.
- Protective fencing to remain installed at all times.
- Working within TPZ restricted to City approved personnel and supervised by Project Arborist.
- No storage of equipment or materials within TPZ, or washing of equipment in or within 10' of TPZ.

- Tree Protection Fencing
- Minimum 6' chain link fencing installed completely around TPZ consistent with Site Plan. See Tree Protection Detail TP-2.
- Fencing shall have 1.5" steel posts to be driven 2' into the ground no more than 10' apart.
- Tree protection signs shall be posted on fencing no more than 20' apart.
- Apply a 4-6" layer of wood chips 12" from tree trunk.

- Drip Line
- Extends from trunk to outer canopy edge - Drip Line.
- Absolutely no storage of equipment or materials within Drip Line.
- Access restricted based on City approval and Project Arborist supervision required.
- No trenching within Drip Line, tunneling must have approval from City.

- Root Protection in Tree Protection Zone
- Use/access into TPZ shall be upon approval from City and supervised by Project Arborist.
- Additional layer of 3" gravel and 3/4" plywood shall cover Drip Line when authorized work being performed in TPZ.
- All wood chips, gravel and plywood to be removed by hand upon project completion.

TREE PROTECTION DETAIL

NOT TO SCALE

PERMANENT & TEMPORARY SEEDING




- 1. SEEDING MAY BE USED THROUGHOUT THE PROJECT ON DISTURBED AREAS THAT HAVE REACHED FINAL GRADE OR THAT WILL REMAIN UNWORKED. SEED AND MULCH ALL DISTURBED AREAS NOT OTHERWISE VEGETATED OR STABILIZED.
2. SEED DURING SEASONS MOST CONDUCTED TO PLANT GROWTH. FOR WASHINGTON THIS IS BETWEEN APRIL 1 THROUGH JUNE 20 AND SEPTEMBER 1 THROUGH OCTOBER 1. SEEDING THAT OCCURS BETWEEN JULY 1 AND AUGUST 30 WILL REQUIRE IRRIGATION UNTIL 5 PERCENT GRASS COVER IS ESTABLISHED. SEEDING THAT OCCURS BETWEEN OCTOBER 1 AND MARCH 30 MAY REQUIRE MULCH OR PLASTIC COVER UNTIL 75 PERCENT GRASS COVER IS ESTABLISHED.
3. REFER TO BMP C120 IN THE STORMWATER MANUAL FOR WESTERN WASHINGTON: VOLUME II FOR FURTHER DETAILS.

MAPPING NOTES

- 1. SITE BOUNDARY AND CONTOURS PROVIDED BY TERRANE SURVEYING, MAPS DATED 01/07/19.
2. HOUSE, SITE LAYOUT, WATERCOURSE LOCATION WITH ASSOCIATED BUFFER PROVIDED BY MZA ARCHITECTURE ON 01/17/19.
3. CONTRACTOR SHALL VERIFY HORIZONTAL AND VERTICAL LOCATIONS OF ALL UTILITIES PRIOR TO CONSTRUCTION OF SPECIFIC UTILITY.
4. CONTRACTOR SHALL KEEP DETAILED NOTES FOR USE DURING ASBUILT DRAWING PREPARATION.
5. TREE NUMBERS PER ARBORISTS NW, LLC REPORT


ROCK-LINED CONSTRUCTION ENTRANCE DETAIL

NOT TO SCALE



CALL 48 HOURS BEFORE YOU DIG 811

REVISIONS table with columns for NO., DESCRIPTION/DATE, and BY.



ESM CONSULTING ENGINEERS LLC
53400 8th Ave S, Suite 205
Everett, WA 98005
www.esmcivil.com
Civil Engineering, Land Surveying, Project Management, Public Works, Landscape Architecture

MZA ARCHITECTURE
PAEK RESIDENCE
CITY OF MERCER ISLAND, WASHINGTON
DEMO & TESC PLAN

Job information table including JOB NO. (1954-003-018), DWG. NAME, DESIGNED BY (BML), DRAWN BY (BML), CHECKED BY, DATE (04/30/2019), DATE OF PRINT, and SHEETS (C1 OF SHEETS).

A PORTION OF A PORTION OF THE SE QUARTER OF SECTION 01, TOWNSHIP 24 N., RANGE 04 E., W.M.

SOIL QUALITY GUIDLINES

2014 SWMMW, BMP 15.13

SOIL RETENTION. RETAIN, IN A UNDISTURBED STATE THE DUFF LAYER AND NATIVE TOPSOIL TO THE MAXIMUM EXTENT PRACTICABLE. IN ANY AREAS REQUIRING GRADING REMOVE AND STOCK-PILE THE THE DUFF LAYER AND TOPSOIL, IF ANY, ON SITE IN A DESIGNATED, CONTROLLED AREA, NOT ADJACENT TO PUBLIC RESOURCES AND CRITICAL AREAS, TO BE REAPPLIED TO OTHER PORTIONS OF THE SIT WHERE FEASIBLE.

SOIL QUALITY. ALL AREAS SUBJECT TO CLEARING AND GRADING THAT HAVE NOT BEEN COVERED BY IMPERVIOUS SURFACE, INCORPORATED INTO A DRAINAGE FACILITY OR ENGINEERED AS STRUCTURAL FILL OR SLOPE SHALL, AT PROJECT COMPLETION, DEMONSTRATE THE FOLLOWING:

1. A TOPSOIL LAYER WITH A MINIMUM ORGANIC MATTER CONTENT OF 5-10% DRY WEIGHT IN PLANTING BEDS, AND 5% ORGANIC MATTER CONTENT IN TURF AREAS, AND A PH FROM 6.0 TO 8.0 OR MATCHING THE PH OF THE UNDISTURBED SOIL. THE TOPSOIL LAYER SHALL A MINIMUM DEPTH OF EIGHT INCHES EXCEPT WHERE TREE ROOTS LIMIT THE DEPTH OF INCORPORATION OF AMENDMENTS NEEDED TO MEET THE CRITERIA. SUBSOILS BELOW THE TOPSOIL LAYER SHOULD BE SCARIFIED AT LEAST 4 INCHES WITH SOME INCORPORATION OF THE UPPER MATERIAL TO AVOID STRATIFIED LAYERS, WHERE FEASIBLE.

2. MULCH PLANTING BEDS WITH 2 INCHES OF ORGANIC MATERIAL

3. USE COMPOST AND OTHER MATERIALS THAT MEET THESE ORGANIC CONTENT REQUIREMENTS:

A. THE ORGANIC CONTENT FOR "PRE-APPROVED" AMENDMENT RATES CAN ONLY BE MET USING COMPOST MEETING THE COMPOST SPECIFICATION FOR BIORETENTION WITH THE EXCEPTION THAT THE COMPOST MUST HAVE AN ORGANIC MATTER CONTENT OF 40 PERCENT TO 65 PERCENT, AND A CARBON TO NITROGEN RATIO BETWEEN 25:1. THE CARBON TO NITROGEN RATIO MAY BE AS HIGH AS 35:1 FOR PLANTING COMPOSED ENTIRELY OF PLANTS NATIVE TO THE PUGET SOUND LOWLANDS REGION.

B. CALCULATED AMENDMENT RATES MAY BE ME THROUGH USE OF COMPOSTED MATERIALS AS DEFINED ABOVE, OR OTHER ORGANIC MATERIALS AMENDED TO MEET THE CARBON TO NITROGEN RATIO REQUIREMENTS, AND NOT EXCEEDING THE CONTAMINANT LIMITS IDENTIFIED IN TABLE 220-B, TESTING PARAMETERS, IN WAC 173-350-220

SOIL AMENDMENT OPTIONS

2014 SWMMW, BMP 15.13

IMPLEMENTATION OPTIONS: THE SOIL QUALITY DESIGN GUIDELINES LISTED ON THIS SHEET CAN BE MET BY USING ONE OF THE METHODS LISTED BELOW:

OPTION 1: LEAVE UNDISTURBED NATIVE VEGETATION AND SOIL, AND PROTECT FROM COMPACTION DURING CONSTRUCTION.

OPTION 2: AMEND EXISTING SITE TOPSOIL OR SUBSOIL EITHER AT DEFAULT "PRE-APPROVED" RATES, OR AT CUSTOM CALCULATED RATES BASED ON TESTS OF THE SOIL AND AMENDMENT.

OPTION 3: STOCKPILE EXISTING TOPSOIL DURING GRADING, AND REPLACE IT PRIOR TO PLANTING. STOCKPILED TOPSOIL MUST ALSO BE AMENDED IF NEEDED TO MEET THE ORGANIC MATTER OR DEPTH REQUIREMENTS, EITHER AT A DEFAULT "PRE-APPROVED" RATE OR AT A CUSTOM CALCULATED RATE.

OPTION 4: IMPORT TOPSOIL MIX OF SUFFICIENT ORGANIC CONTENT AND DEPTH TO MEET THE REQUIREMENTS.

MORE THAN ONE METHOD MAY BE USED ON DIFFERENT PORTIONS OF THE SAME SITE. SOIL THAT ALREADY MEETS THE DEPTH AND ORGANIC MATTER QUALITY STANDARDS, AND IS NOT COMPACTED, DOES NOT NEED TO BE AMENDED.

SITE DATA

PARCEL NUMBER: 545230-2145
SITE ADDRESS: 2215 80TH AVE SE MERCER ISLAND, WA 98040
SITE AREA: 8,800 SF (RECORDED) 8,810 SF (SURVEYED)
ZONING: R-8.5
REQUIRED SETBACKS: FRONT/GARAGE: 20 FT, BACK: 25 FT, INTERIOR: 10 FT EA (15 FT TOTAL)

ON-SITE IMPERVIOUS

NEW PLUS REPLACED
TRIBUTARY TO DETENTION TANK
SINGLE FAMILY ROOFTOP 2,495 SF (0.057 AC TO PUMP)
CONCRETE DRIVE 437 SF
TOTAL 2,932 SF (0.067 AC)
SHEET FLOW DISPERSION
EXPOSED WALKWAYS 233 SF

PROJECT IMPACTS

EXISTING (ALL TO BE REMOVED)
SINGLE FAMILY ROOFTOP 3,629 SF
SIDEWALK 0 SF
BACK PATIO 112 SF
DECK 317 SF
SITE DRIVEWAY 850 SF
TOTAL 4,908 SF
REPLACED
SINGLE FAMILY ROOFTOP 2,495 SF
SIDEWALK 233 SF
DECK 49 SF
TOTAL REPLACED 2,777 SF
NEW
DRIVEWAY 437 SF
TOTAL NEW 437 SF
NEW + REPLACED 3,214 SF

EARTHWORK QUANTITIES

CUT 0 CY
FILL 80 CY
NET 80 CY (FILL)

EARTHWORK VOLUMES SHOWN ARE ESTIMATES ONLY. CONTRACTOR SHALL VERIFY VOLUMES AS NEEDED.

FOOTING DRAIN NOTE

ALL FOOTING WALLS SHALL BE PROVIDED WITH A DRAIN AT THE BASE OF THE FOOTING ELEVATION. DRAINS SHOULD CONSIST OF RIGID PVC PIPE SURROUNDED BY WASHED PEA GRAVEL. THE LEVEL OF THE PERFORATIONS IN THE PIPE SHOULD BE SET AT OR SLIGHTLY BELOW THE BOTTOM OF THE FOOTING AND THE DRAINS SHOULD BE CONSTRUCTION WITH SUFFICIENT GRADIENT TO ALLOW GRAVITY DISCHARGE AWAY FROM THE BUILDING. DAYLIGHT FOOTING DRAIN DOWNSTREAM FROM HOUSE SEPARATE FROM THE PROPOSE FLOW CONTROL BMPs AND AFTER THE DETENTION SYSTEM.




LEGAL DESCRIPTION

PER STATUTORY WARRANTY DEED RECORDING# 20180116001125

LOTS 3 AND 4, BLOCK 21, MERCER PARK, ACCORDING TO THE PLAT THEREOF RECORDED IN VOLUME 9 OF PLATS, PAGE 27, RECORDS OF KING COUNTY, WASHINGTON.

SITUATE IN THE COUNTY OF KING, STATE OF WASHINGTON.

SEE THE TOPOGRAPHY MAP PREPARED BY TERRANE LAND SURVEYING FOR THIS PROJECT FOR FURTHER PROJECT DESCRIPTION, CONTROL, AND EXISTING TOPOGRAPHY INFORMATION.






Professional Engineer information for Brandon Michael Lovell, License No. 65008, dated 4/30/2019. Includes contact info for ESM Consulting Engineers LLC.

Project information including MZA Architecture, PaeK Residence, Drainage & Grading Plan, City of Mercer Island, and sheet number C2 of 2 sheets.

CALL 48 HOURS BEFORE YOU DIG 811

A PORTION OF A PORTION OF THE SE QUARTER OF SECTION 01, TOWNSHIP 24 N., RANGE 04 E., W.M.

**ATTACHMENT 1
CITY OF MERCER ISLAND
ON-SITE DETENTION SYSTEM WORKSHEET
(FOR NEW PLUS REPLACED IMPERVIOUS
AREA OF 9,500 SF OR LESS)**



OWNER: <u>TIM & ELLEN PAEK</u>	ADDRESS: <u>2215 80TH AVE SE</u>	PREPARED BY: <u>ESM CONSULTING ENGINEERS</u>
PERMIT #:	<u>MERCER ISLAND, 98040</u>	PHONE: <u>(253) 838-6113</u>
		DATE: <u>04/24/2019</u>
NEW PLUS REPLACED IMPERVIOUS SURFACE AREA (SF): <u>2,891 (TRIBUTARY)</u>	DETENTION PIPE DIA (INCH): <u>.36"</u>	DETENTION PIPE LENGTH (FT): <u>.66'</u>
SOIL TYPE: <u>C</u>	PIPE MATERIAL: <u>CMP</u>	ORIFICE #1 DIA <u>.05</u> INCH, ELEV <u>80.05</u>
		ORIFICE #2 DIA <u>1.9</u> INCH, ELEV <u>84.45</u>

CONTROL STRUCTURE NOTES:

- ① USE A MINIMUM OF A 54 IN. DIAM. TYPE 2 CATCH BASIN. THE ACTUAL SIZE IS DEPENDENT ON CONNECTING PIPE MATERIAL AND DIAMETER.
- ② OUTLET PIPE: MIN. 6 INCH.
- ③ METAL PARTS: CORROSION RESISTANT. NON-GALVANIZED PARTS PREFERRED. GALVANIZED PIPE PARTS TO HAVE ASPHALT TREATMENT 1.
- ④ FRAME AND LADDER OR STEPS OFFSET SO:
 - A. CLEANOUT GATE IS VISIBLE FROM TOP;
 - B. CLIMB-DOWN SPACE IS CLEAR OF RISER AND CLEANOUT GATE;
 - C. FRAME IS CLEAR OF CURB.
- ⑤ IF METAL OUTLET PIPE CONNECTS TO CEMENT CONCRETE PIPE, OUTLET PIPE TO HAVE SMOOTH O.D. EQUAL TO CONCRETE PIPE I.D. LESS 1/4 IN.
- ⑥ PROVIDE AT LEAST ONE 3 X 0.090 GAUGE SUPPORT BRACKET ANCHORED TO CONCRETE WALL WITH 5/8 IN. STAINLESS STEEL EXPANSION BOLTS OR EMBEDDED SUPPORTS 2 IN. INTO CATCH BASIN WALL (MAXIMUM 3'-0" VERTICAL SPACING).
- ⑦ THE SHEAR GATE SHALL BE MADE OF ALUMINUM ALLOY IN ACCORDANCE WITH ASTM B 26M AND ASTM B 275, DESIGNATION ZG32A; OR CAST IRON IN ACCORDANCE WITH ASTM A 48, CLASS 30B. THE LIFT HANDLE SHALL BE MADE OF A SIMILAR METAL TO THE GATE (TO PREVENT GALVANIC CORROSION), IT MAY BE OF SOLID ROD OR HOLLOW TUBING, WITH ADJUSTABLE HOOK AS REQUIRED. A NEOPRENE RUBBER GASKET IS REQUIRED BETWEEN THE RISER MOUNTING FLANGE AND THE GATE FLANGE. INSTALL THE GATE SO THAT THE LEVEL-LINE MARK IS LEVEL WHEN THE GATE IS CLOSED. THE MATING SURFACES OF THE LID AND THE BODY SHALL BE MACHINED FOR PROPER FIT. ALL SHEAR GATE BOLTS SHALL BE STAINLESS STEEL.
- ⑧ THE UPPER CATCH BASIN IS REQUIRED IF THE LENGTH OF THE DETENTION PIPE IS GREATER THAN 50 FT.

ON-SITE DETENTION SYSTEM NOTES:

1. CALL DEVELOPMENT SERVICES (206-275-7605) 24 HOURS IN ADVANCE FOR A DETENTION SYSTEM INSPECTION BEFORE BACKFILLING AND FOR FINAL INSPECTIONS.
2. RESPONSIBILITY FOR OPERATION AND MAINTANANCE OF DRAINAGE SYSTEMS ON PRIVATE PROPERTY IS RESPONSIBILITY OF THE PROPERTY OWNER. MATERIAL ACCUMULATED IN THE STORAGE PIPE MUST BE REMOVED FROM CATCH BASINS TO ALLOW PROPER OPERATION. THE OUTLET CONTROL ORIFICE MUST BE KEPT OPEN AT ALL TIMES.
3. PIPE MATERIAL, JOINT, AND PROTECTIVE TREATMENT SHALL BE IN ACCORDANCE WITH SECTION 7.04 AND 9.05 OF THE WSDOT STANDARD SPECIFICATION FOR ROAD, BRIDGE, AND MUNICIPAL CONSTRUCTION, LATEST VERSION. SUCH MATERIALS INCLUDE THE FOLLOWING, LINED CORRUGATED POLYETHYLENE PIPE (LCP), ALUMINIZED TYPE 2 CORRUGATED STEEL PIPE AND PIPE ARCH (MEETS AASHTO DESIGNATIONS M274 AND M36), CORRUGATED OR SPIRAL RIB ALUMINUM PIPE, OR REINFORCED CONCRETE PIPE. CORRUGATED STEEL PIPE IS NOT ALLOWED.
4. FOOTING DRAINS SHALL NOT BE CONNECTED TO THE DETENTION SYSTEM.

REVISIONS		
NO.	DESCRIPTION/DATE	BY





ESM CONSULTING ENGINEERS LLC
 53400 8th Ave S, Suite 205
 Everett, WA 98003
 FEDERAL WAY
 (253) 838-6113
 (425) 297-9900
 www.esmcivil.com
 Civil Engineering
 Land Surveying
 Project Management
 Land Planning
 Landscape Architecture
 Public Works

MZA ARCHITECTURE
PAEK RESIDENCE
 NOTES & DETAILS
 CITY OF MERCER ISLAND, WASHINGTON



JOB NO.: 1954-003-018
 DWG. NAME:
 DESIGNED BY: BML
 DRAWN BY: BML
 CHECKED BY:
 DATE: 04/30/2019
 DATE OF PRINT:

File: \\Farm\Temp\ESM-DBS\1954-003\018\paek\1954-003-018-PAEK Residence CIVIL_2019-04-18.dwg
 Plotted: 4/30/2019 2:12 PM
 Plotted By: Brandon Loucks

24" x 36" A11.1 D. 11/15/15



Tree ID	Species	DBH	Notes	Quantity
01	10" DBH MALUS SP. / APPLE	10"		2
02	15" DBH MALUS SP. / APPLE	15"		2
03	8" DBH PRUNUS SP. / CHERRY	8"		1
05	47" DBH POPLUS NIGRA / LOMBARDY POPLAR	47"		1
	43" DBH POPLUS NIGRA / LOMBARDY POPLAR	43"		1
	12" DBH FRAXINUS SP. / ASH	12"		1
	17" DBH PRUNUS LAUROCERASUS / LAUREL	17"		1
	7.5" DBH ACER MACROPHYLLUM / BIG LEAF MAPLE	7.5"		1
Total				5



A Tree Protection Area Details

ANR LANDSCAPE DESIGN

22310 22nd Ave SE, Suite 103, Bellevue, WA 98004

Phone: (206) 835-1311

Website: www.anrlandscape.com

Project Information

Address: 2215 22nd Ave SE, Bellevue, WA 98004

Client: M... ..

Scale

1" = 4'-0"

Notes

- No pruning shall be performed unless under the direction of an arborist.
- No equipment shall be stored or operated inside the protective fencing including during fence installation and removal.
- No storage of materials shall occur inside the protective fencing.
- Refer to Site/Utility Plan for any modifications to the Tree Protection Area.
- Unauthorized activities in tree protection area may require evaluation by private arborist to identify impacts and mitigation required.
- Exposed Roots: For roots >1" damaged during construction, make a clean straight cut to removed damaged portion and inform city arborist.

Tree Protection Area Details

Tree Protection fence: High density polyethylene fencing with 3.5" x 1.5" openings. Color: orange. Steel posts installed at 8' o.c.


2" x 8" steel posts or approved equal.

5" thick layer of mulch.

Maintain existing grade with the tree protection fence unless otherwise indicated on the plans.

Revision Log

Rev	Description
1	Initial Issue



PLAN LEGEND


- PROPERTY LINE
- - - - - ORDINARY HIGH WATER LINE OF TYPE 3 STREAM
- - - - - 35' STANDARD STREAM BUFFER

IMPACT LEGEND

- [Hatched Pattern] BUFFER REDUCTION 141 SF

MITIGATION LEGEND

- [Dotted Pattern] BUFFER REPLACEMENT 141 SF
- [Cross-hatched Pattern] STREAM BUFFER ENHANCEMENT 187 SF




GENERAL NOTES

1. BASE INFORMATION PROVIDED BY MZA ARCHITECTURE, 600 108TH AVE NE, SUITE 108, BELLEVUE, WA 98004, (425) 554-7000.

Revisions	Date	By

Date 04-30-19
 Scale AS NOTED
 Project # 5200



Altmann Oliver Associates, LLC

Environmental Planning & Landscape Architecture

PO Box 578 Cannon, WA 98014


Office (425) 332-4338 Fax (425) 333-4309

PLANTING PLAN
PAEK RESIDENCE
2215 80TH AVE SE
MERCER ISLAND, WA 98040

Revisions	
Date	
By	


Date 04-30-19
Scale AS NOTED
Project# 5200

Sheet # N-2



PLANT SCHEDULE

SHRUBS						
KEY	SCIENTIFIC NAME	COMMON NAME	SPACING	QTY.	SIZE (MIN.)	NOTES
RS	RIBES SANGUINEUM	RED CURRANT	3' O.C.	11	1 GAL.	MULTI-STEM (3 MIN.)
SA	SYMPHORICARPOS ALBUS	SNOWBERRY	3' O.C.	11	1 GAL.	MULTI-STEM (3 MIN.)



GENERAL NOTES

1. BASE INFORMATION PROVIDED BY MZA ARCHITECTURE, 600 108TH AVE NE, SUITE 108, BELLEVUE, WA 98004, (425) 554-7000.


CONSTRUCTION SPECIFICATIONS

- ALL PLANTS SHOULD BE INSTALLED BETWEEN DECEMBER 1ST AND MARCH 15TH, UNLESS SUPPLEMENTAL IRRIGATION IS PROVIDED.
- INTERMEDIATE INSPECTIONS. ALL PLANTS SHALL BE INSPECTED AND APPROVED BY THE LANDSCAPE DESIGNER AND/OR WETLAND BIOLOGIST PRIOR TO INSTALLATION. CONDITION OF ROOTS OF A RANDOM SAMPLE OF PLANTS WILL BE INSPECTED, AS WELL AS ALL ABOVEGROUND GROWTH ON ALL PLANTS. ROOTS OF ANY BARE ROOT PLANTS, IF PERMITTED FOR USE, WILL BE INSPECTED. PLANT MATERIAL MAY BE APPROVED AT THE SOURCE, AT THE DISCRETION OF THE LANDSCAPE DESIGNER AND THE WETLAND BIOLOGIST, BUT ALL MATERIAL MUST BE RE-INSPECTED AND APPROVED ON THE SITE PRIOR TO INSTALLATION. PLANT LOCATIONS SHALL ALSO BE INSPECTED AND APPROVED PRIOR TO PLANTING.
- ALL PLANTS SHALL BE PIT-PLANTED IN PLANTING PITS EXCAVATED 2X THE DIAMETER OF THE PLANT. PITS SHALL BE BACKFILLED WITH A 30/70 MIX OF SIERCO TO NATIVE SOIL. PITS SHALL BE AMENDED WITH A HYDRATED SOIL POLYMER (INSTALLED AT RATES PER MANUFACTURER'S SPECIFICATIONS). PLANTS SHALL BE INSTALLED 3" HIGH AND SURFACED MULCHED TO A DEPTH OF 3" WITH PACIFIC GARDEN MULCH PLACED CONTINUOUSLY THROUGHOUT THE PLANTING BED.
- ALL PLANTS SHALL BE NURSERY GROWN (IN WESTERN WA OR OR) FOR AT LEAST 1 YEAR FROM PURCHASE DATE, FREE FROM DISEASE OR PESTS, WELL-ROOTED, BUT NOT ROOT-BOUND AND TRUE TO SPECIES.
- PLANT LAYOUT SHALL BE APPROVED BY AOA PRIOR TO INSTALLATION AND APPROVED UPON COMPLETION OF PLANTING.
- UPON COMPLETION OF PLANTING, ALL PLANTS SHALL BE THOROUGHLY WATERED.
- UPON APPROVAL OF PLANTING INSTALLATION BY AOA, THE CITY OF MERCER ISLAND WILL BE NOTIFIED TO CONDUCT A SITE REVIEW FOR FINAL APPROVAL OF CONSTRUCTION.
- MAINTENANCE SHALL BE IMPLEMENTED ON A REGULAR BASIS ACCORDING TO THE SCHEDULE BELOW.


ANNUAL MAINTENANCE SCHEDULE

MAINTENANCE ITEM	J	F	M	A	M	J	J	A	S	O	N	D
WATERING - YEARS 1 & 2							Ø	Ø	Ø	Ø		
WEED CONTROL			I		I		I			I		
GENERAL MAINT.			I		I		I			I		


I-Ø = NUMBER OF TIMES TASK SHALL BE PERFORMED PER MONTH.



1 CONTAINER PLANTING DETAIL (TYP.)
SCALE: NTS



2 BARE-ROOT PLANTING DETAIL (TYP.)
SCALE: NTS



3 CUTTING INSTALLATION (TYP.)
SCALE: NTS

- NOTES:
- CUTTINGS SHALL BE SPECIES AS NOTED IN THE PLANT SCHEDULE.
 - CUTTINGS SHALL BE AT LEAST 1/2" DIA. AND 4' (min.) IN LENGTH.
 - CUTTINGS MUST BE ALIVE WITH SIDE BRANCHES CLEARLY REMOVED AND BARK INTACT. CUTTINGS SHALL BE PLANTED WITHIN 24 HOURS OF CUTTING.
 - THE BUTT ENDS SHOULD BE CLEANLY CUT AT AN ANGLE FOR EASY INSERTION INTO THE SOIL. THE TOP SHOULD BE CUT SQUARE OR BLUNT.
 - CUTTINGS MUST BE FRESH AND KEPT MOIST AFTER CUTTING. THEY SHOULD BE PRUNED AND INSTALLED THE SAME DAY.
 - DIP BOTTOM OF CUTTING IN A PLANT ROOTING HORMONE PRIOR TO INSERTION INTO THE SOIL.



AOA
Environmental
Planning &
Landscape
Architecture

Altmann Oliver Associates, LLC
Office (425) 331-4338 Fax (425) 331-4309
PO Box 578
Carnation, WA 98014


SPECIFICATIONS & DETAILS
PAEK RESIDENCE
2215 80TH AVE SE
MERCER ISLAND, WA 98040

Revisions	Date	By

Date 04-30-19
Scale AS NOTED
Project# 5200

Sheet # **N-3**

FILE NAME: C:\Users\mwei\Documents\Paek Residence_new_wsi\mza-us.com.rvt
 PLOT DATE: 4/30/2019 1:58:52 PM
 24" x 36" Arch D - SHEET SIZE



1 Site 02
 3/16" = 1'-0"

PROJECT NAME
PAEK RESIDENCE

PROJECT ADDRESS
 2215 80TH AVE SE
 MERCER ISLAND, WA 98040

CLIENT
 TIMOTHY PAEK

16930 SE 32ND PLACE
 BELLEVUE, WA 98008
 T: 206.228.9404

NO.	DESCRIPTION	DATE
REVISIONS		

CONSULTANTS

CIVIL ENGINEER
 GREEN LAKE ENGINEERING
 6045 4TH AVE NE
 SEATTLE, WA 98115
 T: 206.525.5332


LANDSCAPE ARCHITECT
 ALTMANN OLIVER ASSOC., LLC
 PO BOX 578
 CARNATION, WA 98014
 T: 425.333.4535

STRUCTURAL ENGINEER
 LUND OPSAHL
 1201 FIRST AVE. S, STE 310
 SEATTLE, WA 98134
 T: 206.402.5156

DRAWING STATUS



Discrepancies must be reported to the Architect before proceeding. Only figured dimensions are to be used. Contractors must check all dimensions on site. This drawing is protected by copyright.

ALL DIMENSIONS ARE SHOWN IN IMPERIAL.



MZA
 ARCHITECTURE

600 108th Ave. NE, Suite 108
 Bellevue, WA 98004
 T: 425.556.7886, www.mza-us.com

STAMP 	NORTH ARROW 
---	---


DRAWING TITLE
SITE PLAN

DRAWN Author	CHECKED Checker
SCALE @ ARCH D 3/16" = 1'-0"	DATE 01/11/19

GRAPHIC SCALE
 0 4 8 16 24
 SCALE IN FEET

PROJECT NO.
 18-009



DRAWING NO. A1.1	REVISION NO.
-----------------------------------	---------------------




1. ALL WINDOWS SHALL COMPLY W/ WSEC FRAMERS TO VERIFY R.O.
2. VENT ALL FANS AND DRYER EXHAUST TO OUTSIDE. PROVIDE 2x BLOCKING EACH SIDE OF FAN. HOLD BLOCKING 1/4" UP FROM GWB.
3. TOILET PAPER DISPENSERS TO BE MOUNTED @ 27" AFF. (TYP.)
4. ALL TOWEL BARS MOUNTED @ 42" AFF. UNO.
5. PROVIDE TEMPORARY BRACING AS REQUIRED UNTIL ALL CONNECTIONS AND STIFFENERS HAVE BEEN INSTALLED.
6. WRITTEN DIMENSIONS ARE PRECEDENCE OVER SCALED DIMS. VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD.
7. FIREBLOCK IN ACCORDANCE W/ 2015 IRC R302.11
8. LIMIT SHOWER FLOW TO 2.5 GPM
9. SHOWER WALLS SHALL BE WATERPROOF TO A MIN. 72" AFF
10. ALL BATHROOM GLAZING INCLUDING WINDOWS WITHIN 60" OF A STANDING OR WALKING SURFACE SHALL HAVE SAFETY GLAZING.

LEGEND

- DENOTES SUPPLY AIR GRILLE AT FLOOR
 - 110V SMOKE DETECTOR W/ BATTERY BACKED AND W/ INTERCONNECTED PER 2015 IRC R314
 - CARBON MONOXIDE ALARM AND SMOKE DETECTOR
 - EXHAUST FAN - MIN 50CFM
-
- 18"x24" CRAWL SPACE ACCESS W/ WEATHER STRIPPING
 - HOT AND COLD BIB @ 48" AFF @ UTILITY ROOM
 - PROVIDE 2X8 BLOCK AT 54" AFF FOR THERMOSTAT.
 - BLOCKING REQUIRED FOR TOWEL BARS AND HANDRAILS

PROJECT PAEK RESIDENCE	
ADDRESS 2215 80TH AVE SE MERCER ISLAND, WA 98040	
CLIENT TIMOTHY PAEK	
NO. ISSUED	DATE
REVISIONS	
DRAWING STATUS	
Discrepancies must be reported immediately to the Architect before proceeding. Only figured dimensions are to be used. Contractors must check all dimensions on site. This drawing is protected by copyright. ALL DIMENSIONS ARE SHOWN IN IMPERIAL.	
 ARCHITECTURE 600 108th Ave NE Suite 108 Bellevue WA 98004 425.559.7888 contact@mzaos.com	
STAMP	
	
DRAWING TITLE BASEMENT & GROUND FLOOR PLANS	
DRAWN Author	DESIGNED Designer
DATE 06/05/18	
GRAPHIC SCALE As indicated	
PROJECT NO. 18-009	
DRAWING NO. A2.1	REVISION NO.





1 UPPER LEVEL
1/4" = 1'-0"


1. ALL WINDOWS SHALL COMPLY W/ WSEC FRAMERS TO VERIFY R.O.
2. VENT ALL FANS AND DRYER EXHAUST TO OUTSIDE. PROVIDE 2x BLOCKING EACH SIDE OF FAN. HOLD BLOCKING 1/4" UP FROM GWB.
3. TOILET PAPER DISPENSERS TO BE MOUNTED @ 27" AFF (TYP.)
4. ALL TOWEL BARS MOUNTED @ 42" AFF. UNO.
5. PROVIDE TEMPORARY BRACING AS REQUIRED UNTIL ALL CONNECTIONS AND STIFFENERS HAVE BEEN INSTALLED.
6. WRITTEN DIMENSIONS ARE PRECEDENCE OVER SCALED DIMS. VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD.
7. FIREBLOCK IN ACCORDANCE W/ 2015 IRC R302.11
8. LIMIT SHOWER FLOW TO 2.5 GPM
9. SHOWER WALLS SHALL BE WATERPROOF TO A MIN. 72" AFF
10. ALL BATHROOM GLAZING INCLUDING WINDOWS WITHIN 60" OF A STANDING OR WALKING SURFACE SHALL HAVE SAFETY GLAZING.

LEGEND

- DENOTES SUPPLY AIR GRILLE AT FLOOR
- 110V SMOKE DETECTOR W/ BATTERY BACKED AND W/ INTERCONNECTED PER 2015 IRC R314
- CARBON MONOXIDE ALARM AND SMOKE DETECTOR
- EXHAUST FAN - MIN 50CFM

- 1 18"x24" CRAWL SPACE ACCESS W/ WEATHER STRIPPING
- 2 HOT AND COLD BIB @ 48" AFF @ UTILITY ROOM
- 3 PROVIDE 2X8 BLOCK AT 54" AFF FOR THERMOSTAT.
- 4 BLOCKING REQUIRED FOR TOWEL BARS AND HANDRAILS



PROJECT PAEK RESIDENCE	
ADDRESS 2215 80TH AVE SE MERCER ISLAND, WA 98040	
CLIENT TIMOTHY PAEK	
NO.	ISSUED
REVISIONS	
DRAWING STATUS	
Discrepancies must be reported immediately to the Architect before proceeding. Only figured dimensions are to be used. Contractors must check all dimensions on site. This drawing is protected by copyright. ALL DIMENSIONS ARE SHOWN IN IMPERIAL.	
 ARCHITECTURE 600 108th Ave NE Suite 108 Bellevue WA 98004 425.559.7888 contact@mza.us	
STAMP	
	
DRAWING TITLE UPPER LEVEL PLAN	
DRAWN Author	DESIGNED Designer
DATE 06/05/18	
GRAPHIC SCALE As indicated	
PROJECT NO. 18-009	
DRAWING NO. A2.2	REVISION NO.




1. ALL WINDOWS SHALL COMPLY W/ WSEC FRAMERS TO VERIFY R.O.
2. VENT ALL FANS AND DRYER EXHAUST TO OUTSIDE. PROVIDE 2x BLOCKING EACH SIDE OF FAN. HOLD BLOCKING 1/4" UP FROM GWB.
3. TOILET PAPER DISPENSERS TO BE MOUNTED @ 27" AFF (TYP.)
4. ALL TOWEL BARS MOUNTED @ 42" AFF. UNO.
5. PROVIDE TEMPORARY BRACING AS REQUIRED UNTIL ALL CONNECTIONS AND STIFFENERS HAVE BEEN INSTALLED.
6. WRITTEN DIMENSIONS ARE PRECEDENCE OVER SCALED DIMS. VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD.
7. FIREBLOCK IN ACCORDANCE W/ 2015 IRC R302.11
8. LIMIT SHOWER FLOW TO 2.5 GPM
9. SHOWER WALLS SHALL BE WATERPROOF TO A MIN. 72" AFF
10. ALL BATHROOM GLAZING INCLUDING WINDOWS WITHIN 60" OF A STANDING OR WALKING SURFACE SHALL HAVE SAFETY GLAZING.

LEGEND


- DENOTES SUPPLY AIR GRILLE AT FLOOR
- 110V SMOKE DETECTOR W/ BATTERY BACKED AND W/ INTERCONNECTED PER 2015 IRC R314
- CARBON MONOXIDE ALARM AND SMOKE DETECTOR
- EXHAUST FAN - MIN 50CFM
- 18"x24" CRAWL SPACE ACCESS W/ WEATHER STRIPPING
- HOT AND COLD BIB @ 48" AFF @ UTILITY ROOM
- PROVIDE 2x8 BLOCK AT 54" AFF FOR THERMOSTAT.
- BLOCKING REQUIRED FOR TOWEL BARS AND HANDRAILS

PROJECT PAEK RESIDENCE	
ADDRESS 2215 80TH AVE SE MERCER ISLAND, WA 98040	
CLIENT TIMOTHY PAEK	
NO.	ISSUED
REVISIONS	
DRAWING STATUS	
Discrepancies must be reported immediately to the Architect before proceeding. Only figured dimensions are to be used. Contractors must check all dimensions on site. This drawing is protected by copyright. ALL DIMENSIONS ARE SHOWN IN IMPERIAL.	
 ARCHITECTURE 600 108th Ave NE Suite 1108 Bellevue WA 98004 425.559.7888 contact@mzaos.com	
STAMP	
	
DRAWING TITLE ROOF PLAN	
DRAWN Author	DESIGNED Designer
DATE 08/16/18	
GRAPHIC SCALE As indicated	
PROJECT NO. 18-009	
DRAWING NO. A2.3	REVISION NO.



24"x36" Arch D - SHEET SIZE



1 Section A-A
1/4" = 1'-0"




2 Section B-B
1/4" = 1'-0"

PROJECT PAEK RESIDENCE	
ADDRESS 2215 80TH AVE SE MERCER ISLAND, WA 98040	
CLIENT TIMOTHY PAEK	
NO.	ISSUED
REVISIONS	DATE
DRAWING STATUS	
Discrepancies must be reported immediately to the Architect before proceeding. Only figured dimensions are to be used. Contractors must check all dimensions on site. This drawing is protected by copyright. ALL DIMENSIONS ARE SHOWN IN IMPERIAL.	
 ARCHITECTURE 600 108th Ave NE Suite 108 Bellevue WA 98004 425.559.7888 contact@mza.us	
STAMP	
DRAWING TITLE SECTION	
DRAWN Author	DESIGNED Designer
DATE 07/06/17	
GRAPHIC SCALE 1/4" = 1'-0"	
PROJECT NO. 18-009	
DRAWING NO. A3.0	REVISION NO.

FILE NAME
PLOT TIME
DATE

24"x36" Arch D - SHEET SIZE





1 EAST ELEVATION
1/4" = 1'-0"



2 WEST ELEVATION
1/4" = 1'-0"

KEYNOTES


- (A) ASPHALT SHINGLE ROOFING
25 YEAR ARCHITECTURAL COMPOSITION ROOFING: *CertainTeed, Presidential Solars 'Weathered Wood'*
- (B) WHITEWOOD FASCIA
PRE-PRIMED WHITEWOOD 5/4x8 NOMINAL, COLOR: *Benjamin Moore, BM1596 'Nightfall'*
- (C) ALUMINUM GUTTER/DOWNSPOUT
PRE-FINISHED ALUMINUM GUTTER
COLOR: TO MATCH FASCIA
- (D) METAL COPING OVER WOOD TRIM
MANUFACTURED METAL COPING 0/ 5/4" x 10" NOMINAL WOOD TRIM WITH PAINTED FINISH
COLOR: *Benjamin Moore, BM1596 'Nightfall'*
- (E) FIBER CEMENT PANEL & BATTEN SIDING
4/4" x 2" HARDI TRIM BATTENS AT 1'-0" O.C. OVER 5/16" SMOOTH FIBER CEMENT PANELS, PAINTED FINISH
COLOR: *Benjamin Moore, BM1497 'Rolling Hills'*
- (F) FIBER CEMENT LAP SIDING (ACCENT COLOR)
6.00" SELECT CEDARMILL EXPOSURE, ACCENT PAINTED FINISH
COLOR: *Benjamin Moore, BM1498 'Forest Floor'*
- (G) CONCRETE WALL
CAST-IN-PLACE CONCRETE
COLOR TO MATCH: *Benjamin Moore, BM296 'Almond Bisque'*
- (H) ADHERED MANUFACTURED STONE VENEER
DRY-STACK STONE VENEER WITH MATCHING WAINSCOT SILL CAP
Eldorado Stone, 'Alderwood'
- (J) METAL RAILING
PREMADE, METAL RAILING
- (K) HARDI TRIM, 6"
5/4" x 6", PAINTED FINISH
THROUGH-WALL FLASHING AT TOP EDGE AT ALL HORIZONTAL CONDITIONS
COLOR: *Benjamin Moore, BM1503 'Texas Sage'*
- (L) TIMBER / WOOD ACCENTS
PAINTED WOOD ACCENTS, ASSEMBLY PER RELATED ARCHITECTURAL DETAILS
COLOR: *Benjamin Moore, BM1085 'Vero Beach Tan'*

PROJECT PAEK RESIDENCE	
ADDRESS 2215 80TH AVE SE MERCER ISLAND, WA 98040	
CLIENT TIMOTHY PAEK	
NO.	ISSUED
REVISIONS	
DRAWING STATUS	
Discrepancies must be reported immediately to the Architect before proceeding. Only figured dimensions are to be used. Contractors must check all dimensions on site. This drawing is protected by copyright. ALL DIMENSIONS ARE SHOWN IN IMPERIAL.	
 ARCHITECTURE 600 108th Ave NE Suite 108 Bellevue WA 98004 425.559.7888 contact@mzaos.com	
STAMP	
	
DRAWING TITLE EAST & WEST ELEVATIONS	
DRAWN Author	DESIGNED Designer
DATE 08/02/18	
GRAPHIC SCALE As indicated	
PROJECT NO. 18-009	
DRAWING NO. A4.0	REVISION NO.

1. PROVIDE GALVANIZED SHEET METAL FLASHING AND COUNTER FLASHING AT ALL ROOF PENETRATIONS
2. PROVIDE WEATHER STRIPPING AT ALL DOORS. CAULK ALL JOINTS AND PENETRATIONS IN EXTERIOR WALLS.
3. PROVIDE BUILDING IDENTIFICATION ADDRESS NUMBERS THAT ARE PLAINLY VISIBLE FROM THE STREET OR ROAD COMPLIANT WITH 2015 IRC SECTION R319.1

FILE NAME
PLOT DATE


24"x36" ARCH D - SHEET SIZE



1 NORTH ELEVATION
1/4" = 1'-0"



KEYNOTES

- A ASPHALT SHINGLE ROOFING
25 YEAR ARCHITECTURAL COMPOSITION
ROOFING: *Certainteed, Presidential Solaris*
'Weathered Wood'
- B WHITEWOOD FASCIA
PRE-PRIMED WHITEWOOD 5/4x8 NOMINAL
COLOR: *Benjamin Moore, BM1596 'Nightfall'*
- C ALUMINUM GUTTER/DOWNSPOUT
PRE-FINISHED ALUMINUM GUTTER
COLOR: TO MATCH FASCIA
- D METAL COPING OVER WOOD TRIM
MANUFACTURED METAL COPING 0/ 5/4" x 10"
NOMINAL WOOD TRIM WITH PAINTED FINISH
COLOR: *Benjamin Moore, BM1596 'Nightfall'*
- E FIBER CEMENT PANEL & BATTEN SIDING
4/4" x 2" HARDI TRIM BATTENS AT 1'-0" O.C.
OVER: 5/16" SMOOTH FIBER CEMENT
PANELS, PAINTED FINISH
COLOR: *Benjamin Moore, BM1497 'Rolling Hills'*
- F FIBER CEMENT LAP SIDING (ACCENT
COLOR)
6/00" SELECT CEDARMILL EXPOSURE,
ACCENT PAINTED FINISH
COLOR: *Benjamin Moore, BM1498 'Forest Floor'*
- G CONCRETE WALL
CAST-IN-PLACE CONCRETE
COLOR TO MATCH: *Benjamin Moore,*
BM296 'Almond Bisque'
- H ADHERED MANUFACTURED STONE VENEER
DRystack STONE VENEER WITH MATCHING
WAINSCOT SILL CAP
Eldorado Stone, 'Alderwood'
- J METAL RAILING
PREMADE, METAL RAILING
- K HARDI TRIM, 6"
5/4" x 6", PAINTED FINISH
THROUGH-WALL FLASHING AT TOP
EDGE AT ALL HORIZONTAL CONDITIONS
COLOR: *Benjamin Moore, BM1503 'Texas Sage'*
- L TIMBER / WOOD ACCENTS
PAINTED WOOD ACCENTS, ASSEMBLY PER
RELATED ARCHITECTURAL DETAILS
COLOR: *Benjamin Moore, BM1085 'Vero Beach
Tan'*




2 SOUTH ELEVATION
1/4" = 1'-0"

1. PROVIDE GALVANIZED SHEET METAL FLASHING AND COUNTER FLASHING AT ALL ROOF PENETRATIONS
2. PROVIDE WEATHER STRIPPING AT ALL DOORS. CAULK ALL JOINTS AND PENETRATIONS IN EXTERIOR WALLS.
3. PROVIDE BUILDING IDENTIFICATION ADDRESS NUMBERS THAT ARE PLAINLY VISIBLE FROM THE STREET OR ROAD COMPLIANT WITH 2015 IRC SECTION R319.1


PROJECT PAEK RESIDENCE	
ADDRESS 2215 80TH AVE SE MERCER ISLAND, WA 98040	
CLIENT TIMOTHY PAEK	
NO.	ISSUED
REVISIONS	
DRAWING STATUS	
Discrepancies must be reported immediately to the Architect before proceeding. Only figured dimensions are to be used. Contractors must check all dimensions on site. This drawing is protected by copyright. ALL DIMENSIONS ARE SHOWN IN IMPERIAL.	
 M Z A ARCHITECTURE <small>600 108th Ave NE Suite 108 Bellevue WA 98004 425.559.7888 contact@mzaos.com</small>	
STAMP	
	
DRAWING TITLE NORTH & SOUTH ELEVATIONS	
DRAWN Author	DESIGNED Designer
DATE 08/02/18	
GRAPHIC C SCALE As indicated	
PROJECT NO. 18-009	
DRAWING NO. A4.1	REVISION NO.

FILE NAME
PLOT TIME
DATE


24"x36" Arch D - SHEET SIZE




1 BASEMENT LEVEL - STAIR 1
1/4" = 1'-0"




2 ENTRY LEVEL - STAIR 1
1/4" = 1'-0"




3 UPPER LEVEL - STAIR 1
1/4" = 1'-0"




4 Section 19
1/4" = 1'-0"




5 BASEMENT LEVEL - STAIR 2
1/4" = 1'-0"





7 Section C-C
1/4" = 1'-0"




8 Section D-D
1/4" = 1'-0"




6 ENTRY LEVEL - STAIR 2
1/4" = 1'-0"

PROJECT PAEK RESIDENCE	
ADDRESS 2215 80TH AVE SE MERCER ISLAND, WA 98040	
CLIENT TIMOTHY PAEK	
NO. ISSUED	DATE
REVISIONS	
DRAWING STATUS	
Discrepancies must be reported immediately to the Architect before proceeding. Only figured dimensions are to be used. Contractors must check all dimensions on site. This drawing is protected by copyright. ALL DIMENSIONS ARE SHOWN IN IMPERIAL.	
 ARCHITECTURE 600 108th Ave NE Suite 1108 Bellevue WA 98004 425.559.7888 contact@mza.us.com	
STAMP	
	
DRAWING TITLE VERTICAL CIRCULATION	
DRAWN Author	DESIGNED Designer
DATE 07/06/17	
GRAPHIC SCALE 1/4" = 1'-0"	
PROJECT NO. 18-009	
DRAWING NO. A5.0	REVISION NO.


FILE NAME
PLOT TIME
DATE




1 WALL SECTION @ BALCONY
1/2" = 1'-0"




2 WALL SECTION @ DECK
1/2" = 1'-0"




5 ROOF OVERHANG
1 1/2" = 1'-0"




6 DOOR HEAD @ ENTRY LEVEL
1 1/2" = 1'-0"





3 BALCONY & DOOR SILL
1 1/2" = 1'-0"



4 WINDOW SILL
1 1/2" = 1'-0"




7 DOOR SILL @ DECK
1 1/2" = 1'-0"

PROJECT PAEK RESIDENCE	
ADDRESS 2215 80TH AVE SE MERCER ISLAND, WA 98040	
CLIENT TIMOTHY PAEK	
NO.	ISSUED
REVISIONS	DATE
DRAWING STATUS	
Discrepancies must be reported immediately to the Architect before proceeding. Only figured dimensions are to be used. Contractors must check all dimensions on site. This drawing is protected by copyright. ALL DIMENSIONS ARE SHOWN IN IMPERIAL.	
 ARCHITECTURE 600 108th Ave NE Suite 1108 Bellevue WA 98004 425.559.7888 contact@mza.us	
STAMP	
DRAWING TITLE WALL SECTIONS & DETAILS	
DRAWN Author	DESIGNED Designer
DATE 07/06/17	
GRAPHIC SCALE As indicated	
PROJECT NO. 18-009	
DRAWING NO. A6.0	REVISION NO.


24"x36" Arch D - SHEET SIZE

Window Schedule								
Level	Type Mark	MATERIAL	Width	Height	Sill Height	Window Area	U-Factor	UA
BASEMENT LEVEL	M1	VINYL	5'-2"	5'-0"	3'-0"	26 SF	0.3	7.75
BASEMENT LEVEL	N	VINYL	3'-10"	7'-0"	0'-8 1/4"	27 SF	0.3	8.05
BASEMENT LEVEL	N	VINYL	3'-10"	7'-0"	0'-8 1/2"	27 SF	0.3	8.05
BASEMENT LEVEL	N	VINYL	3'-10"	7'-0"	0'-8 1/2"	27 SF	0.3	8.05
ENTRY LEVEL	B	VINYL	2'-6"	7'-4"	3'-0"	18 SF	0.3	5.5
ENTRY LEVEL	G	VINYL	3'-2"	2'-3"	8'-1"	7 SF	0.3	2.1375
ENTRY LEVEL	L	VINYL	5'-2"	2'-3"	8'-0"	12 SF	0.3	3.4875
ENTRY LEVEL	M1	VINYL	5'-2"	5'-0"	3'-0"	26 SF	0.3	7.75
UPPER LEVEL	A	VINYL	7'-0"	2'-2"	8'-1"	15 SF	0.3	4.55
UPPER LEVEL	B	VINYL	2'-6"	7'-4"	3'-0"	18 SF	0.3	5.5
UPPER LEVEL	B	VINYL	2'-6"	7'-4"	3'-0"	18 SF	0.3	5.5
UPPER LEVEL	B	VINYL	2'-6"	7'-4"	3'-0"	18 SF	0.3	5.5
UPPER LEVEL	B	VINYL	2'-6"	7'-4"	3'-0"	18 SF	0.3	5.5
UPPER LEVEL	B	VINYL	2'-6"	7'-4"	3'-0"	18 SF	0.3	5.5
UPPER LEVEL	C	VINYL	4'-9"	7'-3"	3'-0"	34 SF	0.3	10.33125
UPPER LEVEL	D	VINYL	3'-7"	2'-2"	6'-0"	8 SF	0.3	2.329167
UPPER LEVEL	E	VINYL	2'-6"	5'-2"	3'-0"	13 SF	0.3	3.875
UPPER LEVEL	E	VINYL	2'-6"	5'-2"	3'-0"	13 SF	0.3	3.875
UPPER LEVEL	F1	VINYL	9'-6"	2'-2"	8'-2"	21 SF	0.3	6.175
UPPER LEVEL	H1	VINYL	6'-0"	2'-2"	6'-0"	13 SF	0.3	3.9
UPPER LEVEL	J1	VINYL	7'-8"	5'-2"	3'-0"	40 SF	0.3	11.883333
UPPER LEVEL	J1	VINYL	7'-8"	5'-2"	3'-0"	40 SF	0.3	11.883333
UPPER LEVEL	K	VINYL	12'-0"	2'-2"	6'-0"	26 SF	0.3	7.8
UPPER LEVEL	O1	VINYL	5'-8"	2'-3"	8'-1"	13 SF	0.3	3.825
UPPER LEVEL	P1	VINYL	5'-0"	2'-3"	6'-0"	11 SF	0.3	3.375
						507 SF		152.077083


Door Schedule													
Level	Mark	Type Mark	Height	Width	Door Material	Door Finish	Frame Material	Frame Finish	Fire Rating	Door Area	U-Value	UA	
BASEMENT LEVEL	006	D-1B	8'-0"	6'-0"						NR	48	0.5	24
BASEMENT LEVEL	005	D-7A	6'-8"	2'-6"						NR	16.67		
BASEMENT LEVEL	001	D-7A	6'-8"	2'-6"						NR	16.67		
BASEMENT LEVEL	003	D-7A	6'-8"	2'-6"						NR	16.67		
BASEMENT LEVEL	002	D-7B	6'-8"	2'-8"						NR	17.78		
BASEMENT LEVEL	004	D-11	6'-8"	2'-6"						NR	16.67		
ENTRY LEVEL	109	D-2	10'-0"	20'-6 1/4"						NR	205.29	0.5	102.64
ENTRY LEVEL	D-2	D-2	10'-0"	20'-6 1/4"						NR	205.29	0.5	102.64
ENTRY LEVEL	101	D-3	8'-0"	3'-0"						NR	24		
ENTRY LEVEL	106	D-4	7'-10"	5'-7"						NR	43.74		
ENTRY LEVEL	105	D-5	6'-8"	3'-0"	Finishes - Paint - White	Door - Panel	Finishes - Paint - White		20 MIN.	20			
ENTRY LEVEL	107	D-6	8'-0"	16'-0"						NR	128		
ENTRY LEVEL	102	D-7A	6'-8"	2'-6"						NR	16.67		
ENTRY LEVEL	103	D-7A	6'-8"	2'-6"						NR	16.67		
ENTRY LEVEL	104	D-7A	6'-8"	2'-6"						NR	16.67		
UPPER LEVEL	D1-A	D-1A	8'-0"	5'-8"						NR	45.33	0.5	22.67
UPPER LEVEL	203	D-4A	6'-8"	4'-10"						NR	32.22		
UPPER LEVEL	208	D-7A	6'-8"	2'-6"						NR	16.67		
UPPER LEVEL	207	D-7A	6'-8"	2'-6"						NR	16.67		
UPPER LEVEL	201	D-7A	6'-8"	2'-6"						NR	16.67		
UPPER LEVEL	202	D-7A	6'-8"	2'-6"						NR	16.67		
UPPER LEVEL	210	D-7B	6'-8"	2'-8"						NR	17.78		
UPPER LEVEL	204	D-7B	6'-8"	2'-8"						NR	17.78		
UPPER LEVEL	209	D-8	7'-0"	5'-0"						NR	35		
UPPER LEVEL	205	D-8	7'-0"	5'-0"						NR	35		
UPPER LEVEL	206	D-8	7'-0"	5'-0"						NR	35		
UPPER LEVEL	212	D-9	6'-8"	4'-6"						NR	30		
UPPER LEVEL	213	D-10	9'-9"	2'-3"						NR	21.96		



WINDOW TYPES
1/4" = 1'-0"



DOOR TYPES
1/4" = 1'-0"



S2 GLASS WALL ELEVATION
1/4" = 1'-0"

S1 GLASS WALL ELEVATION
1/4" = 1'-0"

PROJECT
PAEK RESIDENCE

ADDRESS
2215 80TH AVE SE
MERCER ISLAND, WA 98040


CLIENT
TIMOTHY PAEK

NO. ISSUED _____ DATE _____

REVISIONS _____

DRAWING STATUS _____

Discrepancies must be reported immediately to the Architect before proceeding. Only figured dimensions are to be used. Contractors must check all dimensions on site. This drawing is protected by copyright. ALL DIMENSIONS ARE SHOWN IN IMPERIAL.



ARCHITECTURE

600 108th Ave NE
Suite 1108
Bellevue WA 98004

425.559.7888
contact@mzaus.com

STAMP
REGISTERED ARCHITECT
Ming Zhang
STATE OF WASHINGTON

DRAWING TITLE
WINDOW & DOOD TYPE AND SCHEDULE

DRAWN Author DESIGNER Designer

DATE 07/06/17

GRAPHIC SCALE 1/4" = 1'-0"

PROJECT NO. 18-009

DRAWING NO. **A7.0** REVISION NO. _____

FILE NAME
PLOT DATE

SEE EXTERIOR ELEVATIONS FOR LOCATIONS OF INTENDED CLADDING MATERIALS

MARK	WALL ASSEMBLY COMPONENTS	FIRE RATING	SOUND RATING
W1E	EXTERIOR WALL - CAST IN PLACE CONCRETE WALL 		
W2E	EXTERIOR WALL - NICHIIA VINTAGE WOOD 		
W3E	EXTERIOR WALL - FIBER CEMENT PANEL 		
W4E	EXTERIOR WALL - FIBER CEMENT PANEL 		
W5E	EXTERIOR WALL - STONE VENEER 		
W6E	INSULATED CONCRETE WALLS 		

MARK	WALL ASSEMBLY COMPONENTS	FIRE RATING	SOUND RATING
W7E	INSULATED CONCRETE WALLS 		
W8E	EXTERIOR WALL - GARAGE INTERIOR WALL-2X6 		
W9E	PARAPET WALL - FIBER CEMENT PANEL 		
W1	INTERIOR WALL - TYPICAL - 2x4 		
W2	INTERIOR FURRING WALL - TYPICAL - 2x4 		
W3	INTERIOR UNIT PARTY WALL - DBL STUD-2X4 		

MARK	WALL ASSEMBLY COMPONENTS	FIRE RATING	SOUND RATING
W4	INTERIOR WALL - TYPICAL - 2x6 		
W5	INTERIOR WALL - DBL STUD-2X4 		
W6	INTERIOR FURRING WALL - 2X4 		

NOTES:

1. ALL INSULATION SHALL HAVE MAXIMUM FLAME SPREAD INDEX OF 25 AND MAXIMUM SMOKE DEVELOPED INDEX OF 450 IN ACCORDANCE WITH 1BC 719.2.
2. PROVIDE NON-PAPER FACED, MOLD & MILDREW RESISTANT GYPSUM WALL BOARD AT ALL MOISTURE AND DAMPNSS PRONE AREAS.
3. PROVIDE TILE BACKER BOARD(NOT GREENBOARD) AT ALL TILE CONDITIONS.
4. REFER TO STRUCTURAL PLANS FOR STUD SIZE AND SPACING.
5. FIRE RATING AND SOUND TRANSMISSION COEFFICIENTS ARE BASED UPON THE ASSEMBLIES SHOWN WITHOUT INSULATION, UNLESS NOTED OTHERWISE.
6. REFER TO WALL DETAILS FOR TERMINATIONS, CONNECTIONS, PENETRATIONS AND INTERSECTIONS.
7. ACOUSTIC SEALANT SHALL CONFORM TO ASTM C919-02.
8. SEPARATE BACK TO BACK ELECTRICAL OR OTHER UTILITY BOXES BY AT LEAST ONE STUD BAY IN SINGLE STUD WALLS ANT TWO STUD BAYS IN STAGGERED STUD OR DOUBLE STUD WALL ASSEMBLIES.
9. SEAL ALL DUCT, CONDUIT OR PIPING PENETRATIONS THROUGH ACOUSTICALLY RATED CONSTRUCTION TO PREVENT DIRECT CONTACT USING RESILIENT NON-HARDENING CAULK. USE FIRE-RATED ACOUSTICAL CAULK IN FIRE-RATED CONSTRUCTION.
10. REFER TO PLUMBING DRAWINGS AND SPECIFICATIONS FOR VIBRATION INSULATION REQUIREMENTS IN AREAS WHERE PLUMBING RUNS IN PROXIMITY TO NOISE-SENSITIVE SPACES.
11. STAGGER ALL JOINTS WHENEVER TWO OR MORE LAYERS OF GWB ARE SCHEDULED.
12. SECURE BATT INSULATION TO THE STRUCTURE AS REQUIRED TO PREVENT SAGGING OR DISPLACEMENT.
13. CONFORM STRICTLY TO TESTING AGENCY ASSEMBLY DESIGNATION REQUIREMENTS NOTED FOR ALL RATED WALL TYPES.
14. ALL GYPSUM BOARD PARTITIONS SHALL BE TAPED, SPACKLED AND SANDED SMOOTH WITH NO VISIBLE JOINTS. PATCH AND REPAIR SURFACES TO MATCH ADJACENT OR ADJOINING SURFACES WHERE REQUIRED. ALL SURFACES SHALL BE ALIGNED.
15. PROVIDE SOLID WOOD BLOCKING (OR) 18 GA. BACKING/BLOCKING BEHIND ALL FIXTURES AND ACCESSORIES - TYPICAL, U.O.N.
16. REFER TO SHEET XX-XX FOR WEATHER RESISTANT BARRIER SPECIFICATION AND REQUIREMENTS.

PROJECT
PAEK RESIDENCE

ADDRESS
2215 80TH AVE SE
MERCER ISLAND, WA 98040

CLIENT
TIMOTHY PAEK

NO.	ISSUED	DATE
REVISIONS		
DRAWING STATUS		

Discrepancies must be reported immediately to the Architect before proceeding. Only figured dimensions are to be used. Contractors must check all dimensions on site. This drawing is protected by copyright. ALL DIMENSIONS ARE SHOWN IN IMPERIAL.

ARCHITECTURE

600 108th Ave NE Suite 108 Bellevue WA 98004 425.559.7888 contact@mza.com

STAMP

DRAWING TITLE
WALL TYPES

DRAWN Author DESIGNER Designer

DATE 08/15/18

GRAPHIC SCALE 1" = 1'-0"

PROJECT NO. 18-009

DRAWING NO. A7.1 REVISION NO.

MARK	FLOOR/CEILING ASSEMBLY COMPONENTS	FIRE RATING	SOUND RATING
F1	<p>SLAB ON GRADE-BASEMENT AND GARAGE FLOOR</p> <p>4" MIN. C.I.P. CONCRETE SLAB ON GRADE, REINFORCING & THICKNESS PER STRUCT. 2" SAND BED 10 MIL. MINIMUM THICKNESS POLY SHEETING VAPOR/MOISTURE BARRIER 4" THICK CRUSHED ROCK BASE COMPACTED SUBGRADE OR ENGINEERED BACKFILL</p> <p>NOTE: VERIFY SLAB & SUBGRADE DESIGN WITH STRUCTURAL & GEOTECHNICAL RECOMMENDATIONS PRIOR TO INSTALLATION</p>		
F2	<p>TYPICAL FLOOR - ENTRY AND UPPER FLOOR</p> <p>FLOORING PER PLANS FLOOR SHEATHING - TYPE, THICKNESS, AND FASTENING PER STRUCTURAL WOOD JOIST, SIZE AND SPACING PER STRUCTURAL OPTIONAL R-19 SOUND ATTENUATION BATT INSULATION FOR INCREASED ACOUSTIC PERFORMANCE. WOOD CEILING PER PLAN</p> <p>NOT SHOWN: CONTINUOUS BEAD OF ACOUSTIC SEALANT AT PERIMETER OF WALL MEMBRANE WHERE PLANE MEETS ADJACENT WALLS</p>		
F3	<p>TYPICAL FLOOR - ENTRY AND UPPER FLOOR</p> <p>HARD WOOD FLOOR STUD PER STRUCTURAL HARD WOOD CEILING</p>		

MARK	ROOF/CEILING ASSEMBLY COMPONENTS	FIRE RATING	SOUND RATING
R1	<p>TYPICAL ROOF</p> <p>ASPHALT SHINGLES. ROOF FELT UNDERLAYMENT (2 LAYERS) ROOF SHEATHING PER STRUCTURAL R-30 FIBERGLASS INSULATION (BATT OR BLOWN-IN) JOIST PER STRUCTURAL AT 24" O.C.</p> <p>(1) LAYERS 1/2" GYPSUM W DRYWALL SCREWS 24" OC.</p> <p>NOTE: Joints shall have L-rating measured at .30" of water in both ambient temperature and elevated temperature tests, and shall not exceed 1 & 2 per IBC714.5</p>		
R2	<p>FLAT ROOF/DECK @ UPPER LEVEL- 2x WOOD RAFTERS</p> <p>THERMOPLASTIC POLYOLEFIN (TPO) ROOFING MEMBRANE O/ SLIPSHEET R-38 MIN. RIGID XPS OR POLYISO. INSULATION, SLOPE 1/4" / FT. TO DRAIN. WHERE MULTIPLE LAYERS ARE REQUIRED, STAGGER JOINTS ROOF SHEATHING PER STRUCTURAL APPLIED AT RT ANGLES TO TRUSSES W/ 8d NAILS R-30 FIBERGLASS INSULATION (BATT OR BLOWN-IN) 2x ROOF JOISTS PER STRUCTURAL (1) LAYER 1/2" GYPSUM WALLBOARD DRYWALL SCREWS 12" OC.</p>		
R3	<p>FLAT ROOF @ GARAGE- 2x WOOD RAFTERS</p> <p>THERMOPLASTIC POLYOLEFIN (TPO) ROOFING MEMBRANE O/ SLIPSHEET R-38 MIN. RIGID XPS OR POLYISO. INSULATION, SLOPE 1/4" / FT. TO DRAIN. WHERE MULTIPLE LAYERS ARE REQUIRED, STAGGER JOINTS ROOF SHEATHING PER STRUCTURAL APPLIED AT RT ANGLES TO TRUSSES W/ 8d NAILS 2x ROOF JOISTS PER STRUCTURAL (1) LAYER TYPE "X" 5/8" GWB</p>		

PROJECT
PAEK RESIDENCE

ADDRESS
2215 80TH AVE SE
MERCER ISLAND, WA 98040

CLIENT
TIMOTHY PAEK

NO.	ISSUED	DATE

REVISIONS

DRAWING STATUS

Discrepancies must be reported immediately to the Architect before proceeding. Only figured dimensions are to be used. Contractors must check all dimensions on site. This drawing is protected by copyright. ALL DIMENSIONS ARE SHOWN IN IMPERIAL.

MZA
ARCHITECTURE

400 108th Ave NE Suite 108 Bellevue, WA 98004 | 425.559.7888 | contact@mza-us.com

STAMP

REGISTERED ARCHITECT

Ming Zhang






STATE OF WASHINGTON

DRAWING TITLE
FLOOR & ROOF/CEILING TYPES

DRAWN Author	DESIGNED Designer
DATE 08/15/18	
GRAPHIC SCALE 1" = 1'-0"	
PROJECT NO. 18-009	
DRAWING NO. A7.2	REVISION NO.

24"x36" ARCH. D. SHEET SIZE

- NOTES :**
1. PLACE WINDOW ON 1/8" SHIMS TO PROVIDE DRAINAGE GAP BETWEEN WINDOW FRAME AND SILL PAN.
 2. ATTACH WINDOW PER MANUFACTURER'S RECOMMENDATIONS AT SILL AND JAMBS.
 3. APPLY APPROVED SEALANT BEHIND NAIL FLANGES AT HEAD AND JAMBS.



- NOTES**
1. BUILDING ENVELOPE/WRB BASIS OF DESIGN:
 - A. "WRB": VAPRO-SHIELD "REVEAL-SHIELD SA" SELF-ADHERED MEMBRANE INCLUDING APPROPRIATE ACCESSORIES
 - B. SILL FLASHING: AS APPROVED BY WRB MANUFACTURER INCLUDING APPROPRIATE ACCESSORIES
 - C. MUDSILL GASKET: EPDM STRUCTURAL GASKET BY CONSERVATION TECHNOLOGIES
 - D. LIQUID FLASHING: VAPRO-SHIELD "VAPROLIQU-FLASH"
 - E. HEAD FLASHING BED: AS APPROVED BY WRB MANUFACTURER AND PER NOTE 13 BELOW
 - F. FASTENERS & SEAMS: AS APPROVED BY WRB MANUFACTURER AND PER NOTE 13 BELOW
 - G. SEALANT: AS APPROVED BY WRB MANUFACTURER AND PER NOTE 13 BELOW

2. CONTRACTOR SHALL PERFORM ALL WORK WITHIN THIS SCOPE IN ACCORDANCE AND COMPLIANCE WITH ALL RELEVANT CITY, COUNTY, STATE AND/OR FEDERAL ORDINANCES, LAWS, REGULATIONS AND CODES. CONTRACTOR SHALL COMPLY WITH ALL REQUIREMENTS ESTABLISHED BY THE 2012 INTERNATIONAL RESIDENTIAL CODE (IRC) WITH APPROPRIATE STATE AND LOCAL JURISDICTION AMENDMENTS.
3. CONTRACTOR SHALL MAINTAIN THE JOBSITE IN A CLEAN AND WORKMANLIKE CONDITION. ANY DEBRIS GENERATED DURING CONSTRUCTION SHALL BE REMOVED FROM THE JOBSITE CONTINUALLY. THE JOBSITE SHALL BE LEFT IN A CLEAN AND NEAT CONDITION AT THE END OF EACH WORKDAY. DEBRIS REMOVAL FROM THE JOBSITE SHALL BE ONGOING. CONTRACTOR SHALL DISPOSE ALL MATERIALS AND DEBRIS IN A LEGAL MANNER. ALL PEDESTRIAN AND VEHICULAR ACCESS-WAYS SHALL BE MAINTAINED IN A CLEAN CONDITION THROUGHOUT THE PROJECT.

4. CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND SITE CONDITIONS PRIOR TO CONSTRUCTION.
5. CONTRACTOR SHALL FOLLOW SPECIFIED WATERPROOFING SYSTEMS AND INCORPORATION THEREOF. CONTRACTOR SHALL VERIFY THE MATERIAL COMPATIBILITY OF ALL WATERPROOFING COMPONENTS, SUCH AS SEALANTS, CLOSED-CELL BACKER ROD, SELF-ADHERING MEMBRANE, ETC., UTILIZED IN CONJUNCTION WITH OTHER WATERPROOFING OR BUILDING SYSTEM COMPONENTS. SHOULD THE CONTRACTOR DECIDE TO REQUEST MATERIAL SUBSTITUTION FROM THOSE SPECIFIED BY THE ARCHITECT.

6. PRIOR TO PURCHASING AND INSTALLATION, THE CONTRACTOR SHALL PROVIDE THE ARCHITECT FOR THEIR APPROVAL, SHOP DRAWINGS AND SPECS FOR ALL METAL FLASHING AND COUNTER-FLASHINGS IN ORDER TO DEMONSTRATE THEIR UNDERSTANDING OF THE DETAILS.

7. CONTRACTOR IS SOLELY RESPONSIBLE FOR QUALITY CONTROL AND ASSURANCE OF THE WORK PERFORMED BY THE CONTRACTOR, ITS AGENTS, EMPLOYEES OR ANY SUBCONTRACTOR EMPLOYED OR OTHERWISE RETAINED BY THE CONTRACTOR. CONTRACTOR IS FURTHER RESPONSIBLE FOR PROPER INTEGRATION OF BUILDING COMPONENTS TO PROVIDE A WEATHER-RESISTIVE BUILDING SYSTEM AS INTENDED BY THE DETAILS PROVIDED BY ARCHITECT.

8. CONTRACTOR SHALL BE RESPONSIBLE FOR THE MEANS AND METHODS OF WORK AND SHALL CARRY OUT ALL WORK IN COMPLIANCE WITH THE BEST INDUSTRY STANDARDS AND IN COMPLIANCE WITH PUBLISHED MANUFACTURER'S INSTALLATION INSTRUCTIONS AND STANDARDS REFERENCED IN THE SPECIFICATIONS.

9. MOCKUP(S) OF ALL BUILDING ENVELOPE COMPONENTS SUCH AS WINDOWS, DOORS, WRB, CLADDING AND PENETRATION INSTALLATION MUST BE CARRIED OUT PRIOR TO COMMENCEMENT OF EXTERIOR ENVELOPE WORK.

10. DETAILS MAY NOT BE MODIFIED, REVISED OR ELIMINATED BY THE CONTRACTOR WITHOUT PRIOR WRITTEN CONSENT

11. IT IS THE CONTRACTOR'S RESPONSIBILITY TO NOTIFY AND SCHEDULE FOR INSPECTION AND APPROVAL OF THE WORK PERFORMED WITH RESPECT TO EACH OF THE WATERPROOFING COMPONENTS.

12. UNLESS OTHERWISE NOTED, ALL EXPOSED METAL FLASHINGS AND COUNTER-FLASHINGS SHALL BE MADE OF MINIMUM 24 GA PRE-FINISH SHEET METAL. METAL FLASHING SHALL CONFORM TO SMACNA, BUILDING CODE AND OTHER RELEVANT CODES AND INDUSTRY STANDARDS. THE VERTICAL LEGS OF SAID FLASHINGS SHALL BE MINIMUM 6 INCHES LONG. THE JOINTS OF PRE-FINISH METAL FLASHINGS SHALL BE BENT IN PLACE SUCH AS TO PREVENT MOISTURE MIGRATION PAST THE END DAMS. ALL CONCEALED METAL FLASHING AND COUNTER-FLASHING PIECES SHALL BE 24 GA G-90 GALVANIZED SHEET METAL OR SCHEDULE 307 STAINLESS STEEL. JOINTS OF ALL FLASHING PIECES OTHER THAN PRE-FINISH METAL MUST BE WELDED OR SOLDERED. ALL METAL FLASHING SYSTEMS SHALL BE MANUFACTURED & INSTALLED IN ACCORDANCE WITH THE ARCHITECTURAL SHEET METAL MANUAL PUBLISHED BY SMACNA. UNLESS OTHERWISE NOTED, ALL METAL HEAD FLASHINGS SHALL HAVE A MINIMUM 1/2"-TALL END-DAMS. UNLESS OTHERWISE NOTED, ALL SILL PAN FLASHINGS SHALL HAVE END- AND BACK-DAMS. UNLESS OTHERWISE NOTED ALL FLASHINGS AND COUNTER FLASHINGS (METAL AND OTHERWISE) SHALL BE SET IN A CONTINUOUS BEAD OF NON SKINNING BUTYL SEALANT OR APPROVED EQUAL.

13. UNLESS OTHERWISE NOTED, ENGINEERED SEALANT JOINTS SHALL BE 1/2-INCH MINIMUM WIDE BY 1/4-INCH MINIMUM DEEP IN AN ATTEMPT TO MAINTAIN A 2:1 RATIO. SEALANTS SHALL BE ONE-PART SILICONE SEALANT & SINGLE-PART POLYURETHANE FOR SURFACE APPLICATION AND NON-SKINNING BUTYL FOR INSTALLATION BETWEEN CONCEALED MATERIAL INTERFACES. ACCEPTABLE SEALANTS INCLUDE BUT ARE NOT LIMITED TO DOW CORNING 790 AND 795 SILICONE BUILDING SEALANT, SIKAFLEX 15 LM, AND SONOLASTIC 150 VLM.

14. WINDOW AND DOOR UNITS INSTALLED WITHIN THE EXTERIOR WALL SYSTEM MAY NEED TO BE FURRED OUT TO ALLOW FOR PROPER DRAINAGE. IF THIS IS THE CASE, THE FURRING MATERIAL SHALL BE PVC BATTENS OR PRESSURE-TREATED SOLID BLOCKING.

15. THE ROUGH OPENING FOR WINDOWS MUST BE 1/2" WIDER AND 1/2" TALLER THAN THE WIDTH & HEIGHT OF THE WINDOW UNIT AS THE SILL PAN WILL LIFT THE WINDOW UNITS BY APPROXIMATELY 1/8"-1/4" OFF THE SILL. REFER TO WINDOW MFR'S INSTALLATION MANUAL FOR ADDITIONAL ROUGH OPENING REQUIREMENTS.

16. UNLESS OTHERWISE NOTED ON THE PLANS, ALL WOOD BLOCKING SHALL BE PRESSURE-TREATED LUMBER. IF SUCH MATERIAL IS CUT ON-SITE, CUT ENDS MUST BE TREATED WITH STANDARD WOOD PRIMERS IMMEDIATELY.

17. FURRING BATTENS SHALL BE 3/4" BY 1-7/8" PVC VAPROBATTEN (WITH APPROPRIATE ACCESSORIES) MANUFACTURED BY VAPROSHIELD LLC. FURRING BATTENS SHALL ONLY BE INSTALLED VERTICALLY. FURRING BATTENS MUST BE INSTALLED DIRECTLY OVER STUDS SPACED NO MORE THAN 16" o.c. FURRING BATTENS MUST BE SECURELY ATTACHED TO THE STUDS USING APPROVED FASTENERS. ENSURE THAT THE FASTENERS FOR SIDING INSTALLATION ARE LONG ENOUGH TO PENETRATE THROUGH THE FURRING BATTENS, SHEATHING(S) AND INTO STUDS A MINIMUM OF 1/2". WHERE DISSIMILAR MATERIALS ABUT, INSTALL FURRING BATTENS DIRECTLY BEHIND MATERIAL TRANSITIONS.

18. AT RAINSCREEN SYSTEMS INSECT SCREENS SHALL BE PROVIDED AT TOP & BOTTOM OF THE WALLS AS WELL AS TOP & BOTTOM ANY AND ALL WALL PENETRATIONS. IT SHALL BE EITHER 3/4" MIN VAPROVENT STRIP / VAPROVENT HOOK STRIP OR METAL BUG SCREEN. THE SCREEN / STRIP MUST BE INSTALLED CONTINUOUSLY.

19. WINDOW AND DOOR PENETRATION WRAPS SHALL CONSIST OF VAPROSHIELD-WRAPSHIELD MANUFACTURED BY VAPROSHIELD LLC. INSTALL PENETRATION WRAPS PER MANUFACTURER'S RECOMMENDATIONS AS WELL AS THE WATERPROOFING DETAILS. USE FACTORY PRE-FORMED CORNERS. USE APPROPRIATE PRIMER FOR APPLICATIONS AT EXTERIOR SHEATHING OR WHERE THE SURFACE TEMPERATURE IS BELOW 40-DEGREE FAHRENHEIT PURSUANT TO THE MANUFACTURER'S INSTRUCTIONS.

20. UNLESS OTHERWISE NOTED, SELF-ADHERING MEMBRANE (S.A.M.) SHALL BE MINIMUM OF 9" WIDE WRAPSHIELD S.A.M. MANUFACTURED BY VAPROSHIELD LLC, OR THERMFLASH. USE APPROPRIATE PRIMER FOR APPLICATIONS AT EXTERIOR SHEATHING OR WHERE THE SURFACE TEMPERATURE IS BELOW 40-DEGREE FAHRENHEIT PER MANUFACTURER'S RECOMMENDATIONS.

21. WHERE THROUGH WALL PENETRATIONS OCCUR (e.g., HOSE BIBS, PIPES, ELECTRICAL BOXES, LIGHT FIXTURES, ETC.) INSTALL 24 ML THERM FLASH PENETRATION WRAP & BUTYL TAPE AS WELL AS WRB APRONS PER WATERPROOFING DETAILS.

22. THE BUILDING ENVELOPE SYSTEM SHALL BE A CONTINUOUS AIR-BARRIER SYSTEM IN ACCORDANCE WITH 2012 WASHINGTON ENERGY CODE PROVISIONS.

23. AT CONCRETE CONSTRUCTION & COLD-JOINTS APPLY APPROVED DOUBLE LOCKING HYDROPHOBIC WATERSTOP CAPABLE OF 2-TIMES EXPANSION BY VOLUME. BASIS OF DESIGN IS ULTRASEAL P-201 BY ADEKA. CONCRETE SHALL BE CLEANED, TOOLED AND PRIMED BEFORE INSTALLING WATERSTOP MEDIUM.

24. ALL FASTENERS SHALL BE EITHER STAINLESS STEEL, OR DOUBLE-DIPPED, HOT-DIPPED OR HEAVY-DIPPED GALVANIZED CONFORMING TO ASTM A153. ELECTRO-GALVANIZED FASTENERS MUST NOT BE USED UNDER ANY CIRCUMSTANCES.

25. UNDER SLAB VAPOR BARRIER AT SLAB ON GRADE AREAS SHALL BE CLASS B, 15mil GEOMEMBRANE CONFORMING TO ASTM E-1745. BASIS OF DESIGN IS STEGO WRAP 15mil WITH STEGO TAPE, MANUFACTURED BY STEGO INDUSTRIES.






26. MAINTAIN A MINIMUM OF 6" SEPARATION BETWEEN FINISH GRADE AND FRAMING AND SIDING MATERIALS.

27. SLOPE ALL WEATHER-DECKS, WALKS AND PATIOS AWAY FROM THE BUILDING WITH A MINIMUM SLOPE OF 1/4" PER FOOT. INSTALL CRICKETS ON WEATHER-DECK SURFACES, WHERE NEEDED, TO ALLOW FOR PROPER SLOPE AND DRAINAGE. AT A MINIMUM 1/4" PER 1' SLOPE (U.O.N.) MUST BE PROVIDED TOWARD ROOF DRAINS & SCUPPERS.

28. WHOLE BUILDING AIR-LEAKAGE TESTING VIA BLOWER DOOR TEST SHALL BE PERFORMED IN ACCORDANCE WITH THE 2012 WSEC. REFER TO "AIR BARRIER GENERAL NOTES" AND "ENERGY CODE NOTES" FOR ADDITIONAL INFORMATION AND REQUIREMENTS. THE OWNER SHALL ENGAGE A TESTING AGENCY TO PERFORM THE REQUIRED TESTING IN ACCORDANCE WITH 2012 WSEC. TESTING SHALL BE IN COMPLIANCE WITH ASTM E-779 OR SIMILAR APPROVED TEST METHOD.

29. ANY DISCREPANCY NOTED BY THE CONTRACTOR MUST BE BROUGHT TO THE ARCHITECT'S ATTENTION IMMEDIATELY. WHERE DISCREPANCY OCCURS BETWEEN VARIOUS CONTRACT DOCUMENTS, CONTRACTOR SHALL FOLLOW THE MOST STRINGENT REQUIREMENT FOR EACH CATEGORY.


30. CONTRACTOR SHALL SUPPLY AND INSTALL FLASHINGS AND COUNTER-FLASHINGS AT ALL TRANSITIONS AND JUNCTIONS PURSUANT TO THE REQUIREMENTS OF THE BUILDING CODE, INDUSTRY STANDARDS INCLUDING SMACNA, EVEN IF SUCH FLASHING IS NOT SPECIFICALLY CALLED OUT FOR IN A DETAIL PROVIDED FOR HEREIN.




NOTE:
AT SILL, WRB MUST BE INSTALLED BEHIND (UNDER) R.O. MEMBRANE TAPE OF WRB & PENETRATION WRAP

- SILL PAN NOTES:**
1. ALL PANS AT MASONRY TO BE STAINLESS STEEL OR 24 GA GALV. PRE-FINISHED.
 2. RESIDENTIAL WINDOW WALL SYSTEMS TO HAVE ALUMINUM PANS & FLASHINGS PER DETAILS TO MATCH WINDOW FRAME COLORS.
 3. SEAL OR SOLDER JOINTS AT END- & BACK DAMS TO FORM A WATERTIGHT PAN ASSEMBLY. SEAL BACK TO END DAM TRANSITIONS.
 4. COORDINATE BACK DAM HEIGHT WITH THRESHOLD AND/OR INTERIOR FINISHES PER ARCH. PLANS.
 5. PROVIDE HEMMED EDGE AT ALL EXPOSED EDGES.

- WRAP & WRB NOTE:**
1. FASTEN WINDOW/DOOR WRAP & WRB PER WP DETAILS PROVIDED HEREIN WITH STAINLESS STEEL STAPLES w/ 7/16" CROWNS.
 2. WHERE STEEL STUD FRAMING OCCURS, USE APPROVED ADHESIVE TO PROPERLY ATTACH WINDOW/DOOR WRAP THERETO.
 3. WHERE CONCRETE SURFACES OCCUR, USE VAPROSHIELD S.A.M. MEMBRANE FOR WINDOW/DOOR WRAPS AND WRB.
 4. WRAP PENETRATION WRAP INSIDE R.O. AND TAPE TO MAINTAIN AIR-BARRIER SYSTEM.




B SILL PAN AT SLIDING GLASS DOOR




A SILL PAN AT WINDOW



PERMIT- WINDOW-WRAP
1" = 1'-0"



- WRB NOTES:**
1. INSIDE & OUTSIDE CORNER WRAP: APPLY ONE LAYER OF 36" WIDE BREATHABLE MEMBRANE FROM THE SAME MANUFACTURER AS THE WRB PER NOTES PRIOR TO INSTALLATION OF FIELD WRB.
 2. INSTALL WEATHER RESISTIVE BARRIER PER NOTES IN WEATHERBOARD FASHION STARTING FROM THE BOTTOM OF THE WALL. ENSURE THAT THE EDGES OF THE LAYERS OF WRB ARE STAGGERED AT LEAST 6".
 3. TAPE ALL JOINTS OF WRB WITH 3" WIDE BUTYL TAPE AS APPROVED TO CREATE A COMPLETE AIR-BARRIER SYSTEM.
 4. WHERE CONCRETE SURFACES OCCUR, INSTALL VAPROSHIELD S.A.M. THROUGHOUT.



PERMIT-WRB
Scale: 1 1/2" = 1'-0"

PROJECT PAEK RESIDENCE	
ADDRESS 2215 80TH AVE SE MERCER ISLAND, WA 98040	
CLIENT TIMOTHY PAEK	
NO.	ISSUED
REVISIONS	
DRAWING STATUS	
Discrepancies must be reported immediately to the Architect before proceeding. Only figured dimensions are to be used. Contractors must check all dimensions on site. This drawing is protected by copyright. ALL DIMENSIONS ARE SHOWN IN IMPERIAL.	
 <p>600 108th Ave NE Suite 108 Bellevue WA 98004 425.559.7888 contact@mza-arch.com</p>	
STAMP	
DRAWING TITLE BUILDING ENVELOPE DETAILS	
DRAWN Author	DESIGNED Designer
DATE 08/16/18	
GRAPHIC SCALE As indicated	
PROJECT NO. 18-009	
DRAWING NO. A8.0	REVISION NO.

FILE NAME:
PLOT DATE:

General Structural Notes Continued
THE FOLLOWING APPLY UNLESS SHOWN OTHERWISE ON THE DRAWINGS

WOOD

37. FRAMING LUMBER SHALL BE S-DRY, KD, OR MC-19, AND GRADED AND MARKED IN CONFORMANCE WITH WCLIB STANDARD "GRADING RULES FOR WEST COAST LUMBER NO. 17", OR WMPA STANDARD, "WESTERN LUMBER GRADING RULES 2011". FURNISH TO THE FOLLOWING MINIMUM STANDARDS:

JOISTS AND BEAMS	(2X & 3X MEMBERS)	HEM-FIR NO. 2 MINIMUM BASE VALUE, Fb = 850 PSI
	(4X MEMBERS)	DOUGLAS FIR-LARCH NO. 1 MINIMUM BASE VALUE, Fb = 1000 PSI
BEAMS	(INCL. 6X AND LARGER)	DOUGLAS FIR-LARCH NO. 1 MINIMUM BASE VALUE, Fb = 1350 PSI
POSTS	(4X MEMBERS)	DOUGLAS FIR-LARCH NO. 2 MINIMUM BASE VALUE, Fc = 1350 PSI
	(6X AND LARGER)	DOUGLAS FIR-LARCH NO. 1 MINIMUM BASE VALUE, Fc = 1000 PSI
STUDS, PLATES & MISC. FRAMING:		DOUGLAS-FIR-LARCH OR HEM-FIR NO. 2

38. GLUED LAMINATED MEMBERS SHALL BE FABRICATED IN CONFORMANCE WITH ASTM AND ANSI/AITC STANDARDS. EACH MEMBER SHALL BEAR AN AITC OR APA-EWS IDENTIFICATION MARK AND SHALL BE ACCOMPANIED BY AN AITC OR APA-EWS CERTIFICATE OF CONFORMANCE. ALL SIMPLE SPAN BEAMS SHALL BE DOUGLAS FIR COMBINATION 24F-V4, Fb = 2,400 PSI, Fv = 265 PSI. ALL CANTILEVERED BEAMS SHALL BE DOUGLAS FIR COMBINATION 24F-V8, Fb = 2400 PSI, Fv = 265 PSI. CAMBER ALL SIMPLE SPAN GLULAM BEAMS TO 3,500' RADIUS, UNLESS SHOWN OTHERWISE ON THE PLANS.

39. MANUFACTURED LUMBER, PSL, LVL, AND LSL SHOWN ON PLAN ARE BASED PRODUCTS MANUFACTURED BY THE WEYERHAEUSER CORPORATION IN ACCORDANCE WITH ICC-ES REPORT ESR-1387. MEMBERS SHALL HAVE THE FOLLOWING MINIMUM PROPERTIES:

PSL (2.0E)	Fb = 2900 PSI, E = 2000 KSI, Fv = 290 PSI
LVL (2.0E)	Fb = 2600 PSI, E = 2000 KSI, Fv = 285 PSI
LSL (1.55E)	Fb = 2325 PSI, E = 1550 KSI, Fv = 310 PSI

ALTERNATE MANUFACTURED LUMBER MANUFACTURERS MAY BE USED SUBJECT TO REVIEW AND APPROVAL BY THE ARCHITECT AND STRUCTURAL ENGINEER. ALTERNATE MANUFACTURER'S PRODUCTS SHALL BE COMPATIBLE WITH THE JOIST HANGERS AND OTHER HARDWARE SPECIFIED ON PLANS, OR ALTERNATE HANGERS AND HARDWARE SHALL SUBMITTED FOR REVIEW AND APPROVAL. SUBSTITUTED ITEMS SHALL HAVE ICC-ES REPORT APPROVAL FOR EQUAL OR GREATER LOAD CAPACITIES.

MANUFACTURED LUMBER PRODUCTS SHALL BE INSTALLED WITH A MOISTURE CONTENT OF 12% OR LESS. THE CONTRACTOR SHALL MAKE PROVISIONS DURING CONSTRUCTION TO PREVENT THE MOISTURE CONTENT OF INSTALLED BEAMS FROM EXCEEDING 12%. EXCESSIVE DEFLECTIONS MAY OCCUR IF MOISTURE CONTENT EXCEEDS THIS VALUE.

40. PREFABRICATED PLYWOOD WEB JOIST DESIGN SHOWN ON PLANS IS BASED ON JOISTS MANUFACTURED BY THE WEYERHAEUSER CORPORATION. ALTERNATE PLYWOOD WEB JOIST MANUFACTURERS MAY BE USED SUBJECT TO REVIEW AND APPROVAL BY THE ARCHITECT AND STRUCTURAL ENGINEER. ALTERNATE MANUFACTURER'S PRODUCTS SHALL BE COMPATIBLE WITH THE JOIST HANGERS AND OTHER HARDWARE SPECIFIED ON PLANS, OR ALTERNATE HANGERS AND HARDWARE SHALL SUBMITTED FOR REVIEW AND APPROVAL. SUBSTITUTED ITEMS SHALL HAVE ICC-ES REPORT APPROVAL FOR EQUAL OR GREATER LOAD CAPACITIES.

41. PREFABRICATED CONNECTOR PLATE WOOD ROOF TRUSSES SHALL BE DESIGNED BY THE MANUFACTURER IN ACCORDANCE WITH THE "NATIONAL DESIGN STANDARD FOR METAL PLATE-CONNECTED WOOD TRUSS CONSTRUCTION, ANSI/TPI 1" BY THE TRUSS PLATE INSTITUTE FOR THE SPANS AND CONDITIONS SHOWN ON THE PLANS. LOADING SHALL BE AS FOLLOWS:

TOP CHORD LIVE LOAD	25 PSF
TOP CHORD DEAD LOAD	10 PSF
BOTTOM CHORD DEAD LOAD	5 PSF
TOTAL LOAD	40 PSF
WIND UPLIFT (TOP CHORD)	10 PSF
BOTTOM CHORD LIVE LOAD	10 PSF
(BOTTOM CHORD LIVE LOAD DOES NOT ACT CONCURRENTLY WITH THE ROOF LIVE LOAD)	

WOOD TRUSSES SHALL UTILIZE APPROVED CONNECTOR PLATES (GANGNAIL OR EQUAL). SUBMIT SHOP DRAWINGS AND DESIGN CALCULATIONS TO THE ARCHITECT AND STRUCTURAL ENGINEER FOR REVIEW PRIOR TO FABRICATION. SUBMITTED DOCUMENTS SHALL BE SIGNED AND STAMPED BY A STRUCTURAL ENGINEER REGISTERED IN THE STATE OF WASHINGTON. PROVIDE FOR SHAPES, BEARING POINTS, INTERSECTIONS, HIPS, VALLEYS, ETC., SHOWN ON THE DRAWINGS. EXACT COMPOSITION OF SPECIAL HIP, VALLEY, AND INTERSECTION AREAS (USE OF GIRDER TRUSSES, JACK TRUSSES, STEP-DOWN TRUSSES, ETC.) SHALL BE DETERMINED BY THE MANUFACTURER UNLESS SPECIFICALLY INDICATED ON THE PLANS. PROVIDE ALL TRUSS TO TRUSS AND TRUSS TO GIRDER TRUSS CONNECTION DETAILS AND REQUIRED CONNECTION MATERIALS. PROVIDE FOR ALL TEMPORARY AND PERMANENT TRUSS BRACING AND BRIDGING.

42. PLYWOOD SHEATHING SHALL BE GRADE C-D, EXTERIOR GLUE OR STRUCTURAL II, EXTERIOR GLUE IN CONFORMANCE WITH DOC PS 1 OR PS 2. ORIENTED STRAND BOARD OF EQUIVALENT THICKNESS, EXPOSURE RATING AND PANEL INDEX MAY BE USED IN LIEU OF PLYWOOD.

ROOF SHEATHING SHALL BE 1/2" (NOMINAL) WITH SPAN RATING 32/16.

FLOOR AND DECK SHEATHING SHALL BE 3/4" (NOMINAL) WITH SPAN RATING 48/24.

WALL SHEATHING SHALL BE 1/2" (NOMINAL) WITH SPAN RATING 24/0.

PROVIDE APPROVED PLYWOOD EDGE CLIPS CENTERED BETWEEN JOISTS/TRUSSES AT UNBLOCKED ROOF SHEATHING EDGES. ALL FLOOR SHEATHING EDGES SHALL HAVE APPROVED T&G JOINTS OR SHALL BE SUPPORTED WITH SOLID BLOCKING. ALLOW 1/8" SPACING AT ALL PANEL EDGES AND ENDS OF FLOOR AND ROOF SHEATHING.

REFER TO WOOD FRAMING NOTES BELOW FOR TYPICAL NAILING REQUIREMENTS.

43. ALL WOOD IN DIRECT CONTACT WITH CONCRETE OR MASONRY SHALL BE PRESSURE-TREATED WITH AN APPROVED PRESERVATIVE OR (2) LAYERS OF ASPHALT IMPREGNATED BUILDING PAPER SHALL BE PROVIDED BETWEEN UNTREATED WOOD AND CONCRETE OR MASONRY.

44. PRESERVATIVE TREATED WOOD SHALL BE TREATED PER AWPA STANDARD U1 TO THE USE CATEGORY EQUAL TO OR HIGHER THAN THE INTENDED APPLICATION. TREATED WOOD FOR ABOVE GROUND USE SHALL BE TREATED TO AWPA UC3B. WOOD IN CONTINUOUS CONTACT WITH FRESH WATER OR SOIL SHALL BE TREATED TO AWPA UC4A. WOOD FOR USE IN PERMANENT FOUNDATIONS SHALL BE TREATED TO AWPA UC4B.

45. FASTENERS AND TIMBER CONNECTORS USED WITH TREATED WOOD SHALL HAVE CORROSION RESISTANCE AS INDICATED IN THE FOLLOWING TABLE, UNLESS OTHERWISE NOTED.

WOOD TREATMENT	CONDITION	PROTECTION
HAS NO AMMONIA CARRIER	INTERIOR DRY	G90 GALVANIZED
CONTAINS AMMONIA CARRIER	INTERIOR DRY	G185 OR A185 HOT DIPPED OR CONTINUOUS HOT-GALVANIZED PER ASTM A653
CONTAINS AMMONIA CARRIER	INTERIOR WET	TYPE 304 OR 316 STAINLESS
CONTAINS AMMONIA CARRIER	EXTERIOR	TYPE 304 OR 316 STAINLESS
AZCA	ANY	TYPE 304 OR 316 STAINLESS

INTERIOR DRY CONDITIONS SHALL HAVE WOOD MOISTURE CONTENT LESS THAN 19%. WOOD MOISTURE CONTENT IN OTHER CONDITIONS (INTERIOR WET, EXTERIOR WET, AND EXTERIOR DRY) IS EXPECTED TO EXCEED 19%. CONNECTORS AND THEIR FASTENERS SHALL BE THE SAME MATERIAL. COMPLY WITH THE TREATMENT MANUFACTURERS RECOMMENDATIONS FOR PROTECTION OF METAL.

46. TIMBER CONNECTORS CALLED OUT BY LETTERS AND NUMBERS SHALL BE "STRONG-TIE" BY SIMPSON COMPANY, AS SPECIFIED IN THEIR CATALOG NUMBER C-2015. EQUIVALENT DEVICES BY OTHER MANUFACTURERS MAY BE SUBSTITUTED, PROVIDED THEY HAVE ICC-ES APPROVAL FOR EQUAL OR GREATER LOAD CAPACITIES. PROVIDE NUMBER AND SIZE OF FASTENERS AS SPECIFIED BY MANUFACTURER FOR MAXIMUM LOAD CARRYING CAPACITY. CONNECTORS SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.

ALL 2X JOISTS SHALL BE CONNECTED TO FLUSH BEAMS WITH "LUS" SERIES JOIST HANGERS. ALL TJI JOISTS SHALL BE CONNECTED TO FLUSH BEAMS WITH "ITS" SERIES JOIST HANGERS. ALL DOUBLE-JOIST BEAMS SHALL BE CONNECTED TO FLUSH BEAMS WITH "MIT" SERIES JOIST HANGERS.

WHERE CONNECTOR STRAPS CONNECT TWO MEMBERS, PLACE ONE-HALF OF THE NAILS OR BOLTS IN EACH MEMBER.

ALL SHIMS SHALL BE SEASONED AND DRIED AND THE SAME GRADE (MINIMUM)AS MEMBERS CONNECTED.

47. WOOD FASTENERS

A. NAIL SIZES SPECIFIED ON DRAWINGS ARE BASED ON THE FOLLOWING SPECIFICATIONS:

SIZE	LENGTH	DIAMETER
8d	2-1/2"	0.131"
10d	3"	0.148"
16d BOX	3-1/2"	0.135"

IF CONTRACTOR PROPOSES THE USE OF ALTERNATE NAILS, THEY SHALL SUBMIT NAIL SPECIFICATIONS TO THE STRUCTURAL ENGINEER (PRIOR TO CONSTRUCTION) FOR REVIEW AND APPROVAL.

NAILS - PLYWOOD (APA RATED SHEATHING) FASTENERS TO FRAMING SHALL BE DRIVEN FLUSH TO FACE OF SHEATHING WITH NO COUNTERSINKING PERMITTED. TOE-NAILS SHALL BE DRIVEN AT AN ANGLE OF 30 DIGRESS WITH THE MEMBER AND STARTED 1/3 THE LENGTH OF THE NAIL FROM THE MEMBER END.

B. ALL BOLTS IN WOOD MEMBERS SHALL CONFORM TO ASTM A307. PROVIDE WASHERS UNDER THE HEADS AND NUTS OF ALL BOLTS AND LAG BOLTS BEARING ON WOOD. INSTALLATION OF LAG BOLTS SHALL CONFORM TO THE NATIONAL DESIGN SPECIFICATION FOR WOOD CONSTRUCTION WITH A LEAD BORE HOLE OF 60 TO 70 PERCENT OF THE SHANK DIAMETER. LEAD HOLES ARE NOT REQUIRED FOR 3/8" AND SMALLER LAG SCREWS.

48. NOTCHES AND HOLES IN WOOD FRAMING:

A. NOTCHES ON THE ENDS OF SOLID SAWN JOISTS AND RAFTERS SHALL NOT EXCEED ONE-FOURTH THE JOIST DEPTH. NOTCHES IN THE TOP OR BOTTOM OF SOLID SAWN JOISTS SHALL NOT EXCEED ONE-SIXTH THE DEPTH AND SHALL NOT BE LOCATED IN THE MIDDLE THIRD OF THE SPAN. HOLES BORED IN SOLID SAWN JOISTS AND RAFTERS SHALL NOT BE WITHIN 2 INCHES OF THE TOP OR BOTTOM OF THE JOIST, AND THE DIAMETER OF ANY SUCH HOLE SHALL NOT EXCEED ONE-THIRD THE DEPTH OF THE JOIST.

B. IN EXTERIOR WALLS AND BEARING PARTITIONS, ANY WOOD STUD IS PERMITTED TO BE CUT OR NOTCHED TO A DEPTH NOT EXCEEDING 25 PERCENT OF ITS WIDTH. A HOLE NOT GREATER IN DIAMETER THAN 40 PERCENT OF THE STUD WIDTH IS PERMITTED TO BE BORED IN ANY WOOD STUD. IN NO CASE SHALL THE EDGE OF THE BORED HOLE BE NEARER THAN 5/8 INCH TO THE EDGE OF THE STUD. BORED HOLES SHALL NOT BE LOCATED AT THE SAME SECTION OF STUD AS A CUT OR NOTCH.

C. NOTCHES AND HOLES IN MANUFACTURED LUMBER AND PREFABRICATED PLYWOOD WEB JOISTS SHALL BE PER THE MANUFACTURERS RECOMMENDATIONS UNLESS OTHERWISE NOTED.

49. WOOD FRAMING NOTES--THE FOLLOWING APPLY UNLESS OTHERWISE SHOWN ON THE PLANS:

A. ALL WOOD FRAMING DETAILS NOT SHOWN OTHERWISE SHALL BE CONSTRUCTED TO THE MINIMUM STANDARDS OF THE INTERNATIONAL BUILDING CODE, THE AITC "TIMBER CONSTRUCTION MANUAL" AND THE AF&PA "NATIONAL DESIGN SPECIFICATION FOR WOOD CONSTRUCTION". MINIMUM NAILING, UNLESS OTHERWISE NOTED, SHALL CONFORM TO IBC TABLE 2304.10.1. COORDINATE THE SIZE AND LOCATION OF ALL OPENINGS WITH MECHANICAL AND ARCHITECTURAL DRAWINGS.


B. WALL FRAMING: REFER ARCHITECTURAL DRAWINGS FOR THE SIZE OF ALL WALLS. ALL STUDS SHALL BE SPACED AT 16" O.C. UNO. TWO STUDS MINIMUM SHALL BE PROVIDED AT THE END OF ALL WALLS AND AT EACH SIDE OF ALL OPENINGS, AND AT BEAM OR HEADER BEARING LOCATIONS. TWO 2x8 HEADERS SHALL BE PROVIDED OVER ALL OPENINGS NOT OTHERWISE NOTED. SOLID BLOCKING FOR WOOD COLUMNS SHALL BE PROVIDED THROUGH FLOORS TO SUPPORTS BELOW. PROVIDE CONTINUOUS SOLID BLOCKING AT MID-HEIGHT OF ALL STUD WALLS OVER 10'-0" IN HEIGHT.

ALL WALLS SHALL HAVE A SINGLE BOTTOM PLATE AND A DOUBLE TOP PLATE. END NAIL TOP PLATE TO EACH STUD WITH TWO 16d NAILS, AND TOENAIL OR END NAIL EACH STUD TO BOTTOM PLATE WITH TWO 16d NAILS. FACE NAIL DOUBLE TOP PLATE WITH 16d @ 12" O.C. AND LAP MINIMUM 4'-0" AT JOINTS AND PROVIDE EIGHT 16d NAILS @ 4" O.C. EACH SIDE JOINT.

ALL STUD WALLS SHALL HAVE THEIR LOWER WOOD PLATES ATTACHED TO WOOD FRAMING BELOW WITH TWO ROWS OF 16d NAILS @ 12" ON-CENTER, OR ATTACHED TO CONCRETE BELOW WITH 5/8" DIAMETER ANCHOR BOLTS @ 4'-0" ON-CENTER EMBEDDED 7" MINIMUM, UNLESS INDICATED OTHERWISE. INDIVIDUAL MEMBERS OF BUILT-UP POSTS SHALL BE NAILED TO EACH OTHER WITH TWO ROWS OF 16d @12" ON-CENTER. UNLESS OTHERWISE NOTED, GYPSUM WALLBOARD SHALL BE FASTENED TO THE INTERIOR SURFACE OF ALL STUDS AND PLATES WITH NO. 6 X 1-1/4" TYPE S OR W SCREWS @ 8" ON-CENTER. UNLESS INDICATED OTHERWISE, 1/2" (NOMINAL)APA RATED SHEATHING (SPAN RATING 24/0) SHALL BE NAILED TO ALL EXTERIOR SURFACES WITH 8d NAILS @ 6" ON-CENTER AT PANEL EDGES AND TOP AND BOTTOM PLATES (BLOCK UN-SUPPORTED EDGES)AND TO ALL INTERMEDIATE STUDS AND BLOCKING WITH 8d NAILS @ 12" ON-CENTER ALLOW 1/8" SPACING AT ALL PANEL EDGES AND PANEL ENDS.

C. FLOOR AND ROOF FRAMING: PROVIDE DOUBLE JOISTS UNDER ALL PARALLEL PARTITIONS THAT EXTEND OVER MORE THAN HALF THE JOIST LENGTH AND AROUND ALL OPENINGS IN FLOORS OR ROOFS UNLESS OTHERWISE NOTED. PROVIDE SOLID BLOCKING AT ALL BEARING POINTS. TOE-MAIL JOISTS TO SUPPORTS WITH TWO 16d NAILS. ATTACH TIMBER JOISTS TO FLUSH HEADERS OR BEAMS WITH SIMPSON METAL JOIST HANGERS IN ACCORDANCE WITH NOTES ABOVE. NAIL ALL MULTI JOIST BEAMS TOGETHER WITH TWO ROWS 16d @ 12" ON-CENTER.

UNLESS OTHERWISE NOTED ON THE PLANS, PLYWOOD ROOF AND FLOOR SHEATHING SHALL BE LAID UP WITH GRAIN PERPENDICULAR TO SUPPORTS AND NAILED AT 6" ON-CENTER WITH 8d NAILS TO FRAMED PANEL EDGES, STRUTS AND OVER STUD WALLS AS SHOWN ON PLANS AND @ 12" ON-CENTER TO INTERMEDIATE SUPPORTS. PROVIDE APPROVED PLYWOOD EDGE CLIPS CENTERED BETWEEN JOISTS/TRUSSES AT UNBLOCKED ROOF SHEATHING EDGES. ALL FLOOR SHEATHING EDGES SHALL HAVE APPROVED T&G JOINTS OR SHALL BE SUPPORTED WITH SOLID BLOCKING. ALLOW 1/8" SPACING AT ALL PANEL EDGES AND ENDS OF FLOOR AND ROOF SHEATHING. TOENAIL BLOCKING TO SUPPORTS WITH 16d @ 12" ON-CENTER UNLESS OTHERWISE NOTED.



2124 Third Avenue - Suite 100 - Seattle, WA 98121
P: 206.443.6212 ssengineers.com
934 Broadway - Tacoma, WA 98402
P: 253.284.9470 ssengineers.com

Copyright 2018 Swenson Say Fajelt - All Rights Reserved



DRAWN:	SJB
DESIGN:	JRC
CHECKED:	RJA
APPROVED:	ABB

REVISIONS:

DPD:

PROJECT TITLE:

Paek Residence
2215 80th Ave SE
Mercer Island, WA 98040

ARCHITECT:
MZA Architecture
600 108th Ave NE, Suite 108
Bellevue, WA 98004
PH 425.559.7888

ISSUE:

Permit

SHEET TITLE:

**General
Structural Notes
Continued**

SCALE:

DATE: Sept. 4, 2018

PROJECT NO: 10604-2018-01-00

SHEET NO:

S1.1



DRAWN: SJB
DESIGN: JRC
CHECKED: RJA
APPROVED: ABB

REVISIONS:

DPD:

PROJECT TITLE:

Paek Residence
2215 80th Ave SE
Mercer Island, WA 98040

ARCHITECT:

MZA Architecture
600 108th Ave NE, Suite 108
Bellevue, WA 98004
PH 425.559.7888

ISSUE:

Permit

SHEET TITLE:

Basement
Foundation
Plan


SCALE: 1/4" = 1'-0" U.N.O.

DATE: Sept. 4, 2018

PROJECT NO: 10604-2018-01-00

SHEET NO:

S2.1



Legend

- EXISTING FOOTING BELOW
- NEW FOOTING BELOW
- STRUCTURAL WALL OR POST ABOVE
- HOLDOWN PER 4/S3.1

Plan Notes

1. DO NOT SCALE DRAWINGS. REFER TO ARCHITECTURAL DRAWINGS FOR ALL DIMENSIONS.
2. THE BOTTOM OF ALL EXTERIOR FOOTINGS SHALL BE 18" MINIMUM BELOW GRADE.
3. PROVIDE CORNER BARS PER DETAIL 1/S3.1 AT ALL WALL AND FOOTING INTERSECTIONS.
4. PROVIDE EPOXY GROUTED #4 x 2'-4" DOWELS EMBEDDED A MINIMUM OF 4" INTO EXISTING CONCRETE TO MATCH NEW HORIZONTAL REINFORCING. TYPICAL WHERE NEW CONCRETE WALL OR FOOTING TERMINATES AT EXISTING CONCRETE. EPOXY GROUT PER GENERAL STRUCTURAL NOTES.
5. ALL POSTS ABOVE SHALL BEAR FULLY ON BEAMS OR POSTS BELOW AND SHALL HAVE CONTINUOUS FULL BEARING THROUGH FLOORS TO THE FOUNDATION.
6. REFER TO GENERAL STRUCTURAL NOTES FOR ADDITIONAL REQUIREMENTS.

Basement Foundation Plan

Scale: 1/4" = 1'-0"





DRAWN: SJB
 DESIGN: JRC
 CHECKED: RJA
 APPROVED: ABB

REVISIONS:

DPD:

PROJECT TITLE:

Paek Residence
 2215 80th Ave SE
 Mercer Island, WA 98040

ARCHITECT:
 MZA Architecture
 600 108th Ave NE, Suite 108
 Bellevue, WA 98004
 PH 425.559.7888


ISSUE:

Permit
 SHEET TITLE:

Upper Floor Framing Plan

SCALE: 1/4" = 1'-0" U.N.O.
 DATE: Sept. 4, 2018
 PROJECT NO: 10604-2018-01-00
 SHEET NO:

S2.3



Beam Schedule

MARK	BEAM	BRG. STUDS	HANGER
B1	LSL 3/2x14	2	HU14
B2	LSL 3/2x14	3	HHUS410
B3	PSL 5/2x14	4	HHUS5.50/10

- Legend**
- STRUCTURAL WALL BELOW
 - NON-STRUCTURAL WALL BELOW
 - STRUCTURAL WALL OR POST ABOVE
 - SHEARWALL PER 12/S4.1
 - SPAN DIRECTION
 - EXTENT OF JOISTS
 - HEADER/BEAM PER PLAN
 - HANGER (INVERTED)
 - CHANGE IN ELEVATION
 - HOLDOWN PER 5/S4.1
 - CS16 x 4'-0" FRAMING MEMBER TO NO. OF ASTERISKS = NO. OF STUDS

- Plan Notes**
- DO NOT SCALE DRAWINGS. REFER TO ARCHITECTURAL DRAWINGS FOR ALL DIMENSIONS.
 - FLOOR AND ACCESSIBLE ROOF DECK SHEATHING SHALL BE 3/4" A.P.A. RATED PANELS (EXPOSURE 1, SPAN RATING 48/24). NAIL AT ALL FRAMED PANEL EDGES WITH 8d AT 6" oc AND TO ALL INTERMEDIATE FRAMING (FIELD) AT 12" oc.
 - GREEN ROOF SHEATHING SHALL BE 1/2" A.P.A. RATED PANELS (EXPOSURE 1, SPAN RATING 32/16), FACE GRAIN PERPENDICULAR TO SUPPORTS OVER ROOF FRAMING PER PLAN. NAIL SHEATHING AT ALL FRAMED PANEL EDGES WITH 8d AT 6" oc AND TO ALL INTERMEDIATE FRAMING AT 12" oc.
 - AREAS SHADED ON PLAN INDICATED BLOCKED FLOOR DIAPHRAGM. PROVIDE 2x4 FLAT BLOCKING AT ALL UNFRAMED PANEL EDGES. NAIL ALL PANEL EDGES TO FLAT BLOCKING, FRAMING MEMBERS OR BOUNDARY MEMBERS (RIMS, DRAG STRUTS) WITH 8d AT 4" oc AND TO ALL INTERMEDIATE FRAMING (FIELD) AT 12" oc.
 - FLOOR JOISTS SHALL BE 14" TJI 230 @ 16" oc.
 - HEADERS OVER DOOR AND WINDOW OPENINGS SHALL BE FRAMED WITH FLUSH LSL 1-3/4 X 11-7/8 RIM, MINIMUM. DO NOT SPLICE RIM OVER OPENING. HANG JOISTS FROM RIM OVER OPENINGS WITH ITS SERIES HANGERS. PROVIDE (2) TRIMMER STUDS (MINIMUM) AT EACH END OF ALL RIMS UNLESS NOTED OTHERWISE ON PLANS.
 - PROVIDE (2) STUDS (MINIMUM) AT EACH END OF ALL BEAMS UNLESS NOTED OTHERWISE ON PLANS. BEAR BEAM FULLY ON BUILT UP COLUMN AND PROVIDE AC, PC, OR LPC CAP.
 - W# INDICATES SHEAR WALL. SEE SHEARWALL SCHEDULE, 12/S4.1, FOR CONSTRUCTION REQUIREMENTS. ALL EXTERIOR WALLS SHALL BE W6, UNLESS NOTED OTHERWISE ON PLANS.
 - (X)CS16 INDICATES VERTICAL HOLDOWN STRAP AT END OF SHEAR WALL ABOVE. (X) INDICATES STRAP QUANTITY. SEE DETAIL 5/S4.1 FOR INSTALLATION REQUIREMENTS.
 - MANUFACTURED LUMBER PRODUCTS (LSL, LVL, PSL, GL) SHALL BE INSTALLED WITH A MOISTURE CONTENT OF 12% OR LESS. THE CONTRACTOR SHALL MAKE PROVISIONS DURING CONSTRUCTION TO PREVENT THE MOISTURE CONTENT OF INSTALLED BEAMS FROM EXCEEDING 12%.
 - ALL POSTS ABOVE SHALL BEAR FULLY ON BEAMS OR POSTS BELOW AND SHALL HAVE CONTINUOUS VERTICAL GRAIN BLOCKING TO MATCH POST ABOVE FOR FULL BEARING THROUGH FLOORS TO THE FOUNDATION.
 - SPLICE ALL TOP PLATE SPLICES PER DETAIL 10/S4.1.
 - REFER TO GENERAL STRUCTURAL NOTES FOR ADDITIONAL REQUIREMENTS.



DRAWN: SJB
 DESIGN: JRC
 CHECKED: RJA
 APPROVED: ABB

REVISIONS:

DPD:

PROJECT TITLE:

Paek Residence
 2215 80th Ave SE
 Mercer Island, WA 98040

ARCHITECT:
 MZA Architecture
 600 108th Ave NE, Suite 108
 Bellevue, WA 98004
 PH 425.559.7888

ISSUE:

Permit

SHEET TITLE:

Roof Framing Plan


SCALE: 1/4" = 1'-0" U.N.O.

DATE: Sept. 4, 2018

PROJECT NO: 10604-2018-01-00

SHEET NO:

S2.4



Legend

- STRUCTURAL WALL BELOW
- NON-STRUCTURAL WALL BELOW
- Wx SHEARWALL PER 12/S4.1
- SPAN DIRECTION
- EXTENT OF JOISTS
- HEADER/BEAM PER PLAN
- HANGER

Plan Notes

1. DO NOT SCALE DRAWINGS. REFER TO ARCHITECTURAL DRAWINGS FOR ALL DIMENSIONS.
2. ROOF SHEATHING SHALL BE 1/2" A.P.A. RATED PANELS (EXPOSURE 1, SPAN RATING 32/16), FACE GRAIN PERPENDICULAR TO SUPPORTS OVER ROOF FRAMING PER PLAN. NAIL SHEATHING AT ALL FRAMED PANEL EDGES WITH 8d AT 6"oc AND TO ALL INTERMEDIATE FRAMING AT 12"oc.
3. ROOF FRAMING SHALL BE 14" TJI 230 @ 16"oc.
4. HEADERS OVER DOOR AND WINDOW OPENINGS SHALL BE (2) 2x10 MINIMUM. PROVIDE (2) TRIMMER STUDS (MINIMUM) AT EACH END OF ALL HEADERS UNLESS NOTED OTHERWISE ON PLANS. SEE DETAIL 6/S4.1 FOR TYPICAL INSTALLATION.
5. PROVIDE (2) STUDS (MINIMUM) AT EACH END OF ALL BEAMS UNLESS NOTED OTHERWISE ON PLANS. BEAR BEAM FULLY ON BUILT UP COLUMN AND PROVIDE AC, PC, OR LPC CAP.
6. W# INDICATES SHEAR WALL. SEE SHEARWALL SCHEDULE, 12/S4.1, FOR CONSTRUCTION REQUIREMENTS. ALL EXTERIOR WALLS SHALL BE W6, UNLESS NOTED OTHERWISE ON PLANS.
7. PROVIDE H2.5A HURRICANE TIE AT EACH TJI RAFTER WHERE IT BEARS ON EXTERIOR WALL.
8. MANUFACTURED LUMBER PRODUCTS (GL) SHALL BE INSTALLED WITH A MOISTURE CONTENT OF 12% OR LESS. THE CONTRACTOR SHALL MAKE PROVISIONS DURING CONSTRUCTION TO PREVENT THE MOISTURE CONTENT OF INSTALLED BEAMS FROM EXCEEDING 12%.
9. SPLICE ALL TOP PLATE SPLICES PER DETAIL 10/S4.1.
10. REFER TO GENERAL STRUCTURAL NOTES FOR ADDITIONAL REQUIREMENTS.





DRAWN: SJB
DESIGN: JRC
CHECKED: RJA
APPROVED: ABB

REVISIONS:

DPD:

PROJECT TITLE:

Paek Residence
2215 80th Ave SE
Mercer Island, WA 98040

ARCHITECT:
MZA Architecture
600 108th Ave NE, Suite 108
Bellevue, WA 98004
PH 425.559.7888

ISSUE:

Permit

SHEET TITLE:

Typical Wood
Sections & Details


SCALE: 3/4" = 1'-0" U.N.O.

DATE: Sept. 4, 2018


PROJECT NO: 10604-2018-01-00

SHEET NO:

S4.1




1 Typical Shearwall at Changing Wall Thickness 2




- ① PLYWOOD PANEL EDGE NAILING PER SHEARWALL SCHEDULE
- ② BASE PLATE NAILING PER SHEARWALL SCHEDULE
- ③ 16d @ 8"oc


Typical Shearwall Intersections 4



Typical CS16 Holddown 5




Typical Header Support w/2 Bearing Studs 6




NOTE:
SEE SHEARWALL SCHEDULE FOR ALL NAILING AND CONNECTIONS, NOT OTHERWISE NOTED

Typical Shearwall Construction 8




ALL TREAD AND RISER DIMENSIONS PER ARCH.

Typical Stair and Landing Detail 9



Typical Top Plate Splice 10




Shearwall Schedule ①②③④⑤⑥⑦

Mark	Sheathing	Panel Edge Nailing	Top Plate Connection		Base Plate Connection	
			if TJI	if Wood ⑤	at Wood ⑩	at Concrete
W6	15/32" CDX PLYWOOD	8d @ 6"oc	16d @ 6"oc	A35 @ 24"oc	16d @ 6"oc	5/8" A.B. @ 48"oc
W4	15/32" CDX PLYWOOD	8d @ 4"oc	16d @ 4"oc	A35 @ 16"oc	(2)rows 16d @ 6"oc	5/8" A.B. @ 32"oc
W3 ①	15/32" CDX PLYWOOD	8d @ 3"oc	(2)rows 16d @ 4"oc	A35 @ 12"oc	(2)rows 16d @ 6"oc	5/8" A.B. @ 24"oc
W2 ②	15/32" CDX PLYWOOD	8d @ 2"oc	(2)rows 16d @ 4"oc	A35 @ 9"oc	(2)rows 16d @ 4"oc ⑪	5/8" A.B. @ 16"oc


- ① BLOCK PANEL EDGES WITH 2x MIN. LAID FLAT AND NAIL PANELS TO INTERMEDIATE SUPPORTS WITH 8d @ 12"oc.
- ② 8d NAILS SHALL BE 0.131" x 2 1/2" (common) - 16d NAILS SHALL BE 0.135" x 3 1/2" (box)
- ③ EMBED ANCHOR BOLTS AT LEAST 7", EXPANSION BOLTS MAY BE SUBSTITUTED FOR ANCHOR BOLTS WITH 4" EMBEDMENT. TITEN HD SCREW ANCHORS MAY BE SUBSTITUTED FOR ANCHOR BOLTS W/ 4" EMBEDMENT. ALL BOLTS SHALL HAVE 3" x 3" x 1/4" MIN. PLATE WASHERS. PLATE WASHERS SHALL EXTEND TO WITHIN 1/2" OF THE EDGE OF THE BOTTOM PLATE ON THE SIDE WITH SHEATHING. SEE DETAIL C.
- ④ 3x STUDS OR DOUBLE STUDS NAILED TOGETHER W/ BASE PLATE NAILING ARE REQUIRED AT ABUTTING PANEL EDGES OF W3 AND W2. SEE DETAIL B. WHERE 3x STUDS ARE USED FOR W2, STAGGER NAILS AT ADJOINING PANEL EDGES.
- ⑤ TWO STUDS MINIMUM ARE REQUIRED AT EACH END OF ALL SHEARWALLS AND ALL END STUDS SHALL RECEIVE PANEL EDGE NAILING. SEE PLANS AND HOLDOWN SCHEDULE FOR ALTERNATE REQUIREMENTS.
- ⑥ ALL EXTERIOR WALLS SHALL BE W6, UNLESS NOTED OTHERWISE.
- ⑦ 7/16" O.S.B. MAY BE SUBSTITUTED FOR 15/32" CDX.
- ⑧ LTP4's (HORIZONTAL ORIENTATION) W/ 8d COMMON MAY BE SUBSTITUTED FOR A35's AT CONTRACTORS OPTION.
- ⑨ A 2x NAILER ATTACHED W/ BASE PLATE NAILING PER DETAIL A MAY BE SUBSTITUTED FOR A35's AT CONTRACTORS OPTION.
- ⑩ AT MULTI-ROW NAILING, MINIMUM OFFSET BETWEEN ROWS AND ROW SPACING 1/2", SEE DETAIL D.
- ⑪ PROVIDE (3) ROWS 16d @ 6"oc AT LVL RIMS.

Shearwall Schedule - (Sheathed One Side) 12




1

Hinge Connector 2




FOR CALLOUTS
IN COMMON
REFER 2/S4.2

Parapet Over Door 3




Exterior Non-Bearing Wall 4




5


Beam Over Nana Wall 6



Deck/Balcony Framing 7




Exterior Bearing Wall 8




9

Upturned Beam 10



Exterior Wall at Opening 11



Exterior Bearing Wall 12



DRAWN: SJB
DESIGN: JRC
CHECKED: RJA
APPROVED: ABB

REVISIONS:

DPD:

PROJECT TITLE:

Paek Residence
2215 80th Ave SE
Mercer Island, WA 98040

ARCHITECT:

MZA Architecture
600 108th Ave NE, Suite 108
Bellevue, WA 98004
PH 425.559.7888

ISSUE:

Permit

SHEET TITLE:

Wood Framing
Sections & Details

SCALE:

3/4 = 1'-0" U.N.O.

DATE:

Sept. 4, 2018

PROJECT NO:

10604-2018-01-00

SHEET NO:

S4.3



A R C H I T E C T U R E

May 2nd, 2019

Re: 1808-172 Peak Residence

Project Narrative

The project is a significant residential addition. It involves the removal of the entry level walls down to the foundations at that grade and the floor framing above the walk out basement below. The project includes the addition of another story above the current one for a total of 3 stories on the downhill side of the building.

The existing home sits within the 35' buffer of an existing type III watercourse that lies on the neighboring property to the west of our site. The project is proposing the use of buffer averaging as a portion of the remodeled area occurs in the buffer, as does the existing home. Many existing building elements in the buffer are proposed for removal with a few being replaced in kind or similarly.

The project storm drainage will be run to the storm line in 80th as requested by the city through the presubmittal process.

The driveway/curb cut will be relocated due to a change in the garage orientation.

The existing home is approximately 3,352sf. The finished home will be 4,370sf before any basement exclusions.

The project will contain a 330sf accessory dwelling unit on the lowest level.

Altmann Oliver Associates, LLC

AOA



PO Box 578

Carnation, WA 98014

Office (425) 333-4535

Fax (425) 333-4509

Environmental
Planning &
Landscape
Architecture

April 30, 2019

AOA-5800

Kevin Sutton
MZA
600 - 108th Ave. NE, Suite 108
Bellevue, WA 98004

SUBJECT: Critical Areas Study - Watercourse Delineation and Buffer Averaging for: Paek Residence – 2215 80th Ave. SE, Mercer Island, WA Parcel 545230-2145, City File # PRE19-011

Dear Kevin:

On October 30, 2018 I conducted an initial wetland and stream reconnaissance on the subject property utilizing the methodology outlined in the May 2010 *Regional Supplement to the Corps of Engineers Wetland Delineation Manual: Western Mountains, Valleys, and Coast Region (Version 2.0)*. The site is currently entirely developed with an existing single-family residence and associated maintained yard.

Although no wetlands or streams were identified on the property during the site review, one stream (Stream 1) was observed draining from south to north off-site to the west. The ordinary high water (OHW) of this stream adjacent the subject property was delineated on January 3, 2019 and subsequently surveyed.

1.0 EXISTING CRITICAL AREAS

Stream 1 is located within a well-defined historically ditched channel that drains north into a culvert along the south property line of Parcel 531510-1680. The stream was dry during the October 30th site review and conveys only intermittent or seasonal flows.

Vegetation within the riparian corridor of the stream consists of maintained lawn to the edge of the west property line on the site. Vegetation within the off-site portion of the riparian corridor consisted primarily of dense Himalayan blackberry (*Rubus armeniacus*), snowberry (*Symphoricarpos albus*), and English ivy (*Hedera helix*), with scattered Lombardy poplar trees.

Since Stream 1 does not contain fish habitat and conveys only seasonal or intermittent flows, it meets the criteria for a Type 3 watercourse per MICC 19.07.070.A. Type 3 watercourses require a standard buffer of 35 feet from the ordinary high water per MICC 19.070.B.1.

2.0 PROPOSED PROJECT

The standard 35-foot stream buffer currently extends to the western edge of the existing residence. The proposed project consists of a house remodel and a second story addition. A watercourse buffer averaging plan has been prepared for the re-development of the western edge of the house (**Drawings W-1 through W-3**). The area proposed for buffer reduction under the averaging plan currently consists of an existing patio, deck, and stairs and does not provide any functional benefit to the off-site stream. Since no native vegetation would be removed as part of the house addition, there would be no loss of stream buffer function from the expansion project.

2.1 Watercourse Buffer Averaging

The City of Mercer Island may allow buffer averaging if all of the provisions of MICC 19.07.070.B.3 are met:

- a. *The proposal will result in a net improvement of critical area function;*

The area of proposed buffer reduction is currently developed, and no native vegetation would be removed as part of the buffer averaging plan. Since the proposal includes planting native vegetation within the buffer adjacent the existing fence line there would be a net improvement of critical area function.

- b. *The proposal will include replanting of the averaged buffer using native vegetation;*

A planting plan using native vegetation has been prepared for the area of watercourse buffer located along the fence and includes the area of proposed buffer addition in the northwest corner of the site. Since there will be no vegetation removal as part of the buffer averaging plan, it is our opinion that the entire watercourse buffer does not require re-planting and that the proposed planting plan will adequately increase the stream buffer functions over current conditions.

- c. *The total area contained in the averaged buffers on the development proposal site is not decreased below the total area that would be provided if the maximum width were not averaged;*

As part of the buffer averaging plan, 141 s.f. of buffer area would be reduced and replaced with 141 s.f. of additional buffer in the northwest corner of the site and there would be no loss of buffer area.

- d. The standard buffer width is not reduced to a width that is less than the minimum buffer width at any location; and*

The proposed buffer width will not be less than the minimum buffer width (i.e., 25 feet) at any location.

- e. That portion of the buffer that has been reduced in width shall not contain a steep slope.*

The reduced buffer area is not within a steep slope.

3.0 PROPOSED BUFFER PLANTING

Although there would be no loss of buffer function as part of the house project, a mitigation planting plan has been prepared to plant native shrubs within the maintained yard along the west property line (**Drawings W-1 through W-3**). It is my understanding that additional native vegetation is also proposed as part of the overall landscape design for the project. Implementation of the buffer enhancement plan would increase the habitat value of the buffer over current conditions.

Due to the small size of the project it does not appear that long-term performance monitoring should be required. However, if the City determines that monitoring is a requirement, then the following performance standards apply:

3.1 Goal, Objective, and Performance Standard for Enhancement Area

The primary goal of the enhancement plan is to increase the habitat value of the watercourse buffer over current conditions. To meet this goal, the following objectives and performance standards have been incorporated into the design of the plan:

Objective A: Increase the structural and plant species diversity within the enhancement area.

Performance Standard: There will be 100% survival of all woody planted species throughout the enhancement area at the end of the first year of planting. Following Years 2 through 5, success will be based on an 80% survival rate.

Objective B: Limit the amount of invasive and exotic species within the enhancement area.

Performance Standard: After installation and at the end of the fifth year after planting, exotic and invasive plant species will be maintained at levels below 10% total cover in all planted areas.

3.2 Monitoring Methodology

If required, the monitoring program will be conducted for a period of five years, with annual reports submitted to the City of Mercer Island.

Photo-points will be established from which photographs will be taken throughout the monitoring period. These photographs will document general appearance and progress in plant community establishment in the enhancement area. Review of the photos over time will provide a visual representation of success of the plan.

3.3 Maintenance

Maintenance should be conducted on a routine, year-round basis. Contingency measures and remedial action on the site shall be implemented on an as-needed basis at the direction of the consultant or the owner. Tall grasses and weeds shall be removed at the base of plants to prevent engulment. Weed control should be performed by hand removal.

3.4 Contingency Plan

All dead plants will be replaced with the same species or an approved substitute species. Plant material shall meet the same specifications as originally installed material. Replanting will not occur until after reason for failure has been identified (e.g., moisture regime, poor plant stock, disease, shade/sun conditions, wildlife damage, etc.). Replanting shall be completed under the direction of the consultant, City of Mercer Island, or the owner.

3.5 As-built Plan


Following completion of construction activities, an as-built plan for the enhancement area will be provided to the City of Mercer Island. The plan will identify and describe any changes in relation to the original approved plan.

Kevin Sutton
April 30, 2019
Page 5

If you have any questions, please give me a call.

Sincerely,

ALTMANN OLIVER ASSOCIATES, LLC



John Altmann
Ecologist




Photo 1: Panoramic View of back of house and buffer from NW corner of site.



Photo 2: Panoramic View of back of house and buffer looking north from south property line.



Photo 3: Typical view of ditched off-site watercourse.



PLAN LEGEND

- PROPERTY LINE
- - - - - ORDINARY HIGH WATER LINE OF TYPE 3 STREAM
- - - - - 35' STANDARD STREAM BUFFER

IMPACT LEGEND

- [Hatched Box] BUFFER REDUCTION 141 SF


MITIGATION LEGEND

- [Dotted Box] BUFFER REPLACEMENT 141 SF
- [Cross-hatched Box] STREAM BUFFER ENHANCEMENT 187 SF

GRAPHIC SCALE
(IN FEET)



SCALE: 1:5




GENERAL NOTES

1. BASE INFORMATION PROVIDED BY MZA ARCHITECTURE, 600 108TH AVE NE, SUITE 108, BELLEVUE, WA 98004, (425) 554-7000.


Revisions	Date	By

Date 04-30-19
Scale AS NOTED
Project # 5200



PLANT SCHEDULE

SHRUBS						
KEY	SCIENTIFIC NAME	COMMON NAME	SPACING	QTY.	SIZE (MIN.)	NOTES
RS	RIBES SANGUINEUM	RED CURRANT	3' O.C.	11	1 GAL.	MULTI-STEM (3 MIN.)
SA	SYMPHORICARPOS ALBUS	SNOWBERRY	3' O.C.	11	1 GAL.	MULTI-STEM (3 MIN.)



GENERAL NOTES

- BASE INFORMATION PROVIDED BY MZA ARCHITECTURE, 600 108TH AVE NE, SUITE 108, BELLEVUE, WA 98004, (425) 554-7000.

Revisions	Date	By

Date 04-30-19
 Scale AS NOTED
 Project # 5200


CONSTRUCTION SPECIFICATIONS

- ALL PLANTS SHOULD BE INSTALLED BETWEEN DECEMBER 1ST AND MARCH 15TH, UNLESS SUPPLEMENTAL IRRIGATION IS PROVIDED.
- INTERMEDIATE INSPECTIONS. ALL PLANTS SHALL BE INSPECTED AND APPROVED BY THE LANDSCAPE DESIGNER AND/OR WETLAND BIOLOGIST PRIOR TO INSTALLATION. CONDITION OF ROOTS OF A RANDOM SAMPLE OF PLANTS WILL BE INSPECTED, AS WELL AS ALL ABOVEGROUND GROWTH ON ALL PLANTS. ROOTS OF ANY BARE ROOT PLANTS, IF PERMITTED FOR USE, WILL BE INSPECTED. PLANT MATERIAL MAY BE APPROVED AT THE SOURCE, AT THE DISCRETION OF THE LANDSCAPE DESIGNER AND THE WETLAND BIOLOGIST, BUT ALL MATERIAL MUST BE RE-INSPECTED AND APPROVED ON THE SITE PRIOR TO INSTALLATION. PLANT LOCATIONS SHALL ALSO BE INSPECTED AND APPROVED PRIOR TO PLANTING.
- ALL PLANTS SHALL BE PIT-PLANTED IN PLANTING PITS EXCAVATED 2X THE DIAMETER OF THE PLANT. PITS SHALL BE BACKFILLED WITH A 30/70 MIX OF SIERCO TO NATIVE SOIL. PITS SHALL BE AMENDED WITH A HYDRATED SOIL POLYMER (INSTALLED AT RATES PER MANUFACTURER'S SPECIFICATIONS). PLANTS SHALL BE INSTALLED 3" HIGH AND SURFACED MULCHED TO A DEPTH OF 3" WITH PACIFIC GARDEN MULCH PLACED CONTINUOUSLY THROUGHOUT THE PLANTING BED.
- ALL PLANTS SHALL BE NURSERY GROWN (IN WESTERN WA OR OR) FOR AT LEAST 1 YEAR FROM PURCHASE DATE, FREE FROM DISEASE OR PESTS, WELL-ROOTED, BUT NOT ROOT-BOUND AND TRUE TO SPECIES.
- PLANT LAYOUT SHALL BE APPROVED BY AOA PRIOR TO INSTALLATION AND APPROVED UPON COMPLETION OF PLANTING.
- UPON COMPLETION OF PLANTING, ALL PLANTS SHALL BE THOROUGHLY WATERED.
- UPON APPROVAL OF PLANTING INSTALLATION BY AOA, THE CITY OF MERCER ISLAND WILL BE NOTIFIED TO CONDUCT A SITE REVIEW FOR FINAL APPROVAL OF CONSTRUCTION.
- MAINTENANCE SHALL BE IMPLEMENTED ON A REGULAR BASIS ACCORDING TO THE SCHEDULE BELOW.


ANNUAL MAINTENANCE SCHEDULE

MAINTENANCE ITEM	J	F	M	A	M	J	J	A	S	O	N	D
WATERING - YEARS 1 & 2							Ø	Ø	Ø	Ø		
WEED CONTROL			I		I		I			I		
GENERAL MAINT.			I		I		I			I		


I-Ø = NUMBER OF TIMES TASK SHALL BE PERFORMED PER MONTH.



1 CONTAINER PLANTING DETAIL (TYP.)
SCALE: NTS



2 BARE-ROOT PLANTING DETAIL (TYP.)
SCALE: NTS



- NOTES:
- CUTTINGS SHALL BE SPECIES AS NOTED IN THE PLANT SCHEDULE.
 - CUTTINGS SHALL BE AT LEAST 1/2" DIA. AND 4' (min.) IN LENGTH.
 - CUTTINGS MUST BE ALIVE WITH SIDE BRANCHES CLEARLY REMOVED AND BARK INTACT. CUTTINGS SHALL BE PLANTED WITHIN 24 HOURS OF CUTTING.
 - THE BUTT ENDS SHOULD BE CLEANLY CUT AT AN ANGLE FOR EASY INSERTION INTO THE SOIL. THE TOP SHOULD BE CUT SQUARE OR BLUNT.
 - CUTTINGS MUST BE FRESH AND KEPT MOIST AFTER CUTTING. THEY SHOULD BE PRUNED AND INSTALLED THE SAME DAY.
 - DIP BOTTOM OF CUTTING IN A PLANT ROOTING HORMONE PRIOR TO INSERTION INTO THE SOIL.

3 CUTTING INSTALLATION (TYP.)
SCALE: NTS



AOA
Environmental
Planning &
Landscape
Architecture
Altmann Oliver Associates, LLC
Office (425) 333-4338 Fax (425) 333-4309
PO Box 578
Carnation, WA 98014

SPECIFICATIONS & DETAILS
PAEK RESIDENCE
2215 80TH AVE SE
MERCER ISLAND, WA 98040

Revisions	Date	By

Date: 04-30-19
Scale: AS NOTED
Project#: 5200

Sheet # **N-3**

Exhibit 4 - Dev App

CITY OF MERCER ISLAND

COMMUNITY PLANNING & DEVELOPMENT

9611 SE 36TH STREET | MERCER ISLAND, WA 98040

PHONE: 206.275.7605 | www.mercergov.org



CITY USE ONLY

PROJECT#	RECEIPT #	FEE

Date Received:

Received By:

DEVELOPMENT APPLICATION

STREET ADDRESS/LOCATION		ZONE
COUNTY ASSESSOR PARCEL #'S		PARCEL SIZE (SQ. FT.)
PROPERTY OWNER <i>(required)</i>	ADDRESS <i>(required)</i>	CELL/OFFICE <i>(required)</i> E-MAIL <i>(required)</i>
PROJECT CONTACT NAME	ADDRESS	CELL/OFFICE E-MAIL
TENANT NAME	ADDRESS	CELL PHONE E-MAIL

DECLARATION: I HEREBY STATE THAT I AM THE OWNER OF THE SUBJECT PROPERTY OR I HAVE BEEN AUTHORIZED BY THE OWNER(S) OF THE SUBJECT PROPERTY TO REPRESENT THIS APPLICATION, AND THAT THE INFORMATION FURNISHED BY ME IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE.

SIGNATURE

DATE

PROPOSED APPLICATION(S) AND CLEAR DESCRIPTION OF PROPOSAL (PLEASE USE ADDITIONAL PAPER IF NEEDED):

ATTACH RESPONSE TO DECISION CRITERIA IF APPLICABLE

CHECK TYPE OF LAND USE APPROVAL REQUESTED:

APPEALS	DEVIATIONS	WIRELESS COMMUNICATIONS FACILITIES
<input type="checkbox"/> Building (+cost of file preparation)	<input type="checkbox"/> Changes to Antenna requirements	<input type="checkbox"/> Wireless Communications Facilities- 6409 Exemption
<input type="checkbox"/> Code Interpretation	<input type="checkbox"/> Changes to Open Space	<input type="checkbox"/> New Wireless Communications Facility
<input type="checkbox"/> Land use (+cost of verbatim transcript)	<input type="checkbox"/> Critical Areas Setback	VARIANCES (Plus Hearing Examiner Fee)
<input type="checkbox"/> Right-of-Way Use	<input type="checkbox"/> Wet Season Construction Moratorium	<input type="checkbox"/> Type 1**
CRITICAL AREAS	ENVIRONMENTAL REVIEW (SEPA)	<input type="checkbox"/> Type 2***
<input type="checkbox"/> Determination	<input type="checkbox"/> Checklist: Single Family Residential Use	OTHER LAND USE
<input type="checkbox"/> Reasonable Use Exception	<input type="checkbox"/> Checklist: Non-Single Family Residential Use	<input type="checkbox"/> Accessory Dwelling Unit
DESIGN REVIEW	<input type="checkbox"/> Environmental Impact Statement	<input type="checkbox"/> Code Interpretation Request
<input type="checkbox"/> Administrative Review	SHORELINE MANAGEMENT	<input type="checkbox"/> Comprehensive Plan Amendment (CPA)
<input type="checkbox"/> Design Review- Major	<input type="checkbox"/> Exemption	<input type="checkbox"/> Conditional Use (CUP)
<input type="checkbox"/> Design Review – Minor	<input type="checkbox"/> Semi-Private Recreation Tract (modification)	<input type="checkbox"/> Lot Line Revision/ Lot Consolidation
<input type="checkbox"/> Design Review – Study Session	<input type="checkbox"/> Semi-Private Recreation Tract (new)	<input type="checkbox"/> Noise Exception
SUBDIVISION SHORT PLAT	<input type="checkbox"/> Substantial Dev. Permit	<input type="checkbox"/> Reclassification of Property (Rezoning)
<input type="checkbox"/> Short Plat	SUBDIVISION LONG PLAT	<input type="checkbox"/> ROW Encroachment Agreement <i>(requires separate ROW Use Permit)</i>
<input type="checkbox"/> Short Plat Amendment	<input type="checkbox"/> Long Plat	<input type="checkbox"/> Zoning Code Text Amendment
<input type="checkbox"/> Deviation of Acreage Limitation	<input type="checkbox"/> Subdivision Alteration to Existing Plat	
<input type="checkbox"/> Final Short Plat Approval	<input type="checkbox"/> Final Subdivision Review	

**Includes all variances of any type or purpose in all zones other than single family residential zone: B,C-O,PBZ,MF-2,MF2L,MF-2L, MF-3,TC,P

***Includes all variances of any type or purpose in single family residential zone: R-8.4, R-9.6, R-12, R-15)



memorandum

date August 5, 2019
to Lauren Anderson, Planner
from Jessica Redman, Ecologist
subject Paek Residence – 2215 80th Avenue SE Critical Areas Review

Environmental Science Associates (ESA) has prepared this memorandum on the behalf of the City of Mercer Island (City). The purpose of this memo is to verify the accuracy of the critical areas study submitted with the development application and to confirm whether the proposed project complies with Mercer Island City Code (MICC) Chapter 19.07 – *Environment*.

The site is located at 42215 80th Avenue SE (King County Tax Parcel 5452302145) and currently contains a two-story house. The entire parcel is generally flat with a slight slope to the northwest. The City critical area maps show a stream as occurring offsite, which flows north through a culvert on the adjacent parcel to the west. Based on online topographic mapping, land outside of the parcel continues to slope to the southwest at a much higher gradient and into a deep ravine. The City critical area maps depict this watercourse as a Type 2 stream, which would be allotted a 50-foot standard buffer per MIMC 19.07.070.B. The proposed project is a single-family residential development that involves removing the existing structure down to the foundation. A new two-story residential structure will be built on the existing foundation and in the current footprint of the existing house.

At the request of the City, ESA reviewed the *Critical Areas Study – Watercourse Delineation and Buffer Averaging for: Paek Residence* (prepared by Altmann Oliver Associates [AOA] and dated April 30, 2019). Our scope of work included review of regulations for wetlands, streams, and their buffers; ESA did not review steep slopes or geological hazard regulations. ESA also conducted a site visit on August 5, 2019, meeting onsite with the applicant and City planner Lauren Anderson.

Report Summary

According to the *Critical Areas Study – Watercourse Delineation and Buffer Averaging for: Paek Residence* (hereinafter referred to as the AOA Report) the buffer of the offsite stream to the west is the only regulated critical area located within the project area. Additionally, the AOA Report disagrees with the City's watercourse typing and instead believes the watercourse should be classified as a Type 3 watercourse. Per MIMC 19.07.070.A, Type 3 watercourses are those with intermittent or seasonal flow, and not used by fish. The AOA Reports states that no flow or fish habitat was observed during their site visit and therefore meets the

requirements for a Type 3 watercourse. Type 3 watercourses are allotted a 35-foot standard buffer per MIMC 19.07.070.B.

The majority of the buffer which occurs on the proposed project parcel contains lawn, unvegetated soils, a deck and stairs, and a concrete patio. Under the proposed new development, portions of the second-floor deck and stairs will encroach into the buffer. To offset these indirect buffer impacts, the AOA Report proposes a watercourse buffer averaging plan that will reduce 141 square feet of the watercourse's buffer. The proposed area of buffer reduction is currently developed and contains portions of the existing deck, stairs, and concrete patio. To compensate for the reduced stream buffer, the applicant proposes to add 141 square feet of additional buffer to the northern extent of the buffer. This area will subsequently be planted with native shrub species. Additionally, the applicant also proposes installing 187 square feet native vegetation as stream buffer enhancements, along the eastern side of the fence.

Per MICC 19.07.07(B)(3), the City allows buffer averaging if the following conditions are met:

- The proposal will result in a net improvement of critical area function;
- The proposal will include replanting of the average buffer using native vegetation;
- The total area contained in the averaged buffers on the development proposal site is not decreased below the total area that would be provided if the maximum width were not averaged;
- The standard buffer width is not reduced to a width that is less than the minimum buffer width (25 feet) at any location; and
- That portion of the buffer that has been reduced in width shall not contain a steep slope.

Due to the small size of the project, the AOA Report states that a long-term monitoring plan should not be required. However, if the City disagrees, the report presents goals, objectives, and performance standards that the project should meet.

Review and Site Findings

ESA and City staff observed the watercourse from the project parcel during the August 5, 2019 site visit. The watercourse appeared to be a ditched channel that was dug to primarily convey stormwater. No flow was observed during the August site visit. Stream substrate was primarily soil and no fish habitat was observed. Based on the stream characteristics and the location of the parcel near the start of a deep ravine, we also agree that the stream would not support fish and therefore, is a Type 3 watercourse, which would be allotted a 35-foot buffer. ESA did not view the ordinary high water mark (OHWM) of the stream, and therefore, could not locate the exact edge of the buffer in the field. However, the majority of the residence's yard was considered to be in the 35-foot buffer as shown in design drawings provided by the applicant.

During the August 5, 2019 site visit, ESA observed the area of proposed buffer reduction and addition, as well as the proposed area of buffer enhancement. The area of buffer reduction was confirmed to be largely developed. The area of proposed buffer addition as well as the area of buffer enhancement were covered with either grass or bare soil with little native vegetation. No other critical areas were observed on site.

Based on our review of the AOA Report and MICC, as well as the site visit, ESA concludes the proposed buffer addition and enhancement with native plantings will improve buffer conditions at the site and result in an ecological lift in functions. We also agree that due to the small size of the project, annual monitoring of the site should not necessarily be required. However, we recommend that the plants be monitored twice, approximately one year after plant installation (to determine survival and replacement) and five years after plant installation to ensure the mitigation actions of the project are a success.

Therefore, we believe the proposed project has met all requirements for buffer averaging under MICC 19.07.07(B)(3) and is compliant with MICC Chapter 19.07 – *Environment*.

If you have any questions, please call us at (206) 789-9658.















- ### Legend
- Watercourse**
 - 1-Potential Fish Use
 - 2-Perennial
 - - - 3-Seasonal
 - Type 1 Standard 75 ft Buffer
 - Type 2 Standard 50 ft Buffer
 - Type 3 Standard 35 ft Buffer
 - Piped WaterCourses 25ft Buffer
 - Streets & Utilities Projects**
 - Address**
 - Parcels
 - Buildings
 - Docks
 - Shoreline
 - Major Roads
 - Street Centerline
 - Paved Road
 - Paved Driveway
 - Paved Parking Area
 - Parks



1 inch =
62.676822666667
feet



Disclaimer: These maps were developed by the City of Mercer Island and are intended to be a general purpose digital reference tool. These maps are not an accepted legal instrument for describing, establishing, recording or maintaining descriptions for property concerns or boundaries. The City makes no representation or warranty with respect to the accuracy or currency of these data sets, especially in regard to labeling of surveyed dimensions, or agreement with official sources such as records of survey, or mapped locations of features.

Notes