


SW 1/4 OF THE NW 1/4, SEC. 18, T 24N, R 05E, W.M.
MERCERTECH PLAT




PROJECT LOCATION

VICINITY MAP
NO SCALE

4320 ISLAND CREST WAY
MERCER ISLAND, WA 98040

Key Plan



SURVEY INFORMATION

HORIZONTAL DATUM: NAD 83/2011, WASHINGTON COORDINATE SYSTEM, NORTH ZONE, BASED ON GPS MEASUREMENTS USING THE WASHINGTON STATE REFERENCE NETWORK.
 VERTICAL DATUM: NAVD 88, BASED ON GPS MEASUREMENTS USING THE WASHINGTON STATE REFERENCE NETWORK.
 BASIS OF BEARING: NORTH 01°02'57" EAST, BETWEEN THE NORTHWEST CORNER AND THE WEST QUARTER CORNER OF SECTION 18, TOWNSHIP 24 NORTH, RANGE 5 EAST, WILLAMETTE MERIDIAN.
 64.3 FEET FROM PROPERTY LINE TO FIRE HYDRANT.

LEGAL DESCRIPTION

THE NORTH 250 FEET OF THE SOUTH 500 FEET OF THE WEST HALF OF THE SOUTHWEST QUARTER OF THE SOUTHWEST QUARTER OF THE NORTHWEST QUARTER OF SECTION 18, TOWNSHIP 24 NORTH, RANGE 5 EAST, WILLAMETTE MERIDIAN, IN KING COUNTY, WASHINGTON, EXCEPT FOR THE WEST 40 FEET.

UTILITIES:

POWER/GAS: PSE
 STORM: CITY OF MERCER ISLAND
 SEWER: CITY OF MERCER ISLAND
 WATER: CITY OF MERCER ISLAND
 TELEPHONE: CENTURYLINK
 TV: CENTURYLINK
 GARBAGE: COMCAST RECOLOGY

LEGEND

- PROPOSED CONCRETE
- PROPOSED ASPHALT
- PROPERTY BOUNDARY
- PROPOSED STORM DRAIN
- PROPOSED SEWER MAIN
- PROPOSED WATER MAIN
- WETLAND BUFFER LINE
- TREE PROTECTION ZONE
- WETLAND AS BUFFER
- WETLAND TO BE REPLACED
- WETLAND REPLACEMENT AREA

SITE INFORMATION:

PARCEL(S): 1824069031
 ADDRESS: 4320 ISLAND CREST WAY
 MERCER ISLAND, WA 98040
 PARCEL AREA: 72,900± SF (1.67 AC)
 ZONE: R-9.6
 SETBACK ZONE S-9.6:
 MIN. FRONT: 20 FT.
 MIN. SIDE: 5 FT.
 MIN. REAR: 25 FT.
 MAX SITE COVERAGE: 40%
 MAX IMPERVIOUS COVERAGE: 40%
 SR-4.5:
 PARKING REQUIRED: 2 SPACES
 PARKING PROVIDED: 2 SPACES

PROJECT TEAM:

APPLICANT: IHB ARCHITECTS
 IMAD BAHAR
 21520 84TH AVE. S., STE 200
 KENT, WA 98032
 253-468-7696
 CIVIL ENGINEER: FURR ENGINEERING SERVICES PLLC
 4715 142ND PL SW UNIT#B
 EDMONDS, WA 98026
 DEAN FURR
 (206) 890-8291
 FURREENGINEERING@GMAIL.COM
 GEOTECHNICAL CONSULTANT: EARTH SOLUTIONS NW, LLC
 15365 N.E. 90TH STREET
 SUITE 100
 REDMOND, WA 98052
 PHONE: (425) 448-4704
 E-Mail: info@esnw.com
 WETLAND BIOLOGIST AND ARBORIST: THE WATERSHED COMPANY
 750 SIXTH STREET SOUTH
 KIRKLAND, WA 98033
 425-822-5242
 SURVEYOR: PROFESSIONAL LAND SURVEYORS INC.
 1595 NW GILMAN BLVD., #15
 ISSAQUAH, WA 98027
 425-313-9378
 SUPPLEMENTAL AND TREE SURVEY: JOHN CHRISTENSEN, PLS
 CHS ENGINEERS, LLC
 12307 BEL-RED ROAD, SUITE 101
 BELLEVUE, WA 98005
 425-637-3693


DRAWING INDEX

C1.0	COVER SHEET
C1.1	NOTES
	SURVEY
C2.0	TESC, DEMO, & TREE REMOVAL PLAN
C2.1	TESC NOTES & DETAILS
C3.0	GRADING & ROAD PLAN
C3.1	GRADING DETAILS
C3.2	EXCAVATION PLAN
C4.0	STORM WATER PLAN
C4.1	STORM DRAINAGE PROFILES
C4.2	STORM DETAILS
C4.3	STORM FILTER DETAIL
C4.4-C4.8	DETENTION VAULTS 1&2
C5.0	SEWER & WATER PLAN
C5.1	SEWER PROFILE AND DETAILS
C6.0	SIGHT DISTANCE
C6.1	SIGHT DISTANCE PROFILE
C7.0	HORIZONTAL CONTROL PLAN
W1.0-W8.0	MITIGATION PLANS



UTILITIES:

POWER/GAS: PSE
 STORM: CITY OF KENT
 SEWER: CITY OF MERCER ISLAND
 WATER: CITY OF MERCER ISLAND
 TELEPHONE: CENTURYLINK
 TV: XFINITY
 GARBAGE: REPUBLIC SERVICES

TOPOGRAPHY, BOUNDARY, AND UTILITIES STATEMENT:
 FURR ENGINEERING SERVICES PLLC DOES NOT WARRANT THE TOPOGRAPHY, BOUNDARY, AND/OR EXISTING UTILITIES SHOWN ON THESE PLANS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO HAVE ALL EXISTING IMPROVEMENTS FIELD VERIFIED PRIOR TO CONSTRUCTION. ANY SUBSURFACE EXPLORATION OF EXISTING UNDERGROUND UTILITIES (POWER, WATER, SEWER, TELECOM, ETC.) SHALL BE PERFORMED BY THE CONTRACTOR. DISCREPANCIES BETWEEN WHAT IS SHOWN ON THE PLANS AND LOCATED BY THE CONTRACTOR SHALL BE BROUGHT TO THE ATTENTION OF FURR ENGINEERING SERVICES PLLC. PRIOR TO CONSTRUCTION ACTIVITIES.



Registration



4715 142nd Pl. SW #B,
 Edmonds, WA 98026
 ph 206.890.8291

Sheet Title

COVER



Revisions

△	03/30/22	REVISED PER CITY COMMENTS
△	06/03/22	REVISED PER CITY COMMENTS
△	05/23/23	REVISED PER CITY COMMENTS

Scale:

FES Project No: 21084
 Date: Sept 27, 2021
 Designed: DAF
 Drawn: JAB
 Checked: DAF

Sheet Number

C1.0

SW 1/4 OF THE NW 1/4, SEC. 18, T 24N, R 05E, W.M.
MERCERTECH PLAT

CONSTRUCTION NOTES

- 1 FLAG CLEARING LIMITS TO EXTENTS SHOWN ON THE PLAN.
- 2 EXISTING ASPHALT DRIVEWAY TO BE USED AS CONSTRUCTION ENTRANCE PER DETAIL ON SHEET C2.1
- 3 HIGH VISIBILITY SILT FENCE PER DETAIL ON SHEET C2.1
- 4 CATCH BASIN INSERT (TYP) PER DETAIL ON SHEET C2.1
- 5 SAWCUT - THE LIMITS OF PAVEMENT REMOVAL, SIDEWALK REMOVAL AND CURB/GUTTER REMOVAL SHALL BE DETERMINED BY THE CITY INSPECTOR.
- 6 DEMO AND REMOVE GRAVEL ROAD, ASPHALT PARKING, AND EXISTING STRUCTURES
- 7 REMOVE CURB & GUTTER - SIDEWALK WILL REMAIN OPEN TO PEDESTRIAN TRAFFIC; SPOTTER ASSIST WILL BE AVAILABLE DURING CONSTRUCTION HOURS.
- 8 COVERED STOCK PILE PER DETAIL THIS SHEET
- 9 TREE PROTECTION FENCING PER MITIGATION PLAN
- 10 SEDIMENT TRAP: SEE KING COUNTY DETAIL, SHEET C2.1 TEMPORARY UNTIL VAULT INSTALLATION IS COMPLETE
- 11 REMOVE TEMPORARY BENCH MARK
- 12 REMOVE STRUCTURES AND FENCING OUTSIDE OF CLEARING LIMITS SEE WATERSHED PLANS FOR DEMO DETAILS
- 13 REMOVE CONCRETE RETAINING WALL
- 14 ABANDON SEWER AT MAIN AND REMOVE CLEAN OUT - LOCATION SHOWN IS PER TOPOGRAPHIC SURVEY.
- 15 ABANDON EX. WATER SERVICE AT MAIN. CLOSE CORP STOP AND CAP, REMOVE AS NECESSARY.
- 16 REMOVE EXISTING POWER POLE
- 17 ROLL-OFF POLY TANK 6,300 GAL W/PUMP STATION. SEE DETAIL SHEET C2.1

4320 ISLAND CREST WAY
 MERCER ISLAND, WA 98040



LEGEND

- REMOVE CURB & GUTTER
- HIGH VISIBILITY SILT FENCE
- LIMITS OF CLEARING AND GRADING
- STOCKPILE AREA
- TO BE REMOVED
- INLET PROTECTION
- CONSTRUCTION ACCESS
- SAWCUT LINE
- TREE PROTECTION FENCING - PER MITIGATION PLAN
- INTERCEPTOR SWALE WITH ROCK DAM
- EXISTING TREES TO REMAIN
- TREES TO BE REMOVED AFTER SITE DEVELOPMENT PERMIT IS APPROVED
- TREES TO BE REMOVED AFTER BUILDING PERMIT IS APPROVED
- EXISTING TREES TO REMAIN WITH TREE PROTECTION
- TREE TRUNK WRAP PER WATERSHED CO. PLANS SHEET W4.0

Key Plan



Registration



4715 142nd Pl. SW #B,
 Edmonds, WA 98026
 ph 206.890.8291

Sheet Title

**TESC, DEMOLITION,
 AND TREE REMOVAL**

Revisions

Revision	Date	Description
△	03/30/22	REVISED PER CITY COMMENTS
△	06/03/22	REVISED PER CITY COMMENTS
△	05/23/23	REVISED PER CITY COMMENTS


Scale:

FES Project No: 21084
 Date: Sept 27, 2021
 Designed: DAF
 Drawn: JAB
 Checked: DAF

Sheet Number

C2.0


PLASTIC COVERED STOCKPILE C.3.4



TOPOGRAPHY, BOUNDARY, AND UTILITIES STATEMENT:
 FURR ENGINEERING SERVICES PLLC. DOES NOT WARRANT THE TOPOGRAPHY, BOUNDARY, AND/OR EXISTING UTILITIES SHOWN ON THESE PLANS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO HAVE ALL EXISTING IMPROVEMENTS FIELD VERIFIED PRIOR TO CONSTRUCTION. ANY SUBSURFACE EXPLORATION OF EXISTING UNDERGROUND UTILITIES (POWER, WATER, SEWER, TELECOM, ETC.) SHALL BE PERFORMED BY THE CONTRACTOR. DISCREPANCIES BETWEEN WHAT IS SHOWN ON THE PLANS AND LOCATED BY THE CONTRACTOR SHALL BE BROUGHT TO THE ATTENTION OF FURR ENGINEERING SERVICES PLLC. PRIOR TO CONSTRUCTION ACTIVITIES.



Know what's below.
 Call before you dig.



EARTHWORK QUANTITIES
 CUT = 264 CY
 FILL = 27 CY
 NET = 237 CY CUT

NOTES

1. SEE PLAN SET PREPARED BY THE WATERSHED COMPANY FOR TREE PRESERVATION AND WETLAND MITIGATION PLAN. NOTE REQUIREMENTS FOR DEMOLITION OF EXISTING SOUTHERLY HOUSE.
2. REFERENCE WATERSHED PLANS FOR CLEARING, GRADING AND DEMO WITHIN WETLAND BUFFER.
3. DEMOLITION WITHIN THE WETLAND TO BE PERFORMED WITHOUT HEAVY MACHINERY IN ORDER TO MINIMIZE WETLAND IMPACT.
4. TRIM TREE BRANCHES TO 6' AND REMOVE SHRUBS WITHIN SIGHT TRIANGLE, SEE SHEET C6.0 SIGHT DISTANCE PLAN.
5. SEE EXCAVATION PLAN, SHEET C3.2

TESC SEQUENCE

1. CONDUCT PRE-CONSTRUCTION MEETING.
2. FLAG OR FENCE CLEARING LIMITS.
3. POST SIGN WITH NAME AND PHONE NUMBER OF TESC SUPERVISOR.
4. INSTALL CATCH BASIN PROTECTION.
5. INSTALL PERIMETER SILT FENCE PROTECTION.
6. INSTALL TREE PROTECTION.
7. CONSTRUCT SEDIMENT TRAP AND POLY TANK.
8. UTILIZE EXISTING DRIVEWAY FOR INTERIM DEMOLITION ACTIVITY CONSTRUCTION ENTRANCE.
9. DEMO EXISTING BUILDINGS.
10. ADJUST TREE PROTECTION FENCING AS NECESSARY AFTER DEMOLITION.
11. GRADE AND INSTALL NEW CONSTRUCTION ENTRANCE.
12. GRADE AND STABILIZE ACCESS ROAD ALIGNMENT.
13. EXCAVATE FOR VAULTS
14. CONSTRUCT PERMANENT STORMWATER FACILITY.
15. CONSTRUCT TEMPORARY SURFACE WATER CONTROLS AND UTILIZE PERMANENT STORM WATER FACILITIES.
16. CONSTRUCT WATER, SEWER AND DRY UTILITIES.
17. CONSTRUCT PERMANENT ACCESS ROAD & RELATED IMPROVEMENTS.
18. UPON COMPLETION OF THE PLAT IMPROVEMENTS, ALL DISTURBED AREAS MUST BE STABILIZED AND BEST MANAGEMENT PRACTICES REMOVED IF APPROPRIATE
19. MAINTAIN EROSION CONTROL MEASURE IN ACCORDANCE WITH CITY OF MERCER ISLAND STANDARDS AND MANUFACTURER'S RECOMMENDATIONS.
20. RELOCATE EROSION CONTROL MEASURES OR INSTALL NEW MEASURES SO THAT AS SITE CONDITIONS CHANGE, THE EROSION AND SEDIMENT CONTROL IS ALWAYS IN ACCORDANCE WITH THE CITY TESC MINIMUM REQUIREMENTS.
21. COVER ALL AREAS WITHIN THE SPECIFIED TIME FRAME WITH STRAW, WOOD FIBER MULCH, COMPOST, PLASTIC SHEETING, CRUSHED ROCK OR EQUIVALENT.
22. SEED OR SOD ANY AREAS TO REMAIN UNWORKED FOR MORE THAN 30 DAYS.

DEMOLITION NOTES

1. REFER TO PSCAA REGARDING BUILDING DEMOLITION AND ASBESTOS AND LEAD HAZARDS.
2. UTILIZE EX. DRIVEWAYS TO ACCESS SITE FOR BUILDING AND OTHER DEMOLITION ACTIVITIES.
3. COORDINATE WITH PSE TO SHUT DOWN AND DEMO EXISTING GAS AND POWER SERVICE.

TREE REMOVAL NOTES

1. ALL TREES NOT TAGGED FOR REMOVAL ARE TO REMAIN. TREES ADJACENT TO CONSTRUCTION ACTIVITIES SHALL BE PROTECTED VIA TREE PROTECTION FENCING. REFER TO WATERSHED PLANS FOR FENCING AND TRUNK PROTECTION DETAILS.
2. SEE ARBORIST'S REPORT FOR TREE SIZES AND SPECIES.

CLEARING & GRADING NOTES

1. CLEARING AND GRADING ACTIVITIES WILL AFFECT AN AREA GREATER THAN 1 ACRE. A D.O.E. GENERAL STORM WATER PERMIT IS REQUIRED. DEFINITION OF PROPOSED WETLAND BOUNDARY AND BUFFER AS WELL AS TREE REMOVAL, GRADING AND TESC WITHIN THE BUFFER AND WETLAND ARE PRESENTED IN THE WATERSHED CO.'S PLAN SET.

GENERAL NOTES

1. MITIGATED WETLAND & STREAM BOUNDARY & BUFFERS SHOWN. REFER TO THE WATERSHED CO. MITIGATION PLAN.


SW 1/4 OF THE NW 1/4, SEC. 18, T 24N, R 05E, W.M.
MERCERTECH PLAT

TESC NOTES

1. STOCKPILE AT EXISTING GRAVEL AREAS.
2. CATCH BASIN FILTERS SHOULD BE PROVIDED FOR ALL STORM DRAIN CATCH BASINS/INLETS DOWNSLOPE AND WITHIN 500 FEET OF THE CONSTRUCTION AREA. CATCH BASIN FILTERS SHOULD BE DESIGNED BY THE MANUFACTURER FOR THE USE AT CONSTRUCTION SITES AND APPROVED BY THE CITY INSPECTOR. CATCH BASIN FILTERS SHOULD BE INSPECTED FREQUENTLY, ESPECIALLY AFTER STRONG STORM EVENTS. IF THE FILTER BECOMES CLOGGED IT SHOULD BE REPLACED.
3. ALL "LAND DISTURBING ACTIVITY" IS SUBJECT TO PROVISIONS OF MERCER ISLAND ORDINANCE 95C-118 "STORM WATER MANAGEMENT." SPECIFIC ITEMS TO BE FOLLOWED AT YOUR SITE:
4. PROTECT ADJACENT PROPERTIES FROM ANY INCREASED RUNOFF OR SEDIMENTATION DUE TO THE CONSTRUCTION PROJECT THROUGH THE USE OF APPROPRIATE "BEST MANAGEMENT PRACTICES" (BMP). EXAMPLES INCLUDE, BUT ARE NOT LIMITED TO, SEDIMENT TRAPS, SEDIMENT PONDS, FILTER FABRIC FENCES, VEGETATIVE BUFFER STRIPS OR BIO-ENGINEERED SWALES.
5. CONSTRUCTION ACCESS SHOULD BE LIMITED TO ONE ROUTE. STABILIZE ENTRANCE WITH QUARRY SPALLS TO PREVENT SEDIMENT FROM LEAVING THE SITE OR ENTERING THE STORM DRAINS.
6. PREVENT SEDIMENT, CONSTRUCTION DEBRIS, PAINTS, SOLVENTS, ETC., OR ANY OTHER TYPES OF POLLUTION FROM ENTERING PUBLIC STORM DRAINS. KEEP ALL POLLUTION ON YOUR SITE.
7. ALL EXPOSED SOILS SHALL REMAIN DENUDED FOR NO LONGER THAN SEVEN (7) DAYS AND SHALL BE STABILIZED WITH MULCH, HAY, OR THE APPROPRIATE GROUND COVER. ALL EXPOSED SOILS SHALL BE COVERED IMMEDIATELY DURING ANY RAIN EVENT.
8. INSTALLATION OF CONCRETE DRIVEWAYS, TREES, SHRUBS, IRRIGATION, BOULDERS, BERMS, WALLS, GATES, AND OTHER IMPROVEMENTS ARE NOT ALLOWED IN THE PUBLIC RIGHT-OF-WAY WITHOUT PRIOR APPROVAL, AND AN ENCROACHMENT AGREEMENT AND RIGHT-OF-WAY PERMIT FROM THE SENIOR DEVELOPMENT ENGINEER.
9. OWNER SHALL CONTROL DISCHARGE OF SURFACE DRAINAGE RUNOFF FROM EXISTING AND NEW IMPERVIOUS AREAS IN A RESPONSIBLE MANNER. CONSTRUCTION OF MINIMUM DRAINAGE IMPROVEMENTS SHOWN OR CALLED OUT ON THIS PLAN DOES NOT IMPLY RELIEF FROM CIVIL LIABILITY FOR DOWNSTREAM DRAINAGE.
10. POT HOLING THE PUBLIC UTILITIES IS REQUIRED PRIOR TO ANY GRADING ACTIVITIES LESS THAN 6" OVER THE PUBLIC MAINS (WATER, STORM, AND SEWER SYSTEMS). IF THERE IS A CONFLICT, THE APPLICANT IS REQUIRED TO SUBMIT A REVISION FOR APPROVAL PRIOR TO ANY GRADING ACTIVITIES OVER THE PUBLIC MAINS.
11. ROOF DRAINS MUST BE CONNECTED TO THE STORM DRAIN SYSTEM AND INSPECTED BY THE PUBLIC WORKS DEPARTMENT PRIOR TO ANY BACKFILLING OF PIPE.
12. SILT FENCE: CLEAN AND PROVIDE REGULAR MAINTENANCE OF THE SILT FENCE. THE FENCE IS TO REMAIN VERTICAL AND IS TO FUNCTION PROPERLY THROUGHOUT THE TERM OF THE PROJECT.
13. MACHINERY ACCESS FOR DEMOLITION OF EX. SOUTHERLY HOUSE SHALL UTILIZE 5" WOOD CHIP MULCH OVERLAID WITH STEEL PLATE OR 3/4" PLYWOOD TO PREVENT DISTURBANCE OF EX. TREE ROOTS.


CONSTRUCTION NOTES

1. ANY CHANGES TO APPROVED PLANS REQUIRES CITY APPROVAL THROUGH A REVISION.
2. APPLICANT IS RESPONSIBLE FOR ANY DAMAGES TO UNDERGROUND UTILITIES CAUSED FROM THIS CONSTRUCTION.
3. DO NOT BACKFILL WITH NATIVE MATERIAL ON PUBLIC RIGHT-OF-WAY. ALL MATERIAL MUST BE IMPORTED.




- NOTES:**
1. SURFACE WATER — ALL SURFACE WATER FLOWING OR DIVERTED TOWARD CONSTRUCTION ENTRANCES SHALL BE PIPED ACROSS THE ENTRANCE. IF PIPING IS IMPRACTICAL, A MOUNTABLE BERM WITH 5:1 SLOPES WILL BE PERMITTED.
 2. MAINTENANCE — THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT OFF THE SITE AND/OR ONTO PUBLIC RIGHT-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL QUARRY SPALLS AS CONDITIONS DEMAND AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED OFF SITE AND/OR ONTO PUBLIC RIGHT-OF-WAY MUST BE REMOVED IMMEDIATELY.
 3. WHEELS SHALL BE CLEANED TO REMOVE SEDIMENT PRIOR TO LEAVING THE SITE. WHEN WASHING IS USED, IT SHALL BE DONE ON AN AREA STABILIZED WITH QUARRY SPALLS AND WHICH DRAINS INTO AN APPROVED SEDIMENT TRAPPING DEVICE.
 4. INSPECTION AND NEEDED MAINTENANCE SHALL BE PROVIDED AFTER EACH RAIN.

TEMPORARY CONSTRUCTION ENTRANCE
NOT TO SCALE






NOTE: FILTER FABRIC FENCES SHALL BE INSTALLED ALONG CONTOUR WHENEVER POSSIBLE.


SILT FENCE
NOT TO SCALE



SEDIMENT CATCHMENT DETAIL
NO SCALE



CATCH BASIN INSERT
NOT TO SCALE





TOPOGRAPHY, BOUNDARY, AND UTILITIES STATEMENT:
FURR ENGINEERING SERVICES PLLC. DOES NOT WARRANT THE TOPOGRAPHY, BOUNDARY, AND/OR EXISTING UTILITIES SHOWN ON THESE PLANS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO HAVE ALL EXISTING IMPROVEMENTS FIELD VERIFIED PRIOR TO CONSTRUCTION. ANY SUBSURFACE EXPLORATION OF EXISTING UNDERGROUND UTILITIES (POWER, WATER, SEWER, TELECOM, ETC.) SHALL BE PERFORMED BY THE CONTRACTOR. DISCREPANCIES BETWEEN WHAT IS SHOWN ON THE PLANS AND LOCATED BY THE CONTRACTOR SHALL BE BROUGHT TO THE ATTENTION OF FURR ENGINEERING SERVICES PLLC. PRIOR TO CONSTRUCTION ACTIVITIES.



4320 ISLAND CREST WAY
MERCER ISLAND, WA 98040

Key Plan

Registration



4715 142nd Pl. SW #B,
Edmonds, WA 98026
ph 206.890.8291

Sheet Title

TESC NOTES



Revisions

△	03/30/22	REVISED PER CITY COMMENTS
△	06/03/22	REVISED PER CITY COMMENTS
△	05/23/23	REVISED PER CITY COMMENTS


Scale:

FES Project No:	21084
Date:	Sept 27, 2021
Designed:	DAF
Drawn:	JAB
Checked:	DAF

Sheet Number

C2.1

SW 1/4 OF THE NW 1/4, SEC. 18, T 24N, R 05E, W.M.
MERCERTECH PLAT






LEGEND


	PROPOSED CONCRETE
	PROPOSED ASPHALT
	PROPERTY BOUNDARY
	TREE PROTECTION ZONE
	WETLAND BUFFER LINE
	WETLAND AS BUFFER
	WETLAND TO BE REPLACED
	WETLAND REPLACEMENT AREA

- CONSTRUCTION NOTES**
- CEMENT CONCRETE TRAFFIC CURB AND GUTTER. WSDOT STD PLAN F-10.12-04
 - CEMENT CONCRETE SIDEWALK. WSDOT STD PLAN F-30.10-04
 - CURB RAMP TO 7.5% DESIGN SLOPE. 8.3% MAX.
 - SAW CUT. ASPHALT: 1FT FROM EDGE OF EXISTING GUTTER; SIDEWALK, CURB/GUTTER SHOULD BE REMOVED TO NEXT CONCRETE JOINT
 - MATCH EXISTING CURB AND SIDEWALK
 - CEMENT CONCRETE CURB AND GUTTER PAN. WSDOT STD PLAN F-10.16-00
 - ROLLED CURB TO VERTICAL CURB TRANSITION
 - CURB 2. ROUNDABOUT CEMENT CONCRETE CURB AND GUTTER. WSDOT STD PLAN F-10.18-02
 - PARALLEL CURB RAMP (TYPE A). WSDOT STD PLAN F-40.12-03
 - SINGLE DIRECTION CURB RAMP (TYPE A). WSDOT STD PLAN F-40.16-03
 - SECURITY FENCE BY OTHERS
 - MUTCD R3-5R RIGHT TURN ONLY SIGN; SEE DETAIL ON SHEET C3.1
 - LOCK + LOAD RETAINING WALL. SEE DETAILS ON SHEET C3.1
 - 4' HIGH CHAIN LINK FENCE. SEE DETAIL ON SHEET C3.1

- ROAD RESTORATION NOTE**
- THE LIMITS AND EXTENTS OF THE PAVEMENT IN THE PUBLIC RIGHT-OF-WAY SHALL BE DETERMINED BY THE CITY ENGINEER PRIOR TO FINALIZING THE PROJECT.
 - IF DAMAGE OCCURS TO ADJACENT PROPERTIES CONTRACTOR TO REPLACE IN KIND OR BETTER AT NO EXPENSE TO THE CITY.




TOPOGRAPHY, BOUNDARY, AND UTILITIES STATEMENT:
 FURR ENGINEERING SERVICES PLLC. DOES NOT WARRANT THE TOPOGRAPHY, BOUNDARY, AND/OR EXISTING UTILITIES SHOWN ON THESE PLANS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO HAVE ALL EXISTING IMPROVEMENTS FIELD VERIFIED PRIOR TO CONSTRUCTION. ANY SUBSURFACE EXPLORATION OF EXISTING UNDERGROUND UTILITIES (POWER, WATER, SEWER, TELECOM, ETC.) SHALL BE PERFORMED BY THE CONTRACTOR. DISCREPANCIES BETWEEN WHAT IS SHOWN ON THE PLANS AND LOCATED BY THE CONTRACTOR SHALL BE BROUGHT TO THE ATTENTION OF FURR ENGINEERING SERVICES PLLC. PRIOR TO CONSTRUCTION ACTIVITIES.



4320 ISLAND CREST WAY
 MERCER ISLAND, WA 98040

Key Plan

Registration



4715 142nd Pl. SW #B,
 Edmonds, WA 98026
 ph 206.890.8291

Sheet Title

GRADING AND ROAD PLAN



Revisions


△	03/30/22	REVISED PER CITY COMMENTS
△	06/03/22	REVISED PER CITY COMMENTS
△	05/23/23	REVISED PER CITY COMMENTS

Scale:
 FES Project No: 2108
 Date: Sept 27, 2023
 Designed: DAF
 Drawn: JAB
 Checked: DAF


Sheet Number

C3.0


SW 1/4 OF THE NW 1/4, SEC. 18, T 24N, R 05E, W.M.
MERCERTECH PLAT




**LOCK+LOAD RETAINING WALL
 TYPICAL SECTION**
 NOT TO SCALE




**LOCK+LOAD RETAINING WALL
 FOUNDATION PAD**
 NOT TO SCALE




**LOCK+LOAD RETAINING WALL
 REINFORCEMENT LAYOUT**
 NOT TO SCALE




**LOCK+LOAD RETAINING WALL
 FENCE DETAIL**
 NOT TO SCALE



R3-5R 'RIGHT TURN ONLY' SIGN DETAIL
 NOT TO SCALE



**LOCK+LOAD RETAINING WALL
 STANDARD COUNTERFORT**
 NOT TO SCALE



**CHAIN LINK FENCE
 TYPES 4**


- NOTES
1. All concrete post bases shall be 10" (in) minimum diameter.
 2. Along the top and bottom, using Hog Rings, fasten the Chain Link Fence Fabric to the Tension Wire within the limits of the first full fabric weave.
 3. Details are illustrative and shall not limit hardware design or post selection of any particular fence type.
 4. Fencing shall be used for security and boundary delineation only.

**METHOD OF FASTENING
 STRETCHER BAR TO POST**

4320 ISLAND CREST WAY
 MERCER ISLAND, WA 98040

Key Plan

Registration



4715 142nd Pl. SW #B,
 Edmonds, WA 98026
 ph 206.890.8291

Sheet Title

GRADING DETAILS



Revisions


Revision	Date	Description
△	03/30/22	REVISED PER CITY COMMENTS
△	06/03/22	REVISED PER CITY COMMENTS
△	05/23/23	REVISED PER CITY COMMENTS

Scale:
 FES Project No: 2108
 Date: Sept 27, 2023
 Designed: DAF
 Drawn: JAB
 Checked: DAF

Sheet Number



C3.1

TOPOGRAPHY, BOUNDARY, AND UTILITIES STATEMENT:
 FURR ENGINEERING SERVICES PLLC. DOES NOT WARRANT THE TOPOGRAPHY, BOUNDARY, AND/OR EXISTING UTILITIES SHOWN ON THESE PLANS. IT IS THE CONTRACTORS' RESPONSIBILITY TO HAVE ALL EXISTING IMPROVEMENTS FIELD VERIFIED PRIOR TO CONSTRUCTION. ANY SUBSURFACE EXPLORATION OF EXISTING UNDERGROUND UTILITIES (POWER, WATER, SEWER, TELECOM, ETC.) SHALL BE PERFORMED BY THE CONTRACTOR. DISCREPANCIES BETWEEN WHAT IS SHOWN ON THE PLANS AND LOCATED BY THE CONTRACTOR SHALL BE BROUGHT TO THE ATTENTION OF FURR ENGINEERING SERVICES PLLC. PRIOR TO CONSTRUCTION ACTIVITIES.



SW 1/4 OF THE NW 1/4, SEC. 18, T 24N, R 05E, W.M.
MERCERTECH PLAT

4320 ISLAND CREST WAY
 MERCER ISLAND, WA 98040




VAULT EXCAVATION
 SCALE: H:1"=20' ; V:1"=5'

LEGEND

- PROPOSED CONCRETE
- PROPOSED ASPHALT
- PROPERTY BOUNDARY
- WETLAND BUFFER LINE
- LIMITS OF EXCAVATION

Key Plan

Registration



4715 142nd Pl. SW #B,
 Edmonds, WA 98026
 ph 206.890.8291

Sheet Title

EXCAVATION PLAN



Revisions


Revision	Date	Description
△	03/30/22	REVISED PER CITY COMMENTS
△	06/03/22	REVISED PER CITY COMMENTS
△	05/23/23	REVISED PER CITY COMMENTS

Scale:
 FES Project No: 2108
 Date: Sept 27, 2023
 Designed: DAF
 Drawn: JAB
 Checked: DAF

Sheet Number

C3.2

TOPOGRAPHY, BOUNDARY, AND UTILITIES STATEMENT:
 FURR ENGINEERING SERVICES PLLC. DOES NOT WARRANT THE TOPOGRAPHY, BOUNDARY, AND/OR EXISTING UTILITIES SHOWN ON THESE PLANS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO HAVE ALL EXISTING IMPROVEMENTS FIELD VERIFIED PRIOR TO CONSTRUCTION. ANY SUBSURFACE EXPLORATION OF EXISTING UNDERGROUND UTILITIES (POWER, WATER, SEWER, TELECOM, ETC.) SHALL BE PERFORMED BY THE CONTRACTOR. DISCREPANCIES BETWEEN WHAT IS SHOWN ON THE PLANS AND LOCATED BY THE CONTRACTOR SHALL BE BROUGHT TO THE ATTENTION OF FURR ENGINEERING SERVICES PLLC. PRIOR TO CONSTRUCTION ACTIVITIES.



SW 1/4 OF THE NW 1/4, SEC. 18, T 24N, R 05E, W.M. MERCERTECH PLAT

CONSTRUCTION NOTES

- ① DETENTION VAULTS - SEE DETAIL SHEET C4.4-C4.8
- ② FLOW CONTROL STRUCTURE - SEE DETAIL SHEET C4.2
- ③ STORM FILTER MANHOLE - SEE DETAIL SHEET 4.3
- ④ 5 LF 6" PVC @ 2% MIN.
- ⑤ 4" ROOF DRAIN
- ⑥ YARD DRAIN - SEE DETAIL SHEET C4.2
- ⑦ DIRECTIONAL BORE ACCESS PIT; SEE HORIZONTAL BORING NOTE
- ⑧ DIRECTIONAL BORE RECEIVING PIT; SEE HORIZONTAL BORING NOTE

NO.	TOP OF SEWER PIPE ELEVATION	BOTTOM OF STORM PIPE ELEVATION	VERTICAL SEPARATION	BOTTOM OF SEWER PIPE ELEVATION	TOP OF STORM PIPE ELEVATION
PC 1	272.18	273.37	1.19 FT		
PC 2	273.82	275.16	1.34 FT		
PC 3		279.07	3.4 FT	279.07	275.64
PC 4		282.13	6.49 FT	282.13	275.64

LEGEND

- CATCH BASIN TYPE 1
- CATCH BASIN TYPE 2
- YARD DRAIN
- PROPOSED CONCRETE
- PROPOSED ASPHALT
- PROPERTY BOUNDARY
- STORM DRAIN LINE
- ROOF DRAIN (6" @ 2% MIN.)
- WETLAND BUFFER LINE
- TREE PROTECTION ZONE
- WETLAND AS BUFFER
- WETLAND TO BE REPLACED
- WETLAND REPLACEMENT AREA

GENERAL NOTES

1. MITIGATED WETLAND & STREAM BOUNDARY & BUFFERS SHOWN. REFER TO THE WATERSHED CO. MITIGATION PLAN.

HORIZONTAL BORING NOTE

HORIZONTAL BORING ADJACENT TO AND WITHIN TREE ROOT ZONE SHOULD BE PERFORMED BY A QUALIFIED CONTRACTOR UNDER THE DIRECTION OF THE PROJECT ARBORIST AND THE CITY OF MERCER ISLAND ARBORIST IN ORDER TO COMPLY WITH TREE RETENTION REQUIREMENTS.

STORMWATER NOTES


1. ALL STORMWATER MAINS TO BE 8" SDR 35 PVC PIPE OR APPROVED EQUAL.
2. ROOF DOWNSPOUT STUBS SHALL BE 6" MIN SDR 35 PVC OR APPROVED EQUAL.
3. ROUTE FUTURE FOUNDATION DRAINS TO DAYLIGHT.
4. RAISE ALL STORM DRAINS, VALVE BOXES, MANHOLE COVERS AND MONUMENT COVERS TO MATCH ASPHALT FINISH GRADE. MONUMENT COVERS MUST BE RAISED WITHOUT DISTURBING MONUMENT. RISER EXTENSION CASTINGS ARE ACCEPTABLE.
5. DRIVEWAYS SHALL DRAIN TOWARDS ACCESS DRIVE OR OTHERWISE CONNECT TO ROOF DRAIN OR YARD DRAIN STUBS.
6. REFER TO DRAINAGE REPORT FOR SIZING INFORMATION.
7. BOTTOM OF BUILDING FOUNDATION FOR LOTS 1, 2 AND 5 MAX. ELEVATION 283.0.

TOPOGRAPHY, BOUNDARY, AND UTILITIES STATEMENT:

FURR ENGINEERING SERVICES PLLC. DOES NOT WARRANT THE TOPOGRAPHY, BOUNDARY, AND/OR EXISTING UTILITIES SHOWN ON THESE PLANS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO HAVE ALL EXISTING IMPROVEMENTS FIELD VERIFIED PRIOR TO CONSTRUCTION. ANY SUBSURFACE EXPLORATION OF EXISTING UNDERGROUND UTILITIES (POWER, WATER, SEWER, TELECOM, ETC.) SHALL BE PERFORMED BY THE CONTRACTOR. DISCREPANCIES BETWEEN WHAT IS SHOWN ON THE PLANS AND LOCATED BY THE CONTRACTOR SHALL BE BROUGHT TO THE ATTENTION OF FURR ENGINEERING SERVICES PLLC. PRIOR TO CONSTRUCTION ACTIVITIES.




Know what's below.
Call before you dig.



4320 ISLAND CREST WAY
MERCER ISLAND, WA 98040

Key Plan

Registration



4715 142nd Pl. SW #B,
Edmonds, WA 98026
ph 206.890.8291

Sheet Title

STORM WATER PLAN



Revisions

NO.	DATE	DESCRIPTION
△	03/30/22	REVISED PER CITY COMMENTS
△	06/03/22	REVISED PER CITY COMMENTS
△	05/23/23	REVISED PER CITY COMMENTS

Scale:

FES Project No: 21084

Date: Sept 27, 2021

Designed: DAF


Drawn: JAB

Checked: DAF


Sheet Number

C4.0


SW 1/4 OF THE NW 1/4, SEC. 18, T 24N, R 05E, W.M.
MERCERTECH PLAT



PLAN VIEW
 CARTRIDGES AND FLOW KIT NOT SHOWN



SECTION A-A



OUTLET DETAIL
 (ILLUSTRATION ONLY)

MATERIAL LIST (PROVIDED BY CONTECH)

COUNT	DESCRIPTION	INSTALLED BY
2	LOW DROP ZPG CARTRIDGE	CONTECH
3	5 GPM RESTRICTOR DISK (BLU)	CONTECH
1	2" PVC SLIP PLUG	CONTECH
1	40A FLOWKIT	CONTECH
1	LOW DROP OUTLET RISER ASSEMBLY	CONTECH
2	STEPS, P10CTS, LANE LADDER, OR EQUIV.	CONTECH
1	SEALANT FOR JOINTS (BY PRECASTER)	CONTRACTOR
1	Ø30" x 4" FRAME & GRATE, EJ#43600430A01, OR EQUIV.	CONTRACTOR

SITE DESIGN DATA

WATER QUALITY FLOW RATE	0.014 CFS
PEAK FLOW RATE	0.281 CFS
RETURN PERIOD OF PEAK FLOW	100 YRS
FILTER MEDIA TYPE	ZPG

PERFORMANCE SPECIFICATION

FILTER CARTRIDGES SHALL BE MEDIA-FILLED, PASSIVE, SIPHON ACTUATED, RADIAL FLOW, AND SELF CLEANING. **RADIAL MEDIA DEPTH SHALL BE 7-INCHES.** FILTER MEDIA CONTACT TIME SHALL BE AT LEAST **38 SECONDS.** SPECIFIC FLOW RATE SHALL BE **1 GPM/SF (MAXIMUM).** SPECIFIC FLOW RATE IS THE MEASURE OF THE FLOW (GPM) DIVIDED BY THE MEDIA SURFACE CONTACT AREA (SF). MEDIA VOLUMETRIC FLOW RATE SHALL BE **6 GPM/CF OF MEDIA (MAXIMUM).**

GENERAL NOTES

- CONTECH TO PROVIDE ALL MATERIALS UNLESS NOTED OTHERWISE.
- FOR FABRICATION DRAWINGS WITH DETAILED STRUCTURE DIMENSIONS AND WEIGHT, PLEASE CONTACT YOUR CONTECH ENGINEERED SOLUTIONS LLC REPRESENTATIVE. www.ContechES.com
- STORMFILTER WATER QUALITY STRUCTURE SHALL BE IN ACCORDANCE WITH ALL DESIGN DATA AND INFORMATION CONTAINED IN THIS DRAWING. CONTRACTOR TO CONFIRM STRUCTURE MEETS REQUIREMENTS OF PROJECT.
- STRUCTURE SHALL MEET AASHTO HS-20 LOAD RATING, ASSUMING EARTH COVER OF 0' - 5', AND GROUNDWATER ELEVATION AT, OR BELOW, THE OUTLET PIPE INVERT ELEVATION. ENGINEER OF RECORD TO CONFIRM ACTUAL GROUNDWATER ELEVATION. CASTINGS SHALL MEET AASHTO M306 LOAD RATING AND BE CAST WITH THE CONTECH LOGO.
- STORMFILTER STRUCTURE SHALL BE PRECAST CONCRETE CONFORMING TO ASTM C-478 AND AASHTO LOAD FACTOR DESIGN METHOD.

INSTALLATION NOTES

- ANY SUB-BASE, BACKFILL DEPTH, AND/OR ANTI-FLOTATION PROVISIONS ARE SITE-SPECIFIC DESIGN CONSIDERATIONS AND SHALL BE SPECIFIED BY ENGINEER OF RECORD.
- CONTRACTOR TO PROVIDE EQUIPMENT WITH SUFFICIENT LIFTING AND REACH CAPACITY TO LIFT AND SET THE STORMFILTER STRUCTURE (LIFTING CLUTCHES PROVIDED).
- CONTRACTOR TO INSTALL JOINT SEALANT BETWEEN ALL STRUCTURE SECTIONS AND ASSEMBLE STRUCTURE.
- CONTRACTOR TO PROVIDE, INSTALL, AND GROUT INLET PIPE(S). ALL PIPE CENTERLINES TO MATCH PIPE OPENING CENTERLINES.
- CONTRACTOR TO PROVIDE AND INSTALL CONNECTOR TO THE OUTLET RISER STUB. STORMFILTER EQUIPPED WITH A DUAL DIAMETER HDPE OUTLET STUB. IF OUTLET PIPE IS LARGER THAN 8 INCHES, CONTRACTOR TO REMOVE THE 8 INCH OUTLET STUB AT MOLDED IN CUT LINE. COUPLING BY FERNCO OR EQUAL AND PROVIDED BY CONTRACTOR.
- CONTRACTOR TO TAKE APPROPRIATE MEASURES TO PROTECT CARTRIDGES FROM CONSTRUCTION-RELATED EROSION RUNOFF.
- CONTRACTOR TO INSTALL SUPPLIED PLUG IN CONSTRUCTION FLOW BYPASS WHEN SYSTEM IS BROUGHT ON LINE (PRESSURE FIT ONLY, DO NOT GLUE).

STRUCTURE WEIGHT
 APPROXIMATE HEAVIEST PICK = 5500 LBS. OF 2 PIECES
 BASE SECTION SHIPPED WITH CARTRIDGES INSTALLED
 MAX FOOTPRINT = Ø4'-10"

CONTECH
PROPOSAL
 DRAWING

CUZ001
 LAYOUT 1A
 5784 / CUZ


The design and information shown on this drawing is provided as a service to the project owner, engineer and contractor by Contech Engineered Solutions LLC ("Contech"). Neither this drawing, nor any part hereof, shall be used for any purpose other than that intended by the contractor without the prior written consent of Contech. Failure to comply is done at the user's own risk and Contech shall not be held responsible for any liability or responsibility for such use. If discrepancies between the supplied information upon which the drawing is based and actual field conditions are noted, the contractor shall be responsible for these discrepancies and shall report to Contech immediately for re-evaluation of the design. Contech shall not be held responsible for any liability or responsibility for incomplete or inaccurate information supplied by others.

MARK	DATE	REVISION DESCRIPTION	BY

STORMFILTER SFMH48 - 569225-20
 4320 ISLAND CREST WAY
 MERCER ISLAND, WA
 for SYSTEM: SFMH

CONTECH
 ENGINEERED SOLUTIONS LLC
 www.ContechES.com
 8025 Centre Pointe Dr., Suite 400, West Chester, OH 45089
 800-338-1122 513-545-7985 FAX
 The Stormwater Management
StormFilter
 THE PATENTED, SELF-CLEANING, MEDIA-FILLED, RADIAL FLOW, SIPHON ACTUATED, SELF-CLEANING, WATER QUALITY STRUCTURE.

DATE:	04/20/18	SCALE:	3/8" = 1'-0"
DESIGNED:	MSG	DRAWN:	SKJ
CHECKED:		APPROVED:	
PROJECT No.:	569225	SEQUENCE No.:	20
SHEET:	1	OF	1




ELEVATION VIEW

4320 ISLAND CREST WAY
 MERCER ISLAND, WA 98040

Key Plan

Registration



4715 142nd Pl. SW #B,
 Edmonds, WA 98026
 ph 206.890.8291

Sheet Title

STORM FILTER DETAIL



Revisions


△	03/30/22	REVISED PER CITY COMMENTS
△	06/03/22	REVISED PER CITY COMMENTS
△	05/23/23	REVISED PER CITY COMMENTS

Scale:
 FES Project No: 21084
 Date: Sept 27, 2021
 Designed: DAF
 Drawn: JAB
 Checked: DAF



Sheet Number

4.3


TOPOGRAPHY, BOUNDARY, AND UTILITIES STATEMENT:
 FURR ENGINEERING SERVICES PLLC. DOES NOT WARRANT THE TOPOGRAPHY, BOUNDARY, AND/OR EXISTING UTILITIES SHOWN ON THESE PLANS. IT IS THE CONTRACTORS' RESPONSIBILITY TO HAVE ALL EXISTING IMPROVEMENTS FIELD VERIFIED PRIOR TO CONSTRUCTION. ANY SUBSURFACE EXPLORATION OF EXISTING UNDERGROUND UTILITIES (POWER, WATER, SEWER, TELECOM, ETC.) SHALL BE PERFORMED BY THE CONTRACTOR. DISCREPANCIES BETWEEN WHAT IS SHOWN ON THE PLANS AND LOCATED BY THE CONTRACTOR SHALL BE BROUGHT TO THE ATTENTION OF FURR ENGINEERING SERVICES PLLC. PRIOR TO CONSTRUCTION ACTIVITIES.



SW 1/4 OF THE NW 1/4, SEC. 18, T 24N, R 05E, W.M.
MERCERTECH PLAT





TOPOGRAPHY, BOUNDARY, AND UTILITIES STATEMENT:
 FURR ENGINEERING SERVICES PLLC. DOES NOT WARRANT THE TOPOGRAPHY, BOUNDARY, AND/OR EXISTING UTILITIES SHOWN ON THESE PLANS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO HAVE ALL EXISTING IMPROVEMENTS FIELD VERIFIED PRIOR TO CONSTRUCTION. ANY SUBSURFACE EXPLORATION OF EXISTING UNDERGROUND UTILITIES (POWER, WATER, SEWER, TELECOM, ETC.) SHALL BE PERFORMED BY THE CONTRACTOR. DISCREPANCIES BETWEEN WHAT IS SHOWN ON THE PLANS AND LOCATED BY THE CONTRACTOR SHALL BE BROUGHT TO THE ATTENTION OF FURR ENGINEERING SERVICES PLLC. PRIOR TO CONSTRUCTION ACTIVITIES.



4320 ISLAND CREST WAY
 MERCER ISLAND, WA 98040

Key Plan

Registration



4715 142nd Pl. SW #B,
 Edmonds, WA 98026
 ph 206.890.8291

Sheet Title

**STORM DRAINAGE
 PROFILES**



Revisions

△	03/30/22	REVISED PER CITY COMMENTS
△	06/03/22	REVISED PER CITY COMMENTS
△	05/23/23	REVISED PER CITY COMMENTS

Scale:

FES Project No: 21084
 Date: Sept 27, 2021
 Designed: DAF
 Drawn: TJW
 Checked: DAF

Sheet Number


C4.1

SW 1/4 OF THE NW 1/4, SEC. 18, T 24N, R 05E, W.M.
MERCERTECH PLAT

4320 ISLAND CREST WAY
 MERCER ISLAND, WA 98040

Key Plan

Registration



4715 142nd Pl. SW #B,
 Edmonds, WA 98026
 ph 206.890.8291

Sheet Title

DETENTION VAULT 1




Revisions

NO.	DATE	REVISION
1	03/30/22	REVISED PER CITY COMMENTS
2	06/03/22	REVISED PER CITY COMMENTS
3	05/23/23	REVISED PER CITY COMMENTS

Scale:
 FES Project No: 21084
 Date: Sept 27, 2021
 Designed: DAF
 Drawn: JAB
 Checked: DAF

Sheet Number

C4.4



PLAN VIEW
 SCALE: 3/16" = 1'-0"

MODULE NOTES

TYPE	QUANTITY	HEIGHT
F	2	8
D	1	8
B	1	8
A	1	8
C	1	8
G	1	8
TOTAL	7	
VOLUME	6,182	CUBIC FEET

PIPE SCHEDULE

PIPE	SIZE	INVERT
M1-P1	12" RCP	0.00'
M5-P1	12" RCP	0.00'

MANHOLE SCHEDULE

MANHOLE	TYPE	RIM
M1-M1	30" DIA. E&C	0.00'

- DESIGN NOTES:**
- DESIGN LOADINGS:
 - A. AASHTO HS-20-44 W/ IMPACT.
 - C. ASSUMED WATER TABLE = BELOW BOTTOM OF PRECAST.
 - D. DRY LATERAL EARTH PRESSURE (EFP) = 45 PCF.
 - E. LATERAL LIVE LOAD SURCHARGE = 80 PSF (APPLIED TO 8' BELOW GRADE).
 - F. NO LATERAL SURCHARGE FROM ADJACENT BUILDINGS, WALL PIERS, OR FOUNDATIONS.
 - CONCRETE 28 DAY COMPRESSIVE STRENGTH SHALL BE 6,000 PSI.
 - STEEL REINFORCEMENT: REBAR, ASTM A-615 OR A-706, GRADE 60.
 - MESH REINFORCEMENT: ASTM A-1064, S1.2, GRADE 60.
 - CEMENT: ASTM C-150 SPECIFICATION.
 - STORMCAPTURE MODULE TYPE = DETENTION
 - REQUIRED BASE LAYER DEPTH = 2" SAND BEDDING LAYER.
 - REQUIRED NATIVE ALLOWABLE SOIL BEARING PRESSURE = 2,500 PSF. NATIVE SOIL SHOULD BE LEVEL/SCREEDED AND COMPACTED ADEQUATELY TO ALLOW FOR REQUIRED BEARING CAPACITY.
 - REFERENCE STANDARDS:
 - A. ASTM C 890
 - B. ASTM C 891
 - C. ASTM C 913
 - CONSTRUCTION EQUIPMENT EXCEEDING DESIGN LOADING SHALL NOT BE ALLOWED ON STRUCTURE. ANY DESIGN CONSTRAINT DIFFERENT FROM ABOVE REQUIRES CUSTOM STRUCTURAL DESIGN AND MAY REQUIRE THICKER SUBGRADE AND REVISED PRICING.

- NOTES TO REVIEWING ENGINEER:**
- THIS SYSTEM IS DESIGNED TO THE PARAMETERS NOTED. PLEASE VERIFY THAT THESE PARAMETERS MEET PROJECT REQUIREMENTS (I.E. LIVE LOAD AND FILL RANGE). IF DESIGN PARAMETERS ARE INCORRECT NOTIFY OLDCASTLE IMMEDIATELY FOR REDESIGN AND RE-PRICING.
 - ENGINEER OF RECORD TO CONFIRM ALL PIPE PENETRATION LOCATIONS, SIZES, AND INVERTS.
 - ENGINEER OF RECORD TO CONFIRM ALL MANWAY ACCESS LOCATIONS AND RIM ELEVATIONS.
 - UNLESS OTHERWISE NOTED, ALL PIPE SUPPLIED AND INSTALLED BY OTHERS.
 - THIS SYSTEM IS DESIGNED FOR A GROUNDWATER TABLE BELOW SYSTEM INVERT. ENGINEER OF RECORD TO VERIFY THAT THE DESIGN GROUNDWATER TABLE IS BELOW INVERT OF PRECAST. IF DESIGN PARAMETERS ARE INCORRECT NOTIFY OLDCASTLE IMMEDIATELY FOR REDESIGN AND REVISED PRICING.
 - THIS SYSTEM IS DESIGNED WITH A CONTAINMENT MEMBRANE LINER. IF A LINER IS NOT NEEDED PLEASE CONTACT OLDCASTLE TO PROVIDE THIS OPTION IN THE FINAL DESIGN. FOR WATERTIGHT PIPE BOOT CONNECTION TO LINER, CORRUGATED PIPE ADAPTER BY TRELLEBORG (OR EQUAL) REQUIRED FOR CONNECTION TO CORRUGATED HDPE PIPE, SUPPLIED AND INSTALLED BY OTHERS.

**- PRELIMINARY -
 NOT FOR CONSTRUCTION**

Oldcastle Infrastructure
 A CRH COMPANY
 Ph: 800.579.8819 | www.oldcastleinfrastructure.com/stormwater


THIS DOCUMENT IS THE PROPERTY OF OLDCASTLE INFRASTRUCTURE, INC. IT IS CONFIDENTIAL, SUBMITTED FOR REFERENCE PURPOSES ONLY, AND SHALL NOT BE USED IN ANY WAY INJURIOUS TO THE INTERESTS OF OR WITHOUT THE WRITTEN PERMISSION OF OLDCASTLE INFRASTRUCTURE, INC. COPYRIGHT © 2019 OLDCASTLE INFRASTRUCTURE, INC. ALL RIGHTS RESERVED.

**STORMCAPTURE®
 SC2 DETENTION SYSTEM**

CUSTOMER:
 Furr Engineering Services

JOB NAME & LOCATION:
 Mercertech Plat Detention - Vault 1 (Revision)

DRAWING NUMBER	REVISION	SHEET
WSCDD-3051-0_SC2_DT	3/30/22	1 OF 2



TOPOGRAPHY, BOUNDARY, AND UTILITIES STATEMENT:
 FURR ENGINEERING SERVICES PLLC DOES NOT WARRANT THE TOPOGRAPHY, BOUNDARY, AND/OR EXISTING UTILITIES SHOWN ON THESE PLANS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO HAVE ALL EXISTING IMPROVEMENTS FIELD VERIFIED PRIOR TO CONSTRUCTION. ANY SUBSURFACE EXPLORATION OF EXISTING UNDERGROUND UTILITIES (POWER, WATER, SEWER, TELECOM, ETC.) SHALL BE PERFORMED BY THE CONTRACTOR. DISCREPANCIES BETWEEN WHAT IS SHOWN ON THE PLANS AND LOCATED BY THE CONTRACTOR SHALL BE BROUGHT TO THE ATTENTION OF FURR ENGINEERING SERVICES PLLC, PRIOR TO CONSTRUCTION ACTIVITIES.




Know what's below.
 Call before you dig.

SW 1/4 OF THE NW 1/4, SEC. 18, T 24N, R 05E, W.M.
MERCERTECH PLAT

4320 ISLAND CREST WAY
 MERCER ISLAND, WA 98040

Key Plan


Registration



4715 142nd Pl. SW #B,
 Edmonds, WA 98026
 ph 206.890.8291

Sheet Title

DETENTION VAULT 1




Revisions

NO.	DATE	DESCRIPTION
△	03/30/22	REVISED PER CITY COMMENTS
△	06/03/22	REVISED PER CITY COMMENTS
△	05/23/23	REVISED PER CITY COMMENTS

Scale:
 FES Project No: 21084
 Date: Sept 27, 2021
 Designed: DAF
 Drawn: JAB
 Checked: DAF

Sheet Number

C4.5



TYPICAL ELEVATION
 SCALE: 3/8" = 1'-0"

**- PRELIMINARY -
 NOT FOR CONSTRUCTION**




Ph: 800.579.8819 | www.oldcastleinfrastructure.com/stormwater
 THIS DOCUMENT IS THE PROPERTY OF OLDCASTLE INFRASTRUCTURE, INC. IT IS CONFIDENTIAL, SUBMITTED FOR REFERENCE PURPOSES ONLY, AND SHALL NOT BE USED IN ANY WAY INJURIOUS TO THE INTERESTS OF OR WITHOUT THE WRITTEN PERMISSION OF OLDCASTLE INFRASTRUCTURE, INC. COPYRIGHT © 2019 OLDCASTLE INFRASTRUCTURE, INC. ALL RIGHTS RESERVED.

**STORMCAPTURE®
 SC2 DETENTION SYSTEM**

CUSTOMER:
Furr Engineering Services

JOB NAME & LOCATION:
Mercertech Plat Detention - Vault 1 (Revision

DRAWING NUMBER	REVISION	SHEET
WSCDD-3051-0_SC2_DT	3/30/22	2 OF 2



TOPOGRAPHY, BOUNDARY, AND UTILITIES STATEMENT:
 FURR ENGINEERING SERVICES PLLC DOES NOT WARRANT THE TOPOGRAPHY, BOUNDARY, AND/OR EXISTING UTILITIES SHOWN ON THESE PLANS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO HAVE ALL EXISTING IMPROVEMENTS FIELD VERIFIED PRIOR TO CONSTRUCTION. ANY SUBSURFACE EXPLORATION OF EXISTING UNDERGROUND UTILITIES (POWER, WATER, SEWER, TELECOM, ETC.) SHALL BE PERFORMED BY THE CONTRACTOR. DISCREPANCIES BETWEEN WHAT IS SHOWN ON THE PLANS AND LOCATED BY THE CONTRACTOR SHALL BE BROUGHT TO THE ATTENTION OF FURR ENGINEERING SERVICES PLLC, PRIOR TO CONSTRUCTION ACTIVITIES.



Know what's below.
 Call before you dig.

SW 1/4 OF THE NW 1/4, SEC. 18, T 24N, R 05E, W.M.
MERCERTECH PLAT

Module Sizes & Capacities


Modules are 8'x16' outside dimensions.
 Capacity varies by configuration of openings.

INSIDE DIMENSIONS (FT)	CAPACITY RANGE (FT ³)	INSIDE DIMENSIONS (FT)	CAPACITY RANGE (FT ³)
7x15x2	210-212	7x15x9	945-1,027
7x15x3	315-325	7x15x10	1,050-1,140
7x15x4	420-442	7x15x11	1,155 - 1,257
7x15x5	525-559	7x15x12	1,260 - 1,374
7x15x6	630-678	7x15x13	1,365 - 1,491
7x15x7	735-793	7x15x14	1,470 - 1,608
7x15x8	840-910		


INSTALLED IN JUST ONE DAY




StormCapture Modules




SC1 - Single piece modules can be used for applications from 2' to 7' tall. Appropriate for cisterns, infiltration, detention and retention systems. SC1 modules are typically installed on minimally compacted gravel base, depending on specific project requirements.



SC2 - Two piece modules can be used for applications from 7' to 14' tall for maximum storage capacity in a condensed footprint. Appropriate for cisterns, infiltration, detention and retention systems. SC2 modules are typically installed on compacted native subgrade.



Link Slab - Unique design allows for significant reduction in the quantity of modules and associated costs, while providing maximum storage capacity.



PERMECAPTURE



CISTERNS

TOPOGRAPHY, BOUNDARY, AND UTILITIES STATEMENT:
 FURR ENGINEERING SERVICES PLLC. DOES NOT WARRANT THE TOPOGRAPHY, BOUNDARY, AND/OR EXISTING UTILITIES SHOWN ON THESE PLANS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO HAVE ALL EXISTING IMPROVEMENTS FIELD VERIFIED PRIOR TO CONSTRUCTION. ANY SUBSURFACE EXPLORATION OF EXISTING UNDERGROUND UTILITIES (POWER, WATER, SEWER, TELECOM, ETC.) SHALL BE PERFORMED BY THE CONTRACTOR. DISCREPANCIES BETWEEN WHAT IS SHOWN ON THE PLANS AND LOCATED BY THE CONTRACTOR SHALL BE BROUGHT TO THE ATTENTION OF FURR ENGINEERING SERVICES PLLC. PRIOR TO CONSTRUCTION ACTIVITIES.




Know what's below.
 Call before you dig.

4320 ISLAND CREST WAY
 MERCER ISLAND, WA 98040

Key Plan

Registration



4715 142nd Pl. SW #B,
 Edmonds, WA 98026
 ph 206.890.8291

Sheet Title

**DETENTION VAULT
 DETAILS**



Revisions

Revision	Date	Description
1	03/30/22	REVISED PER CITY COMMENTS
2	06/03/22	REVISED PER CITY COMMENTS
3	05/23/23	REVISED PER CITY COMMENTS

Scale:

FES Project No: 21084

Date: Sept 27, 2021

Designed: DAF

Drawn: JAB


Checked: DAF

Sheet Number

C4.6

SW 1/4 OF THE NW 1/4, SEC. 18, T 24N, R 05E, W.M.
MERCERTECH PLAT

4320 ISLAND CREST WAY
 MERCER ISLAND, WA 98040



PLAN VIEW
 SCALE: 1/8" = 1'-0"

MODULE NOTES		
TYPE	QUANTITY	HEIGHT
C	2	8
D	4	8
F	2	8
TOTAL	8	
VOLUME	7,088	CUBIC FEET

PIPE SCHEDULE		
PIPE	SIZE	INVERT
M8-P1	12" RCP	0.00'

MANHOLE SCHEDULE		
MANHOLE	TYPE	RIM
M8-M1	30" DIA. E&C	0.00'

DESIGN NOTES:

- DESIGN LOADINGS:
 - AASHTO HS-20-44 W/ IMPACT.
 - ASSUMED WATER TABLE = BELOW BOTTOM OF PRECAST.
 - DRY LATERAL EARTH PRESSURE (EFP) = 45 PCF.
 - LATERAL LIVE LOAD SURCHARGE = 80 PSF (APPLIED TO 8' BELOW GRADE).
 - NO LATERAL SURCHARGE FROM ADJACENT BUILDINGS, WALL PIERS, OR FOUNDATIONS.
- CONCRETE 28 DAY COMPRESSIVE STRENGTH SHALL BE 6,000 PSI.
- STEEL REINFORCEMENT: REBAR, ASTM A-615 OR A-706, GRADE 60.
- MESH REINFORCEMENT: ASTM A-1064, S1.2, GRADE 80.
- CEMENT: ASTM C-150 SPECIFICATION.
- STORMCAPTURE MODULE TYPE = DETENTION
- REQUIRED BASE LAYER DEPTH = 2" SAND BEDDING LAYER.
- REQUIRED NATIVE ALLOWABLE SOIL BEARING PRESSURE = 2,500 PSF. NATIVE SOIL SHOULD BE LEVEL/SCREEDED AND COMPACTED ADEQUATELY TO ALLOW FOR REQUIRED BEARING CAPACITY.
- REFERENCE STANDARDS:
 - ASTM C 890
 - ASTM C 891
 - ASTM C 913
- CONSTRUCTION EQUIPMENT EXCEEDING DESIGN LOADING SHALL NOT BE ALLOWED ON STRUCTURE. ANY DESIGN CONSTRAINT DIFFERENT FROM ABOVE REQUIRES CUSTOM STRUCTURAL DESIGN AND MAY REQUIRE THICKER SUBGRADE AND REVISED PRICING.

NOTES TO REVIEWING ENGINEER:

- THIS SYSTEM IS DESIGNED TO THE PARAMETERS NOTED. PLEASE VERIFY THAT THESE PARAMETERS MEET PROJECT REQUIREMENTS (I.E. LIVE LOAD AND FILL RANGE). IF DESIGN PARAMETERS ARE INCORRECT NOTIFY OLDCASTLE IMMEDIATELY FOR REDESIGN AND RE-PRICING.
- ENGINEER OF RECORD TO CONFIRM ALL PIPE PENETRATION LOCATIONS, SIZES, AND INVERTS.
- ENGINEER OF RECORD TO CONFIRM ALL MANWAY ACCESS LOCATIONS AND RIM ELEVATIONS.
- UNLESS OTHERWISE NOTED, ALL PIPE SUPPLIED AND INSTALLED BY OTHERS.
- THIS SYSTEM IS DESIGNED FOR A GROUNDWATER TABLE BELOW SYSTEM INVERT. ENGINEER OF RECORD TO VERIFY THAT THE DESIGN GROUNDWATER TABLE IS BELOW INVERT OF PRECAST. IF DESIGN PARAMETERS ARE INCORRECT NOTIFY OLDCASTLE IMMEDIATELY FOR REDESIGN AND REVISED PRICING.
- THIS SYSTEM IS DESIGNED WITH A CONTAINMENT MEMBRANE LINER. IF A LINER IS NOT NEEDED PLEASE CONTACT OLDCASTLE TO PROVIDE THIS OPTION IN THE FINAL DESIGN. FOR WATERTIGHT PIPE BOOT CONNECTION TO LINER, CORRUGATED PIPE ADAPTER BY TRELLEBORG (OR EQUAL) REQUIRED FOR CONNECTION TO CORRUGATED HDPE PIPE, SUPPLIED AND INSTALLED BY OTHERS.

**- PRELIMINARY -
 NOT FOR CONSTRUCTION**

Oldcastle Infrastructure
 A CRH COMPANY

Ph: 800.579.8819 | www.oldcastleinfrastructure.com/stormwater

THIS DOCUMENT IS THE PROPERTY OF OLDCASTLE INFRASTRUCTURE, INC. IT IS CONFIDENTIAL. SUBMITTED FOR REFERENCE PURPOSES ONLY AND SHALL NOT BE USED IN ANY WAY INJURIOUS TO THE INTERESTS OF OR WITHOUT THE WRITTEN PERMISSION OF OLDCASTLE INFRASTRUCTURE, INC. COPYRIGHT © 2019 OLDCASTLE INFRASTRUCTURE, INC. ALL RIGHTS RESERVED.


STORMCAPTURE®

SC2 DETENTION SYSTEM

CUSTOMER:
 Furr Engineering Services

JOB NAME & LOCATION:
 Mercertech Plat Detention - Vault 2

DRAWING NUMBER	REVISION	SHEET
WSCDD-3055-0_SC2_DT	REV. DATE: 3/30/22	1 OF 2




TOPOGRAPHY, BOUNDARY, AND UTILITIES STATEMENT:
 FURR ENGINEERING SERVICES PLLC. DOES NOT WARRANT THE TOPOGRAPHY, BOUNDARY, AND/OR EXISTING UTILITIES SHOWN ON THESE PLANS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO HAVE ALL EXISTING IMPROVEMENTS FIELD VERIFIED PRIOR TO CONSTRUCTION. ANY SUBSURFACE EXPLORATION OF EXISTING UNDERGROUND UTILITIES (POWER, WATER, SEWER, TELECOM, ETC.) SHALL BE PERFORMED BY THE CONTRACTOR. DISCREPANCIES BETWEEN WHAT IS SHOWN ON THE PLANS AND LOCATED BY THE CONTRACTOR SHALL BE BROUGHT TO THE ATTENTION OF FURR ENGINEERING SERVICES PLLC., PRIOR TO CONSTRUCTION ACTIVITIES.



Key Plan


Registration



4715 142nd Pl. SW #B,
 Edmonds, WA 98026
 ph 206.890.8291

Sheet Title

DETENTION VAULT 2



Revisions

NO.	DATE	REVISION
1	03/30/22	REVISED PER CITY COMMENTS
2	06/03/22	REVISED PER CITY COMMENTS
3	05/23/23	REVISED PER CITY COMMENTS

Scale:

FES Project No: 21084

Date: Sept 27, 2021

Designed: DAF


Drawn: JAB

Checked: DAF

Sheet Number

C4.7

SW 1/4 OF THE NW 1/4, SEC. 18, T 24N, R 05E, W.M.
MERCERTECH PLAT



WATER INSTALLATION NOTES

- 1 1" WATER METER PER DETAIL SHEET C5.1
- 2 1-1/2" WATER SERVICE LINES AND 1-1/2" WATER SUPPLY LINES (TYP)
- 3 UPGRADE EX. 5/8" WATER METER TO 1". REUSE EX. WATER SERVICE FOR IRRIGATION TO TRACT. INSTALL DCVA AT BACKSIDE OF RIGHT OF WAY
- 4 REMOVE EX METER AND ABANDON EX WATER SERVICE

SEWER INSTALLATION NOTES

- 1 REMOVE EXISTING SSCO - ABANDON EXISTING SS 6" STUB
- 2 6" SSCO PER COMI DETAIL S-19 SHEET C5.2 (TYP)
- 3 6" PVC PIPE (TYP) SEE TABLE BELOW
- 4 CONNECT TO EXISTING MAIN PER COMI DETAIL S-17 SHEET C5.1

LEGEND

- CATCH BASIN TYPE 1
- CATCH BASIN TYPE 2
- PROPOSED CONCRETE
- PROPOSED ASPHALT
- PROPERTY BOUNDARY
- STORM DRAIN LINE
- ROOF DRAIN
- WETLAND BUFFER LINE
- TREE PROTECTION ZONE
- SANITARY SEWER SERVICE
- SEWER SERVICE CLEANOUT
- WATER SERVICE AND METER
- IRRIGATION METER

LOT #	SSCO IE	IE AT 6"	SLOPE
1	282.56	277.63	35.5%
3	281.00	276.27	24.1%
4	282.56	281.86	4.5%
5	283.00	281.91	4.0%

WATER NOTES

1. INSTALL ALL WATER METERS PER DETAIL W-13. ALL WATER METERS SHALL BE 1" AND SERVED BY INDIVIDUAL SERVICE LINES. INSTALL 1" TYPE K SOFT COPPER TUBING BETWEEN EX. WATER MAIN AND EACH METER. PRIVATE WATER SERVICE LINES SHALL BE 1.5" DR 9 OR 11 HDPE. SLEEVES WHERE SHOWN SHALL BE 4" SDR 35 PVC OR APPROVED EQUAL.
2. CONSTRUCTION OF ALL WATER FACILITIES SHALL CONFORM TO THE CITY OF MERCER ISLAND REQUIREMENTS AND STANDARD DETAILS.
3. REFER TO WATER SERVICE PERMIT FOR ACTUAL LOCATION OF NEW WATER METER AND SERVICE LINE DETERMINED BY MERCER ISLAND WATER DEPARTMENT.
4. LOCATE WATER SERVICE STUB, AT EDGE OF EASEMENT OR WHERE OTHERWISE SHOWN.
5. WATER SERVICE INSTALLATION FOR LOTS 1 AND 2 SHALL BE PERFORMED TO ENSURE RETENTION OF THE ADJACENT TREES. AIR TRENCHING, HAND EXCAVATION, AND/OR TRENCHLESS METHODS MAY BE REQUIRED. COORDINATE METER LOCATION AND INSTALLATION WITH THE CITY AND PROJECT ARBORIST.

SEWER NOTES

1. CONSTRUCTION OF ALL SEWER FACILITIES SHALL CONFORM TO THE CITY OF MERCER ISLAND REQUIREMENTS AND STANDARD DETAILS DATED JUNE 5, 2009, INCORPORATED BY REFERENCE.
2. 6" SIDE SEWER CONNECTION AND STUB PER CITY OF MERCER ISLAND STANDARD DETAIL S-4.
3. SEWER PIPE BEDDING PER CITY STANDARD DETAIL S-4, BACKFILL PER S-3.
4. CLEANOUTS PER DETAIL S-19.
5. LOCATE SEWER STUB AT EDGE OF EASEMENT.
6. ALL INDIVIDUAL SIDE SEWERS SHALL HAVE 2% SLOPE.

GENERAL NOTES



1. MITIGATED WETLAND & STREAM BOUNDARY & BUFFERS SHOWN. REFER TO THE WATERSHED CO. MITIGATION PLAN.

TOPOGRAPHY, BOUNDARY, AND UTILITIES STATEMENT:

FURR ENGINEERING SERVICES PLLC. DOES NOT WARRANT THE TOPOGRAPHY, BOUNDARY, AND/OR EXISTING UTILITIES SHOWN ON THESE PLANS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO HAVE ALL EXISTING IMPROVEMENTS FIELD VERIFIED PRIOR TO CONSTRUCTION. ANY SUBSURFACE EXPLORATION OF EXISTING UNDERGROUND UTILITIES (POWER, WATER, SEWER, TELECOM, ETC.) SHALL BE PERFORMED BY THE CONTRACTOR. DISCREPANCIES BETWEEN WHAT IS SHOWN ON THE PLANS AND LOCATED BY THE CONTRACTOR SHALL BE BROUGHT TO THE ATTENTION OF FURR ENGINEERING SERVICES PLLC. PRIOR TO CONSTRUCTION ACTIVITIES.




Know what's below.
 Call before you dig.



4320 ISLAND CREST WAY
 MERCER ISLAND, WA 98040

Key Plan

Registration



4715 142nd Pl. SW #B,
 Edmonds, WA 98026
 ph 206.890.8291

Sheet Title

SEWER & WATER PLAN



Revisions

Date	Description
03/30/22	REVISED PER CITY COMMENTS
06/03/22	REVISED PER CITY COMMENTS
05/23/23	REVISED PER CITY COMMENTS

Scale:

FES Project No: 21084

Date: Sept 27, 2021

Designed: DAF





Drawn: JAB

Checked: DAF


Sheet Number

C5.0

SW 1/4 OF THE NW 1/4, SEC. 18, T 24N, R 05E, W.M.
MERCERTECH PLAT




TOPOGRAPHY, BOUNDARY, AND UTILITIES STATEMENT:
 FURR ENGINEERING SERVICES PLLC. DOES NOT WARRANT THE TOPOGRAPHY, BOUNDARY, AND/OR EXISTING UTILITIES SHOWN ON THESE PLANS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO HAVE ALL EXISTING IMPROVEMENTS FIELD VERIFIED PRIOR TO CONSTRUCTION. ANY SUBSURFACE EXPLORATION OF EXISTING UNDERGROUND UTILITIES (POWER, WATER, SEWER, TELECOM, ETC.) SHALL BE PERFORMED BY THE CONTRACTOR. DISCREPANCIES BETWEEN WHAT IS SHOWN ON THE PLANS AND LOCATED BY THE CONTRACTOR SHALL BE BROUGHT TO THE ATTENTION OF FURR ENGINEERING SERVICES PLLC. PRIOR TO CONSTRUCTION ACTIVITIES.



4320 ISLAND CREST WAY
 MERCER ISLAND, WA 98040

Key Plan

Registration



4715 142nd Pl. SW #B,
 Edmonds, WA 98026
 ph 206.890.8291

Sheet Title

PROFILE AND DETAILS



Revisions

△	03/30/22	REVISED PER CITY COMMENTS
△	06/03/22	REVISED PER CITY COMMENTS
△	05/23/23	REVISED PER CITY COMMENTS




Scale:
 FES Project No: 21084
 Date: Sept 27, 2021
 Designed: DAF
 Drawn: JAB
 Checked: DAF

Sheet Number

5.1

SW 1/4 OF THE NW 1/4, SEC. 18, T 24N, R 05E, W.M.
MERCERTECH PLAT


DESIGN SPEED (MI/H)	STOPPING SIGHT DISTANCE				INTERSECTION SIGHT DISTANCE		MULTI-LANE ADJUSTMENT	
	BRAKE REACTION DISTANCE (FT)	BRAKING DISTANCE ON LEVEL (FT)	CALCULATED (FT)	DESIGN (FT)	CALCULATED (FT)	DESIGN (FT)	ADJUSTMENT LENGTH	DESIGN (FT)
40	147.00	153.60	300.60	305.00	441.00	445.00	25.00	470.00



4320 ISLAND CREST WAY
 MERCER ISLAND, WA 98040

Key Plan

Registration



4715 142nd Pl. SW #B,
 Edmonds, WA 98026
 ph 206.890.8291

Sheet Title

SIGHT DISTANCE PLAN



Revisions

△	03/30/22	REVISED PER CITY COMMENTS
△	06/03/22	REVISED PER CITY COMMENTS
△	05/23/23	REVISED PER CITY COMMENTS

Scale:

FES Project No: 2108

Date: Sept 27, 2023

Designed: DAF

Drawn: JAB


Checked: DAF

Sheet Number


C6.0

SW 1/4 OF THE NW 1/4, SEC. 18, T 24N, R 05E, W.M.
MERCERTECH PLAT

DESIGN SPEED (MI/H)	STOPPING SIGHT DISTANCE				INTERSECTION SIGHT DISTANCE		MULTI-LANE ADJUSTMENT	
	BRAKE REACTION DISTANCE (FT)	BRAKING DISTANCE ON LEVEL (FT)	CALCULATED (FT)	DESIGN (FT)	CALCULATED (FT)	DESIGN (FT)	ADJUSTMENT LENGTH	DESIGN (FT)
40	147.00	153.60	300.60	305.00	441.00	445.00	25.00	470.00



PLAT ROAD
 H: 1"=40' V 1"=10'




Department of Transportation
 Road Services Division
 2016 Design and Construction Standards
MEASURING SIGHT DISTANCE
 FIG. 2-013
 2-38

4320 ISLAND CREST WAY
 MERCER ISLAND, WA 98040

Key Plan


Registration



4715 142nd Pl. SW #B,
 Edmonds, WA 98026
 ph 206.890.8291

Sheet Title

SIGHT DISTANCE PROFILE



ISLAND CREST WAY ISD
 H: 1"=40' V 1"=10'

TOPOGRAPHY, BOUNDARY, AND UTILITIES STATEMENT:
 FURR ENGINEERING SERVICES PLLC. DOES NOT WARRANT THE TOPOGRAPHY, BOUNDARY, AND/OR EXISTING UTILITIES SHOWN ON THESE PLANS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO HAVE ALL EXISTING IMPROVEMENTS FIELD VERIFIED PRIOR TO CONSTRUCTION. ANY SUBSURFACE EXPLORATION OF EXISTING UNDERGROUND UTILITIES (POWER, WATER, SEWER, TELECOM, ETC.) SHALL BE PERFORMED BY THE CONTRACTOR. DISCREPANCIES BETWEEN WHAT IS SHOWN ON THE PLANS AND LOCATED BY THE CONTRACTOR SHALL BE BROUGHT TO THE ATTENTION OF FURR ENGINEERING SERVICES PLLC. PRIOR TO CONSTRUCTION ACTIVITIES.



Know what's below.
 Call before you dig.

Revisions


△	03/30/22	REVISED PER CITY COMMENTS
△	06/03/22	REVISED PER CITY COMMENTS
△	05/23/23	REVISED PER CITY COMMENTS

Scale:
 FES Project No: 2108
 Date: Sept 27, 2023
 Designed: DAF
 Drawn: JAB
 Checked: DAF

Sheet Number

C6.1

SW 1/4 OF THE NW 1/4, SEC. 18, T 24N, R 05E, W.M.
MERCERTECH PLAT



VICINITY MAP
 NO SCALE

4320 ISLAND CREST WAY
 MERCER ISLAND, WA 98040

Key Plan

SURVEY INFORMATION

HORIZONTAL DATUM: NAD 83/2011, WASHINGTON COORDINATE SYSTEM, NORTH ZONE, BASED ON GPS MEASUREMENTS USING THE WASHINGTON STATE REFERENCE NETWORK.

VERTICAL DATUM: NAVD 88, BASED ON GPS MEASUREMENTS USING THE WASHINGTON STATE REFERENCE NETWORK.


BASIS OF BEARING: NORTH 01°02'57" EAST, BETWEEN THE NORTHWEST CORNER AND THE WEST QUARTER CORNER OF SECTION 18, TOWNSHIP 24 NORTH, RANGE 5 EAST, WILLAMETTE MERIDIAN.

64.3 FEET FROM PROPERTY LINE TO FIRE HYDRANT.

LEGAL DESCRIPTION

THE NORTH 250 FEET OF THE SOUTH 500 FEET OF THE WEST HALF OF THE SOUTHWEST QUARTER OF THE SOUTHWEST QUARTER OF THE NORTHWEST QUARTER OF SECTION 18, TOWNSHIP 24 NORTH, RANGE 5 EAST, WILLAMETTE MERIDIAN, IN KING COUNTY, WASHINGTON, EXCEPT FOR THE WEST 40 FEET.

Registration



4715 142nd Pl. SW #B,
 Edmonds, WA 98026
 ph 206.890.8291

Sheet Title

HORIZONTAL CONTROL PLAN



Revisions

Revision	Date	Description
△	03/30/22	REVISED PER CITY COMMENTS
△	06/03/22	REVISED PER CITY COMMENTS
△	05/23/23	REVISED PER CITY COMMENTS

Scale:

FES Project No: 21084

Date: Sept 27, 2021


Designed: DAF

Drawn: JAB


Checked: DAF

Sheet Number

C7.0



TOPOGRAPHY, BOUNDARY, AND UTILITIES STATEMENT:
 FURR ENGINEERING SERVICES PLLC. DOES NOT WARRANT THE TOPOGRAPHY, BOUNDARY, AND/OR EXISTING UTILITIES SHOWN ON THESE PLANS. IT IS THE CONTRACTORS' RESPONSIBILITY TO HAVE ALL EXISTING IMPROVEMENTS FIELD VERIFIED PRIOR TO CONSTRUCTION. ANY SUBSURFACE EXPLORATION OF EXISTING UNDERGROUND UTILITIES (POWER, WATER, SEWER, TELECOM, ETC.) SHALL BE PERFORMED BY THE CONTRACTOR. DISCREPANCIES BETWEEN WHAT IS SHOWN ON THE PLANS AND LOCATED BY THE CONTRACTOR SHALL BE BROUGHT TO THE ATTENTION OF FURR ENGINEERING SERVICES PLLC. PRIOR TO CONSTRUCTION ACTIVITIES.



MERCERTECH INTERNATIONAL LLC LONG PLAT MITIGATION AND RESTORATION PLAN



750 Sixth Street South
Kirkland WA 98033

p 425.822.5242
www.watershedco.com




Science & Design

MERCERTECH INTERNATIONAL LLC
LONG PLAT MITIGATION AND RESTORATION PLAN
PREPARED FOR ALAN CHIU
PARCEL # 1824059031
4320 ISLAND CREST WAY
MERCER ISLAND, WA 98040

SUBMITTALS & REVISIONS	
NO.	DESCRIPTION
1	08-29-17 30% SUBMITTAL - PREAPP
2	10/17/17 30% SUBMITTAL - PREAPP 2
3	10/27/17 30% SUBMITTAL - APPLICATION
4	04/18/18 CITY COMMENT RESPONSE 1

SHEET SIZE:
ORIGINAL PLAN IS 22" x 34".
SCALE ACCORDINGLY.

PROJECT MANAGER: MD
DESIGNED: LV, RH
DRAFTED: LV, RH
CHECKED: LV, AM
JOB NUMBER: 160905
SHEET NUMBER: W1.0 OF 14



VICINITY MAPS

LEGEND

- PARCEL BOUNDARY
- - - EXISTING CONTOUR
- WETLAND BOUNDARY (DELINEATED)
- DATA POINT
- WATERCOURSE BOUNDARY (DELINEATED)
- WATERCOURSE BOUNDARY (APPROX.)
- ⊛ EXISTING TREE
- ⤵ CULVERT (QTY. 3)

SHEET INDEX

- W1.0 EXISTING CONDITIONS
- W2.0 IMPACTS PLAN
- W3.0 RESTORATION AND MITIGATION PLAN
- W4.0 TREE PRESERVATION PLAN
- W4.1 TREE INVENTORY TABLES 1-3
- W4.2 TREE INVENTORY TABLES 4-6
- W4.3 TREE INVENTORY TABLE 7 AND TREE PRESERVATION DETAILS
- W5.0 TESC AND SITE PREPARATION PLAN
- W5.1 TESC DETAILS AND INVASIVE SPECIES REMOVAL NOTES
- W6.0 WETLAND CREATION AREA GRADING PLAN
- W7.0 PLANTING PLAN
- W7.1 TYPICAL PLANTING SCHEDULES
- W7.2 PLANT INSTALLATION DETAILS AND NOTES
- W8.0 MITIGATION AND RESTORATION NOTES

NOTES

1. CRITICAL AREAS DELINEATED BY THE WATERSHED COMPANY ON SEPTEMBER 21, 2016.
2. ONLY LEFT BANK OF WATERCOURSE A DELINEATED WITHIN WETLAND C.
3. SURVEY RECEIVED FROM PLS, INC. 1595 NW GILMAN BOULEVARD, #15 ISSAQUAH, WA 98027. (425) 313-9378.

EXISTING CONDITIONS



NFC
NOT FOR
CONSTRUCTION



**MERCERTECH INTERNATIONAL LLC
LONG PLAT MITIGATION AND RESTORATION PLAN
PREPARED FOR ALAN CHIU
PARCEL # 1824059031
4320 ISLAND CREST WAY
MERCER ISLAND, WA 98040**

SUBMITTALS & REVISIONS

NO.	DATE	DESCRIPTION	BY
1	08/29/17	30% SUBMITTAL - PREAPP	LV, RH
2	10/17/17	30% SUBMITTAL - PREAPP 2	RH, RH
3	10/27/17	30% SUBMITTAL - APPLICATION	RH, RH
4	04/18/18	CITY COMMENT RESPONSE	RH

SHEET SIZE:
ORIGINAL PLAN IS 22" x 34".
SCALE ACCORDINGLY.

PROJECT MANAGER: MD
DESIGNED: LV, RH
DRAFTED: LV, RH
CHECKED: LV, AM
JOB NUMBER:
160905
SHEET NUMBER:
W2.0 OF 14



LEGEND


- EXISTING FEATURES**
- EXISTING CONTOUR
 - WETLAND BOUNDARY (DELINEATED)
 - WATERCOURSE BOUNDARY (DELINEATED)
 - WATERCOURSE BOUNDARY (APPROX.)
 - VIOLATION AREA (12,748 SF)
 - EXISTING TREE
- PROPOSED FEATURES**
- PROPOSED PROPERTY BOUNDARY
 - WETLAND/WATERCOURSE BUFFER (50 FT)
 - REDUCED WETLAND/WATERCOURSE BUFFER (25 FT)
 - TREE TO BE REMOVED WITH PLAT IMPROVEMENTS (QTY. 15)
 - TREE TO BE REMOVED WITH HOME CONSTRUCTION (QTY.6)
 - WETLAND AS BUFFER (1,988 SF)

IMPACT CALCULATIONS

IMPACT	AREA (SF)
WETLAND VIOLATION	12,748
WETLAND AS BUFFER	1,988
TOTAL IMPACTS	14,736

NOTES

- SEE SHEETS 34.0-W4.3 FOR TREE PRESERVATION INFORMATION.
- WETLAND VIOLATION AREA PER NOTICE OF CORRECTION FROM CITY OF MERCER ISLAND, DATED AUGUST 10, 2016.
- EXISTING WETLAND VIOLATION AREA EXTRAPOLATED FROM 2012 AND 2015 KING COUNTY IMAP AERIAL PHOTOGRAPHY. ADDITIONALLY, SEE INVOICE IN REQUEST FOR INFORMATION #1 LETTER FROM THE WATERSHED COMPANY, DATED APRIL 13, 2013.
- SEE CIVIL PLANS FOR PROPOSED GRADING OUTSIDE MITIGATION AREA.




IMPACTS PLAN



NFC
NOT FOR
CONSTRUCTION

MERCERTECH INTERNATIONAL LLC
LONG PLAT MITIGATION AND RESTORATION PLAN
PREPARED FOR ALAN CHIU
PARCEL # 1824059031
4320 ISLAND CREST WAY
MERCER ISLAND, WA 98040



(A) SPLIT RAIL FENCE WITH SIGN ON POST

Scale: NTS

LEGEND

- EXISTING FEATURES**
- EXISTING CONTOUR
 - WETLAND BOUNDARY (DELINEATED)
 - WATERCOURSE BOUNDARY (DELINEATED)
 - WATERCOURSE BOUNDARY (APPROX.)
 - EXISTING TREE
- PROPOSED FEATURES**
- PROPOSED PROPERTY BOUNDARY
 - WETLAND/WATERCOURSE AREA BUFFER (50 FT)
 - REDUCED WETLAND/WATERCOURSE BUFFER (25 FT)
 - TREE TO BE REMOVED WITH PLAT IMPROVEMENTS (QTY. 15)
 - TREE TO BE REMOVED WITH HOME CONSTRUCTION (QTY. 6)
 - EXISTING STRUCTURES AND DRIVEWAY TO BE REMOVED WITHIN BUFFER (5,703 SF)
 - CULVERT TO BE REMOVED (QTY. 2)
 - WETLAND CREATION AREA (2,305 SF)
 - WETLAND RESTORATION AREA (24,670 SF)
 - BUFFER MITIGATION AREA (21,080 SF)
 - SPLIT RAIL FENCE WITH SIGN ON POST

MITIGATION CALCULATIONS

MITIGATION	AREA (SF)
BUFFER RESTORATION	21,080
WETLAND RESTORATION	24,670
WETLAND CREATION	2,305
TOTAL MITIGATION	48,054



SUBMITTALS & REVISIONS

NO.	DATE	DESCRIPTION	BY
1	08-29-17	30% SUBMITTAL - PREAPP	LV
2	10-17-17	30% SUBMITTAL - PREAPP 2	RH
3	10-27-17	30% SUBMITTAL - APPLICATION	RH
4	04/18/18	CITY COMMENT RESPONSE	RH

SHEET SIZE:
ORIGINAL PLAN IS 22" x 34".
SCALE ACCORDINGLY.

PROJECT MANAGER: MD
DESIGNED: LV, RH
DRAFTED: LV, RH
CHECKED: LV, AM
JOB NUMBER:


160905
SHEET NUMBER:

W3.0 OF 14

DATE PRINTED BY: 10/27/17 RCN/HON/FIELD FILENAME: 160905 MERCER ISLAND CHIU MITIGATION PLANDING



RESTORATION AND MITIGATION PLAN



NFC
NOT FOR CONSTRUCTION

MERCERTECH INTERNATIONAL LLC
LONG PLAT MITIGATION AND RESTORATION PLAN
PREPARED FOR ALAN CHIU
PARCEL # 1824059031
4320 ISLAND CREST WAY
MERCER ISLAND, WA 98040

LEGEND

- EXISTING FEATURES**
- EXISTING CONTOUR
 - WETLAND BOUNDARY (DELINEATED)
 - WATERCOURSE BOUNDARY (DELINEATED)
 - WATERCOURSE BOUNDARY (APPROX.)
 - EXISTING TREE
- PROPOSED FEATURES**
- 284 PROPOSED CONTOUR (WETLAND CREATION AREA)
 - WETLAND/WATERCOURSE BUFFER (50 FT)
 - REDUCED WETLAND/WATERCOURSE BUFFER (25 FT)
 - TREE TO BE REMOVED WITH PLAT IMPROVEMENTS (QTY. 15)
 - TREE TO BE REMOVED WITH HOME CONSTRUCTION (QTY. 6)
 - TREE TRUNK WRAP (B/W4.3, C/W4.3)
 - TREE PROTECTION FENCING
 - APPROX. LIMITS OF GRADING (WETLAND CREATION AREA)

NOTES

- QUANTITIES OF TREES TO BE REMOVED IN THE TREE RETENTION LEGEND REFLECT TOTAL TREES THAT WILL REQUIRE REMOVAL AS PART OF THE SITE DEVELOPMENT.
- PER MICC 19.16.010, A SIGNIFICANT TREE IS ANY CONIFER THAT IS MORE THAN SIX FEET TALL OR ANY DECIDUOUS TREE WITH A DIAMETER OF SIX INCHES OR MORE.
- TREES DESIGNATED FOR REMOVAL WITHIN TREE PROTECTION FENCE SHOULD BE SNAGGED OR FLUSH CUT TO MINIMIZE ROOT DAMAGE TO REMAINING TREES. DO NOT REMOVE TREES DESIGNATED FOR REMOVAL WITHIN TREE PROTECTION FENCING AREA BY PUSHING OVER WITH MACHINERY.
- CONSTRUCTION WITHIN TREE PROTECTION FENCING SHALL BE COMPLETED BY HAND, MAINTAINING EXISTING GRADE UNLESS OTHERWISE INDICATED ON THE CIVIL PLANS.
- EXISTING TREES TO REMAIN SHALL NOT BE DISTURBED DURING DEMOLITION OF EXISTING STRUCTURES OR CONSTRUCTION OF PROPOSED FEATURES. THIS INCLUDES DAMAGES TO TREE TRUNK, ROOTS, AND LIMBS. IF TREE LIMBS RESTRICT VERTICAL LIMITS OF DEMOLITION MACHINERY, A CERTIFIED ARBORIST MAY LIFT CANOPY BY PRUNING LIMBS UP TRUNK.
- MACHINERY ACCESS FOR DEMOLITION OF EXISTING SOUTHERLY HOUSE SHALL UTILIZE 5" OF WOOD CHIP MULCH OVERLAID WITH STEEL PLATE OR 1/4" INCH PLYWOOD TO PREVENT DISTURBANCE OF EXISTING TREE ROOTS.




SUBMITTALS & REVISIONS	
NO.	DESCRIPTION
1	08-29-17 30% SUBMITTAL - PREAPP
2	10-17-17 30% SUBMITTAL - PREAPP 2
3	10-27-17 30% SUBMITTAL - APPLICATION
4	04-18-18 CITY COMMENT RESPONSE

SHEET SIZE:
ORIGINAL PLAN IS 22" x 34".
SCALE ACCORDINGLY.

PROJECT MANAGER: MD
DESIGNED: LV, RH
DRAFTED: LV, RH
CHECKED: LV, AM
JOB NUMBER:
160905
SHEET NUMBER:
W4.0 OF 14

NFC
NOT FOR CONSTRUCTION

TREE PRESERVATION PLAN



MERCERTECH INTERNATIONAL LLC
LONG PLAT MITIGATION AND RESTORATION PLAN
PREPARED FOR ALAN CHIU
PARCEL # 1824059031
4320 ISLAND CREST WAY
MERCER ISLAND, WA 98040

THE WATERSHED COMPANY
MERCER ISLAND CHIU
4320 Island Crest Way, Mercer Island, WA 98040 Site Visit: 5/16/2017 and 8/24/2017
parcel # 1824059031
Table Issued: 4/9/2018

TAG #	TREE NAME	EV / DEC	# STEMS	COMB DBH (IN. ROUNDED)	HEIGHT (FT)	RADIUS (FT)	CONDITION	REMOVE (Y/N)	NOTES
100	Malus domestica (Apple)	D	1	10	25	10	3	N	
101	Prunus emarginata (Bitter cherry)	D	1	14	55	20	4	N	broken main leader at 50'
102	Pinus monticola (Western white pine)	E	1	6	30	8	2	N	
103	Pinus monticola (Western white pine)	E	1	5	30	12	2	N	
104	Picea sitchensis (Sitka spruce)	E	1	2	20	5	2	N	
105	Tsuga canadensis (Canadian hemlock)	E	1	7	40	9	2	N	
106	Tsuga canadensis (Canadian hemlock)	E	1	5	30	10	2	N	
107	Sorbus aucuparia (European mountain ash)	D	1	12	50	15	3	N	
108	Cedrus deodara (Deodar cedar)	E	1	13	55	15	3	N	
109	Prunus avium <cultivated> (Fruiting Cherry)	D	1	14	30	10	4	N	sig. ivy on trunk
110	Crataegus monogyna (Common hawthorn)	D	3	8	20	12	3	N	
111	Fraxinus latifolia (Oregon ash)	D	1	13	50	17	3	N	
112	Pseudotsuga menziesii (Douglas-fir)	E	1	27	85	20	3	N	
113	Fraxinus latifolia (Oregon ash)	D	1	12	45	17	3	N	
114	Gleditsia triacanthos (Honeylocust)	D	1	10	40	13	3	N	
115	Thuja plicata (Western red cedar)	E	1	14	40	13	4	N	chlorotic foliage
116	Thuja plicata (Western red cedar)	E	2	15	50	20	3	N	flagging
117	Thuja plicata (Western red cedar)	E	1	10	50	10	3	N	
118	Thuja plicata (Western red cedar)	E	1	10	35	10	3	N	
119	Acer macrophyllum (Bigleaf maple)	D	1	28	75	29	3	N	
120	Thuja plicata (Western red cedar)	E	1	10	40	10	4	N	chlorotic foliage, stressed cone crop
121	>Hesperotropsis leylandii (Leyland cypress)	E	1	4	20	6	3	N	
122	Thuja plicata (Western red cedar)	E	1	6	15	6	3	N	
123	Betula pendula (European white birch)	D	1	15	40	15	3	N	
124	Betula pendula (European white birch)	D	1	14	60	20	3	N	
125	Betula pendula (European white birch)	D	1	9	50	16	3	N	leader failure
126	Thuja plicata (Western red cedar)	E	1	18	50	12	3	N	
127	Thuja plicata (Western red cedar)	E	1	18	50	14	3	N	
128	Prunus avium <cultivated> (Fruiting Cherry)	D	1	7	25	15	3	N	
129	Prunus avium <cultivated> (Fruiting Cherry)	D	1	7	17	12	4	N	decay in trunk; necrotic foliage; deadwood
130	Prunus avium <cultivated> (Fruiting Cherry)	D	1	8	17	15	4	N	deadwood; chlorotic foliage
131	Prunus avium <cultivated> (Fruiting Cherry)	D	1	14	18	12	4	N	significant ivy on trunk
132	Pseudotsuga menziesii (Douglas-fir)	E	1	15	26	16	4	N	topped for utility lines; significant ivy on trunk
652	Pseudotsuga menziesii (Douglas-fir)	E	1	6	15	5	3	N	topped for power line
653	Tsuga heterophylla (Western hemlock)	E	1	8	15	10	4	N	
654	Pseudotsuga menziesii (Douglas-fir)	E	1	4	20	10	3	N	growing into power lines
655	Pinus sylvestris (Scots pine)	E	1	14	50	15	3	N	
656	Prunus cerasifera 'thundercloud' (Cherry plum)	D	2	16	30	20	4	N	poor branch form
657	Quercus palustris (Pin oak)	E	1	28	70	26	2	N	ivy on trunk
658	Pseudotsuga menziesii (Douglas-fir)	E	1	8	49	12	2	N	
659	Pinus sylvestris (Scots pine)	E	1	15	50	10	4	N	necrotic foliage

A TREE INVENTORY TABLE (1 OF 7)

Scale: NTS

THE WATERSHED COMPANY
MERCER ISLAND CHIU
4320 Island Crest Way, Mercer Island, WA 98040 Site Visit: 5/16/2017 and 8/24/2017
parcel # 1824059031
Table Issued: 4/9/2018

TAG #	TREE NAME	EV / DEC	# STEMS	COMB DBH (IN. ROUNDED)	HEIGHT (FT)	RADIUS (FT)	CONDITION	REMOVE (Y/N)	NOTES
660	Pseudotsuga menziesii (Douglas-fir)	E	1	15	65	12	3	N	
661	Pseudotsuga menziesii (Douglas-fir)	E	1	18	75	13	3	N	self corrected lean
668	Pinus sylvestris (Scots pine)	E	1	11	30	13	4	N	topped for utility line
669	Pseudotsuga menziesii (Douglas-fir)	E	1	8	20	12	4	N	topped for utility line
670	Pseudotsuga menziesii (Douglas-fir)	E	1	12	20	20	4	N	topped for utility line; poor root flare
671	Pseudotsuga menziesii (Douglas-fir)	E	1	5	25	8	3	N	
672	Pseudotsuga menziesii (Douglas-fir)	E	1	8	20	15	4	N	topped for utility line
729	Arbutus menziesii (Pacific madrone)	E	1	10	50	14	3	N	50% of drip-line impervious
730	Thuja plicata (Western red cedar)	E	1	15	40	15	3	N	retaining wall 1-ft from trunk
731	Thuja plicata (Western red cedar)	E	4	16	45	15	3	N	included bark
732	Arbutus menziesii (Pacific madrone)	E	1	6	15	20	4	N	not on survey
733	Arbutus menziesii (Pacific madrone)	E	1	12	55	15	3	N	3-ft from retaining wall; ivy on trunk; self-corrected lean
734	Picea abies (Norway spruce)	E	1	13	45	10	4	Y	low kr
735	Betula pendula (European white birch)	D	3	26	60	17	3	Y	ivy on trunk; co-dominant from base
736	Pinus sylvestris (Scots pine)	E	1	14	17	12	3	N	photographically oriented
737	Ginkgo biloba (Maidenhair tree)	D	1	5	20	6	2	Y	not on survey
738	>Hesperotropsis leylandii (Leyland cypress)	E	1	8	25	10	2	Y	
739	>Hesperotropsis leylandii (Leyland cypress)	E	1	6	25	8	2	Y	
740	Prunus domestica (Plum)	D	1	16	40	20	4	N	low kr
741	Prunus domestica (Plum)	D	1	10	35	12	4	N	low kr
742	Prunus domestica (Plum)	D	1	8	20	14	3	Y	low kr; not on survey
743	Prunus domestica (Plum)	D	1	17	60	15	3	Y	
744	Prunus domestica (Plum)	D	2	10	35	10	4	N	low kr; not on survey
745	Prunus domestica (Plum)	D	1	12	40	15	4	N	virginia creeper on trunk
746	>Hesperotropsis leylandii (Leyland cypress)	E	1	4	13	8	3	N	base at 2'+5.4"; not on survey
747	>Hesperotropsis leylandii (Leyland cypress)	E	1	4	15	6	3	N	base at 2'+7.5"; not on survey
748	>Hesperotropsis leylandii (Leyland cypress)	E	1	3	15	6	3	N	base at 2'+4.5"; not on survey
749	>Hesperotropsis leylandii (Leyland cypress)	E	1	4	18	6	3	N	base at 2'+5.2"; not on survey
750	>Hesperotropsis leylandii (Leyland cypress)	E	1	5	18	8	3	N	base at 2'+5.8"; not on survey
751	>Hesperotropsis leylandii (Leyland cypress)	E	1	3	15	6	3	N	base at 2'+4"; not on survey
752	>Hesperotropsis leylandii (Leyland cypress)	E	1	5	15	8	3	N	base at 2'+5.3"; not on survey
753	>Hesperotropsis leylandii (Leyland cypress)	E	1	3	15	8	3	N	base at 2'+5"; not on survey
754	>Hesperotropsis leylandii (Leyland cypress)	E	1	5	20	9	3	N	base at 2'+6"; not on survey
755	>Hesperotropsis leylandii (Leyland cypress)	E	1	5	15	9	3	N	base at 2'+5.8"; not on survey
756	>Hesperotropsis leylandii (Leyland cypress)	E	1	4	15	8	3	N	base at 2'+5"; not on survey
757	>Hesperotropsis leylandii (Leyland cypress)	E	1	4	15	9	3	N	base at 2'+4.7"; not on survey
758	>Hesperotropsis leylandii (Leyland cypress)	E	1	4	18	8	3	N	base at 2'+4.4"; not on survey
759	>Hesperotropsis leylandii (Leyland cypress)	E	1	5	18	6	3	N	base at 2'+5.4"; not on survey
760	>Hesperotropsis leylandii (Leyland cypress)	E	1	3	12	6	3	N	base at 2'+4"; not on survey
761	Alnus rubra (Red alder)	D	2	26	60	25	3	N	
762	Alnus rubra (Red alder)	D	1	9	60	17	3	N	

B TREE INVENTORY TABLE (2 OF 7)

Scale: NTS

THE WATERSHED COMPANY
MERCER ISLAND CHIU
4320 Island Crest Way, Mercer Island, WA 98040 Site Visit: 5/16/2017 and 8/24/2017
parcel # 1824059031
Table Issued: 4/9/2018

TAG #	TREE NAME	EV / DEC	# STEMS	COMB DBH (IN. ROUNDED)	HEIGHT (FT)	RADIUS (FT)	CONDITION	REMOVE (Y/N)	NOTES
763	Alnus rubra (Red alder)	D	4	32	65	28	3	N	
764	Prunus armeniaca (Apricot)	D	1	14	55	20	4	N	low kr
765	Prunus armeniaca (Apricot)	D	1	9	50	15	4	N	low kr; ivy on trunk; not on survey
766	>Hesperotropsis leylandii (Leyland cypress)	E	1	4	12	6	3	N	base at 2'+4.3"; not on survey
767	>Hesperotropsis leylandii (Leyland cypress)	E	1	4	25	8	3	N	base at 2'+5"; not on survey
768	>Hesperotropsis leylandii (Leyland cypress)	E	1	6	25	9	3	N	base at 2'+6.5"; not on survey
769	>Hesperotropsis leylandii (Leyland cypress)	E	1	5	25	8	3	N	base at 2'+6.2"; not on survey
770	>Hesperotropsis leylandii (Leyland cypress)	E	1	5	25	10	3	N	base at 2'+5.3"; not on survey
771	>Hesperotropsis leylandii (Leyland cypress)	E	1	6	25	10	3	N	base at 2'+6.7"; not on survey
772	>Hesperotropsis leylandii (Leyland cypress)	E	1	5	30	8	3	N	base at 2'+5"; not on survey
773	>Hesperotropsis leylandii (Leyland cypress)	E	1	6	25	8	3	N	base at 2'+5.5"; not on survey
774	>Hesperotropsis leylandii (Leyland cypress)	E	1	5	18	8	3	N	base at 2'+5.5"; not on survey
775	>Hesperotropsis leylandii (Leyland cypress)	E	1	5	25	12	3	N	base at 2'+4.8"; not on survey
776	>Hesperotropsis leylandii (Leyland cypress)	E	1	4	20	12	3	N	base at 2'+4.8"; not on survey
777	>Hesperotropsis leylandii (Leyland cypress)	E	1	6	20	10	3	N	base at 2'+6.5"; not on survey
778	>Hesperotropsis leylandii (Leyland cypress)	E	1	4	18	10	3	N	base at 2'+4.6"; not on survey
779	>Hesperotropsis leylandii (Leyland cypress)	E	1	5	25	10	3	N	base at 2'+6.4"; not on survey
780	>Hesperotropsis leylandii (Leyland cypress)	E	1	5	20	12	3	N	base at 2'+5.8"; not on survey
781	>Hesperotropsis leylandii (Leyland cypress)	E	1	5	18	6	3	N	base at 2'+5.5"; not on survey
782	>Hesperotropsis leylandii (Leyland cypress)	E	1	5	20	6	3	N	base at 2'+5.5"; not on survey
783	>Hesperotropsis leylandii (Leyland cypress)	E	1	4	18	8	3	N	base at 2'+5"; not on survey
784	>Hesperotropsis leylandii (Leyland cypress)	E	1	4	20	8	3	N	base at 2'+5.2"; not on survey
785	>Hesperotropsis leylandii (Leyland cypress)	E	1	4	18	5	3	N	
786	>Hesperotropsis leylandii (Leyland cypress)	E	1	4	17	8	3	N	base at 2'+4.3"; not on survey
787	>Hesperotropsis leylandii (Leyland cypress)	E	1	4	20	7	3	N	base at 2'+5"; not on survey
788	>Hesperotropsis leylandii (Leyland cypress)	E	1	4	20	6	3	N	base at 2'+4.8"; not on survey
789	Pseudotsuga menziesii (Douglas-fir)	E	1	18	50	15	3	N	30% impervious within drip-line
790	Pseudotsuga menziesii (Douglas-fir)	E	1	14	20	15	4	N	topped at 20-ft for powerlines, 50% impervious in drip-line
791	Betula pendula (European white birch)	D	2	18	35	25	4	N	included bark
792	Thuja plicata (Western red cedar)	E	1	19	55	7	3	N	codominate at 30'
793	Cunninghamia lanceolata (China fir)	E	1	13	30	8	2	Y	
794	Thuja plicata (Western red cedar)	E	1	20	45	12	2	Y	ivy on trunk
795	Prunus domestica (Plum)	D	1	11	45	16	3	Y	trunk wound at base with good response growth
796	Pinus monticola (Western white pine)	E	1	26	65	19	2	N	50% of drip-line is a house
797	Pseudotsuga menziesii (Douglas-fir)	E	1	22	20	18	4	N	limited root zone; topped at 20'; fungi on trunk
798	>Hesperotropsis leylandii (Leyland cypress)	E	1	4	18	6	3	N	base at 2'+4.1"; not on survey
799	Cedrus deodara (Deodar cedar)	E	1	25	65	24	2	N	not on survey
800	Pseudotsuga menziesii (Douglas-fir)	E	1	16	60	15	3	N	
801	Cedrus deodara (Deodar cedar)	E	1	16	55	12	4	N	suppressed canopy
802	Pseudotsuga menziesii (Douglas-fir)	E	1	19	65	17	4	N	self-corrected lean; low kr
803	Acer macrophyllum (Bigleaf maple)	D	1	22	70	20	3	N	not on survey

C TREE INVENTORY TABLE (3 OF 7)

Scale: NTS



TREE INVENTORY TABLES 1-3

NFC
NOT FOR
CONSTRUCTION

SUBMITTALS & REVISIONS		NO.	DATE	DESCRIPTION	BY
1	08/29/17	30% SUBMITTAL - PREAPP	LV		
2	10/17/17	30% SUBMITTAL - PREAPP 2	RH		
3	10/27/17	30% SUBMITTAL - APPLICATION	RH		
4	04/18/18	CITY COMMENT RESPONSE	RH		

SHEET SIZE:
ORIGINAL PLAN IS 22" x 34".
SCALE ACCORDINGLY.

PROJECT MANAGER: MD
DESIGNED: LV, RH
DRAFTED: LV, RH
CHECKED: LV, AM
JOB NUMBER:
160905

SHEET NUMBER:
W4.1 OF 14

MERCERTECH INTERNATIONAL LLC
LONG PLAT MITIGATION AND RESTORATION PLAN
PREPARED FOR ALAN CHIU
PARCEL # 1824059031
4320 ISLAND CREST WAY
MERCER ISLAND, WA 98040

THE WATERSHED COMPANY
MERCER ISLAND CHIU
4320 Island Crest Way, Mercer Island, WA 98040 Site Visit: 5/16/2017 and 8/24/2017
parcel # 1824059031
Table Issued: 4/9/2018

TAG #	TREE NAME	EV / DEC	# STEMS	COMB DBH (IN, ROUNDED)	HEIGHT (FT)	RADIUS (FT)	CONDITION	REMOVE (Y/N)	NOTES
804	Acer macrophyllum (Bigleaf maple)	D	1	28	65	30	3	N	12-in cavity at 10'; potential circling root; 10-degree lean to the south
805	Acer macrophyllum (Bigleaf maple)	D	1	18	70	30	3	N	
806	Acer macrophyllum (Bigleaf maple)	D	1	7	30	20	4	N	not on survey; phototropic lean
807	Thuja plicata (Western red cedar)	E	1	18	70	15	3	N	
808	Thuja plicata (Western red cedar)	E	1	13	40	12	3	N	suppressed canopy; pistol butt trunk
809	Acer macrophyllum (Bigleaf maple)	D	2	11	20	20	4	N	co-dominant; topped at 12'; not on survey
810	Thuja plicata (Western red cedar)	E	1	21	60	15	3	N	rooting branches that look like separate trees growing
811	Acer macrophyllum (Bigleaf maple)	D	1	21	70	30	3	N	trunk cavity 6-in in dia.; codominate at 15-ft
812	Acer macrophyllum (Bigleaf maple)	D	1	22	60	30	3	N	scaffold branch failure at 25-ft with good response growth
813	Acer macrophyllum (Bigleaf maple)	D	3	39	70	30	3	N	co-dominant at base; included bark; significant trunk wound
814	Alnus rubra (Red alder)	D	1	4	15	6	3	N	base at 2'-4.3"; not on survey
815	Prunus domestica (Plum)	D	1	14	20	8	4	N	poor pruning history; ivy on trunk; not on survey
816	Alnus rubra (Red alder)	D	1	5	20	10	3	N	not on survey
817	Pyrus domestica (Common pear)	D	1	5	15	8	4	Y	base at 2'-5.8"; not on survey
818	Fraxinus latifolia (Oregon ash)	D	1	10	30	12	3	Y	topped at 10-ft; not on survey
819	Styrax japonicus (Japanese snowbell)	D	6	20	25	16	4	Y	additional DBH-8", 6"
820	Castanea dentata (American chestnut)	D	2	44	70	30	3	Y	
821	Acer macrophyllum (Bigleaf maple)	D	1	34	75	35	2	Y	
822	Thuja plicata (Western red cedar)	E	1	17	50	8	2	Y	
823	Acer macrophyllum (Bigleaf maple)	D	1	32	70	30	3	N	co-dominant at 6'; not on survey
824	Acer macrophyllum (Bigleaf maple)	D	5	32	80	30	3	N	additional DBH-7"
825	Crataegus monogyna (Common hawthorn)	D	2	7	25	15	3	N	not on survey
826	Prunus emarginata (Bitter cherry)	D	1	7	40	10	3	N	not on survey
827	Pinus nigra (Austrian pine)	E	1	21	50	12	4	N	co-dominant at 20'; included bark; low LCR
828	Pinus sylvestris (Scots pine)	E	1	18	65	20	3	N	
829	Acer macrophyllum (Bigleaf maple)	D	1	14	15	20	4	Y	co-dominant at 10'; topped at 15' for power lines
830	Betula pendula (European white birch)	D	2	25	65	25	3	Y	
831	Pinus sylvestris (Scots pine)	E	1	21	70	16	3	Y	co-dominant at 15'; included bark; circling root
832	Arbutus menziesii (Pacific madrone)	E	2	8	25	15	3	Y	
833	Acer macrophyllum (Bigleaf maple)	D	1	10	50	20	3	Y	pistol-butt trunk
842	Thuja plicata (Western red cedar)	E	1	1	10	2	2	N	
843	Pseudotsuga menziesii (Douglas-fir)	E	1	1	8	3	3	N	se lean, self corrected
844	xHesperotropis leylandii (Leyland cypress)	E	1	4	20	6	3	N	
845	xHesperotropis leylandii (Leyland cypress)	E	1	4	15	5	3	N	
846	xHesperotropis leylandii (Leyland cypress)	E	1	4	15	5	4	N	topped at 10'
847	xHesperotropis leylandii (Leyland cypress)	E	1	2	15	6	3	N	
848	xHesperotropis leylandii (Leyland cypress)	E	1	3	18	5	3	N	
849	xHesperotropis leylandii (Leyland cypress)	E	1	3	15	5	3	N	
850	xHesperotropis leylandii (Leyland cypress)	E	1	3	18	5	2	N	
851	xHesperotropis leylandii (Leyland cypress)	E	1	1	15	4	3	N	
852	xHesperotropis leylandii (Leyland cypress)	E	1	3	20	5	3	N	

A TREE INVENTORY TABLE (4 OF 7)

Scale: NTS

THE WATERSHED COMPANY
MERCER ISLAND CHIU
4320 Island Crest Way, Mercer Island, WA 98040 Site Visit: 5/16/2017 and 8/24/2017
parcel # 1824059031
Table Issued: 4/9/2018

TAG #	TREE NAME	EV / DEC	# STEMS	COMB DBH (IN, ROUNDED)	HEIGHT (FT)	RADIUS (FT)	CONDITION	REMOVE (Y/N)	NOTES
853	xHesperotropis leylandii (Leyland cypress)	E	1	3	20	5	3	N	
854	xHesperotropis leylandii (Leyland cypress)	E	1	4	20	8	3	N	
855	xHesperotropis leylandii (Leyland cypress)	E	1	3	18	6	3	N	
856	xHesperotropis leylandii (Leyland cypress)	E	1	3	15	6	3	N	
857	xHesperotropis leylandii (Leyland cypress)	E	1	3	15	5	3	N	
858	xHesperotropis leylandii (Leyland cypress)	E	1	4	20	7	3	N	
859	xHesperotropis leylandii (Leyland cypress)	E	1	2	20	6	3	N	
860	xHesperotropis leylandii (Leyland cypress)	E	1	1	15	6	3	N	
861	xHesperotropis leylandii (Leyland cypress)	E	1	1	12	4	3	N	
862	xHesperotropis leylandii (Leyland cypress)	E	1	2	14	4	3	N	
863	xHesperotropis leylandii (Leyland cypress)	E	1	2	18	5	3	N	
864	xHesperotropis leylandii (Leyland cypress)	E	1	1	13	3	3	N	
865	xHesperotropis leylandii (Leyland cypress)	E	1	1	12	3	3	N	
866	xHesperotropis leylandii (Leyland cypress)	E	1	1	13	4	3	N	
867	xHesperotropis leylandii (Leyland cypress)	E	1	1	10	5	3	N	suppressed
869	xHesperotropis leylandii (Leyland cypress)	E	1	1	8	4	3	N	
870	xHesperotropis leylandii (Leyland cypress)	E	1	1	10	3	3	N	suppressed
871	xHesperotropis leylandii (Leyland cypress)	E	1	1	11	4	3	N	
872	xHesperotropis leylandii (Leyland cypress)	E	1	2	10	6	3	N	suppressed
873	xHesperotropis leylandii (Leyland cypress)	E	1	2	14	5	3	N	
874	xHesperotropis leylandii (Leyland cypress)	E	1	4	20	8	3	N	
875	xHesperotropis leylandii (Leyland cypress)	E	1	2	20	6	3	N	
876	xHesperotropis leylandii (Leyland cypress)	E	1	4	20	5	3	N	
877	xHesperotropis leylandii (Leyland cypress)	E	1	3	20	9	3	N	
878	xHesperotropis leylandii (Leyland cypress)	E	1	4	20	7	3	N	
879	xHesperotropis leylandii (Leyland cypress)	E	1	4	22	5	3	N	
880	xHesperotropis leylandii (Leyland cypress)	E	1	4	20	6	3	N	
881	xHesperotropis leylandii (Leyland cypress)	E	1	4	6	6	3	N	
882	xHesperotropis leylandii (Leyland cypress)	E	1	4	20	6	3	N	
883	xHesperotropis leylandii (Leyland cypress)	E	1	2	17	8	3	N	
884	xHesperotropis leylandii (Leyland cypress)	E	1	2	15	5	4	N	chlorotic foliage
885	xHesperotropis leylandii (Leyland cypress)	E	1	4	15	6	3	N	
886	xHesperotropis leylandii (Leyland cypress)	E	1	2	12	6	4	N	chlorotic foliage
887	xHesperotropis leylandii (Leyland cypress)	E	1	2	17	5	3	N	
888	xHesperotropis leylandii (Leyland cypress)	E	1	3	15	5	3	N	
889	xHesperotropis leylandii (Leyland cypress)	E	1	4	15	10	3	N	
890	xHesperotropis leylandii (Leyland cypress)	E	1	1	10	3	3	N	
891	xHesperotropis leylandii (Leyland cypress)	E	1	1	10	5	3	N	
892	xHesperotropis leylandii (Leyland cypress)	E	1	1	10	4	3	N	
893	xHesperotropis leylandii (Leyland cypress)	E	1	1	13	3	3	N	
894	xHesperotropis leylandii (Leyland cypress)	E	1	4	18	5	3	N	

B TREE INVENTORY TABLE (5 OF 7)

Scale: NTS

THE WATERSHED COMPANY
MERCER ISLAND CHIU
4320 Island Crest Way, Mercer Island, WA 98040 Site Visit: 5/16/2017 and 8/24/2017
parcel # 1824059031
Table Issued: 4/9/2018

TAG #	TREE NAME	EV / DEC	# STEMS	COMB DBH (IN, ROUNDED)	HEIGHT (FT)	RADIUS (FT)	CONDITION	REMOVE (Y/N)	NOTES
895	xHesperotropis leylandii (Leyland cypress)	E	1	3	13	5	3	N	
896	xHesperotropis leylandii (Leyland cypress)	E	1	3	18	6	3	N	
897	xHesperotropis leylandii (Leyland cypress)	E	1	3	20	7	3	N	
898	xHesperotropis leylandii (Leyland cypress)	E	1	3	20	5	3	N	
899	xHesperotropis leylandii (Leyland cypress)	E	1	2	18	5	3	N	
900	xHesperotropis leylandii (Leyland cypress)	E	1	3	20	5	3	N	
968	xHesperotropis leylandii (Leyland cypress)	E	1	1	12	6	3	N	
969	xHesperotropis leylandii (Leyland cypress)	E	1	3	15	6	3	N	
970	xHesperotropis leylandii (Leyland cypress)	E	1	2	20	6	3	N	
971	xHesperotropis leylandii (Leyland cypress)	E	1	3	20	6	3	N	
972	xHesperotropis leylandii (Leyland cypress)	E	1	3	20	6	4	N	sig trunk wound on ne side
973	xHesperotropis leylandii (Leyland cypress)	E	1	3	20	7	3	N	
974	xHesperotropis leylandii (Leyland cypress)	E	1	2	15	6	3	N	
975	xHesperotropis leylandii (Leyland cypress)	E	1	3	18	6	4	N	trunk wound on ne side
976	xHesperotropis leylandii (Leyland cypress)	E	1	2	15	6	3	N	
977	xHesperotropis leylandii (Leyland cypress)	E	1	3	14	6	4	N	trunk wounds
978	xHesperotropis leylandii (Leyland cypress)	E	1	2	15	6	3	N	
979	xHesperotropis leylandii (Leyland cypress)	E	1	3	13	8	3	N	
980	xHesperotropis leylandii (Leyland cypress)	E	1	3	22	7	3	N	
981	xHesperotropis leylandii (Leyland cypress)	E	1	4	20	8	3	N	
982	xHesperotropis leylandii (Leyland cypress)	E	1	3	20	8	3	N	
983	xHesperotropis leylandii (Leyland cypress)	E	1	2	17	6	3	N	
984	xHesperotropis leylandii (Leyland cypress)	E	1	4	22	8	3	N	
985	xHesperotropis leylandii (Leyland cypress)	E	1	3	21	6	3	N	
986	xHesperotropis leylandii (Leyland cypress)	E	1	4	20	6	3	N	
987	xHesperotropis leylandii (Leyland cypress)	E	1	2	15	6	3	N	
988	xHesperotropis leylandii (Leyland cypress)	E	1	3	18	7	3	N	
989	xHesperotropis leylandii (Leyland cypress)	E	1	1	12	4	4	N	suppressed
990	xHesperotropis leylandii (Leyland cypress)	E	2	1	9	4	4	N	
991	xHesperotropis leylandii (Leyland cypress)	E	1	1	8	6	4	N	
992	xHesperotropis leylandii (Leyland cypress)	E	1	1	7	4	4	N	
993	xHesperotropis leylandii (Leyland cypress)	E	1	3	15	6	3	N	
994	xHesperotropis leylandii (Leyland cypress)	E	1	2	15	6	3	N	
995	xHesperotropis leylandii (Leyland cypress)	E	1	3	20	6	3	N	
996	xHesperotropis leylandii (Leyland cypress)	E	1	3	13	6	3	N	
997	xHesperotropis leylandii (Leyland cypress)	E	1	3	20	7	3	N	
998	xHesperotropis leylandii (Leyland cypress)	E	1	3	20	7	3	N	
999	xHesperotropis leylandii (Leyland cypress)	E	2	2	15	6	3	N	
1000	xHesperotropis leylandii (Leyland cypress)	E	2	3	15	6	3	N	
1001	xHesperotropis leylandii (Leyland cypress)	E	1	3	20	6	3	N	
1002	xHesperotropis leylandii (Leyland cypress)	E	1	3	25	8	3	N	

C TREE INVENTORY TABLE (6 OF 7)

Scale: NTS



TREE INVENTORY TABLES 4-6

NFC
NOT FOR
CONSTRUCTION

SHEET SIZE:
ORIGINAL PLAN IS 22" x 34".
SCALE ACCORDINGLY.

PROJECT MANAGER: MD
DESIGNED: LV, RH
DRAFTED: LV, RH
CHECKED: LV, AM
JOB NUMBER:
160905
SHEET NUMBER:
W4.2 OF 14

MERCERTECH INTERNATIONAL LLC
LONG PLAT MITIGATION AND RESTORATION PLAN
PREPARED FOR ALAN CHIU
PARCEL # 1824059031
4320 ISLAND CREST WAY
MERCER ISLAND, WA 98040


SUBMITTALS & REVISIONS	
NO.	DESCRIPTION
1	08/29/17 30% SUBMITTAL - PREAPP
2	10/17/17 30% SUBMITTAL - PREAPP 2
3	10/27/17 30% SUBMITTAL - APPLICATION
4	04/18/18 CITY COMMENT RESPONSE

BY	DATE
LV	
RH	
RH	
RH	


MERCER ISLAND CHIU Table Issued: 4/9/2018
4320 Island Crest Way, Mercer Island, WA 98040 Site Visit: 5/16/2017 and 8/24/2017
parcel # 1824059031

TAG #	TREE NAME	BY / DEC	# STEMS	FORM DBH (IN ROUNDED)	HEIGHT (FT)	RADIUS (FT)	FOUNDATION	REMOVE (Y/N)	NOTES
1003	*Hesperotropsis leylandii (Leyland cypress)	E	2	3	17	6	3	N	
1004	*Hesperotropsis leylandii (Leyland cypress)	E	1	3	20	6	3	N	
1005	*Hesperotropsis leylandii (Leyland cypress)	E	1	3	20	6	3	N	
1006	*Hesperotropsis leylandii (Leyland cypress)	E	1	2	20	6	3	N	
1007	*Hesperotropsis leylandii (Leyland cypress)	E	1	2	13	5	3	N	
1008	*Hesperotropsis leylandii (Leyland cypress)	E	1	2	15	5	3	N	
1009	*Hesperotropsis leylandii (Leyland cypress)	E	1	1	10	4	3	N	
1010	*Hesperotropsis leylandii (Leyland cypress)	E	1	1	7	3	4	N	
1011	*Hesperotropsis leylandii (Leyland cypress)	E	1	1	12	4	3	N	
1012	*Hesperotropsis leylandii (Leyland cypress)	E	1	1	6	5	4	N	trunk wound
1013	*Hesperotropsis leylandii (Leyland cypress)		1	0	6	3	4	N	trunk wound


A TREE INVENTORY TABLE (7 OF 7) Scale: NTS



C TREE PROTECTION FENCING Scale: NTS



B TREE TRUNK WRAP Scale: NTS



D LARGE WOODY DEBRIS Scale: NTS



NFC
NOT FOR CONSTRUCTION

TREE INVENTORY TABLE 7 AND TREE PRESERVATION DETAILS

TESC NOTES - ALL AREAS

1. CONTRACTOR TO VERIFY TEMPORARY HIGH VISIBILITY FENCE IS INSTALLED AROUND THE LIMITS OF WORK PRE-CONSTRUCTION.
2. SEE SHEETS W4.0-4.3 FOR TREE PRESERVATION INFORMATION.
3. SURVEY AND STAKE THE LIMITS OF WETLAND BUFFER ENHANCEMENT AREA PRE-CONSTRUCTION.
4. INSTALL SILT FENCE AND FIBER ROLL AS SHOWN ON THIS SHEET. MITIGATION CONTRACTOR SHALL COORDINATE WITH OTHER CONTRACTORS AS NEEDED TO ASSURE PROPER TESC MEASURES ARE IN-PLACE.

SOIL PREPARATION NOTES - WETLAND RESTORATION PLANTING AREAS

1. REMOVE ALL WOOD CHIPS PLACED IN WETLAND AND DISPOSE OF OFF-SITE. WOOD CHIP REMOVAL IS TO BE DONE WITHOUT MECHANIZED TOOLS.
2. REMOVE INVASIVE PLANT SPECIES AS SPECIFIED IN INVASIVE SPECIES REMOVAL NOTES ON W5.1.
3. PLANT PER W7.0-W7.2.
4. INSTALL MULCH RINGS 4" DEEP WITH RADIUS OF 18" FROM PLANT STEM. SEE PLANTING PLAN FOR PLANT TYPE AND SPACING.

SOIL PREPARATION NOTES - WETLAND BUFFER PLANTING AREAS

1. REMOVE INVASIVE PLANT SPECIES AS SPECIFIED ON W5.1.
2. BACKFILL ANY DIVOTS WITH TOPSOIL TO RETURN TO EXISTING GRADE.
3. PLANT PER W7.0-7.2.
4. INSTALL MULCH RINGS 4" DEEP WITH RADIUS OF 18" FROM PLANT STEM. SEE PLANTING PLAN FOR PLANT TYPE AND SPACING.

LEGEND

- EXISTING FEATURES**
- EXISTING CONTOUR
 - WETLAND BOUNDARY (DELINEATED)
 - WATERCOURSE BOUNDARY (DELINEATED)
 - WATERCOURSE BOUNDARY (APPROX.)
 - EXISTING TREE
- PROPOSED FEATURES**
- PROPOSED CONTOUR (WETLAND CREATION AREA)
 - WETLAND/WATERCOURSE BUFFER (50 FT)
 - REDUCED COMBINED WETLAND/WATERCOURSE BUFFER (25 FT)
 - WETLAND CREATION AREA (2,305 SF)
 - WETLAND RESTORATION AREA (24,670 SF)
 - BUFFER MITIGATION AREA (21,080 SF)
 - FIBER ROLL
 - SILT FENCE



MERCERTECH INTERNATIONAL LLC
LONG PLAT MITIGATION AND RESTORATION PLAN
PREPARED FOR ALAN CHIU
PARCEL # 1824059031
4320 ISLAND CREST WAY
MERCER ISLAND, WA 98040

SUBMITTALS & REVISIONS	
NO.	DESCRIPTION
1	08/29/17 30% SUBMITTAL - PREAPP
2	10/17/17 30% SUBMITTAL - PREAPP 2
3	10/27/17 30% SUBMITTAL - APPLICATION
4	04/18/18 CITY COMMENT RESPONSE

SHEET SIZE:
ORIGINAL PLAN IS 22" x 34".
SCALE ACCORDINGLY.

PROJECT MANAGER: MD
DESIGNED: LV, RH
DRAFTED: LV, RH
CHECKED: LV, AM
JOB NUMBER:
160905
SHEET NUMBER:
W5.0 OF 14

NFC
NOT FOR
CONSTRUCTION

TESC AND SITE PREPARATION PLAN



MERCERTECH INTERNATIONAL LLC
LONG PLAT MITIGATION AND RESTORATION PLAN
PREPARED FOR ALAN CHIU
PARCEL # 1824059031
4320 ISLAND CREST WAY
MERCER ISLAND, WA 98040

SUBMITTALS & REVISIONS	
NO.	DESCRIPTION
1	08/29/17 30% SUBMITTAL - PREAPP
2	10/17/17 30% SUBMITTAL - PREAPP 2
3	10/27/17 30% SUBMITTAL - APPLICATION
4	04/18/18 CITY COMMENT RESPONSE

SHEET SIZE:
ORIGINAL PLAN IS 22" x 34".
SCALE ACCORDINGLY.

PROJECT MANAGER: MD
DESIGNED: LV, RH
DRAFTED: LV, RH
CHECKED: LV, AM
JOB NUMBER:
160905
SHEET NUMBER:
W7.0 OF 14

FILENAME: 160905 MERCER ISLAND CHIU MITIGATION PLANTING
DATE PRINTED BY: RCHEN/HOF/ELD



LEGEND

- EXISTING FEATURES
- EXISTING CONTOUR
- WETLAND BOUNDARY (DELINEATED)
- WATERCOURSE BOUNDARY (DELINEATED)
- WATERCOURSE BOUNDARY (APPROX.)
- EXISTING TREE
- PROPOSED FEATURES
- 284 PROPOSED CONTOUR
- WETLAND/WATERCOURSE AREA BUFFER (50 FT)
- REDUCED WETLAND/WATERCOURSE BUFFER (25 FT)
- WETLAND CREATION PLANTING (2,305SF)
- WETLAND RESTORATION PLANTING (24,670 SF)
- BUFFER MITIGATION PLANTING (21,080 SF)


NOTES

1. SEE SHEET W7.1 FOR PLANTING SCHEDULE.



NFC
NOT FOR CONSTRUCTION

PLANTING PLAN



MERCERTECH INTERNATIONAL LLC
LONG PLAT MITIGATION AND RESTORATION PLAN
PREPARED FOR ALAN CHIU
PARCEL # 1824059031
4320 ISLAND CREST WAY
MERCER ISLAND, WA 98040

SUBMITTALS & REVISIONS	
NO.	DESCRIPTION
1	08-29-17 30% SUBMITTAL - PREAPP
2	10/17/17 30% SUBMITTAL - PREAPP 2
3	10/27/17 30% SUBMITTAL - APPLICATION
4	04/18/18 CITY COMMENT RESPONSE 1

DATE	BY
08-29-17	LV
10/17/17	RH
10/27/17	RH
04/18/18	RH

WETLAND CREATION CANDIDATE PLANT SCHEDULE (2,305 SF)

TREES*	QTY	SPACING	SIZE	NOTE
ALNUS RUBRA / RED ALDER	3	9' O.C.	2 GAL.	ALL PLANTS TO BE FULL AND WELL ROOTED
PICEA SITCHENSIS / SITKA SPRUCE	3	9' O.C.	2 GAL.	
THUJA PLICATA / WESTERN REDCEDAR	4	9' O.C.	2 GAL.	
SHRUBS				
CORNUS SERICEA / REDTWIG DOGWOD	10	6' O.C.	1 GAL.	ALL PLANTS TO BE FULL AND WELL ROOTED
PHYSCARPUS CAPITATUS / PACIFIC NINEBARK	10	6' O.C.	1 GAL.	
RUBUS SPECTABILIS / SALMONBERRY	10	6' O.C.	1 GAL.	
GROUNDCOVER** **SPECIES TO BE PLACED IN GROUPS OF 9 - 15 AND SPACED TRIANGULARLY				ALL PLANTS TO BE FULL AND WELL ROOTED
CAREX OBNUPTA / SLOUGH SEDGE	165	24" O.C.	4" POT	
JUNCUS EFFUSUS / SOFT RUSH	165	24" O.C.	4" POT	
SCIRPUS MICROCARPUS / SMALL-FRUITED BULRUSH	165	24" O.C.	4" POT	

WETLAND RESTORATION CANDIDATE PLANT SCHEDULE (24,670 SF)

TREES*	QTY	SPACING	SIZE	NOTE
SALIX LUCIDA / PACIFIC WILLOW	31	9' O.C.	6' TALL	ALL PLANTS TO BE FULL AND WELL ROOTED
SALIX SITCHENSIS / SITKA WILLOW	30	9' O.C.	2 GAL.	
PICEA SITCHENSIS / SITKA SPRUCE	31	9' O.C.	6' TALL	
PRUNUS EMARGINATA / BITTER CHERRY	31	9' O.C.	6' TALL	
THUJA PLICATA / WESTERN REDCEDAR	31	9' O.C.	6' TALL	ALL PLANTS TO BE FULL AND WELL ROOTED
SHRUBS				
CORNUS SERICEA / REDTWIG DOGWOD	90	6' O.C.	1 GAL.	
PHYSCARPUS CAPITATUS / PACIFIC NINEBARK	90	6' O.C.	1 GAL.	ALL PLANTS TO BE FULL AND WELL ROOTED
ROSA PISOCARPA / CLUSTER ROSE	90	6' O.C.	1 GAL.	
SPIRAEA DOUGLASII / HARDHACK	90	6' O.C.	1 GAL.	

BUFFER MITIGATION CANDIDATE PLANT SCHEDULE (21,080 SF)

TREES*	QTY	SPACING	SIZE	NOTE
ACER MACROPHYLLUM / BIG-LEAF MAPLE	35	9' O.C.	2 GAL.	ALL PLANTS TO BE FULL AND WELL ROOTED
PSEUDOTSUGA MENZIESII / DOUGLAS-FIR	35	9' O.C.	2 GAL.	
TSUGA HETEROPHYLLA / WESTERN HEMLOCK	35	9' O.C.	2 GAL.	
SHRUBS				ALL PLANTS TO BE FULL AND WELL ROOTED
OEMLERIA CERASIFORMIS / OSOBERRY	75	6' O.C.	1 GAL.	
SAMBUCUS RACEMOSA / RED ELDERBERRY	75	6' O.C.	1 GAL.	
CORYLUS CORNUTA / BEAKED HAZELNUT	75	6' O.C.	1 GAL.	
RUBUS SPECTABILIS / SALMONBERRY	75	6' O.C.	1 GAL.	ALL PLANTS TO BE FULL AND WELL ROOTED
GROUNDCOVER** **SPECIES TO BE PLACED IN GROUPS OF 9 - 15 AND SPACED TRIANGULARLY				
FRAGARIA CHILOENSIS / COASTAL STRAWBERRY	600	3' O.C.	4" POT	
POLYSTICHUM MUNITUM / WESTERN SWORDFERN	600	3' O.C.	4" POT	
MAHONIA NERVOSA / LOW OREGON GRAPE	600	3' O.C.	4" POT	



NFC
NOT FOR CONSTRUCTION

TYPICAL PLANTING SCHEDULES

MITIGATION / RESTORATION SPECIFICATIONS

PROJECT SUMMARY

THIS PLAN HAS BEEN PREPARED 1) TO RESTORE PREVIOUSLY ALTERED AREAS SUBJECT TO A NOTICE OF CORRECTION AND 2) TO MITIGATE WETLAND AND WATERCOURSE BUFFER IMPACTS ASSOCIATED WITH THE PROPOSED SUBDIVISION.

THE NOTICE OF CORRECTION INDICATED THAT FILL MATERIAL SUCH AS WOOD CHIPS HAD BEEN PLACED ON THE SUBJECT PROPERTY, AND THAT TREES AND SHRUBBY VEGETATION HAVE BEEN CLEARED OVER TIME. THE AREA SUBJECT TO THE NOTICE OF CORRECTION APPEARS TO HAVE BEEN APPLIED TO APPROXIMATELY 12,748 SQUARE FEET OF THE SUBJECT PROPERTY. RESTORATION OF THE AREA SUBJECT TO THE NOTICE OF CORRECTION INCLUDES REMOVAL OF THE WOOD CHIPS AND NON-NATIVE AND INVASIVE PLANT SPECIES, AND THE INSTALLATION OF A NATIVE TREE, SHRUB AND GROUNDCOVER PLANT COMMUNITY.

THE PROJECT PROPOSES BUFFER REDUCTION WITH ENHANCEMENT IN AREAS ADJACENT TO THE PROPOSED RESIDENTIAL DEVELOPMENT. ENHANCEMENT OF THE EXISTING DEGRADED BUFFER AREAS WILL INCLUDE THE REMOVAL OF NON-NATIVE AND INVASIVE SPECIES, AND THE INSTALLATION OF A NATIVE TREE, SHRUB AND GROUNDCOVER PLANT COMMUNITY.

THE PROPOSED BUFFER REDUCTION INCLUDES 1,988 SQUARE FEET OF WETLAND AS BUFFER. TO MITIGATE FOR THE WETLAND AS BUFFER, THE CREATION OF 2,305 SQUARE FEET OF WETLAND IS PROPOSED. THE WETLAND CREATION AREA WILL BE PLANTED WITH A NATIVE TREE, SHRUB AND EMERGENT PLANT COMMUNITY.

WORK SEQUENCE (SEE MATERIALS SECTION FOR MATERIAL INFORMATION)

A RESTORATION SPECIALIST SHALL MAKE SITE VISITS TO VERIFY THE FOLLOWING PROJECT MILESTONES:

1. BEFORE BEGINNING CONSTRUCTION WORK, ESTABLISH AND DEFINE THE WORK AREA. IDENTIFY AND DEMARCATATE THE LIMITS OF PROJECT GRADING AND CLEARING WITH HIGH VISIBILITY FENCING OR SIMILAR MEANS.
2. INSTALL TEMPORARY EROSION CONTROL MEASURES AS IDENTIFIED ON THE TESC PLANS.
3. CLEAR AND GRUB THE MITIGATION AND RESTORATION AREAS. CLEARING AND GRUBBING IN WETLAND AND WATERCOURSE AREAS TO BE PERFORMED USING HAND TOOLS ONLY. INVASIVE SPECIES AREA TO BE REMOVED FROM ENTIRE SITE.
4. REMOVE PREVIOUSLY PLACED WOOD CHIPS FROM VIOLATION AREA. REMOVAL TO BE PERFORMED USING HAND TOOLS ONLY.
5. SURVEY AND PAINT PROPOSED 1-FOOT CONTOURS AND STAKE CUT/FILL DEPTHS WITHIN THE WETLAND CREATION AREA BASED ON THE APPROVED PLAN SET.
6. EXCAVATE AS NECESSARY TO TIE INTO THE SURROUNDING GRADE AND CREATE WETLAND TOPOGRAPHY. ALL EXCAVATED MATERIAL NOT NEEDED FOR RE-USE IS TO BE DISPOSED OF OFFSITE. OVER-EXCAVATION MAY BE RECOMMENDED TO ACCOMMODATE THE PLACEMENT OF TOPSOIL AND/OR COMPOST AMENDMENTS. EQUIPMENT USED TO CONDUCT EXCAVATION WOULD LIKELY INCLUDE TRACKED EXCAVATORS AND DUMP TRUCKS.
7. UNDER THE DIRECTION OF THE RESTORATION SPECIALIST, PERFORM FINISHING TOUCHES ON THE WETLAND AND RESTORATION AREAS. COMPLETE ANY ADDITIONAL TOUCH-UP WORK AS DIRECTED.
8. PRIOR TO FINISH GRADING, THE RESTORATION SPECIALIST SHALL INSPECT THE SOIL CONDITION AND DETERMINE IF SOIL AMENDMENTS OTHER THAN COMPOST ARE NECESSARY.
9. INCORPORATE 5 INCHES OF COMPOST INTO THE FINISH GRADE OF THE WETLAND CREATION AREA. SEE SHEET W3 FOR SOIL PREPARATION NOTES.
10. INCORPORATE 3 INCHES OF COMPOST INTO THE FINISH GRADE OF THE BUFFER AREAS, INCLUDING THE RESTORED PORTION OF THE CONSTRUCTION ACCESS AREAS. SEE SHEET W3 FOR SOIL PREPARATION NOTES.
11. LAYOUT PLANTS PER SEQ W7
12. INSTALL NATIVE PLANTS PER PLANTING DETAILS ON SHEET W8.

- A. NATIVE PLANT INSTALLATION SHALL OCCUR DURING THE DORMANT SEASON (OCTOBER 15TH THROUGH MARCH 1ST) IN FROST-FREE PERIODS ONLY.

- B. LAYOUT PLANT MATERIAL PER PLAN FOR INSPECTION BY THE RESTORATION SPECIALIST. PLANT SUBSTITUTIONS WILL NOT BE ALLOWED WITHOUT PRIOR WRITTEN APPROVAL OF THE RESTORATION SPECIALIST.
 - C. INSTALL PLANTS PER PLANTING DETAILS
13. WATER EACH PLANT THOROUGHLY TO REMOVE AIR POCKETS.
 14. INSTALL A TEMPORARY IRRIGATION SYSTEM CAPABLE OF SUPPLYING AT LEAST 1-INCH OF WATER PER WEEK TO THE ENTIRE PLANTED AREA OUTSIDE WETLAND DURING THE DRY SEASON (JUNE 1ST THROUGH SEPTEMBER 30TH).
 15. ONE YEAR AFTER INITIAL PLANTING, APPLY A SLOW-RELEASE, PHOSPHOROUS-FREE, GRANULAR FERTILIZER TO EACH INSTALLED PLANT.
 16. PLANT GROUNDCOVERS IN WETLAND RESTORATION AREA IN YEAR 3 AFTER INVASIVE PLANTS HAVE BEEN SUCCESSFULLY MANAGED.

MAINTENANCE

THE SITE SHALL BE MAINTAINED FOR FIVE YEARS FOLLOWING SUCCESSFUL INSTALLATION.

1. REPLACE EACH PLANT FOUND DEAD IN THE SUMMER MONITORING VISITS IN THE FOLLOWING DORMANT SEASON (OCTOBER 15 - MARCH 1). REPLACEMENT SHALL BE OF THE SAME SPECIES AND SIZE PER PLAN UNLESS OTHERWISE APPROVED BY THE RESTORATION SPECIALIST.
2. GENERAL WEEDING FOR ALL PLANTED AREAS
 - A. AT LEAST TWICE ANNUALLY, REMOVE COMPETING GRASSES AND WEEDS FROM AROUND THE BASE OF EACH INSTALLED PLANT TO A RADIUS OF 12 INCHES. WEEDING SHOULD OCCUR AT LEAST ONCE IN THE SPRING AND ONCE IN THE SUMMER. THOROUGH WEEDING WILL RESULT IN LOWER PLANT MORTALITY AND ASSOCIATED PLANT REPLACEMENT COSTS.
 - B. MORE FREQUENT WEEDING MAY BE NECESSARY DEPENDING ON WEED CONDITIONS THAT DEVELOP AFTER PLANT INSTALLATION.
 - C. NOXIOUS WEEDS MUST BE REMOVED FROM THE ENTIRE MITIGATION AREA, AT LEAST TWICE ANNUALLY.
 - D. DO NOT USE STRING TRIMMERS IN THE VICINITY OF INSTALLED PLANTS, AS THEY MAY DAMAGE OR KILL THE PLANTS.
3. MAINTAIN A FOUR-INCH-THICK LAYER OF WOODCHIP MULCH ACROSS THE ENTIRE BUFFER MITIGATION PLANTING AREA. MULCH SHOULD BE PULLED BACK TWO INCHES FROM THE PLANT STEMS. 4. INSPECT AND REPAIR THE IRRIGATION SYSTEM AS NECESSARY EACH SPRING. DURING AT LEAST THE FIRST TWO GROWING SEASONS, MAKE SURE THAT THE ENTIRE PLANTING AREA RECEIVES A MINIMUM OF ONE INCH OF WATER PER WEEK FROM JUNE 1ST THROUGH SEPTEMBER 30TH.

GOALS

1. RESTORE 24,670 SQUARE FEET OF DEGRADED WETLAND AREA.
 - A. CREATE A DENSE, NATIVE TREE AND SHRUB COMMUNITY.
 - B. REMOVE NON-NATIVE AND INVASIVE PLANT SPECIES FROM THE WETLAND RESTORATION AREA.
2. ENHANCE 21,080 SQUARE FEET OF DEGRADED BUFFER AREA.
 - A. CREATE A DENSE, NATIVE TREE AND SHRUB COMMUNITY.
 - B. REMOVE NON-NATIVE AND INVASIVE PLANT SPECIES FROM THE ENTIRE SITE.
3. CREATE 2,303 SQUARE FEET OF ADDITIONAL WETLAND AREA.
 - A. CREATE A DENSE, NATIVE SHRUB AND EMERGENT COMMUNITY.
 - B. REMOVE NON-NATIVE AND INVASIVE PLANT SPECIES FROM THE WETLAND CREATION AREA.
4. RE-ESTABLISH HISTORIC STREAM/WETLAND CONDITIONS BY DAYLIGHTING PIPED WATERCOURSE AND REMOVING DRIVEWAY.

PERFORMANCE STANDARDS

THE FOLLOWING PERFORMANCE STANDARDS WILL BE USED TO GAUGE THE SUCCESS OF THE PROJECT OVER TIME. IF ALL PERFORMANCE STANDARDS HAVE BEEN SATISFIED BY THE END OF YEAR FIVE, THE PROJECT SHALL BE CONSIDERED COMPLETE AND THE CITY OF MERCER ISLAND SHALL RELEASE THE PERFORMANCE BOND (IF REQUIRED).

1. SURVIVAL:
 - A. ACHIEVE 100% SURVIVAL OF INSTALLED PLANTS BY THE END OF YEAR 1.
 - B. ACHIEVE 80% SURVIVAL OF INSTALLED WOODY PLANTS BY THE END OF YEAR 2.

THIS STANDARD CAN BE MET THROUGH PLANT ESTABLISHMENT OR THROUGH REPLANTING AS NECESSARY TO ACHIEVE THE REQUIRED NUMBERS.
2. COVER:
 - A. ACHIEVE 60% COVER OF NATIVE TREES AND SHRUBS BY YEAR 3 WITHIN PLANTED WETLAND AND BUFFER AREAS. VOLUNTEER SPECIES MAY COUNT TOWARDS THIS COVER STANDARD.
 - B. ACHIEVE 10% COVER OF NATIVE EMERGENT PLANTS WITHIN THE CREATED WETLAND AREA BY YEAR 3.
 - C. ACHIEVE 80% COVER OF NATIVE TREES AND SHRUBS BY YEAR 5 WITHIN PLANTED WETLAND AND BUFFER AREAS. VOLUNTEER SPECIES MAY COUNT TOWARDS THIS COVER STANDARD.
 - D. ACHIEVE 30% COVER OF NATIVE EMERGENT PLANTS WITHIN WETLAND AREAS BY YEAR 5.
3. DIVERSITY:
 - A. ESTABLISH AT LEAST THREE NATIVE TREE SPECIES, FIVE NATIVE SHRUB SPECIES, AND TWO NATIVE GROUNDCOVERS WITHIN THE WETLAND RESTORATION AND BUFFER MITIGATION AREAS. VOLUNTEER SPECIES MAY COUNT TOWARDS THIS STANDARD.
 - B. ESTABLISH AT LEAST TWO NATIVE TREE SPECIES, THREE NATIVE SHRUB SPECIES, AND TWO NATIVE GROUNDCOVERS WITHIN THE WETLAND CREATION AREA.

ESTABLISHMENT IS DEFINED AS FIVE OR MORE INDIVIDUAL PLANTS OF THE SAME SPECIES ALIVE AND HEALTHY.
4. INVASIVE COVER: NO MORE THAN 10% COVER BY INVASIVE WEED SPECIES WITHIN ALL PLANTED AREAS IN ANY MONITORING YEAR.
5. HYDROLOGY STANDARD (WETLAND CREATION AREA ONLY):
 - A. EVIDENCE OF WETLAND HYDROLOGY IN THE WETLAND CREATION AREA. SOIL SATURATION WITHIN THE UPPER 12 INCHES OF THE SOIL SURFACE, PRESENT FOR TWO CONSECUTIVE WEEKS DURING THE GROWING SEASON (MARCH 1ST TO OCTOBER 15TH) DURING EACH MONITORING YEAR AS MEASURED PER THE PROTOCOL IN THE MONITORING METHODS SECTION, BELOW.
 - B. HYDRIC SOILS WILL BE ASSUMED PRESENT IF THE HYDROLOGY STANDARD IS MET.

MONITORING

PRIOR TO THE COMMENCEMENT OF THE MONITORING PHASE, AN AS-BUILT PLAN DOCUMENTING THE SUCCESSFUL INSTALLATION OF THE PROJECT WILL BE SUBMITTED TO THE CITY OF MERCER ISLAND. IF NECESSARY, THE AS-BUILT REPORT MAY INCLUDE A MARK-UP OF THE ORIGINAL PLAN THAT NOTES ANY SIGNIFICANT CHANGES OR SUBSTITUTIONS THAT OCCURRED. DURING THE AS-BUILT INSPECTION, THE RESTORATION SPECIALIST WILL ESTABLISH AT LEAST FOUR PERMANENT PHOTO-POINTS.

DURING THE AS-BUILT INSPECTION, THE RESTORATION SPECIALIST SHALL INSTALL AT LEAST TWO REPRESENTATIVELY LOCATED SHALLOW GROUNDWATER WELLS IN THE WETLAND CREATION AREA. GROUNDWATER WELLS SHALL BE INSTALLED TO A MINIMUM DEPTH OF 24 INCHES. WELLS TO BE CONSTRUCTED OF 2-INCH DIAMETER PVC PIPE WITH CAPS. BELOW GROUND PORTIONS ARE TO BE PERFORATED WITH ¼" HOLES SPACED NO FARTHER THAN ½" APART. ALTERNATIVELY, AUTOMATED GROUNDWATER MONITORING DATA LOGGING DEVICES MAY BE USED IN-LIEU OF MANUALLY MONITORED WELLS.

THE SITE WILL BE MONITORED TWICE ANNUALLY FOR FIVE YEARS BEGINNING WITH APPROVAL OF THE AS-BUILT REPORT. EACH SPRING THE RESTORATION SPECIALIST WILL CONDUCT A BRIEF MAINTENANCE INSPECTION FOLLOWED BY A MEMO SUMMARIZING MAINTENANCE ITEMS NECESSARY FOR THE UPCOMING GROWING SEASON. THE FORMAL LATE-SEASON MONITORING INSPECTION WILL TAKE PLACE ONCE ANNUALLY DURING LATE SUMMER OR EARLY FALL. DURING EACH LATE-SEASON MONITORING INSPECTION, THE FOLLOWING DATA WILL BE COLLECTED:

1. PERCENT SURVIVAL OF ALL INSTALLED PLANTINGS, INCLUDING SPECIES SPECIFIC COUNTS OF INSTALLED TREE AND SHRUB PLANTINGS (NOTE: GROUNDCOVER PLANTS COUNTED IN YEAR-1 ONLY, FOR WARRANTY PURPOSES).
2. NATIVE WOODY COVER AS DETERMINED USING VISUAL COVER CLASS ESTIMATES.
3. NATIVE GROUNDCOVER PLANT COVER AS DETERMINED USING VISUAL COVER CLASS ESTIMATES.
4. ESTIMATES OF INVASIVE HERBACEOUS PLANTS OR GROUNDCOVER USING VISUAL COVER ESTIMATES.
5. THE SPECIES COMPOSITION, NOTING WHETHER A SPECIES IS NATIVE OR EXOTIC AND WHETHER PLANTS WERE INSTALLED OR ARE VOLUNTEERS.
6. THE GENERAL HEALTH AND VIGOR OF THE INSTALLED VEGETATION.
7. PHOTOGRAPHS FROM FIXED PHOTO-POINTS ESTABLISHED DURING THE AS-BUILT INSPECTION.
8. ANY EVIDENCE OF WILDLIFE USAGE.
9. DEPTH OF GROUNDWATER BELOW THE SOIL SURFACE SHALL BE RECORDED AT ESTABLISHED WELLS IN THE WETLAND CREATION AREA.

MONITORING REPORTS SHALL BE SUBMITTED ANNUALLY TO THE CITY. REPORTS SHALL DOCUMENT THE CONDITIONS OF THE SITE, INCLUDING QUANTITATIVE DATA COLLECTED DURING THE MONITORING INSPECTION, AND SHALL PROVIDE MAINTENANCE RECOMMENDATIONS THAT MAY BE NECESSARY TO HELP THE SITE ACHIEVE THE STATED PERFORMANCE STANDARDS.

CONTINGENCY PLAN

IF ANY MONITORING REPORT REVEALS THAT THE RESTORATION PLAN HAS FAILED IN WHOLE OR IN PART, AND SHOULD THAT FAILURE BE BEYOND THE SCOPE OF ROUTINE MAINTENANCE, THE APPLICANT WILL SUBMIT A CONTINGENCY PLAN TO THE CITY OF MERCER ISLAND FOR APPROVAL. THIS PLAN MAY INCLUDE REPLANTING, SOIL AMENDMENTS OR TOPDRESSING, SUBSTITUTIONS FOR SPECIES SELECTED IN THE ORIGINAL PLAN, AND ADAPTIVE WEED CONTROL METHODS.

MATERIALS

1. WOODCHIP MULCH: "ARBORIST CHIPS" (CHIPPED WOODY MATERIAL) APPROXIMATELY ONE TO THREE INCHES IN MAXIMUM DIMENSION (NOT SAWDUST). THIS MATERIAL IS COMMONLY AVAILABLE IN LARGE QUANTITIES FROM ARBORISTS OR TREE-PRUNING COMPANIES. THIS MATERIAL IS SOLD AS "ANIMAL FRIENDLY HOG FUEL" AT PACIFIC TOPSOILS [(800) 884-7645]. MULCH SHALL NOT CONTAIN APPRECIABLE QUANTITIES OF GARBAGE, PLASTIC, METAL, SOIL, AND DIMENSIONAL LUMBER OR CONSTRUCTION/DEMOLITION DEBRIS. APPROX. QUANTITY REQUIRED: 60 CUBIC YARDS.
2. COMPOST: CEDAR GROVE COMPOST OR EQUIVALENT "COMPOSTED MATERIAL" PER WASHINGTON ADMIN. CODE 173-350-220. QUANTITY REQUIRED: 35 CUBIC YARDS
3. FERTILIZER: SLOW-RELEASE, PHOSPHOROUS-FREE GRANULAR FERTILIZER. MOST COMMERCIAL NURSERIES CARRY THIS PRODUCT. FOLLOW MANUFACTURER'S INSTRUCTIONS FOR USE. KEEP FERTILIZER IN WEATHER-TIGHT CONTAINER WHILE ON-SITE. FERTILIZER IS ONLY TO BE APPLIED IN YEARS TWO AND THREE, NOT IN YEAR ONE.
4. RESTORATION SPECIALIST: QUALIFIED PROFESSIONAL ABLE TO EVALUATE AND MONITOR THE CONSTRUCTION OF ENVIRONMENTAL RESTORATION PROJECTS.
5. FERTILIZER (FOR NEAR AQUATIC ENVIRONMENTS): SLOW-RELEASE, PHOSPHOROUS-FREE GRANULAR FERTILIZER. LABEL MUST INDICATE THAT PRODUCT IS SAFE FOR AQUATIC ENVIRONMENTS. FOLLOW MANUFACTURER'S INSTRUCTIONS FOR USE. KEEP FERTILIZER IN WEATHER-TIGHT CONTAINER WHILE ON-SITE. FERTILIZER IS ONLY TO BE APPLIED IN YEARS TWO AND THREE, NOT IN YEAR ONE.



NFC

NOT FOR CONSTRUCTION



750 Sixth Street South
Kirkland WA 98033

p 425.822.5242
www.watershedco.com

Science & Design

MERCERTECH INTERNATIONAL LLC

LONG PLAT MITIGATION AND RESTORATION PLAN

PREPARED FOR ALAN CHIU

PARCEL # 1824059031

4320 ISLAND CREST WAY
MERCER ISLAND, WA 98040

SUBMITTALS & REVISIONS		NO.	DATE	DESCRIPTION	BY
1	08-29-17	30% SUBMITTAL - PREAPP	LV		
2	10/17/17	30% SUBMITTAL - PREAPP 2	RH		
3	10/27/17	30% SUBMITTAL - APPLICATION	RH		
4	04/18/18	CITY COMMENT RESPONSE 1	RH		

SHEET SIZE:
ORIGINAL PLAN IS 22" x 34".
SCALE ACCORDINGLY.

PROJECT MANAGER: MD
DESIGNED: LV, RH
DRAFTED: LV, RH
CHECKED: LV, AM

JOB NUMBER: 160905

SHEET NUMBER: W8.0 OF 14

MITIGATION AND RESTORATION NOTES