



OVERHEAD DOOR MODELS

CUSTOM OPTIONS

FINISH OPTIONS

MOTOR OPTIONS

COLLECTIONS



Titan® is our most popular aluminum and glass model due to its symmetrical rails and stiles.

This model is available with or without windload and can be manufactured up to 24'-2" wide. Since 1958, ArmRLite has been consistently manufacturing the Titan® Model and has never compromised on the quality of our doors. Because of this, ArmRLite is able to produce replacement sections for any of our welded models, regardless of purchase date.

- Maximum Width of 24'-2"
- Windload Available
- 20-Year Welded Frame Warranty*
- Lifetime Residential Warranty*

*Except the top section when trolley operated.

MATERIAL	6063-T6 Alloy
CONSTRUCTION METHOD	Heli-Arc Welding
TOP RAIL	2 ³ / ₄ " , 4 ¹ / ₂ " or 7 ¹ / ₂ "
BOTTOM RAIL	4 ¹ / ₂ " or 7 ¹ / ₂ "
END STILES	3 ³ / ₈ " , 4 ¹ / ₂ " or 7 ¹ / ₂ "
CENTER STILES	3 ³ / ₈ "
MEETING RAILS	3 ³ / ₈ " wide per pair
FRAME THICKNESS	1 ³ / ₄ "



Custom Garage Door Options

Due to our exclusive welded construction, ArmRLite's aluminum overhead sectional doors are capable of the highest degree of customization. Many of the options listed below are exclusive to ArmRLite due to our superior construction method.



GLASS GLAZING OPTIONS

DSB / Annealed	Acoustical*	GLASS THICKNESS:	
Tempered / Safety	Frosted		1/8" non-insulated
Acrylic	Tinted		1/4" non-insulated
Laminated	Polycarbonate		7/16" insulated
Insulated	Custom		5/8" insulated
Hurricane / Impact			1" insulated



INTERIOR PANEL OPTIONS

Solid	Perforated	Stamped Panel Designs	Operable / Inoperable Louvers
Insulated	Mesh	Custom Panels	

Fine Metal Mesh



FINISH OPTIONS

Anodized Finishes: The standard finish is clear anodized aluminum. Optional anodized finishes include dark bronze and black anodized in stock for an upgrade. Custom Anodized finishes are available such as champagne bronze, medium bronze, ETC. Anodized finishes are the most resilient in corrosive environments. Includes a 20-year finish warranty except on installations within 1 mile of water.

Fluoropon[®] Finishes: Upgrade option featuring hundreds of colors including metallic and non-metallic options. Custom color matches are also available upon request. Includes a 1-year finish warranty except on installations within 1 mile of water.

RAL Powdercoat: Upgrade option featuring over 150 color choices to be selected from RAL color chart. Includes a 1-year finish warranty except on installations within 1 mile of water.

Finish



CUSTOM OPTIONS

ADA or Step-Over Pass Door*	Motor or Manual Operation
Sloping Bottom	Corrosion Resistant Package
Awning Windows	High Cycle Springs
Mail Slots	Exhaust Ports
Energy Efficiency Package	Matching Transoms, Side Lites, Entrance Doors, and Gates

*Please consult with ArmRLite regarding limitations.

accessible door in western garage- eastern facade vehicular gate- manufacturer has confirmed this can have panic hardware installed.