

Datum



SCALE: 1" = 30

Legend

COMPACTED DIRT SURFACING

WOOD DECKING

DISPERSION IN VEGETATION

FINISHED GRADE (FG) ELEVATION --¹⁷⁵ − FG CONTOUR

Notes

- 1. SEE SHEET C2.0 FOR GENERAL NOTES.
- 2. PERFORM SUBGRADE PREPARATION IN ACCORDANCE WITH THE REQUIREMENTS AND RECOMMENDATIONS OF GEOTECHNICAL REPORT PREPARED FOR THIS PROJECT.
- 3. FINISHED GRADE INDICATED IS FINAL SURFACE ELEVATION FOLLOWING PLACEMENT OF ALL SURFACING MATERIALS.
- 4. GRADE ALL AREAS TO PROVIDE DRAINAGE IN THE DIRECTION NOTED.
- 5. COORDINATE AND VERIFY LAYOUT OF ALL NEW WALKWAYS WITH OWNER PRIOR TO PERFORMING ANY PREPARATION OR INSTALLATION WORK.
- 6. FINE GRADE AREAS TO DIRECT SURFACE RUNOFF OF TRAILS INTO VEGETATION.
- THE SITE IS SUBJECT TO RESTRICTIONS ON GRADING AND CONSTRUCTION ACTIVITIES DURING THE WET SEASON. LAND DISTURBING ACTIVITIES ARE RESTRICTED FROM OCTOBER 1st TO APRIL 30th UNLESS A WET SEASON CONSTRUCTION REQUEST IS SUBMITTED, REVIEWED, AND A WET SEASON CONSTRUCTION APPROVAL LETTER IS GRANTED BY THE CITY OF MERCER ISLAND. munum



206.419.0873



Call Before You Dig! 811

1 8/23/23 Grading Plan

Description

Rev # Date

Sta10 Project #:	
	23004
Submittal:	
	Permit

Bike Skills Area at Deane's Children's Park

5701 Island Crest Way Mercer Island, WA 98040

Design:		
	SEH	
Drafting:		
Checked:		
	SEH	
Date:		
	6/28/23	

