

# Applicant Information

Project Address: 8440 Benotho Place, Mercer Island, WA 98040

Parcel Number: 073610-0100

Applicant: Seaborn Pile Driving Company, 1080 W Ewing St Building B, Seattle, WA 98119  
206-236-1700

Property Owner: Chen, Xiaowei

Legal Description: BENOTHO BEACH UNREC TGW SH LDS ADJ LESS C/M RGTS

Description of Work: We propose to replace the existing wooden bulkhead with a granite rock bulkhead.

## Job specific comments

Purpose

Habitat Enhancement

The proposed planting plan has been designed to mitigate for the proposed work.

Water Quality

In order to prevent debris from entering the lake during the demolition stage of the project, a containment boom will surround the crane barge and work area.

## Permits

**Mercer Island Exemption With SEPA Review Permit:**

**We are applying for the permit to be reviewed under the:**

**“Bulkheads and Shoreline Stabilization Structures” Per MIMC 19.13.050(B)(1)”**

## Mitigation

**Shoreline Plantings:** The shoreline plantings have been designed to provide the spread of tree and shrub nutrients into the adjacent waters of Lake Washington.

Contractor: Seaborn Pile Driving Company      License #: SEABOPD942CG

Address: 1080 W Ewing St. Bldg B. Seattle WA 98119

Office: 206.236.1700

Mobile: 253-459-3267

Contact: Madison Johnson

Email: permits@seabornpiledriving.com

## **Construction Narrative**

### Mobilization

Mobilize crew, crane barge, supply and debris barges, and materials on site

### Rock Bulkhead Repair

1. Set out a Sediment Containment Curtain around the work area waterward of the bulkhead to contain any silt and debris that may be generated during construction.
2. Remove soil and material from behind the bulkhead.
3. Install filter fabric into the excavated area and backfill with 2" – 4" cleaned crushed rock, and then envelope with the filter fabric.
4. Finish with 10" – 12" of topsoil and blend into the existing elevation.
5. Clean the work area and remove the silt fence/boom.

## **Structural Notes**

### General

- All materials, workmanship, design, and construction shall conform to the submitted drawings and the International Building Code.
- The contractor will be responsible for all safety precautions and methods and processes to perform the designated work.

### Best Management Practices

#### **1. Above the Water Line Work**

1. Seaborn Pile Driving Company will employ one crane barge, one supply and one debris barge to complete the scope of work. A tug will tow the barges on and off the job site.

2. Seaborn Pile Driving Company personnel working in, near or over the water will at all time wear either USCG approved life vests or work vest as well as hard hats and safety glasses.

## **2. Material Handling**

1. While at the job site, a floating containment boom will completely surround the work area.
2. All removed material and the existing bulkhead structure will be placed on the debris barge where they will be contained and kept out of the lake.

## **3. Hazardous Materials**

- No hazardous materials will be mixed or stored in or near the water. No cleaning of materials will be performed in or near the water.

## **4. Polluting Materials in Water**

- Seaborn Pile Driving Company will take extra precautions to ensure materials don't fall into or pollute the water. Any material that enters the water will be removed immediately. Any hazardous material such as oily rags will not be handled near or over the water.
- A spill kit will be employed on the barges at the job site.
- If any pollutants enter the water, Seaborn Pile Driving Company will contact the appropriate agencies and report the spill immediately.

## **5. Materials Disposal**

- Seaborn Pile Driving Company will dispose of the existing bulkhead material in an approved legal disposal site in accordance with all applicable laws and permit requirements.