

O'Neil Pier

Project Narrative

Remove a portion of the existing shared fixed pier (approx. 315sf) and associated wood piles (nine total). Drive one new pile at waterward end of the existing pier to support the reconfigured structure. Remove one existing bottom based boatlift and canopy. Relocate one existing bottom based boatlift to the new pier. Install new fully grated single family pier (approx. 528sf overwater) & 552sf total. Install new native shoreline plantings.