

O'Neil Pier

Project Narrative

Remove a portion of the existing shared fixed pier (approx. 315sf) and associated wood piles (nine total). Note: this work is being performed by others under a separate permit. Remove one existing bottom based boatlift and canopy. Relocate one existing bottom based boatlift to the new pier. Install new fully grated single family pier (approx. 528sf overwater) & 552sf total. Install new native shoreline plantings.