





**BOUNDARY SURVEY NOTES**

1. INSTRUMENTATION FOR THIS SURVEY WAS A 3-SECOND LEICA VIVA TS15 SMART POLE TOTAL STATION/RTK GPS.
2. PROCEDURES USED IN THIS SURVEY MEET OR EXCEED STANDARDS SET BY WAC 332-130-090. SURVEY WAS COMPLETED BY A FIELD TRAVERSE.
3. ALL MONUMENTS WERE LOCATED DURING THIS SURVEY UNLESS OTHERWISE NOTED.
4. ENCROACHMENTS NOTED AS "IN" OR "OUT" ARE RELATIVE TO THE SUBJECT PROPERTY.
5. FENCE DIMENSIONS ARE GENERALLY TO THE CENTERLINE OF THE FENCE UNLESS OTHERWISE NOTED.
6. STRUCTURE LOCATIONS ARE MEASURED TO THE FINISHED FASCIA UNLESS OTHERWISE NOTED.
7. TREE LOCATIONS ARE MEASURED TO THE ESTIMATED CENTER OF THE TREE.
8. ALL DIMENSIONS ARE IN DECIMAL FEET.

**TOPOGRAPHIC SURVEY NOTES**

1. UTILITIES SHOWN ON THIS SURVEY ARE BASED UPON ABOVE GROUND OBSERVATIONS, UTILITY LOCATES BY THIRD PARTIES, AND AS-BUILT PLANS WHERE AVAILABLE. ACTUAL LOCATIONS OF UNDERGROUND UTILITIES MAY VARY AND UTILITIES NOT SHOWN ON THIS SURVEY MAY EXIST ON THIS SITE.
2. CONTOURS SHOWN ARE BASED ON A FIELD SURVEY.
3. TREE IDENTIFICATION WAS PERFORMED BY SURVEY FIELD PERSONNEL AND SHOULD BE CONSIDERED A BEST GUESS. AN ARBORIST SHOULD BE RELIED UPON FOR MORE ACCURATE AND DETAILED IDENTIFICATION OF TREE SPECIES AND HEALTH.

**PROJECT INFORMATION**

SURVEYOR: PLOG ENGINEERING, PLLC  
P.O. BOX 412  
RAVENSDALE, WA 98051  
PH.: (206) 420-7130

PROPERTY OWNER: MIKE & ANNE SEIFERT  
3261 67TH AVE SE  
MERCER ISLAND, WA 98040

TAX PARCEL NUMBER: 370890-0065

PROJECT ADDRESS: 3261 67TH AVE SE  
MERCER ISLAND, WA 98040

PARCEL AREA: 18,962 S.F. (0.435 ACRES ±)  
AS SURVEYED TO BULK HEAD

**REFERENCE SURVEYS**

P1 - PLAT OF SQUIRES LAKE ADDITION, VOL 11, PG 50  
R1 - AF# 20110613900004  
R2 - AF# 20050923900004  
R3 - AF# 8606099010  
R4 - AF# 8010079002  
R5 - AF# 20160328900015

**VERTICAL DATUM & CONTOUR INTERVAL**

ELEVATIONS SHOWN ON THIS DRAWING ARE BASE ON THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD88) AND WERE ESTABLISHED USING RTK GPS.

2.0' CONTOUR INTERVAL - THE EXPECTED VERTICAL ACCURACY IS EQUAL TO 1/2 THE CONTOUR INTERVAL OR ± 1.0' FOR THIS PROJECT.

**BASIS OF BEARINGS**

PER THE RECORD OF SURVEY (R3) AF# 8606099010, RECORDS OF KING COUNTY WASHINGTON.



ACCEPTED THE BEARING OF N 0°00'00" E FOR 67TH AVE SE BASED ON VARIOUS FOUND MONUMENTS.

**LEGAL DESCRIPTION**

THAT PORTION OF TRACT 7, JERSEY WATER FRONT ADDITION TO EAST SEATTLE, ACCORDING TO THE PLAT THEREOF RECORDED IN VOLUME 8 OF PLATS, PAGE 64, RECORDS OF KING COUNTY, WASHINGTON, DESCRIBED AS FOLLOWS:

COMMENCING AT THE POINT ON THE WEST LINE OF HOOD AVENUE IN THE PLAT OF SAID ADDITION, WHERE SAID WEST LINE OF HOOD AVENUE IS INTERSECTED BY THE NORTHERLY LINE OF SAID TRACT 7; THENCE SOUTH ALONG THE WEST LINE OF HOOD AVENUE AND THE EAST LINE OF TRACT 7, A DISTANCE OF 60 FEET TO THE TRUE POINT OF BEGINNING; THENCE SOUTH 53°35'36" WEST TO THE SHORE LINE OF LAKE WASHINGTON; THENCE SOUTHEASTERLY ALONG THE SHORE LINE OF LAKE WASHINGTON 100 FEET; THENCE NORTHEASTERLY TO A POINT ON THE EASTERLY LINE OF SAID TRACT 7, WHICH POINT IS 100 FEET SOUTH OF THE TRUE POINT OF BEGINNING; THENCE NORTH ALONG SAID HOOD AVENUE AND THE EAST LINE OF SAID TRACT 7, A DISTANCE OF 100 FEET TO THE TRUE POINT OF BEGINNING; TOGETHER WITH SECOND CLASS SHORE LANDS ADJOINING SAID PREMISES.

SITUATE IN THE COUNTY OF KING, STATE OF WASHINGTON.



- SYMBOL LEGEND**
- MONUMENT AS NOTED
  - SECTION CORNER
  - QUARTER SECTION CORNER
  - FOUND REBAR AS NOTED
  - SET REBAR AND CAP LS 31976
  - FOUND SURFACE MARKER/DISK
  - SET SURFACE MARKER/DISK LS 31976
  - SEWER MAINTENANCE HOLE
  - SEPTIC MAINTENANCE HOLE
  - SEWER CLEAN OUT
  - SEWER LINE
  - STORM DRAIN MAINTENANCE HOLE
  - CATCH BASIN (TYPE 2)
  - CATCH BASIN (TYPE 1)
  - STORM DRAIN CLEAN OUT
  - ROUND YARD DRAIN
  - SQUARE YARD DRAIN
  - STORM DRAIN LINE
  - WATER MAINTENANCE HOLE
  - WATER VALVE
  - WATER METER
  - FIRE HYDRANT
  - BLOW OFF VALVE
  - IRRIGATION VALVE/JUNCTION
  - WATER LINE
  - GAS VALVE
  - GAS METER
  - GAS LINE
  - CABLE RISER
  - CABLE BOX
  - CABLE MAINTENANCE HOLE
  - FIBER OPTIC MAINTENANCE HOLE
  - TELEPHONE MAINTENANCE HOLE
  - TRAFFIC SIGNAL MAINTENANCE HOLE
  - PAD MOUNTED TRANSFORMER
  - HAND HOLE
  - A/C COMPRESSOR
  - YARD LIGHT
  - POWER POLE
  - GUY WIRE
  - STREET LIGHT
  - OVERHEAD UTILITIES (GENERAL/MIXED)
  - OVERHEAD ELECTRICAL
  - OVERHEAD CABLE
  - OVERHEAD TELEPHONE
  - UNDERGROUND UTILITIES (GENERAL/MIXED)
  - UNDERGROUND ELECTRICAL
  - UNDERGROUND CABLE
  - UNDERGROUND TELEPHONE
  - UNDERGROUND FIBER OPTIC
  - BOLLARD
  - MAILBOX
  - SIGN
  - WETLAND FLAG
  - SNAG
  - DECIDUOUS MULTI-TRUNK
  - DECIDUOUS
  - CONIFER MULTI-TRUNK
  - CONIFER

**ABBREVIATION LEGEND**

MON = MONUMENT  
DN = DOWN  
SP = SHORT PLAT  
BLA = BOUNDARY LINE ADJUSTMENT  
DBH = DIAMETER AT BREAST HEIGHT (FT)  
DLR = DRIP LINE RADIUS (FT)  
APN = ASSESSORS PARCEL NUMBER  
AF# = AUDITOR'S FILE NUMBER  
WD = WOOD  
CL = CHAIN LINK  
(M) = AS MEASURED  
(C) = AS CALCULATED  
(P) = PER PLAT  
(D) = PER DEED  
(R#) = PER REFERENCE SURVEY  
(H) = HELD



**PLOG ENGINEERING**  
Surveyors & Civil Engineers

P.O. Box 412  
Ravensdale, WA 98051  
(206) 420-7130  
www.PlogEngineering.com

NE1/4, SE1/4, SEC 11, TWP 24N, RNG 4E, W.M.  
**BOUNDARY & TOPOGRAPHIC SURVEY**

MIKE & ANNE SEIFERT  
3261 67TH AVE SE, MERCER ISLAND, WA 98040

PROJECT NO.: 173-22	REVISION DATE: 10/08/2022	REVISION NO.: 0	SHEET: 1 OF 1
---------------------	---------------------------	-----------------	---------------















GFA MAIN FLOOR  
SCALE: 1/8" = 1'-0"




**Seifert Addition/Remodel**  
Gross Floor Area  
22-Dec-23

Allowable Area:	Lot Area	Code factor	7,595
Proposed Areas:			
Lower Floor:			880
Main Floor:			3,355
Interior Entry 200%:			154
BBO Deck:			44
Upper Floor:			1,655
Attached Garage:			1,075
<b>Total Area:</b>			<b>7,162</b>
<b>Proposed % of Lot Area:</b>			<b>38%</b>



Lower Floor Area exclusions  
Seifert Residence  
Revised 1/09/2024

Point	Length	Wall ht.	midpoint ht.	Coverage	Result	Percentage
A	7.33	8.38	0.00	0.00	0.00	0%
B	6.83	8.38	0.00	0.00	0.00	0%
C	6.42	8.38	1.79	0.21	1.37	1%
D	1.00	8.38	2.29	0.27	0.27	0%
E	10.58	8.38	3.04	0.36	3.84	4%
F	2.00	8.38	4.00	0.48	0.96	1%
G	0.83	8.38	4.13	0.49	0.41	0%
H	4.86	8.38	4.29	0.51	2.39	2%
I	12.50	8.38	5.79	0.69	8.64	9%
J	23.19	8.38	6.00	0.72	16.63	17%
K	7.69	8.38	5.13	0.61	4.70	5%
L	19.48	8.38	4.16	0.50	9.68	10%
M	1.35	8.38	4.00	0.48	0.65	1%
N	6.00	8.38	3.79	0.45	2.72	3%
O	1.35	8.38	3.68	0.44	0.59	1%
P	4.33	8.38	3.54	0.42	0.57	1%
Q	16.83	8.38	2.83	0.34	1.46	1%
R	31.00	8.38	2.29	0.27	8.48	8%
S	18.66	8.38	1.50	0.18	3.34	3%
T	5.33	8.38	0.00	0.00	0.00	0%
	187.37					67%

Total floor area to outside of exterior wall:	1366
Total % / Total length:	0.36
<b>Total area excluded from Gross Floor area:</b>	<b>486.15</b>
<b>Total area remaining that counts toward Gross Floor Area</b>	<b>879.85</b>



GFA UPPER FLOOR  
SCALE: 1/8" = 1'-0"



GFA LOWER FLOOR  
SCALE: 1/8" = 1'-0"




SEIFERT REMODEL

37261 67TH AVE SE  
MERCER ISLAND, WA 98040

Job No. 2219  
Project Manager: DG  
Issue Date: 03/06/2024

NO.	DATE	REVISION



GROSS FLOOR AREA  
CALCS


A1.03

PERMIT SET (03.06.2024)






GELOTTE HOMMAS DRIVDAHL  
ARCHITECTURE  
2340 130th Ave. NE, Suite 100, Bellevue, WA 98005  
425.828.3081



**BUILDING HEIGHTS SITE PLAN**  
SCALE: 1/8" = 1'-0"



**Seifert Remodel/Addition**  
Building Height Calculations  
01.21.2024


Point	Length	Mid. Elev	Product
A	7.30	20.71	151.18
B	6.83	20.71	141.45
C	6.42	21.00	134.82
D	1.00	21.17	21.17
E	10.58	23.75	251.28
F	2.00	24.33	48.66
G	0.83	24.50	20.34
H	4.86	24.58	119.54
I	12.50	25.00	312.50
J	0.33	26.67	8.80
K	3.83	27.00	103.41
L	5.00	27.25	136.25
M	69.50	30.33	2107.94
N	3.71	34.33	127.36
O	10.00	34.67	346.70
P	10.00	34.67	346.70
Q	3.71	34.33	127.36
R	55.17	29.82	1645.17
S	7.00	30.00	210.00
T	3.33	29.80	99.23
U	7.19	30.00	215.83
V	3.00	30.00	90.00
W	8.29	30.00	248.70
X	3.00	30.00	90.00
Y	2.19	30.00	65.70
Z	9.33	30.00	279.90
A1	7.00	30.00	210.00
B1	4.50	30.00	135.00
C1	7.08	30.00	212.50
D1	3.00	30.00	90.00
E1	10.50	28.83	302.72
F1	0.67	27.83	18.56
G1	16.83	29.75	498.89
H1	4.00	24.33	97.32
I1	27.48	29.75	817.95
J1	4.29	22.58	96.78
K1	3.00	22.50	67.50
L1	3.30	22.50	74.25
M1	21.06	22.33	470.33
N1	3.30	22.25	73.43
O1	3.00	22.25	66.75
P1	6.67	22.25	148.32
Q1	3.00	22.17	66.51
R1	3.30	22.17	73.16
S1	3.00	22.17	66.51
T1	6.33	21.83	138.25
U1	13.13	20.70	271.89
V1	8.35	20.70	172.77
W1	4.75	20.71	98.37
<b>TOTAL</b>	<b>421.93</b>		<b>7895.61</b>

Ave. Bldg. Elevation: 26.92  
Height Allowed: 30.00  
Allowable Height: 56.92

**SEIFERT REMODEL**  
3261 67TH AVE SE  
MERCER ISLAND, WA 98040

Job No. 2219  
Project Manager: DG  
Issue Date: 03/06/2024

NO.	DATE	REVISION



**BUILDING HEIGHT CALCS**

**A1.04**


**PERMIT SET (03.06.2024)**

FILE: 2219 Seifert Remodel and Addition - RFRD - Worksheet: AArch, 6.2024










**SEIFERT REMODEL**  
32261 67TH AVE SE  
MERCER ISLAND, WA 98040

Job No. 2219  
Project Manager: DG  
Issue Date: 03/06/2024


NO.	DATE	REVISION




SITE DETAILS



**1 PARTIAL SITE PLAN**  
SCALE: 1/8" = 1'-0"




**3 DETAIL @ (N) EXT. STAIRS**  
SCALE: 1 1/2" = 1'-0"



**2 DETAIL @ (N) WALKWAY**  
SCALE: 1 1/2" = 1'-0"

NOTE:  
S.G. TO FIELD VERIFY EXACT  
EXISTING CONDITIONS OF  
CONCRETE WALLS & FOOTING  
AND COORDINATE W/ ARCHITECT  
AND ENGINEER AS NEEDED.






GELOTTE HOMMAS DRIVDAHL  
ARCHITECTURE  
2340 130th Ave. NE, Suite 100, Bellevue, WA 98005  
425.828.3081

**SEIFERT REMODEL**  
3261 67TH AVE SE  
MERCER ISLAND, WA 98040

Job No. 2219  
Project Manager: DG  
Issue Date: 03/06/2024

NO.	DATE	REVISION




LOWER FLOOR PLAN  
DEMO


**A2.01D**

© 2023 GELOTTE HOMMAS DRIVDAHL ARCHITECTURE, P.L.L.C.

	EXISTING BUILDING ELEMENTS TO REMAIN
	EXISTING BUILDING ELEMENTS TO BE DEMOLISHED
	PROPOSED BUILDING ELEMENTS



**LOWER FLOOR DEMO**  
SCALE: 1/4" = 1'-0"




**PERMIT SET (03.06.2024)**











GELOTTE HOMMAS DRIVDAHL  
ARCHITECTURE  
23401 130th Ave. NE, Suite 100, Bellevue, WA 98005  
425.628.3081

EXISTING BUILDING ELEMENTS TO REMAIN  
 EXISTING BUILDING ELEMENTS TO BE DEMOLISHED  
 PROPOSED BUILDING ELEMENTS




**UPPER FLOOR DEMO**  
 SCALE: 1/4" = 1'-0"



**PERMIT SET (03.06.2024)**

Job No. 2219  
 Project Manager: DG  
 Issue Date: 03/06/2024


NO.	DATE	REVISION



UPPER FLOOR PLAN  
DEMO

**A2.03D**






GELOTTE HOMMAS DRIVDAHL  
ARCHITECTURE  
2340 130th Ave. NE, Suite 100, Bellevue, WA 98005  
425.828.3081


EXISTING BUILDING ELEMENTS TO REMAIN

EXISTING BUILDING ELEMENTS TO BE DEMOLISHED

PROPOSED BUILDING ELEMENTS



**ROOF PLAN DEMO**  
SCALE: 1/4" = 1'-0"




PERMIT SET (03.06.2024)

Job No. 2219  
Project Manager: DG  
Issue Date: 03/06/2024

NO.	DATE	REVISION



**SEIFERT REMODEL**  
3261 67TH AVE SE  
MERCER ISLAND, WA 98040




ROOF PLAN DEMO

**A2.04D**





**2 SOUTH ELEVATION DEMO**  
SCALE: 1/4" = 1'-0"



**1 EAST ELEVATION DEMO**  
SCALE: 1/4" = 1'-0"


**PERMIT SET (03.06.2024)**

**SEIFERT REMODEL**

3261 67TH AVE SE  
MERCER ISLAND, WA 98040

Job No. 2219  
Project Manager: DG  
Issue Date: 03/06/2024


NO.	DATE	REVISION




EXTERIOR ELEVATIONS  
DEMO

**A3.01D**






GELOTTE HOMMAS DRIVDAHL  
 ARCHITECTURE  
 2340 130th Ave. NE, Suite 100, Bellevue, WA 98005  
 425.828.3081



**4 NORTH ELEVATION DEMO**  
 SCALE: 1/4" = 1'-0"




**3 WEST ELEVATION DEMO**  
 SCALE: 1/4" = 1'-0"

**PERMIT SET (03.06.2024)**

**SEIFERT REMODEL**  
 3261 67TH AVE SE  
 MERCER ISLAND, WA 98040

Job No. 2219  
 Project Manager: DG  
 Issue Date: 03/06/2024


NO.	DATE	REVISION




EXTERIOR ELEVATIONS  
 DEMO

**A3.02D**





GELOTTE HOMMAS DRIVDAHL  
ARCHITECTURE  
2340 130th Ave. NE, Suite 100, Bellevue, WA 98005  
425.628.3081



SEIFERT REMODEL  
37261 67TH AVE SE  
MERCER ISLAND, WA 98040

Job No. 2219  
Project Manager: DG  
Issue Date: 03/06/2024

NO.	DATE	REVISION


10226 REGISTERED ARCHITECT  
ERIC L. DRIVDAHL  
STATE OF WASHINGTON  
March 7, 2024

LOWER FLOOR PLAN  
PROPOSED

A2.01

© 2023 GELOTTE HOMMAS DRIVDAHL ARCHITECTURE, P.S.

PERMIT SET (03.06.2024)



EXISTING BUILDING ELEMENTS TO REMAIN  
EXISTING BUILDING ELEMENTS TO BE DEMOLISHED  
PROPOSED BUILDING ELEMENTS

OUTDOOR SHOWER (OR LOCATE IN LANDSCAPE?)  
LINE OF DECK ABOVE  
REMOVE (E) WOOD BOX  
(N) GAS FIREPLACE INSERT  
(E) RECREATION ROOM  
BAR COUNTER  
(E) TASTING ROOM  
(N) KITCHENETTE  
(N) BATH  
(N) LAUNDRY/CLOS.  
(E) WINE STRG.  
(E) FURS  
(N) GYM  
(E) CRAWL  
(E) CRAWL SPACE  
(N) CLOTHES STORAGE  
MIRRORED WALL  
MAIN LEVEL ABOVE

PLAN NOTES

- INTERIOR STAIRWAYS SHALL BE ILLUMINATED PER IRC SECTION R303.7. EXTERIOR STAIRWAYS SHALL BE ILLUMINATED PER IRC SECTION R303.8. EXTERIOR STAIRS SHALL BE PROVIDED WITH AN ARTIFICIAL LIGHT SOURCE LOCATED AT THE TOP LANDING OF THE STAIRWAY.
- 2" ALL HANDRAILS TO BE 34"-38" ABOVE TREAD NOSING, 1 1/2" FROM WALL, NOT LESS THAN 1 1/4" OR MORE THAN 2" IN DIAMETER PER IRC SECTION R311 & R312
- 3" ALL GUARD RAILS SHALL BE MIN 36" HIGH AND HAVE A MAXIMUM OPENING SUCH THAT A 4" SPHERE CANNOT PASS THROUGH PER IRC SECTIONS R312.1.2 & R312.1.3
- 4) PROTECT ENCLOSED UNDERSTAIR SURFACES WITH MIN 1/2" GYPSUM BOARD PER IRC SECTION R302.7
- 5) THE GARAGE SHALL BE SEPARATED FROM THE RESIDENCE WITH A MIN 1/2" GYPSUM BOARD OR EQUIV. APPLIED TO THE GARAGE SIDE. 5/8" TYPE "X" GYPSUM BOARD IS REQUIRED WHERE THERE ARE HABITABLE ROOMS ABOVE THE GARAGE. SUPPORTING COLUMNS, WALLS AND BEAMS USE 1/2" GYPSUM WALL BOARD PER IRC SECTION 302.6
- 6) OPENINGS BETWEEN THE GARAGE AND RESIDENCE SHALL HAVE A SOLID WOOD, SOLID OR HONEYCOMB-CORE STEEL DOORS NOT LESS THAN 1 3/8" IN THICKNESS OR 29-MIN FIRE-RATED DOORS. ALL DOORS SHALL BE EQUIPPED WITH A SELF-CLOSING OR AUTOMATIC CLOSING DEVICE. PER IRC SECTION R302.5.1
- 7) CRAWL SPACE: UNDERLOOR AREAS SHALL BE UNVENTILATED AND COMPLY WITH ALL ASPECTS OF IRC R408.3 FOR UNVENTED CRAWL SPACE AS FOLLOWS:  
- CONTINUOUS CLASS 1 VAPOR RETARDER WITH 6" LAPS AT SEAMS AND STEM WALLS, RADON VENTILATION, MECHANICAL VENTILATION AND REQD. CFM OF VENTILATION PER R408.3
- 8) HOT TUB SHALL BE PROVIDED WITH COVER THAT COMPLIES WITH ASTM F-1346 OR AN APPROVED BARRIER
- 9) KITCHEN RANGE HOODS CAPABLE OF EXHAUSTING MORE THAN 400 CFM REQUIRE MAKE UP AIR PER IRC M1503.6
- 10) COMBO ALARMS SHALL BE INSTALLED OUTSIDE SEPARATE SLEEPING AREA IN THE IMMEDIATE VICINITY OF THE BEDROOMS IN ACCORDANCE WITH IRC R314/R315
- 11) OPEN TOP BROILER UNITS SHALL BE PROVIDED WITH A METAL EXHAUST HOOD HAVING THICKNESS OF NOT LESS THAN 0.0157 INCH. BROILER UNITS PERMANENTLY INSTALLED OUTSIDE THE BUILDING ENVELOPE AND HAVING THE COOKING SURFACE AT LEAST 5 FEET BELOW A 1 HOUR FIRE RESISTANCE RATED CEILING SHALL NOT BE REQUIRED TO HAVE AN EXHAUST HOOD (IRC M1503.2.1)
- 12) ACCESS OPENINGS THROUGH THE CEILING SHALL BE MINIMUM 22" X 30" WITH A MINIMUM HEADROOM OF 30" (IRC R307.1). ACCESS OPENING SHALL BE WEATHER STRIPPED PER WSEC R402.2.4

WHOLE HOUSE VENTILATION  
PER IRC M1505.4.1 THROUGH M1505.4.4  
THE MINIMUM EXHAUST FLOW RATE OF THE EXHAUST SYSTEM SHALL BE 133 CFM (PER TABLE M1505.4.3(1))

MECH. & HOT WATER HEATER NOTES

- IGNITION SOURCE OF MECHANICAL EQUIPMENT TO BE 18" ABOVE THE FINISHED FLOOR (IRC M1303)
- HW TANK SHALL BE STRAPPED SECURELY TO WALL AT UPPER ONE-THIRD AND LOWER ONE-THIRD WHILE MAINTAINING AT LEAST 4" SPACE FROM CONTROLS. (IRC M1307.2)
- HVAC SYSTEMS SHALL COMPLY WITH REQUIREMENTS FOR INTERMITTENT WHOLE HOUSE VENTILATION INTEGRATED WITH FORCE AIR SYSTEM PER SECTION IRC M1508.5

LEGEND

- CONCRETE WALL
- EXTERIOR WALL 2X
- ELEMENT ABOVE
- SMOKE DETECTOR
- COMBINED SMOKE & CARBON MONOXIDE DETECTOR
- HEAT ALARM
- FAN MIN. KITCHEN- 100CFM BATHRM ETC. MIN. 50 CFM


NOTE: CONTRACTOR TO VERIFY ALL EXISTING CONDITIONS IN FIELD

BLDG AREA - ALL STORIES	
LOWER FLOOR	
(E) FINISHED AREAS	1,096
(N) FINISHED AREAS	272
MAIN FLOOR	
(E) FINISHED AREAS	3,244
(E) GARAGE	1,075
(N) FINISHED AREAS	198
UPPER FLOOR	
(E) FINISHED AREAS	789
(N) FINISHED AREAS	967
	<b>7,640 ft<sup>2</sup></b>

LOWER FLOOR PROPOSED  
SCALE: 1/4" = 1'-0"  
0 2' 4' 6'


FILE: 2219 Seifert Remodel and Addition - FINISHED - Worksheet: Arch. A. 2024





GELOTTE HOMMAS DRIVDAHL  
ARCHITECTURE  
2340 130th Ave. NE, Suite 100, Bellevue, WA 98005  
425.628.3081

- EXISTING BUILDING ELEMENTS TO REMAIN
- EXISTING BUILDING ELEMENTS TO BE DEMOLISHED
- PROPOSED BUILDING ELEMENTS



NOTE:  
1. SEMI-CUSTOM CABINETS IN (N) LAUNDRY/MUD ROOM  
2. EXISTING FLOOR CONDITIONS TO BE ASSESSED ON SITE ONCE DEMO IS COMPLETE.

- PLAN NOTES**
- 1) INTERIOR STAIRWAYS SHALL BE ILLUMINATED PER IRC SECTION R303.7. EXTERIOR STAIRWAYS SHALL BE ILLUMINATED PER IRC SECTION R303.8. EXTERIOR STAIRS SHALL BE PROVIDED WITH AN ARTIFICIAL LIGHT SOURCE LOCATED AT THE TOP LANDING OF THE STAIRWAY.
  - 2) RAIL HANDRAILS TO BE 34"-38" ABOVE TREAD NOSING, 1 1/2" FROM WALL, NOT LESS THAN 1 1/4" OR MORE THAN 2" IN DIAMETER PER IRC SECTION R311 & R312
  - 3) RAIL GUARD RAILS SHALL BE MIN 36" HIGH AND HAVE A MAXIMUM OPENING SUCH THAT A 4" SPHERE CANNOT PASS THROUGH PER IRC SECTIONS R312.1.2 & R312.1.3
  - 4) PROTECT ENCLOSED UNDERSTAIR SURFACES WITH MIN 1/2" GYPSUM BOARD PER IRC SECTION R302.7
  - 5) THE GARAGE SHALL BE SEPARATED FROM THE RESIDENCE WITH A MIN 1/2" GYPSUM BOARD OR EQUIV. APPLIED TO THE GARAGE SIDE. 5/8" TYPE 'X' GYPSUM BOARD IS REQUIRED WHERE THERE ARE HABITABLE ROOMS ABOVE THE GARAGE. SUPPORTING COLUMNS, WALLS AND BEAMS USE 1/2" GYPSUM WALL BOARD PER IRC SECTION 302.6
  - 6) OPENINGS BETWEEN THE GARAGE AND RESIDENCE SHALL HAVE A SOLID WOOD, SOLID OR HONEYCOMB-CORE STEEL DOORS NOT LESS THAN 1 3/8" IN THICKNESS OR 25-MIN FIRE-RATED DOORS. ALL DOORS SHALL BE EQUIPPED WITH A SELF-CLOSING OR AUTOMATIC CLOSING DEVICE. PER IRC SECTION R302.5.1
  - 7) CRAWL SPACE UNDER FLOOR AREAS SHALL BE UNVENTILATED AND COMPLY WITH ALL ASPECTS OF IRC R408.3 FOR UNVENTED CRAWL SPACE AS FOLLOWS:  
- CONTINUOUS CLASS 1 VAPOR RETARDER WITH 6" LAPS AT SEAMS AND STEM WALLS, RADON VENTILATION, MECHANICAL VENTILATION AND REQ. CFM OF VENTILATION PER R408.3
  - 8) HOT TUB SHALL BE PROVIDED WITH COVER THAT COMPLIES WITH ASTM F 1346 OR AN APPROVED BARRIER
  - 9) KITCHEN RANGE HOODS CAPABLE OF EXHAUSTING MORE THAN 400 CFM REQUIRE MAKE UP AIR PER IRC M1503.6
  - 10) COMBO ALARMS SHALL BE INSTALLED OUTSIDE SEPARATE SLEEPING AREA IN THE IMMEDIATE VICINITY OF THE BEDROOMS IN ACCORDANCE WITH IRC R314/R315
  - 11) OPEN TOP BLOWER UNITS SHALL BE PROVIDED WITH A METAL EXHAUST HOOD HAVING THICKNESS OF NOT LESS THAN 0.0157 INCH. BLOWER UNITS PERMANENTLY INSTALLED OUTSIDE THE BUILDING ENVELOPE AND HAVING THE COOKING SURFACE AT LEAST 5 FEET BELOW A 1 HOUR FIRE RESISTANCE RATED CEILING SHALL NOT BE REQUIRED TO HAVE AN EXHAUST HOOD (IRC M1503.2.1)
  - 12) ACCESS OPENINGS THROUGH THE CEILING SHALL BE MINIMUM 22" X 30" WITH A MINIMUM HEADROOM OF 30" (IRC R307.1). ACCESS OPENING SHALL BE WEATHER STRIPPED PER WSEC R402.2.4

- WHOLE HOUSE VENTILATION**  
PER IRC M1505.4.1 THROUGH M1505.4.4  
THE MINIMUM EXHAUST FLOW RATE OF THE EXHAUST SYSTEM SHALL BE 133 CFM (PER TABLE M1505.4.3(1))
- MECH. & HOT WATER HEATER NOTES**
1. IGNITION SOURCE OF MECHANICAL EQUIPMENT TO BE 18" ABOVE THE FINISHED FLOOR (IRC M1303)
  2. HW TANK SHALL BE STRAPPED SECURELY TO WALL AT UPPER ONE-THIRD AND LOWER ONE-THIRD WHILE MAINTAINING AT LEAST 4" SPACE FROM CONTROLS. (IRC M1307.2)
  3. HVAC SYSTEMS SHALL COMPLY WITH REQUIREMENTS FOR INTERMITTENT WHOLE HOUSE VENTILATION INTEGRATED WITH FORCE AIR SYSTEM PER SECTION IRC M1508.5

- LEGEND**
- CONCRETE WALL
  - EXTERIOR WALL 2X
  - ELEMENT ABOVE
  - SMOKE DETECTOR
  - COMBINED SMOKE & CARBON MONOXIDE DETECTOR
  - HEAT ALARM
  - FAN MIN. KITCHEN- 100CFM BATHRM ETC. MIN. 50 CFM

NOTE: CONTRACTOR TO VERIFY ALL EXISTING CONDITIONS IN FIELD

BLDG AREA - ALL STORIES	
LOWER FLOOR	
(E) FINISHED AREAS	1,096
(N) FINISHED AREAS	272
MAIN FLOOR	
(E) FINISHED AREAS	3,244
(E) GARAGE	1,075
(N) FINISHED AREAS	198
UPPER FLOOR	
(E) FINISHED AREAS	789
(N) FINISHED AREAS	967
<b>TOTAL</b>	<b>7,640 ft²</b>


**MAIN FLOOR PROPOSED**  
SCALE: 1/4" = 1'-0"

PERMIT SET (03.06.2024)

SEIFERT REMODEL  
3261 67TH AVE SE  
MERCER ISLAND, WA 98040

Job No. 2219  
Project Manager: DG  
Issue Date: 03/06/2024


NO.	DATE	REVISION



MAIN FLOOR PLAN  
PROPOSED

**A2.02**






GELOTTE HOMMAS DRIVDAHL  
ARCHITECTURE  
23401 130th Ave. NE, Suite 100, Bellevue, WA 98005  
425.828.3081

**SEIFERT REMODEL**  
37261 67TH AVE SE  
MERCER ISLAND, WA 98040

Job No. 2219  
Project Manager: DG  
Issue Date: 03/06/2024

NO.	DATE	REVISION




UPPER FLOOR PLAN  
PROPOSED

**A2.03**

© 2023 GELOTTE HOMMAS DRIVDAHL ARCHITECTURE, P.S.

EXISTING BUILDING ELEMENTS TO REMAIN  
EXISTING BUILDING ELEMENTS TO BE DEMOLISHED  
PROPOSED BUILDING ELEMENTS



- PLAN NOTES**
- INTERIOR STAIRWAYS SHALL BE ILLUMINATED PER IRC SECTION R303.7. EXTERIOR STAIRWAYS SHALL BE ILLUMINATED PER IRC SECTION R303.8. EXTERIOR STAIRS SHALL BE PROVIDED WITH AN ARTIFICIAL LIGHT SOURCE LOCATED AT THE TOP LANDING OF THE STAIRWAY.
  - ALL HANDRAILS TO BE 34"-38" ABOVE TREAD NOSING, 1 1/2" FROM WALL, NOT LESS THAN 1 1/4" OR MORE THAN 2" IN DIAMETER PER IRC SECTION R311 & R312
  - ALL GUARD RAILS SHALL BE MIN 36" HIGH AND HAVE A MAXIMUM OPENING SUCH THAT A 4" SPHERE CANNOT PASS THROUGH PER IRC SECTIONS R312.1.2 & R312.1.3
  - PROTECT ENCLOSED UNDERSTAIR SURFACES WITH MIN 1/2" GYPSUM BOARD PER IRC SECTION R302.7
  - THE GARAGE SHALL BE SEPARATED FROM THE RESIDENCE WITH A MIN 1/2" GYPSUM BOARD OR EQUIV. APPLIED TO THE GARAGE SIDE. 5/8" TYPE 'X' GYPSUM BOARD IS REQUIRED WHERE THERE ARE HABITABLE ROOMS ABOVE THE GARAGE. SUPPORTING COLUMNS, WALLS AND BEAMS USE 1/2" GYPSUM WALL BOARD PER IRC SECTION 302.6
  - OPENINGS BETWEEN THE GARAGE AND RESIDENCE SHALL HAVE A SOLID WOOD, SOLID OR HONEYCOMB-CORE STEEL DOORS NOT LESS THAN 1 3/8" IN THICKNESS OR 20-MIN FIRE-RATED DOORS. ALL DOORS SHALL BE EQUIPPED WITH A SELF-CLOSING OR AUTOMATIC CLOSING DEVICE. PER IRC SECTION R302.5.1
  - CRAWL SPACE: UNDERLOOR AREAS SHALL BE UNVENTILATED AND COMPLY WITH ALL ASPECTS OF IRC R408.3 FOR UNVENTED CRAWL SPACE AS FOLLOWS:  
- CONTINUOUS CLASS 1 VAPOR RETARDER WITH 6" LAPS AT SEAMS AND STEM WALLS, RADON VENTILATION, MECHANICAL VENTILATION AND REQ. CFM OF VENTILATION PER R408.3
  - HOT TUB SHALL BE PROVIDED WITH COVER THAT COMPLIES WITH ASTM F-1346 OR AN APPROVED BARRIER
  - KITCHEN RANGE HOODS CAPABLE OF EXHAUSTING MORE THAN 400 CFM REQUIRE MAKE UP AIR PER IRC M1503.6
  - COMBO ALARMS SHALL BE INSTALLED OUTSIDE SEPARATE SLEEPING AREA IN THE IMMEDIATE VICINITY OF THE BEDROOMS IN ACCORDANCE WITH IRC R314/R315
  - OPEN TOP BROILER UNITS SHALL BE PROVIDED WITH A METAL EXHAUST HOOD HAVING THICKNESS OF NOT LESS THAN 0.0157 INCH. BROILER UNITS PERMANENTLY INSTALLED OUTSIDE THE BUILDING ENVELOPE AND HAVING THE COOKING SURFACE AT LEAST 5 FEET BELOW A 1 HOUR FIRE RESISTANCE RATED CEILING SHALL NOT BE REQUIRED TO HAVE AN EXHAUST HOOD (IRC M1503.2.1)
  - ACCESS OPENINGS THROUGH THE CEILING SHALL BE MINIMUM 22" X 30" WITH A MINIMUM HEADROOM OF 30" (IRC R907.1). ACCESS OPENING SHALL BE WEATHER STRIPPED PER WSEC R402.2.4

- WHOLE HOUSE VENTILATION**  
PER IRC M1505.4.1 THROUGH M1505.4.4  
THE MINIMUM EXHAUST FLOW RATE OF THE EXHAUST SYSTEM SHALL BE 133 CFM (PER TABLE M1505.4.3(1))
- MECH. & HOT WATER HEATER NOTES**
- IGNITION SOURCE OF MECHANICAL EQUIPMENT TO BE 18" ABOVE THE FINISHED FLOOR (IRC M1303)
  - HW TANK SHALL BE STRAPPED SECURELY TO WALL AT UPPER ONE-THIRD AND LOWER ONE-THIRD WHILE MAINTAINING AT LEAST 4" SPACE FROM CONTROLS. (IRC M1307.2)
  - HVAC SYSTEMS SHALL COMPLY WITH REQUIREMENTS FOR INTERMITTENT WHOLE HOUSE VENTILATION INTEGRATED WITH FORCE AIR SYSTEM PER SECTION IRC M1508.5


**LEGEND**

- CONCRETE WALL
- EXTERIOR WALL 2X
- ELEMENT ABOVE
- SMOKE DETECTOR
- COMBINED SMOKE & CARBON MONOXIDE DETECTOR
- HEAT ALARM
- FAN MIN. KITCHEN- 100CFM BATHRM ETC. MIN. 50 CFM

NOTE: CONTRACTOR TO VERIFY ALL EXISTING CONDITIONS IN FIELD

BLDG AREA - ALL STORIES	
LOWER FLOOR	
(E) FINISHED AREAS	1,096
(N) FINISHED AREAS	272
MAIN FLOOR	
(E) FINISHED AREAS	3,244
(E) GARAGE	1,075
(N) FINISHED AREAS	198
UPPER FLOOR	
(E) FINISHED AREAS	789
(N) FINISHED AREAS	967
<b>TOTAL</b>	<b>7,640 ft<sup>2</sup></b>

UPPER FLOOR PROPOSED  
SCALE: 1/4" = 1'-0"




FILE: 2219 Seifert Remodel and Addition - FINISHED - Worksheet: ARCH. A. 2024

PERMIT SET (03.06.2024)










GELOTTE HOMMAS DRIVDAHL  
ARCHITECTURE  
2340 130th Ave. NE, Suite 100, Bellevue, WA 98005  
425.828.3081



2 SOUTH ELEVATION PROPOSED  
SCALE: 1/4" = 1'-0"




1 EAST ELEVATION PROPOSED  
SCALE: 1/4" = 1'-0"

PERMIT SET (03.06.2024)

**SEIFERT REMODEL**  
3261 67TH AVE SE  
MERCER ISLAND, WA 98040

Job No. 2219  
Project Manager: DG  
Issue Date: 03/06/2024


NO.	DATE	REVISION




EXTERIOR ELEVATIONS  
PROPOSED

**A3.01**





4 NORTH ELEVATION PROPOSED  
SCALE: 1/4" = 1'-0"



3 WEST ELEVATION PROPOSED  
SCALE: 1/4" = 1'-0"

PERMIT SET (03.06.2024)

SEIFERT REMODEL

3261 67TH AVE SE  
MERCER ISLAND, WA 98040

Job No. 2219  
Project Manager: DG  
Issue Date: 03/06/2024

NO.	DATE	REVISION




EXTERIOR ELEVATIONS  
PROPOSED

A3.02











GEOLITE HOMMAS DRIVDAHL  
ARCHITECTURE  
2340 130th Ave. NE, Suite 100, Bellevue, WA 98005  
425.828.3081



**D BUILDING SECTION**  
SCALE: 1/4" = 1'-0"

- FLOOR**
- FLOOR ASSEMBLY #1**  
(LOCATED AT EXISTING MAIN AND UPPER FLOOR SPACE)
- \* (N) FLOORING PER I.D.
  - \* (E) SUBFLOOR
  - \* (E) FLOOR JOIST
  - \* (N) SOUND INSULATION AS NEEDED
  - \* (N) 5/8" G.W.B. + PVA PRIMER
- FLOOR ASSEMBLY #2**  
(LOCATED AT NEW UPPER FLOOR SPACE)
- \* (N) FLOORING PER I.D.
  - \* (N) SUBFLOOR
  - \* (N) FLOOR JOIST
  - \* (N) SOUND INSULATION AS NEEDED
  - \* (N) 5/8" G.W.B. + PVA PRIMER
- FLOOR ASSEMBLY #3**  
(LOCATED AT LOWER FLOOR AT NEW CONDITIONED SPACES)
- \* (N) FLOORING PER I.D.
  - \* (E) & (N) CONCRETE SLAB
  - \* (N) R-10 RIDGE INSULATION AT NEW LOCATIONS, WHERE POSSIBLE.
  - \* (N) VAPOR BARRIER 10 MIL.
  - \* (N) 5/8" G.W.B. + PVA PRIMER
- ROOF**
- ROOF ASSEMBLY #1**  
(LOCATED AT EXISTING ROOFS)
- \* (E) CEDAR SHAKE SHINGLES
  - \* (E) ROOF UNDERLAYMENT
  - \* (E) ROOF SHEATHING
  - \* (E) TRUSSES OR RAFTERS
  - \* (E) INSULATION (IF CEILING EXPOSED, NEW INSULATION TO COMPLY WITH CURRENT WSEC)
  - \* (E) G.W.B. (NEW G.W.B. IF CEILING EXPOSED, MATCH EXISTING THICKNESS.)
- ROOF ASSEMBLY #2**  
(LOCATED AT NEW UPPER ROOFS)
- \* (N) CEDAR SHAKE SHINGLES
  - \* (N) ROOF UNDERLAYMENT
  - \* (N) ROOF SHEATHING, PER STRUCTURAL
  - \* (N) TRUSSES OR RAFTERS, PER STRUCTURAL
  - \* (N) BATT INSULATION PER CURRENT CODE
  - \* (N) 5/8" G.W.B. + PVA PRIMER
- WALLS**
- WALL ASSEMBLY #1**  
(LOCATED AT EXISTING WALLS)
- \* (E) VERTICAL CEDAR T&G SIDING
  - \* (E) BUILDING PAPER
  - \* (E) WALL SHEATHING
  - \* (E) 2X4 STUD WALL @ 16" O.C.
  - \* (E) INSULATION (IF WALL EXPOSED, NEW INSULATION TO COMPLY WITH CURRENT WSEC)
  - \* (E) G.W.B. (NEW G.W.B. IF WALL EXPOSED, MATCH EXISTING THICKNESS.)
- WALL ASSEMBLY #2**  
(LOCATED AT NEW TYPICAL WALLS)
- \* (N) VERTICAL CEDAR T&G SIDING, MATCH EXISTING
  - \* (E) BUILDING PAPER
  - \* (E) WALL SHEATHING
  - \* (E) 2X4 STUD WALL @ 16" O.C.
  - \* (E) INSULATION (IF WALL EXPOSED, NEW INSULATION TO COMPLY WITH CURRENT WSEC)
  - \* (E) G.W.B. (NEW G.W.B. IF WALL EXPOSED, MATCH EXISTING THICKNESS.)




**C BUILDING SECTION**  
SCALE: 1/4" = 1'-0"

**PERMIT SET (03.06.2024)**

**SEIFERT REMODEL**  
3261 67TH AVE SE  
MERCER ISLAND, WA 98040

Job No. 2219  
Project Manager: DG  
Issue Date: 03/06/2024

NO.	DATE	REVISION



BUILDING SECTIONS

**A4.02**










GELOTTE HOMMAS DRIVDAHL  
ARCHITECTURE  
2340 130th Ave. NE, Suite 100, Bellevue, WA 98005  
425.828.3081

**SEIFERT REMODEL**

3261 67TH AVE SE  
MERCER ISLAND, WA 98040

Job No. 2219  
Project Manager: DG  
Issue Date: 03/06/2024

NO.	DATE	REVISION



WALL SECTIONS


**A5.01**

T.O. PLATE  
49'-4 1/8"


UPPER FLOOR  
41'-3"

MAIN FLOOR  
30'-0"

LOWER FLOOR  
20'-7 1/2"



**C** WALL SECTION  
SCALE: 3/4" = 1'-0"



ATTIC

UPPER FLOOR  
41'-3"


(E) STAIR 2

FLOOR ASSEMBLY #1


(E) REC. ROOM

MAIN FLOOR  
30'-0"

LOWER FLOOR  
20'-7 1/2"



**A** WALL SECTION  
SCALE: 3/4" = 1'-0"





PERMIT SET (03.06.2024)













**2 TYP. EAVE DETAIL**  
SCALE: 1 1/2" = 1'-0"



**1 DECK RAILING & SOFFIT**  
SCALE: 1 1/2" = 1'-0"



**G WALL SECTION**  
SCALE: 1/2" = 1'-0"




PERMIT SET (03.06.2024)

**SEIFERT REMODEL**  
3261 67TH AVE SE  
MERCER ISLAND, WA 98040

Job No. 2219  
Project Manager: DG  
Issue Date: 03/06/2024

NO.	DATE	REVISION



WALL SECTIONS

**A5.03**







## STRUCTURAL NOTES

### GENERAL REQUIREMENTS

**BUILDING CODE & REFERENCE STANDARDS:** The "International Building Code" (IBC), 2018 Edition, as adopted and modified by the City of Mercer Island, governs the design and construction of this project. Reference to a specific section in the Code does not relieve the contractor from compliance with the entire materials referenced standards noted below. The latest edition of the materials reference shall be used.

**SCOPE OF STRUCTURAL WORK:** Structural engineering of an expanded second story and removal of existing first story of a single-family residence.

**DEFINITIONS:** The following definitions apply to these general notes:

- "Structural Engineer of Record" (EOR) – The Structural Engineer who is legally responsible for stamping & signing the structural documents for the project. The EOR is responsible for the design of the Primary Structural System.
- "Specialty Structural Engineer" (SSE) – A Licensed professional Engineer, not the EOR, who performs specialty structural engineering services necessary to complete the structure, who has experience and training in the specific specialty. The General Contractor, subcontractor, or supplier who is responsible for the design, fabrication and installation of specialty-engineered elements shall retain the SSE. Submittals shall be stamped and signed by the SSE. Documents stamped and signed by the SSE shall be completed by or under the direct supervision of the SSE with a PE or SE license issued by the State of Washington.
- "Deferred Submittals" - Deferred Submittal is engineering work to be designed-by-others or bidder-designed.

**NOTE PRIORITIES:** Notes on the individual drawings shall govern over these general notes.

**SPECIFICATIONS:** Refer to the contract specifications for information in addition to that contained in these notes and the structural drawings. Refer to these notes, structural drawings, and architectural drawings which serve as general character and extent of the project.

**STRUCTURAL DETAILS:** The structural drawings are intended to show the general character and extent of the project and are not intended to show all details of the work.

**ARCHITECTURAL DRAWINGS:** Refer to the Architectural drawings for information including, but not limited to: dimensions, elevations, slopes, door and window openings, non-bearing walls, curtain walls, stairs, elevators, curbs, drains, depressions, railings, waterproofing, finishes and other nonstructural items.

**STRUCTURAL RESPONSIBILITIES:** The EOR is responsible for the strength and stability of the Primary Structure in its completed state.

**CONTRACTOR RESPONSIBILITIES:** The contractor is responsible for the means and methods of construction and all job-related safety standards such as OSHA and WISHA. The contractor is responsible for the strength and stability of the structure during construction and shall provide temporary shoring, bracing and other elements required to maintain stability until the structure is completed. It is the contractor's responsibility to be familiar with the work required in the construction documents and the requirements for executing it properly.

**DISCREPANCIES:** In case of discrepancies between these general notes, the contract drawings, and specifications, and/or reference standards, the EOR shall determine which shall govern. Discrepancies shall be brought to the attention of the EOR before proceeding with the work. Accordingly, any conflict in or between the Contract Documents shall not be a basis for adjustment in the Contract Price.

**SITE VERIFICATION:** The contractor shall verify all dimensions and conditions at the site prior to fabrication and/or construction. Conflicts between the drawings and actual site conditions shall be brought to the attention of the EOR before proceeding with the work. All underground utilities shall be determined by the Contractor prior to excavation.

**ADJACENT UTILITIES:** The contractor shall determine the locations of all adjacent underground utilities prior to excavation. Any utility information shown on the drawings and details is approximate and not necessarily complete.

### DESIGN CRITERIA

**CONSTRUCTION LOADS:** Loads on the structure during construction shall not exceed the design loads or the capacity of the partially completed construction.

**DEAD LOAD:**  
Wood Deck with concrete topping = 36 psf  
Wood Floor = 15 psf

**SNOW LOAD:** The roof snow load is determined by using Chapter 7 of ASCE 7-16 in accordance with IBC Section 1608 and with the following factors:  
Ground Snow Load,  $P_g = 10$  psf

**WIND DESIGN:** Wind load is determined using Chapter 28 to 30 of ASCE 7-16 in accordance with IBC Section 1609 with the following factors:  
Basic Wind Speed (3-Second Gust)  $V = 91$  MPH (Ultimate) / 75 MPH (ASD)  
Wind Importance Factor  $I_w = 1.0$  Risk Category = II  
Exposure Category = C  $G_C p_i = \pm 0.18$   
Components & Cladding Pressure = 25.7 PSF (Ultimate) Components & Cladding End Zone Pressure = 31.7 PSF (Ultimate)  
 $K_c = 1.0$

Analysis Procedure - Directional Procedure per ASCE 7, Table 27-2.1

**SEISMIC DESIGN:** Earthquake design is determined using Chapter 12 ASCE 7-16 in accordance with IBC Chapter 16 with the following factors:  
Importance Factor  $I_e = 1.0$   
Risk Category = II  
 $S_s = 1.415$  g  
 $S_1 = 0.492$  g  
Site Class = D Seismic Design Category = D  
Redundancy Factor,  $\rho = 1.3$

Wood Structure  
Basic Seismic Force Resisting System: A-15 (Bearing Wall Systems) Light-framed walls with wood structural panels rated for shear resistance  
Analysis Procedure: Equivalent lateral force procedure, per ASCE 7-16, Section 12.8  
 $R = 6.5$   
 $C_d = 0.15$   
 $C_e = 4$   
 $\alpha = 2.5$

Seismic demands on nonstructural components, structural components engineered as part of deferred submittals, and connections of those components to the primary structure shall be designed in accordance with the aforementioned building code, the general seismic criteria listed above and the requirements of ASCE 7-16.

**DESIGN BASE SHEAR:** Design Base Shear (Seismic Governed) (ASD),  $V = 30.47$  K

### DEFLECTIONS:

Floor Total Load Deflection Limit: L/360  
Floor Live Load Deflection Limit: L/480  
Roof Total Load Deflection Limit: L/240  
Roof Live Load Deflection Limit: L/360  
Operable Partition Support Members: L/600 or 1/4" (whichever is less)

### LIVE LOADS:

Roof (Live) 20 PSF  
Roof (Snow) 25 PSF  
Balconies and Decks 1.5 X occupancy served  $\leq 100$  psf  
Residential Floor 40 PSF

**DEFERRED SUBMITTAL LOADS:** All pre-engineered, pre-fabricated, pre-manufactured, or other products designed by others shall be designed for the tributary dead and live loads plus wind, earthquake, and component, and cladding loads when applicable. Design shall conform to the project drawings and specifications, reference standards, and governing code.

Roof Dead Load 20 PSF  
Top Chord Dead Load 12 PSF  
Bottom Chord Dead Load 8 PSF  
A-15 Bottom Chord Dead Load 18 PSF  
Roof Live Load 20 PSF  
Top Chord Live Load 20 PSF  
Bottom Chord Live Load 10 PSF  
Total Deflection Limit L/240  
Live Load Deflection Limit L/360  
Truss Uplift Load (Cross) 10 PSF

**SUBMITTALS**  
Shop Drawings shall be submitted to the Architect/EOR prior to any fabrication or construction for all structural items as noted below. The contractor shall review and place a shop drawings stamp on the submittal before forwarding to the EOR. Submittals shall be made in time to provide a minimum of one week for review by the EOR. Additional submittals required for this project are specified in the specific sections below. Reference the individual material section for specific information to be included in the submittal.

If the shop drawings differ from or add to the design of the Structural Drawings, they shall bear the seal and signature of the Washington State Registered Professional Engineer who is responsible for the design.

**ALTERNATES:** Product or manufacturer components specified in these drawings are used as the basis of design for this project. Alternates for specified items may be submitted to the EOR for review. However, contractor shall submit a current ICC-ESRIAPMO-ER report identifying that an alternate component has the same or greater load capacity than the specified item.

**SHOP DRAWING REVIEW:** Review by the Architect/EOR is for general compliance with the design contract and the contract documents. Dimensions and quantities are not reviewed by the EOR, and therefore, must be verified by the General Contractor. Markings or comments shall not be construed as relieving the contractor from compliance with the project plans and specifications, nor departures therefrom. The contractor remains responsible for details and accuracy, for confirming and controlling all quantities and dimensions, for selecting fabrication processes; for techniques of assembly, and for performing work in a secure manner. When shop drawings (component design drawings) differ from or add to the requirements of the Structural drawings they shall be designed and stamped by the responsible SSE. Allow one week for EOR review time.

**DEFERRED SUBMITTALS:** Per IBC Section 107.3.4.1, drawings, calculations, and product data for the design and fabrication of items that are designed-by-others shall bear the seal and signature of the Washington State Registered Professional Engineer (SSE) who is responsible for the design and shall be submitted to the Architect/EOR and the building department for review prior to fabrication. Allow one week for EOR review time.

The SSE shall submit stamped and signed calculations and shop drawings to the EOR for review. Review of the SSE's shop drawings is for general compliance with design criteria and compatibility with the design of the primary structure, and does not relieve the SSE of the responsibility for that design. All necessary bracing, ties, anchors, and proprietary products shall be furnished and installed per manufacturer's instructions or the SSE's design drawings and calculations. Submitted drawings shall indicate all reaction forces imparted to the primary structure. The design of the connection to the primary structure is the responsibility of the supplier & SSE. Submitted calculations are for cursory review only and will generally not be returned. Deferred submittals include but are not limited to the following:

Pre-fabricated Wood Roof Trusses/Joints (RTJ)

**NON-STRUCTURAL COMPONENTS:** Design, detailing and anchorage of all nonstructural components shall be in accordance with ASCE 7-16, Chapter 13 and the project specifications. Nonstructural components designed by others shall not induce torsional loading into supporting steel structural members without additional bracing of those members to eliminate torsional forces. Torsional bracing shall be designed by the nonstructural component designer and approved by the EOR. Anchorage to the primary structure is the per the bidder-designer contractor or supplier.

### TESTS & INSPECTIONS

**INSPECTIONS:** All construction is subject to inspection by the Building Official in accordance with IBC Sec 110. The contractor shall coordinate all required inspections with the Building Official. Submit copies of all inspection reports to the Architect/EOR for review. The Building Official may accept inspection and reports by approved inspection agencies in lieu of Building Official's inspections. The contractor shall obtain approval of Building Official to use the third-party inspection agency and contractor shall alert the Architect/EOR as such.

**SPECIAL INSPECTIONS:** In addition to the inspections required by IBC Sec 110, a Special Inspector shall be hired by the Owner as an independent third-party inspector to perform the special inspections per IBC Ch. 17. Special inspections shall be performed by an approved testing agency as outlined in the Special Inspection Schedule, the contract documents, and/or the project specification. Special inspections shall meet the requirements outlined in the specific materials sections of IBC Sec 1703. The contractor is responsible for scheduling the inspections, per the city/Building Official requirements. The EOR shall be independent of the special inspection process. All questions regarding Special Inspections shall be directed to the Building Department or an approved special inspection agency.

Special Inspections shall be performed for the following:

Concrete  
Periodic inspection of reinforcing steel and cast-in-place anchors  
Periodic verification of use of the required design mix.

Steel

Periodic inspection of steel, bolts, nuts and washers' identification marks conform to ASTM standard and weld field material conforms to AWS.

Wood

Periodic inspection of anchor bolts, hold-downs, drag stud connections, nailing steel and spacing.

Periodic verification of moisture content of wood studs, plates, beams, and joists.

Periodic inspection of 2x and 3x bottom plates and plate washers.

**PRE-FABRICATED CONSTRUCTION:** All prefabricated construction shall conform to the inspection requirements of the same material or construction type used for this project.

### SOILS AND FOUNDATIONS

**REFERENCE STANDARDS:** Conform to IBC Chapter 18 "Soils and Foundations."

**GEOTECHNICAL REPORT:** Recommendations contained in "Foundation and Critical Area Considerations" by Geotech Consultants, Inc., dated October 5, 2023, and were used for design.

**GEOTECHNICAL INSPECTION:** The Geotechnical Engineer or third-party inspector shall inspect all prepared soil bearing surfaces prior to placement of concrete and reinforcing steel and provide a letter to the Owner stating that soils are adequate to support the "Allowable Foundation Pressure" shown below. Soil compaction shall be supervised by an approved testing agency or Geotechnical Engineer. Site soil conditions, fill placement, and load-bearing requirements shall be as required by IBC Section 1705.6 and Table 1705.6. Assumed values shall be field verified by the Building Official or the Geotechnical Engineer prior to placing concrete. The Building Official shall be notified of a geotechnical investigation where satisfactory data from adjacent areas is available that demonstrates an investigation is not necessary for any of the conditions in IBC Sections 1803.5.1 - 1803.5.6 and IBC Sections 1803.5.10 - 1803.5.11.

### DESIGN SOIL VALUES:

Allowable Soil Bearing Pressure 2500 PSF DL + LL  
3332 PSF DL + LL + Seismic/Wind  
Retaining Walls  
Passive Lateral Pressure 300 PSF/FT  
Active Lateral Pressure (unrestrained) 30 PSF/FT  
Active Lateral Pressure (restrained) 60 PSF/FT  
Uniform Seismic 8H  
Coefficient of Sliding Friction 0.40

**SLABS-ON-GRADE & FOUNDATIONS:** All slabs-on-grade and foundations shall bear on structural compacted fill or competent native soil per the Geotechnical report or as noted in these documents. Exterior perimeter footings shall bear not less than 18 inches below finish grade, or as required by the Geotechnical Engineer and the Building Official. Interior footings shall bear not less than 12 inches below finish floor.

**FOUNDATION STEM WALLS:** Unless otherwise noted on the drawings, the maximum unbalanced soil condition for all foundation stem walls (difference in elevation between interior and exterior soil grades) shall be 2'-0". Maintain a minimum 8" separation between finish grade and untreated wood framing.

**BACKFILLING:** Backfill behind retaining and foundation walls shall be of free-draining material placed in maximum loose lifts of 12" or as directed by the Geotechnical Report. Backfill behind walls shall not be placed before the wall is properly supported by the fill slab or temporary bracing. Backfill shall be compacted using hand-operated equipment only. The contractor shall refrain from operating heavy equipment behind retaining and foundation walls within a distance equal to or greater than the height of the wall, unless otherwise approved by the EOR. All topsoil between and below surface soil shall be removed from beneath fill supporting concrete slab or parking.

**COMPACTION:** Unless otherwise specified by a Geotechnical Engineer, footings shall be placed on compacted material and shall be well-graded granular material with no more than 5% passing a #200 sieve. Fills placed shall be in maximum 8" lifts and all bearing soils shall be compacted to 95% maximum density at optimum moisture content using the Modified Proctor Test.

### CAST-IN-PLACE CONCRETE

**REFERENCE STANDARDS:** Conform to the latest editions of the following:  
(1) ACI 318 "Building Code Requirements for Structural Concrete and Commentary."  
(2) IBC Chapter 19.

**FIELD REFERENCE:** The contractor shall keep a copy of ACI Field Reference manual, SP-15, "Standard Specifications for Structural Concrete (ACI 301) with Selected ACI and ASTM References."

**CONCRETE MIXTURES:** Conform to ACI 318 Chapter 19 "Concrete: Design and Durability Requirements."

**MATERIALS:** Conform to ACI 318 Chapters 19 & 20.

**SUBMITTALS:** Provide all submittals required by ACI 301 Sec 4.1.2. Submit mix designs for each mix in the table below.

**TABLE OF MIX DESIGN REQUIREMENTS**

Member Strength Test Age Maximum Exposure Maximum Minimum Type/location (psi) (days) Aggregate Classification W/C Ratio Air Content  
Basement walls, foundation walls 2500 28 1" F2, C1 0.45 4.5%  
& concrete retaining walls

**CONCRETE MIXTURES:** Conform to ACI 318 Chapter 19 "Concrete: Design and Durability Requirements."

**MATERIALS:** Conform to ACI 318 Chapters 19 & 20.

**SUBMITTALS:** Provide all submittals required by ACI 301 Sec 4.1.2. Submit mix designs for each mix in the table below.

**TABLE OF MIX DESIGN REQUIREMENTS**

Member Strength Test Age Maximum Exposure Maximum Minimum Type/location (psi) (days) Aggregate Classification W/C Ratio Air Content  
Basement walls, foundation walls 2500 28 1" F2, C1 0.45 4.5%  
& concrete retaining walls

**CONCRETE MIXTURES:** Conform to ACI 318 Chapter 19 "Concrete: Design and Durability Requirements."

**MATERIALS:** Conform to ACI 318 Chapters 19 & 20.

**SUBMITTALS:** Provide all submittals required by ACI 301 Sec 4.1.2. Submit mix designs for each mix in the table below.

**TABLE OF MIX DESIGN REQUIREMENTS**

Member Strength Test Age Maximum Exposure Maximum Minimum Type/location (psi) (days) Aggregate Classification W/C Ratio Air Content  
Basement walls, foundation walls 2500 28 1" F2, C1 0.45 4.5%  
& concrete retaining walls

**CONCRETE MIXTURES:** Conform to ACI 318 Chapter 19 "Concrete: Design and Durability Requirements."

**MATERIALS:** Conform to ACI 318 Chapters 19 & 20.

**SUBMITTALS:** Provide all submittals required by ACI 301 Sec 4.1.2. Submit mix designs for each mix in the table below.

**TABLE OF MIX DESIGN REQUIREMENTS**

Member Strength Test Age Maximum Exposure Maximum Minimum Type/location (psi) (days) Aggregate Classification W/C Ratio Air Content  
Basement walls, foundation walls 2500 28 1" F2, C1 0.45 4.5%  
& concrete retaining walls

**CONCRETE MIXTURES:** Conform to ACI 318 Chapter 19 "Concrete: Design and Durability Requirements."

**MATERIALS:** Conform to ACI 318 Chapters 19 & 20.

**SUBMITTALS:** Provide all submittals required by ACI 301 Sec 4.1.2. Submit mix designs for each mix in the table below.

**TABLE OF MIX DESIGN REQUIREMENTS**

Member Strength Test Age Maximum Exposure Maximum Minimum Type/location (psi) (days) Aggregate Classification W/C Ratio Air Content  
Basement walls, foundation walls 2500 28 1" F2, C1 0.45 4.5%  
& concrete retaining walls

**CONCRETE MIXTURES:** Conform to ACI 318 Chapter 19 "Concrete: Design and Durability Requirements."

**MATERIALS:** Conform to ACI 318 Chapters 19 & 20.

**SUBMITTALS:** Provide all submittals required by ACI 301 Sec 4.1.2. Submit mix designs for each mix in the table below.

**TABLE OF MIX DESIGN REQUIREMENTS**

Member Strength Test Age Maximum Exposure Maximum Minimum Type/location (psi) (days) Aggregate Classification W/C Ratio Air Content  
Basement walls, foundation walls 2500 28 1" F2, C1 0.45 4.5%  
& concrete retaining walls

**CONCRETE MIXTURES:** Conform to ACI 318 Chapter 19 "Concrete: Design and Durability Requirements."

**MATERIALS:** Conform to ACI 318 Chapters 19 & 20.

**SUBMITTALS:** Provide all submittals required by ACI 301 Sec 4.1.2. Submit mix designs for each mix in the table below.

**TABLE OF MIX DESIGN REQUIREMENTS**

Member Strength Test Age Maximum Exposure Maximum Minimum Type/location (psi) (days) Aggregate Classification W/C Ratio Air Content  
Basement walls, foundation walls 2500 28 1" F2, C1 0.45 4.5%  
& concrete retaining walls

**CONCRETE MIXTURES:** Conform to ACI 318 Chapter 19 "Concrete: Design and Durability Requirements."

**MATERIALS:** Conform to ACI 318 Chapters 19 & 20.

**SUBMITTALS:** Provide all submittals required by ACI 301 Sec 4.1.2. Submit mix designs for each mix in the table below.

**TABLE OF MIX DESIGN REQUIREMENTS**

Member Strength Test Age Maximum Exposure Maximum Minimum Type/location (psi) (days) Aggregate Classification W/C Ratio Air Content  
Basement walls, foundation walls 2500 28 1" F2, C1 0.45 4.5%  
& concrete retaining walls

**CONCRETE MIXTURES:** Conform to ACI 318 Chapter 19 "Concrete: Design and Durability Requirements."

**MATERIALS:** Conform to ACI 318 Chapters 19 & 20.

**SUBMITTALS:** Provide all submittals required by ACI 301 Sec 4.1.2. Submit mix designs for each mix in the table below.

**TABLE OF MIX DESIGN REQUIREMENTS**

Member Strength Test Age Maximum Exposure Maximum Minimum Type/location (psi) (days) Aggregate Classification W/C Ratio Air Content  
Basement walls, foundation walls 2500 28 1" F2, C1 0.45 4.5%  
& concrete retaining walls

**CONCRETE MIXTURES:** Conform to ACI 318 Chapter 19 "Concrete: Design and Durability Requirements."

**MATERIALS:** Conform to ACI 318 Chapters 19 & 20.

**SUBMITTALS:** Provide all submittals required by ACI 301 Sec 4.1.2. Submit mix designs for each mix in the table below.

**TABLE OF MIX DESIGN REQUIREMENTS**

Member Strength Test Age Maximum Exposure Maximum Minimum Type/location (psi) (days) Aggregate Classification W/C Ratio Air Content  
Basement walls, foundation walls 2500 28 1" F2, C1 0.45 4.5%  
& concrete retaining walls

**CONCRETE MIXTURES:** Conform to ACI 318 Chapter 19 "Concrete: Design and Durability Requirements."

**MATERIALS:** Conform to ACI 318 Chapters 19 & 20.

**SUBMITTALS:** Provide all submittals required by ACI 301 Sec 4.1.2. Submit mix designs for each mix in the table below.

**TABLE OF MIX DESIGN REQUIREMENTS**

Member Strength Test Age Maximum Exposure Maximum Minimum Type/location (psi) (days) Aggregate Classification W/C Ratio Air Content  
Basement walls, foundation walls 2500 28 1" F2, C1 0.45 4.5%  
& concrete retaining walls

**CONCRETE MIXTURES:** Conform to ACI 318 Chapter 19 "Concrete: Design and Durability Requirements."

**MATERIALS:** Conform to ACI 318 Chapters 19 & 20.

**SUBMITTALS:** Provide all submittals required by ACI 301 Sec 4.1.2. Submit mix designs for each mix in the table below.

**TABLE OF MIX DESIGN REQUIREMENTS**

Member Strength Test Age Maximum Exposure Maximum Minimum Type/location (psi) (days) Aggregate Classification W/C Ratio Air Content  
Basement walls, foundation walls 2500 28 1" F2, C1 0.45 4.5%  
& concrete retaining walls

**CONCRETE MIXTURES:** Conform to ACI 318 Chapter 19 "Concrete: Design and Durability Requirements."

**MATERIALS:** Conform to ACI 318 Chapters 19 & 20.

**SUBMITTALS:** Provide all submittals required by ACI 301 Sec 4.1.2. Submit mix designs for each mix in the table below.

**TABLE OF MIX DESIGN REQUIREMENTS**

Member Strength Test Age Maximum Exposure Maximum Minimum Type/location (psi) (days) Aggregate Classification W/C Ratio Air Content  
Basement walls, foundation walls 2500 28 1" F2, C1 0.45 4.5%  
& concrete retaining walls

**CONCRETE MIXTURES:** Conform to ACI 318 Chapter 19 "Concrete: Design and Durability Requirements."

**MATERIALS:** Conform to ACI 318 Chapters 19 & 20.

**SUBMITTALS:** Provide all submittals required by ACI 301 Sec 4.1.2. Submit mix designs for each mix in the table below.

**TABLE OF MIX DESIGN REQUIREMENTS**

Member Strength Test Age Maximum Exposure Maximum Minimum Type/location (psi) (days) Aggregate Classification W/C Ratio Air Content  
Basement walls, foundation walls 2500 28 1" F2, C1 0.45 4.5%  
& concrete retaining walls

### SUBMITTALS:

(1) Submit shop drawings in accordance with AISC Specification Sec M1 "Shop and Erection Drawings."

### MATERIALS:

Structural WF Shapes ASTM A992,  $F_y = 50$  ksi  
Bars & Plates ASTM A36,  $F_y = 36$  ksi  
Anchor Bolts & Bolts in Wood ASTM A307

Nuts ASTM A563 or ASTM A194, Grade 2H  
Washers (flat or beveled) ASTM F436

Anchor Rods (hooked, headed, threaded/nutted) ASTM F1554, Grade 36  
Threaded Rods ASTM A36,  $F_y = 36$  ksi  
Welded Headed/Threaded Studs (WHS, WTS) ASTM A193

Expansion Anchors E7018, 70 ksi, low hydrogen, typical  
Per Drawings Simpson Strong-Tie

Adhesive Anchors Per Drawings Simpson SET-3G  
Concrete Screws Simpson TITEN HD

**WELDING:** Conform to AWS D1.1, D1.3 & D1.8. Welders shall be certified in accordance with AWS and WABO requirements. Use E70 electrodes of type required for materials to be welded.

**FABRICATION/ERECTION:** Conform to AISC Specification Sec M2 "Fabrication," AISC Code Sec 6 "Fabrication and Delivery" and AISC Code Sec 8 "Quality Control." The fabricator and erector shall maintain a quality control program to the extent deemed necessary so that all of the work is performed in accordance with this Code, the AISC Specification, contract documents, and project specifications.

**SHOP PAINTING:** Conform to AISC 308, AISC Specification Sec M3, and AISC Code Sec 6.5. Do not paint steel to be embedded in concrete. Reprofiled, or concealed by the interior building finish. Do not paint surfaces to be field welded or where slip-critical bolts are specified. All other exterior steel shall be painted with one coat of grey shop primer. All exposed exterior steel shall be painted with an exterior multi-coat system as per the Architect or project specifications or galvanized per section below. Field touch-up painting shall be with primer for exposed interior surfaces and as per the Architect or project specifications for exposed exterior surfaces.

**GALVANIZING:** Where required, all exposed steel outside the building envelope shall be hot-dipped galvanized. Apply field touch-ups per project specifications.

**ERECTION:** Conform to AISC Specification Sec M4 "Erection" and AISC Code Sec 7 "Erection." Steel work shall be carried up true and plumb within the limits defined in AISC 303-16 Sec 7.1.1.

### WOOD FRAMING

**REFERENCE STANDARDS:** Conform to:  
(1) IBC Chapter 23 "WOOD."  
(2) NDS and NDS Supplement - "National Design Specification for Wood Construction."  
(3) ANSI/TPI 1 "National Design Standard for Metal-Plate-Connected Wood Truss Construction."  
(4) BCSP 2013 "Building Component Safety Information."

**ALTERNATES:** Alternates for specified item may be submitted to the EOR for review. Contractor shall submit a current ICC-ESRIAPMO-ER report identifying that an alternate component has the same or greater load capacity than the specified item.

**IDENTIFICATION:** All sawn lumber and pre-manufactured wood products shall be identified by the grade mark or a certificate of inspection issued by the certifying agency.

### MATERIALS:

Sawn Lumber: Conform to grading rules of WWPA, WCLB, or NLGA. Finger jointed studs acceptable at interior non-structural walls only.

Member Size Species Grade  
Studs & Plates 2x, 3x HF No. 2  
Posts 4x HF No. 2  
Joists 2x HF No. 2  
Beams 4x HF No. 2  
Beams 6x DF No. 1  
Posts 6x DF No. 1


Glued Laminated Timber: Conform to AITC 117 "Standard Specifications for Structural Glued Laminated Timber of Softwood Species, Manufacturing and Design" and ANSI/AITC A190.1 "Structural Glued Laminated Timber." Glued laminated member beams shall not be webbed threaded than the stock member of 5000' unless shown otherwise on the plans or specifications.

Member Size Species Stress Class Uses  
Beams 24F









**SEIFERT RESIDENCE**  
 REMODEL  
 3261 67TH AVE SE  
 MERCER ISLAND, WA 98040

PROJECT NAME:

PROJECT #:  
 24005

BY:  
 BCU

DATE:  
 MWD

REVIEWED BY:

DATE:

REVISIONS:

#

DATE

COMMENTS

PERMIT SUBMITTAL

DATE

COMMENTS

PERMIT SUBMITTAL

DATE

COMMENTS

PERMIT SUBMITTAL

DATE

COMMENTS

PERMIT SUBMITTAL

DATE

COMMENTS

PERMIT SUBMITTAL

DATE

COMMENTS

PERMIT SUBMITTAL

DATE

COMMENTS

PERMIT SUBMITTAL

DATE

COMMENTS

PERMIT SUBMITTAL

DATE

COMMENTS

PERMIT SUBMITTAL

DATE

COMMENTS

PERMIT SUBMITTAL


DATE

COMMENTS

PERMIT SUBMITTAL


**FLOOR FRAMING PLAN NOTES**

1. REFERENCE S1.0 FOR STRUCTURAL GENERAL NOTES, DRAWING LIST & ABBREVIATIONS.
2. DIMENSIONS: VERIFY ALL DIMENSIONS AND ELEVATIONS WITH THE ARCHITECTURAL DRAWINGS.
3. ALL DUCTS, CHASES AND PIPE/CONDUIT OPENINGS SHALL BE PER ARCHITECTURAL, MECHANICAL, PLUMBING, ELECTRICAL AND SPRINKLER DRAWINGS. CONTACT EOR FOR APPROVAL OF ANY OPENING NOT SHOWN ON THE STRUCTURAL DRAWINGS. FOR STAIR DETAILS AND GUARDRAILS, REFERENCE ARCHITECTURAL DRAWINGS.
4. CONTRACTOR IS RESPONSIBLE FOR ALL TEMPORARY SHORING.
5. ALL BEAMS ARE FLUSH WITH JOISTS UNO AS "DROP" INDICATING A DROPPED BEAM.
6. PROVIDE FULL HEIGHT SOLID BLOCKING OR DOUBLE JOISTS OVER SHEAR WALLS AND BEARING WALLS AT REPETITIVE FRAMING MEMBERS. AT SHEAR WALLS AND BEARING WALLS PARALLEL TO FRAMING, ALIGN (1) JOIST/BEARING OVER WALL (ADDITIONAL JOISTS MAY BE REQUIRED).
7. EXTERIOR RIM SHALL BE A MINIMUM LSL 1 1/2" x FULL-DEPTH.
8. ALL WOOD EXPOSED TO WEATHER OR IN DIRECT CONTACT WITH CONCRETE SHALL BE PRESSURE-TREATED PER STRUCTURAL GENERAL NOTES.
9. PROVIDE DOUBLE JOISTS AROUND ALL ROOF OPENINGS GREATER THAN 24"OC ONE SIDE.
10. ---HDR--- INDICATES (2) 2x10 TYPICAL HEADER. 6'-0" MAXIMUM HEADER SPAN.
11. PROVIDE SW-6 SHEATHING/NAILING ON EXTERIOR BUILDING, TYPICAL.
12. MATCH BUNDLED STUDS FROM ABOVE & EXTEND TO FOUNDATION.
13. HANGERS: ALL 2x HANGERS TO BE SIMPSON 'LUS' SERIES.
14. JOIST BRIDGING PER JOIST MANUFACTURER, TYP.




**MAIN FLOOR FRAMING PLAN**

SCALE: 1/4" = 1'-0"



**MAIN FLOOR SHEAR WALL KEY PLAN**

SCALE: NTS



**SHEAR WALL KEY PLAN NOTES**

1. VERIFY ALL DIMENSIONS AND ELEVATIONS WITH THE ARCHITECTURAL DRAWINGS.
2. SW-# INDICATES SHEAR WALL TYPE PER 20/S3.0.
3. ---#--- INDICATES TYPICAL HOLDOWN PER 17/S3.0 OR TIEDOWN PER 6/S3.0.
4. CONTRACTOR TO COORDINATE HOLDOWN ANCHOR BOLTS WITH STEEL POST BASE PLATES.
5. PROVIDE FULL HEIGHT SOLID BLOCKING OR DOUBLE JOISTS OVER SHEARWALLS AND BEARING WALLS AT REPETITIVE FRAMING MEMBERS. AT SHEARWALLS AND BEARING WALLS PARALLEL TO FRAMING, ALIGN (1) JOIST OVER WALL (ADDITIONAL JOISTS MAY BE REQUIRED).
6. AT MSTC40 CALLOUT REFERENCE 7/S3.2.

**STRUCTURAL**  
**MAIN FLOOR**  
**FRAMING PLAN**

SHEET NUMBER:

**S 2.1**



**FLOOR FRAMING PLAN NOTES**


- REFERENCE S1.0 FOR STRUCTURAL GENERAL NOTES, DRAWING LIST & ABBREVIATIONS.
- DIMENSIONS: VERIFY ALL DIMENSIONS AND ELEVATIONS WITH THE ARCHITECTURAL DRAWINGS.
- ALL DUCTS, CHASES AND PIPE/CONDUIT OPENINGS SHALL BE PER ARCHITECTURAL, MECHANICAL, PLUMBING, ELECTRICAL AND SPRINKLER DRAWINGS. CONTACT EOR FOR APPROVAL OF ANY OPENING NOT SHOWN ON THE STRUCTURAL DRAWINGS. FOR STAIR DETAILS AND GUARDRAILS, REFERENCE ARCHITECTURAL DRAWINGS.
- CONTRACTOR IS RESPONSIBLE FOR ALL TEMPORARY SHORING.
- ALL BEAMS ARE FLUSH WITH JOISTS UNO AS "DROP" INDICATING A DROPPED BEAM.
- PROVIDE FULL HEIGHT SOLID BLOCKING OR DOUBLE JOISTS OVER SHEAR WALLS AND BEARING WALLS AT REPETITIVE FRAMING MEMBERS AT SHEAR WALLS AND BEARING WALLS PARALLEL TO FRAMING, ALIGN (1) JOIST/BREAM OVER WALL (ADDITIONAL JOISTS MAY BE REQUIRED).
- EXTERIOR RIM SHALL BE A MINIMUM LSL 1 1/2" x FULL-DEPTH.
- ALL WOOD EXPOSED TO WEATHER OR IN DIRECT CONTACT WITH CONCRETE SHALL BE PRESSURE-TREATED PER STRUCTURAL GENERAL NOTES.
- PROVIDE DOUBLE JOISTS AROUND ALL ROOF OPENINGS GREATER THAN 24"OC ONE SIDE.
- HDR INDICATES TYPICAL (2) 2x10 TYPICAL HEADER, 6'-0" MAXIMUM HEADER SPAN.
- PROVIDE SW-6 SHEATHING/NAILING ON EXTERIOR BUILDING, TYPICAL.
- MATCH BUNDLED STUDS FROM ABOVE & EXTEND TO FOUNDATION.
- HANGERS: ALL 2x HANGERS TO BE SIMPSON 'LUS' SERIES.
- JOIST BRIDGING PER JOIST MANUFACTURER, TYP.

**ROOF FRAMING PLAN NOTES**

- REFERENCE S1.0 FOR STRUCTURAL GENERAL NOTES, ABBREVIATIONS & SHEET INDEX.
- VERIFY ALL DIMENSION AND ELEVATIONS WITH THE ARCHITECTURAL DRAWINGS.
- ALL DUCTS, CHASES AND PIPE/CONDUIT OPENINGS SHALL BE PER ARCHITECTURAL, MECHANICAL, PLUMBING, ELECTRICAL AND SPRINKLER DRAWINGS. CONTACT EOR FOR APPROVAL OF ANY OPENING NOT SHOWN ON THE STRUCTURAL DRAWINGS.
- REFERENCE ARCHITECTURAL PLANS FOR ROOF SLOPES, SCUPPERS AND DRAIN LOCATIONS.
- CONTRACTOR RESPONSIBLE FOR ALL TEMPORARY SHORING.
- ALL BEAMS ARE FLUSH WITH JOISTS UNO AS "DROP" INDICATING A DROPPED BEAM.
- PROVIDE FULL HEIGHT SOLID BLOCKING OR DOUBLE JOISTS OVER SHEAR WALLS AND BEARING WALLS AT REPETITIVE FRAMING MEMBERS, AT SHEAR WALLS AND BEARING WALLS PARALLEL TO FRAMING, ALIGN (1) JOIST OVER WALL (ADDITIONAL JOISTS MAY BE REQUIRED).
- PROVIDE SW-6 SHEATHING & NAILING ON EXTERIOR BUILDING, TYPICAL.
- PROVIDE DOUBLE JOISTS AROUND ALL ROOF OPENINGS GREATER THAN 24"OC ONE SIDE.
- REFERENCE 8/S3.1 FOR HEADER SUPPORT JAMBS. PROVIDE MINIMUM (2) 2x STUDS UNO.
- "HDR" INDICATES TYPICAL (2) 2x10 DROPPED HEADER WITH 6'-0" MAXIMUM SPAN.
- BALLOON FRAME ALL WALLS GREATER THAN ONE LEVEL WITHOUT FLOOR OR ROOF SUPPORT. ALL EXTERIOR WALL STUDS 12'-0" HIGH OR GREATER, USE (2) SISTERED STUDS AT 16"OC, UNO.
- ALL WOOD EXPOSED TO WEATHER SHALL BE PRESSURE-TREATED PER STRUCTURAL GENERAL NOTES.
- HORIZONTAL STRAP TIES INDICATED ON THE SHEAR WALL PLANS ARE TO BE CENTERED OVER WALL TOP PLATE AND/OR HEADER, BLOCKING OR BEAM. CONTRACTOR SHALL COORDINATE ADDITIONAL WALL FURRING REQUIRED AT BEAMS AND POSTS WITH CONNECTIONS OR HOLDDOWNS THAT EXCEED THE NOMINAL WALL THICKNESS.
- TYPICAL TOP PLATE SPICE: PROVIDE A MINIMUM 48" LAP W/ 16d @ 6"OC STAGGERED. REFERENCE DETAIL 10/S3.1.
- TRUSS BRACING PER TRUSS MANUFACTURER, TYP.



**17. ROOF TRUSSES SHALL BE DESIGNED FOR THE FOLLOWING CRITERIA:**

- REFER TO THE STRUCTURAL GENERAL NOTES FOR STANDARD DEAD AND LIVE LOADS AND SUBMITTAL INFORMATION.
- TRUSS SUPPLIER IS BIDDER DESIGNED AND RESPONSIBLE FOR FINAL TRUSS LAYOUT AND CONFIGURATION. TRUSS LAYOUT SHOWN IS A SUGGESTED LAYOUT, CHANGES MUST BE SUBMITTED TO THE ENGINEER-OF-RECORD THRU THE ARCHITECT WITH BEARING POINTS AND REACTIONS TO STRUCTURE.
- SHADDED REGION INDICATES APPROXIMATE AREA OF OVER FRAMING. TRUSS MANUFACTURER IS RESPONSIBLE FOR DESIGNING THE OVER FRAMING REQUIRED. TRUSSES SHALL BE DESIGNED TO SUPPORT OVER FRAMING IN ADDITION TO THE STANDARD DESIGN LOADS.
- ALL GIRDER TRUSSES SHALL BE SUPPORTED BY A MINIMUM OF (3) STUDS. TRUSS MANUFACTURER TO SUBMIT TO ENGINEER ALL LOCATIONS WHERE REACTIONS FROM GIRDER TRUSSES EXCEED 10,000 LBS. FOR REVIEW OF COLUMN SUPPORT CAPACITY.
- ALL MULTIPLE STUDS UNDER HIP MASTER AND GIRDER TRUSS ENDS TO CONTINUE TO FOUNDATION.
- PROVIDE SIMPSON H2.5A HURRICANE TIES AT ALL ROOF TRUSSES AND ROOF JOISTS, TYP.




**UPPER FLOOR FRAMING PLAN**

SCALE: 1/4" = 1'-0"




**UPPER FLOOR SHEAR WALL KEY PLAN**

SCALE: NTS



**SHEAR WALL KEY PLAN NOTES**

- VERIFY ALL DIMENSIONS AND ELEVATIONS WITH THE ARCHITECTURAL DRAWINGS.
- INDICATES SHEAR WALL TYPE PER 20/S3.0.
- INDICATES TYPICAL HOLDDOWN PER 17/S3.0 OR TIEDOWN PER 6/S3.0.
- CONTRACTOR TO COORDINATE HOLDDOWN ANCHOR BOLTS WITH STEEL POST BASE PLATES.
- PROVIDE FULL HEIGHT SOLID BLOCKING OR DOUBLE JOISTS OVER SHEARWALLS AND BEARING WALLS AT REPETITIVE FRAMING MEMBERS, AT SHEARWALLS AND BEARING WALLS PARALLEL TO FRAMING, ALIGN (1) JOIST OVER WALL (ADDITIONAL JOISTS MAY BE REQUIRED).



**SEIFERT RESIDNECE**  
REMODEL  
3261 67TH AVE SE  
MERCER ISLAND, WA 98040

PROJECT #	24005
PROJECT NAME	SEIFERT RESIDNECE REMODEL
DATE	03/07/2024
BY	BJU
REVIEWED BY	MWD
DATE	

**STRUCTURAL UPPER FLOOR FRAMING PLAN**


SHEET NUMBER:

**S 2.2**










**NEW FOUNDATION CONNECTION TO EXISTING**

SCALE: NTS

1



**TYPICAL CONCRETE MEMBER INTERSECTIONS**


SCALE: NTS

2

**TYPICAL LAP SPlice & DEVELOPMENT LENGTH SCHEDULE**

SCALE: N.T.S.


3



**TYPICAL REBAR BEND SCHEDULE**

SCALE: NTS

4




**TYPICAL SLAB-ON-GRADE JOINT DETAILS**

SCALE: NTS

5

TIE-DOWN STRAP SCHEDULE							
MARK	STRAP	HEM-FIR STUDS			ALTERNATE		
		MINIMUM END LENGTH	NAILING REQUIRED AT EACH END LENGTH	NAIL SPACING	ALLOWABLE UPLIFT (LBS)	STRAP	CLEAR SPAN
A	CMST14	9"	(8) 16d	1 3/4"	1569	CS16	13"
B	CMST14	14"	(13) 16d	1 3/4"	2550	MSTC40	16"
C	CMST14	19"	(20) 16d	1 3/4"	3924	MSTC52	16"
D	CMST14	28"	(29) 16d	1 3/4"	5690	MSTC66	16"
E	CMST14	30"	(33) 16d	1 3/4"	6475	N/A	N/A


- NOTES:
- FOLLOW ALL SIMPSON STRONG-TIE GUIDELINES NECESSARY TO ACHIEVE FULL ICC DESIGN VALUES.
  - STRAP MAY BE INSTALLED OVER OR UNDERNEATH PLYWOOD.
  - EDGE NAIL PLYWOOD TO STRAPPED POST.
  - WHERE STRAPS OCCUR OVER FLOOR BEAM, SEE 3/S3.2.
  - ADDED BLOCKING MAY BE ELIMINATED WHERE FLOOR FRAMING IS DIRECTLY BETWEEN POSTS.
  - INDICATES FLOOR-TO-FLOOR STRAP ON PLAN.
  - BASED ON SIMPSON CATALOG 2021-2023.



**FLR-TO-FLR HOLDOWN STRAP SCHEDULE**

SCALE: NTS


6



**SHEAR WALL HOLDOWN CONNECTION (NO RIM)**

SCALE: NTS


7



**TYPICAL POST FOOTING WITH PLINTH**

SCALE: NTS


8



**TYPICAL INTERIOR THICKENED SLAB FOOTING AT BEARING / SHEAR WALL**

SCALE: NTS


9



**TYPICAL FOUNDATION FOOTING AND STEM WALL WITH SOG (8" STEM)**

SCALE: NTS


10



**PLAN VIEW - SHEAR WALL HOLDOWNS AT CORNER**

SCALE: NTS


11



**PLAN VIEW - TYPICAL ANCHOR BOLT INSTALLATION**

SCALE: NTS

12




**TYPICAL SHEAR WALL ELEVATION**

SCALE: NTS


13

WOOD-FRAMED SHEAR WALL SCHEDULE											
FOR HEM-FIR FRAMING W/ 8d COMMON NAILS (2018 BIC) & SIMPSON CATALOG 2021-2023											
SW TYPE	WALL SHEATHING APA RATED	EDGE NAILING	BOTTOM PLATE ATTACHMENT	FRAMING CLIP TO WALL BELOW	MINIMUM RIM BOARD THICKNESS	FRAMING AT PANEL EDGES	BLOCKING AT ALL PANEL EDGES	ANCHOR BOLT TO CONCRETE FOUNDATION	SILL PLATE AT FOUNDATION	ALLOWABLE SHEAR WALL CAPACITY (PLF)	
										SEISMIC	WIND
SINGLE-SIDED	SW-6	1 5/8"	8d @ 6"OC	16d SINKER @ 5"OC	LTP5 @ 16"OC	1 1/4"	2x	2x	P.T. 2x	241	339
	SW-4	1 5/8"	8d @ 4"OC	16d SINKER @ 6"OC, STAGGERED	LTP5 @ 10"OC	1 3/4"	2x	2x	P.T. 2x	35.3	495
SW-3	1 5/8"	8d @ 3"OC	16d SINKER @ 6"OC, STAGGERED	LTP5 @ 8"OC	1 3/4"	2x	2x	P.T. 2x	455	637	
											5/8" @ 24"OC
SW-2	1 5/8"	8d @ 2"OC STAGGERED	16d SINKER @ 4"OC, STAGGERED	LTP5 @ 6"OC	3 1/2"	3x	3x -OR- FLAT 2x	P.T. 2x	595	832	
											5/8" @ 32"OC
2SW-4	1 5/8" BOTH SIDES	8d @ 4"OC (1)	16d SINKER @ 5"OC	LTP5 @ 12"OC & A35 @ 12"OC	3 1/2"	3x	3x	P.T. 3x	706	990	
											5/8" @ 18"OC
2SW-3	1 5/8" BOTH SIDES	8d @ 3"OC (1)	16d SINKER @ 4"OC, STAGGERED	LTP5 @ 8"OC & A35 @ 8"OC	3 1/2"	3x	3x	P.T. 3x	911	1274	
											5/8" @ 16"OC

- NOTES:
- ALL NAILS ARE COMMON, UNO, REFERENCE GENERAL STRUCTURAL NOTES FOR NAIL DIAMETER AND LENGTH.
  - REFERENCE SHEAR WALL KEY DETAIL FOR DESCRIPTION OF TERMS.
  - PROVIDE SHEAR WALL SHEATHING AND NAILING FOR ENTIRE LENGTH OF THE WALLS INDICATED ON THE PLANS. ENDS OF SHEAR WALLS ARE TYPICALLY AT WINDOWS, DOORWAYS OR AS SHOWN ON PLAN.
  - EDGE NAILING IS REQUIRED AT ALL HOLDOWN POSTS. EDGE NAILING IS REQUIRED TO EACH STUD USED IN BUILT-UP HOLDOWN POSTS. REFERENCE HOLDOWN SCHEDULE & DETAILS FOR ADDITIONAL INFORMATION.
  - INTERMEDIATE FRAMING TO BE 2x MINIMUM MEMBERS UNO IN SCHEDULE. ATTACH SHEATHING TO INTERMEDIATE FRAMING WITH FIELD NAILING AT 12"OC WHERE STUDS ARE SPACED AT 16"OC AND FIELD NAILING AT 6"OC WHERE STUDS ARE SPACED AT 24"OC.
  - SIMPSON STRONG-TIE "A35" MAY BE USED IN LIEU OF "LTP5." "LTP5" CLIPS SHALL BE ORIENTED LENGTHWISE (HORIZONTAL) AT PLATE TO RIM. USE 0.131"Øx1 1/2" NAILS WHERE CLIPS ARE ATTACHED DIRECTLY TO FRAMING. USE 0.131"Øx2 1/2" WHERE CLIPS ARE INSTALLED OVER SHEATHING.
  - (2) 2x STUDS NAILED TOGETHER MAY BE USED IN PLACE OF SINGLE 3x STUD. DOUBLE 2x STUDS SHALL BE SECURED TOGETHER WITH FASTENERS OF THE SAME DIAMETER AND SPACING AS THE BOTTOM PLATE ATTACHMENT PER SCHEDULE.
  - ANCHOR BOLTS SHALL BE PROVIDED WITH HOT-DIPPED GALVANIZED STEEL PLATE WASHERS PER 12/S3.0. EMBED ANCHOR BOLTS 7" MINIMUM INTO THE CONCRETE. PROVIDE AN ANCHOR BOLT AT EACH END OF EACH PLATE AND SHALL BE AT LEAST 7 TIMES THE ANCHOR BOLT DIAMETER FROM THE ENDS OF THE PLATE, BUT NOT MORE THAN 1/2 THE TABULATED ANCHOR BOLT SPACING OR 12", WHICHEVER IS LESS. SEE ANCHOR BOLT DETAIL FOR PLATE WASHER REQUIREMENTS. [ALT: 5/8"Øx8" TITEN HD ANCHOR SCREWS MAY BE USED IN LIEU OF ANCHOR BOLTS AT EXISTING CONCRETE, WITH PLATE WASHER & SPACING REQUIREMENTS PER SCHEDULE.]
  - PROVIDE HOT-DIPPED GALVANIZED NAILS AND CONNECTOR PLATES (FRAMING ANGLES, ETC.) AT ALL PRESSURE TREATED LUMBER.
  - PANELS MAY BE INSTALLED HORIZONTALLY IF STUDS ARE SPACED AT 16"OC MAX.
  - THE TOP EDGE OF THE WOOD STRUCTURAL PANEL SHALL BE ATTACHED TO THE UPPER TOP PLATE WITH EDGE NAILING. ROOF OR UPPER LEVEL UPLIFT CONNECTORS SHALL BE ON THE SAME SIDE OF THE WALL AS THE SHEATHING.
  - THE BOTTOM EDGE OF THE WOOD STRUCTURAL PANEL SHALL EXTEND TO AND BE ATTACHED TO THE BOTTOM OR SILL PLATE WITH EDGE NAILING.
  - REFERENCE DETAIL BELOW FOR STAGGERED NAIL AND SCREW SPACING AT RIM BOARDS.
  - WALL TYPE ACCEPTABLE WITH TRUSJOIST AND BOISE CASCADE RIM JOIST AND BLOCKING.
  - WHERE SHEATHING IS APPLIED ON BOTH SIDES OF A SHEAR WALL AND NAIL SPACING IS LESS THAN 6"OC ON EITHER SIDE, THE WIDTH OF THE NAILED FACE OF THE FRAMING MEMBER SHALL BE 3x OR GREATER AT ADJOINING PANEL EDGES AND NAILS AT ALL PANEL EDGES SHALL BE STAGGERED. ALTERNATIVELY, PANELS SHALL BE STAGGERED SO THAT EDGE JOINTS ON OPPOSITE SIDES ARE NOT LOCATED ON THE SAME STUD.
  - INDICATES FORCE TRANSFER AROUND OPENING (FTAO) SHEAR WALL. NAILING PER CORRESPONDING SHEAR WALL REQUIREMENTS ON SCHEDULE. REFERENCE 16/S3.0 FOR ADDITIONAL DETAIL REQUIREMENTS.



**SHEAR WALL KEY DETAIL**



**TYPICAL HOLDDOWN ANCHOR INSTALLATION**

SCALE: NTS

16


HOLDOWN SCHEDULE (HF-WIND)					
MARK	MODEL #	ALLOWABLE UPLIFT (LBS)	MIN END STUDS	STUD FASTENERS	CONCRETE ANCHOR
2	HDU2-SDS2.5	2215	(2) 2x	(6) 1/4"Øx2 1/2" SDS	5/8" ATR W/ 4" EMBED EPOXY @ (E) & PER NOTE 4 @ (N)
11	HDU11-SDS2.5	8030	(4) 2x OR 6x	(30) 1/4"Øx2 1/2" SDS	1 7/8" ATR W/ 9" EMBED (H)

- NOTES:
- HOLDOWNS SPECIFIED ARE AS MANUFACTURED BY SIMPSON STRONG-TIE CO. INC.; ACCEPTABLE EQUIVALENT PRODUCT SUBSTITUTIONS ARE AVAILABLE FROM OTHER MANUFACTURERS WITH EOR APPROVAL. FOLLOW ALL MANUFACTURER GUIDELINES NECESSARY TO ACHIEVE FULL ICC DESIGN VALUES.
  - REFERENCE PLANS FOR ADDITIONAL STUD REQUIREMENTS WHERE OCCURS.
  - HOLDOWN SHALL BE INSTALLED TIGHT TO STUDS WITHOUT FILLERS OR NOTCHING. DO NOT BEND ANCHORS.
  - PROVIDE 1/4"x3"SO PLATE WASHER IN BETWEEN STANDARD DOUBLE NUTS. EMBED LENGTH (Le) EQUAL TO TOP OF CONCRETE DOWN TO TOP OF PLATE WASHER.
  - INDICATES HOLDOWN ON PLAN, TYP.
  - CONTRACTOR TO COORDINATE WHERE "R" HOLDOWNS ARE REQUIRED.
  - BASED ON SIMPSON CATALOG 2021-2023

**HOLDOWN SCHEDULE (8" MIN STEM WALL)**

SCALE: NTS

17



**TYPICAL FTAO SHEAR WALL ELEVATION**

SCALE: NTS

18

**WOOD-FRAMED SHEAR WALL SCHEDULE**

SCALE: NONE

**(2) ROWS BOTTOM PLATE NAILING**

**(3) ROWS BOTTOM PLATE NAILING**

**DEI DIBBLE ENGINEERS INC**  
www.dibbleengineers.com  
1039 Market Street, Kirkland, WA 98033  
425.828.4200

SEAL:

**SEIFERT RESIDENCE REMODEL**  
3261 67TH AVE SE  
MERCER ISLAND, WA 98040

PROJECT NAME: SEIFERT RESIDENCE REMODEL  
PROJECT # 24005  
DRAWN BY: BDU  
REVIEWED BY: MWD  
DATE: 03/07/2024  
PERMIT SUBMITTAL

REVISIONS:  
# DATE COMMENTS  
1 03/07/2024 PERMIT SUBMITTAL

SHEET TITLE: STRUCTURAL SECTIONS & DETAILS  
SHEET NUMBER: S3.0

1608



















FIGURE 1: EXISTING SITE PLAN  
 PRELIMINARY SHORELINE MITIGATION PLAN  
 SEIFERT PROPERTY  
 3261 67TH AVE. SE  
 MERCER ISLAND, WA 98040  
 PARCEL 370890-0065


**PLAN LEGEND**

- PROPERTY LINE
- ..... LAKE ORDINARY HIGH WATER
- 25' SHORELINE BUFFER
- 50' SHORELINE SETBACK
- PIPED WATERCOURSE
- 45' PIPED WATERCOURSE STRUCTURE SETBACK




**NOTES**

1. BASE INFORMATION PROVIDED BY GELOTTE, HOMMAS, DRIVDAHL ARCHITECTURE, P.O. BOX 160, KIRKLAND, WA 98083, 425.828.3081.



**Altmann Oliver Associates, LLC**  
 Environmental Planning & Landscape Architecture  
 PO Box 578 - Camanion, WA 98014  
 Office (425) 333-4338 Fax (425) 333-4399







**SHORELINE VEGETATIVE AREA CALCS**

**PLAN LEGEND**

	AREA A - 5' SHORELINE VEGETATIVE BUFFER - 584 SF
	AREA B - 20' SHORELINE VEGETATIVE BUFFER - 1,645 SF
	PLANTING AREA WITHIN THE 20' VEGETATIVE BUFFER - 1,206 SF
	EXISTING BEACH GRAVELS - 253 SF
	EXISTING IMPERVIOUS WITHIN THE 20' VEGETATIVE BUFFER - 421 SF



**CONCEPTUAL SHORELINE VEGETATIVE PLANTING PLAN**



**NOTES**

1. BASE INFORMATION PROVIDED BY GELOTTE, HOMMAS, DRIVDAHL ARCHITECTURE, P.O. BOX 160, KIRKLAND, WA 98083, 425.828.3081.
2. BULKHEAD AND GRAVELS WILL NOT BE ABLE TO BE PLANTED DUE TO WAVE ACTION AND WIND.

**CANDIDATE PLANT LIST**

**TREES**

COMMON NAME
VINE MAPLE
SHORE PINE

**SHRUBS**


COMMON NAME
RED-OSIER DOGWOOD
BLACK TWIN-BERRY
COMPACT OREGON GRAPE
PACIFIC WAX MYRTLE
OCEAN SPRAY
CLUSTERED ROSE
SNOWBERRY

**H GROUNDCOVER**

COMMON NAME
SLOUGH SEDGE
COAST STRAWBERRY
SALAL

PROJECT	7217
DRAWN	SO
SCALE	AS NOTED
DATE	3-07-24
REVISION	2/2

FIGURE 2: SHORELINE CALCS & PLANTING PRELIMINARY SHORELINE MITIGATION PLAN SEIFERT PROPERTY 3261 67TH AVE. SE MERCER ISLAND, WA 98040 PARCEL 370890-0065



**Almann Oliver Associates, LLC**  
 Environmental Planning & Landscape Architecture  
 PO Box 578 - Camanion, WA 98014  
 Office (425) 333-6338 Fax (425) 333-4599