

PRELIMINARY DRAINAGE REPORT

For

LORENZINI SHORT PLAT
4719 86TH AVE SE Mercer Island, WA



03.11.22

DRS Project No. 21071
Mercer Island Permit No. XXXX

Applicant

Design Built Homes
11400 SE 8th ST, Suite 415
Bellevue, WA 98004

Report Prepared by



D. R. STRONG Consulting Engineers, Inc.
620 7th Ave.
Kirkland WA 98033
(425) 827-3063

Report Issue Date:

March 11, 2022

PRELIMINARY DRAINAGE REPORT

4719 89th AVE SE SHORT PLAT

TABLE OF CONTENTS

| | |
|---|-----------|
| SECTION I: PROJECT OVERVIEW | 1 |
| General Description | 1 |
| Predeveloped Site Conditions | 1 |
| Developed Site Conditions | 1 |
| Minimum Requirement #1: Preparation of Stormwater Site Plans | 2 |
| Minimum Requirement #2: Construction Stormwater Pollution Prevention (SWPP) | 2 |
| Minimum Requirement #3: Source Control of Pollution..... | 2 |
| Minimum Requirement #4: Preservation of Natural Drainage Systems and Outfalls | 2 |
| Minimum Requirement #5: On-site Stormwater Management..... | 2 |
| Minimum Requirement #6: Runoff Treatment | 4 |
| Minimum Requirement #7: Flow Control | 4 |
| Minimum Requirement #8: Wetlands Protection | 4 |
| Minimum Requirement #9: Operation and Maintenance | 4 |
| Proposed Site Downstream Drainage System..... | 4 |
| SECTION II: SITE MAPS..... | 7 |
| APPENDICES | 18 |
| APPENDIX A | 19 |
| APPENDIX B | 21 |
| APPENDIX C | 22 |

List of Figures

| | |
|-----------------------------------|----|
| Figure 1 Vicinity Map..... | 8 |
| Figure 2 Predeveloped Figure..... | 9 |
| Figure 3 Developed Figure..... | 10 |
| Figure 4 Soils Map | 11 |
| Figure 5 Downstream Map | 17 |

SECTION I: PROJECT OVERVIEW

GENERAL DESCRIPTION

The Site is located at 4719 86th Ave SE, Mercer Island Washington, also known as Tax Parcel Numbers 7598100420. Project is the subdivision one existing parcel into two single-family residential lots. Access to project will be along 89th Ave SE where it connects with the existing roadway facility; the second lot will be accessed from a proposed private drive located along the northern edge of the property line. The Project is required to meet the standards in the 2019 Department of Ecology Stormwater Management Manual for Western Washington. The existing residence will be removed.

PREDEVELOPED SITE CONDITIONS

The total area of the existing parcel is 28,644 s.f. (0.658 ac). The total project area is 29,138 s.f. (0.669 ac). The Site is currently developed with a single-family residence, driveways and landscaping. Vegetation consists of lawn and landscaping with evergreen and deciduous trees. There are no critical areas identified on the Site.

The Site is encompassed in one Threshold Discharge Area (TDA). This TDA consists of one Natural Discharge Areas (NDA) and one Natural Discharge Locations (NDL). The topography of NDA 1 slopes from a high point in the north east corner of the site at approximately 12.2% within Lot 1 to 4.4% within Lot 2; runoff travels southwest along the western property line exiting the Site through sheet flow along the southwest property corner and continues southwest through the existing stormwater conveyance system in SE 47th PL. The system along SE 47th PL conveys runoff until it outfalls to Lake Washington.

The USDA Web Soil Survey describes the soil on Site as Arents, Alderwood material, 6 to 15 percent slopes (AmC - 6-15% slopes), Kitsap silt loam, 2 to 8 percent slopes and Kitsap silt loam, 15 to 30 percent slopes.

DEVELOPED SITE CONDITIONS

The applicant is seeking approval for development of 28,644 s.f. (0.658 ac) into two single-family residential lots through the City of Mercer Island short plat process (Project), with lot sizes of 13,670 and 14,974 s.f. (Project). Lots 1 and 2 will contain new development; Lot 1 will contain a 20qwide shared use driveway. Lot 2 will access the lot from the shared driveway. A total of 4,002 s.f. of pavement will be provided for access to Lots 1 and 2. The existing residence will be removed. A total of 5,097 CF of volume is required for flow control; accordingly, all runoff is being routed to a 110-foot long, 8-foot diameter tank.

The Project is located in R-9.6 zoning, which has a minimum lot area of 9,600 s.f. Maximum impervious is limited to 40% per lot and the maximum lot coverage by structure is limited to 40% per lot.

- Total area of land-disturbing activities = 29,138 s.f.
- Total Lot Impervious Area Allowed = 11,457 s.f. (40% of Site area)
- Total Impervious Area Added = 11,951 s.f.

Applicable Minimum Requirements for the Project are determined by Flow chart (see Appendix A). The Project is defined as new development and therefore does not qualify for Redevelopment thresholds.

The Project will result in more than 2,000 s.f. of new, replaced, and new plus replaced impervious surfaces. Lots 1 and 2 will provide 11,457 s.f. of impervious surfaces; accordingly, all minimum requirements apply to the new and replaced hard surfaces and the land disturbed.

Minimum Requirement #1: Preparation of Stormwater Site Plans

This Stormwater Site Plan has been prepared in accordance with the 2019 Department of Ecology Stormwater Management Manual for Western Washington.

Minimum Requirement #2: Construction Stormwater Pollution Prevention (SWPP)

The Project will comply with the Construction SWPP thirteen elements. An erosion control plan will be provided with each building permit.

Minimum Requirement #3: Source Control of Pollution

All known, available, and reasonable source control BMPs will be applied to this Project.

Minimum Requirement #4: Preservation of Natural Drainage Systems and Outfalls

The natural drainage patterns will be maintained for this Project. Surface runoff will be collected for flow control and discharged to the existing system in SE 47th PL.

Minimum Requirement #5: On-site Stormwater Management

The project will apply On-site Stormwater Management BMPs in accordance with the project thresholds, standards, and lists found in Table 1-3-2 of the 2019 Department of Ecology Stormwater Management Manual for Western Washington. For the process of selecting on-site BMPs see Appendix A.

Since all nine minimum requirements are triggered by this project, On-site Stormwater Management BMPs from List #2 will be applied according to feasibility to each type of surface. The result of the selection process for Lot 1 is outlined below.

Lawn and Landscaped Areas:

- Post-Construction Soil Quality and Depth BMP T5.13 will be applied to all feasible areas in accordance with the 2019 Department of Ecology Stormwater Management Manual for Western Washington. See soil management plan, below.

Roofs:

- Full Dispersion: Not feasible as there is not enough available area that is in the native or forested condition.
- Full Infiltration: Not permitted per Mercer Island infiltration feasibility map.
- Bioretention: Not feasible due to the lack of a safe and available overflow pathway to the municipal storm system.
- Downspout Dispersion Systems: A downspout dispersion system consistent with DOE BMP T5.10B will be provided.

Other Hard Surfaces (Driveways/Sidewalks) .

- Full Dispersion: Not feasible as there is not enough available area that is in the native or forested condition.
- Permeable Pavement: Not permitted per Mercer Island infiltration feasibility map.
- Bioretention: Not feasible due to the lack of a safe and available overflow pathway to the municipal storm system.
- Sheet Flow Dispersion: Basic sheet flow dispersion may be utilized to the maximum extent feasible per Figure V-3.2 of the 2019SWMMWW; location of sheet flow dispersion strips to be determined as applicable with final engineering plans.

The result of the BMP selection process for Lot 2 is outlined below.

Lawn and Landscaped Areas:

- Post-Construction Soil Quality and Depth BMP T5.13 will be applied to all feasible areas in accordance with the 2020 SWES. See soil management plan, below.

Roofs:

- Full Dispersion: Not feasible as there is not enough available area that is in the native or forested condition.
- Full Infiltration: Not permitted per Mercer Island infiltration feasibility map.
- Bioretention: Not feasible due to the lack of a safe and available overflow pathway to the municipal storm system.
- Downspout Dispersion Systems: A downspout dispersion system consistent with DOE BMP T5.10B will be provided.

Other Hard Surfaces (Driveways/Sidewalks) .

- Full Dispersion: Not feasible as there is not enough available area that is in the native or forested condition.
- Permeable Pavement: Not permitted per Mercer Island infiltration feasibility map.
- Bioretention: Not feasible due to the lack of a safe and available overflow pathway to the municipal storm system.

- Sheet Flow Dispersion: Basic sheet flow dispersion may be utilized to the maximum extent feasible per Figure V-3.2 of the 2019SWMMWW; location of sheet flow dispersion strips to be determined as applicable with final engineering plans. There are no sidewalks to be constructed along the proposed private drive.

Soil Management Plan

Within the limits of Site disturbance, duff and topsoil will be retained in an undisturbed state and stockpiled for later use to stabilize and amend soils throughout the Site. Post-construction soil amendment will meet the requirements of BMP T5.13 Post-Construction Soil Quality and Depth. Detailed calculation for imported soil amendment compost, if necessary, will be provided during engineering review for the Project.

Minimum Requirement #6: Runoff Treatment

Not applicable for this project. The total effective PGIS for the Project is less than 5,000 s.f. (4,002 s.f.) and therefore, according per the TDA thresholds as outlined in 1-3.4.6 of the 2019 Department of Ecology Stormwater Management Manual for Western Washington, a treatment facility is not applicable.

Minimum Requirement #7: Flow Control

A continuous simulation model, WWHM 2012, was used to analyze the pre- and post-developed runoff rates. The soil type is modeled as hydrologic soil group C for the Alderwood SCS classification as shown in Figure 4. In the pre-developed condition, the entire Site is modeled as %Forest+. In post-development conditions, the soil types are unchanged from the pre-developed conditions. Pursuant to the 2019 Department of Ecology Stormwater Management Manual for Western Washington, Volume III-Appendix C, all areas that meet the soil quality and depth requirement are to be entered into the model as pasture rather than lawn/landscaping; accordingly, landscaped areas are modeled as %Rasture+for this Project. The remaining portions of the developed Site tributary to the proposed detention tank are modeled impervious as appropriate. Results of the WWHM2012 analysis are included in Appendix B.

Minimum Requirement #8: Wetlands Protection

Not applicable to this Project. There are no wetlands on the Project Site nor in the vicinity of the downstream discharge area.

Minimum Requirement #9: Operation and Maintenance

An operation and maintenance manual will be provided at final engineering.

PROPOSED SITE DOWNSTREAM DRAINAGE SYSTEM

Upstream Analysis

In evaluating the upstream area, we reviewed the USGS topographic survey mapping of the area, and field topographic survey, performed by D.R. STRONG Consulting Engineers Inc. The majority of upstream runoff appears to be drained away from the Site. Runoff from the parcel to the north drains toward the west and is either collected

along SE 47th ST or sheet flows across neighboring parcels to the west until it is collected along 84th AVE SE. A negligible amount of stormwater may enter the Project Site over the northern property line before draining to the west, away from the Site. Runoff from parcels to the south drains southwest and away from the Site. In summary, the amount of upstream stormwater the Site is expected to receive is negligible.

Downstream Analysis

The downstream area is located within the Mercer Island Drainage Basin. The downstream area was evaluated by reviewing available resources, and by conducting a field reconnaissance. The field reconnaissance was performed on June 18, 2021 under sunny conditions and no precipitation.

The Site is encompassed in one Threshold Discharge Area (TDA). This TDA consists of one Natural Discharge Areas (NDA) and one Natural Discharge Locations (NDL). The topography of NDA 1 slopes from a high point in the north east corner of the site at approximately 12.2% within Lot 1 to 4.4% within Lot 2; runoff travels southwest along the western property line exiting the Site through as sheet flow along the southwest property corner and continues southwest through the existing stormwater conveyance system in SE 47th PL. The system along SE 47th PL conveys runoff until it outfalls to Lake Washington.

Downstream Path of the NDA 1

Point %A1+ is the natural discharge location where runoff sheet flows over the southwestern property corner of the Site. (0q)

From %A1+to Point %A2+, runoff travels south as surface flow over vegetation. (0q±200q) No flow was observed.

Point %A2+, runoff enters an existing catch basin located in the loop of SE 47TH PL (±200q)

From Point %A2+ to Point %A3+, Runoff continues southwest as pipe flow through a 12-inch diameter concrete pipe. (±260) No flow was observed.

Point %A3+, runoff from the 12-inch PVC converges with an open water course. (±260q)

From Point %A3+ to Point %A4+, Runoff continues west as channelized flow through. (±420) No flow was observed.

Point %A4+, runoff from the channelized flow enters a 12+concrete pipe. (±420q)

From Point %A4+ to Point %A5+, Runoff continues southwest as pipe flow through a stormwater conveyance system. (±515) No flow was observed.

Point %A5+, runoff enters a Type 2 manhole just north of Mercer Way. (±515q)

From Point %A5+ to Point %A6+, Runoff continues southwest as pipe flow through a 12-inch concrete pipe. (±620) No flow was observed.

From Point %A6,+ stormwater outfalls from a 12-inch concrete pipe into an open watercourse (±620)

From Point %A6+to Point %A7+, Runoff continues south as channel flow. (±705) No flow was observed.

From Point %A7,+stormwater enters an 18-inch corrugated metal pipe (±705)

From Point %A7+to Point %A8+, Runoff continues south as pipe flow through an 18-inch corrugated metal pipe. (±725) No flow was observed.

From Point %A8,+stormwater enters a type 1 CB east of 84th Ave SE. (±725)

From Point %A8+to Point %A9+, Runoff continues west as pipe flow through a 12-inch concrete pipe. (±740) No flow was observed.

From Point %A9,+stormwater outfalls from a 12-inch concrete pipe to an open water course (±740)

From Point %A9+to Point %A10+, Runoff continues west as channelized flow through an open water course. (±1320) No flow was observed.

From Point %A10,+stormwater enters an 18-inch corrugated metal pipe where it travels through a series of catch basins, and open water courses until it ultimately outfalls to Lake Washington (±1320)

SECTION II: SITE MAPS

FIGURE 1

VICINITY MAP

4719 86TH AVE SE, MERCER ISLAND, WA





FIGURE 2
PREDEVELOPED FIGURE

TPN 759810-0412

TPN 759810-0411

TPN 759810-0410

- FOUND 1/2" REBAR AND CAP, "LS 22688", 0.15' NORTH AND 0.07' EAST OF PROPERTY CORNER, VISITED JUNE 10, 2021



AREA BREAKDOWN

TOTAL SITE/PROJECT AREA:

29,138 S.F. (0.669 ACRES)

LEGEND


— — — — SITE/PROJECT BOUNDARY



C, PASTURE, MODERATE

29,138 S.F. (0.669 ACRES)

PREDEVELOPED FIGURE
SHORT PLAT
LORENZINI SP
MERCER ISLAND, WA



NORTH

GRAPHIC SCALE


GRAPHIC SCALE

1 INCH = 40 FT.

R:\2021\0\21071\3\Drawings\Plots\Figures\PREDEV21071.dwg 2/25/2022 3:52:36 PM

COPYRIGHT © 2019, D.R. STRONG CONSULTING ENGINEERS INC.

FIGURE 3
DEVELOPED FIGURE



AREA BREAKDOWN

TOTAL SITE/PROJECT AREA:

29,138 S.F. (0.669 ACRES)

LEGEND


— — — — SITE/PROJECT BOUNDARY



| | |
|---------------------------------------|---------------------------|
| <u>LOT 1 & 2 AREA (PROPOSED):</u> | 28,644 S.F. (0.658 ACRES) |
| PERVIOUS: | 17,187 S.F. (0.395 ACRES) |
| IMPERVIOUS: | 11,457 S.F. (0.263 ACRES) |



ROW: 494 S.F. (0.011 ACRES)
PERVIOUS: 0 S.F. (0.000 ACRES)
IMPERVIOUS: 494 S.F. (0.011 ACRES)



NORTH

GRAPHIC SCALE

A horizontal scale bar with tick marks at 0, 20, 40, and 80. A thick black line segment starts at the 0 mark and ends at the 40 mark. Below the scale bar, the text "1 INCH = 40 FT." is written.

COPYRIGHT © 2019, D.R. STRONG CONSULTING ENGINEERS INC.

ENGINEERS PLANNERS SURVEYORS
620 - 79th AVENUE KIRKLAND, WA 98033
O 425.827.3063 F 425.827.2423

DEVELOPED FIGURE

DRAFTED BY: JSK
DESIGNED BY: JSK
PROJECT ENGINEER: MAJ
DATE: 12.23.21
PROJECT NO.: 21071

FIGURE: 03

FIGURE 4 SOILS MAP



King County Area, Washington

AmC—Arents, Alderwood material, 6 to 15 percent slopes

Map Unit Setting

National map unit symbol: 1hmsq

Elevation: 50 to 660 feet

Mean annual precipitation: 35 to 60 inches

Mean annual air temperature: 50 degrees F

Frost-free period: 150 to 200 days

Farmland classification: Prime farmland if irrigated

Map Unit Composition

Arents, alderwood material, and similar soils: 100 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Arents, Alderwood Material

Setting

Landform: Till plains

Parent material: Basal till

Typical profile

H1 - 0 to 26 inches: gravelly sandy loam

H2 - 26 to 60 inches: very gravelly sandy loam

Properties and qualities

Slope: 6 to 15 percent

Depth to restrictive feature: 20 to 40 inches to dense material

Drainage class: Moderately well drained

Capacity of the most limiting layer to transmit water (Ksat): Very low to moderately low (0.00 to 0.06 in/hr)

Depth to water table: About 16 to 36 inches

Frequency of flooding: None

Frequency of ponding: None

Available water supply, 0 to 60 inches: Very low (about 2.3 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 4s

Hydrologic Soil Group: B/D

Hydric soil rating: No

Data Source Information

Soil Survey Area: King County Area, Washington

Survey Area Data: Version 17, Aug 23, 2021

King County Area, Washington

KpB—Kitsap silt loam, 2 to 8 percent slopes

Map Unit Setting

National map unit symbol: 1hmt9

Elevation: 0 to 590 feet

Mean annual precipitation: 37 inches

Mean annual air temperature: 50 degrees F

Frost-free period: 160 to 200 days

Farmland classification: All areas are prime farmland

Map Unit Composition

Kitsap and similar soils: 85 percent

Minor components: 15 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Kitsap

Setting

Landform: Terraces

Parent material: Lacustrine deposits with a minor amount of volcanic ash

Typical profile

H1 - 0 to 5 inches: silt loam

H2 - 5 to 24 inches: silt loam

H3 - 24 to 60 inches: stratified silt to silty clay loam

Properties and qualities

Slope: 2 to 8 percent

Depth to restrictive feature: More than 80 inches

Drainage class: Moderately well drained

Capacity of the most limiting layer to transmit water

(Ksat): Moderately low to moderately high (0.06 to 0.20 in/hr)

Depth to water table: About 18 to 36 inches

Frequency of flooding: None

Frequency of ponding: None

Available water supply, 0 to 60 inches: High (about 11.4 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 3w

Hydrologic Soil Group: C

Ecological site: F002XA004WA - Puget Lowlands Forest

Forage suitability group: Soils with Few Limitations
(G002XN502WA)

Other vegetative classification: Soils with Few Limitations
(G002XN502WA)

Hydric soil rating: No

Minor Components

Alderwood

Percent of map unit: 10 percent
Hydric soil rating: No

Bellingham

Percent of map unit: 3 percent
Landform: Depressions
Other vegetative classification: Wet Soils (G002XN102WA)
Hydric soil rating: Yes

Seattle

Percent of map unit: 1 percent
Landform: Depressions
Other vegetative classification: Wet Soils (G002XN102WA)
Hydric soil rating: Yes

Tukwila

Percent of map unit: 1 percent
Landform: Depressions
Other vegetative classification: Wet Soils (G002XN102WA)
Hydric soil rating: Yes

Data Source Information

Soil Survey Area: King County Area, Washington
Survey Area Data: Version 17, Aug 23, 2021

King County Area, Washington

KpD—Kitsap silt loam, 15 to 30 percent slopes

Map Unit Setting

National map unit symbol: 1hmctc

Elevation: 0 to 590 feet

Mean annual precipitation: 37 inches

Mean annual air temperature: 50 degrees F

Frost-free period: 160 to 200 days

Farmland classification: Farmland of statewide importance

Map Unit Composition

Kitsap and similar soils: 97 percent

Minor components: 3 percent

Estimates are based on observations, descriptions, and transects of the mapunit.

Description of Kitsap

Setting

Landform: Terraces

Parent material: Lacustrine deposits with a minor amount of volcanic ash

Typical profile

H1 - 0 to 5 inches: silt loam

H2 - 5 to 40 inches: silt loam

H3 - 40 to 60 inches: stratified silt to silty clay loam

Properties and qualities

Slope: 15 to 30 percent

Depth to restrictive feature: More than 80 inches

Drainage class: Moderately well drained

Capacity of the most limiting layer to transmit water

(Ksat): Moderately low to moderately high (0.06 to 0.20 in/hr)

Depth to water table: About 18 to 36 inches

Frequency of flooding: None

Frequency of ponding: None

Available water supply, 0 to 60 inches: High (about 11.4 inches)

Interpretive groups

Land capability classification (irrigated): None specified

Land capability classification (nonirrigated): 4e

Hydrologic Soil Group: C

Ecological site: F002XA004WA - Puget Lowlands Forest

Forage suitability group: Sloping to Steep Soils (G002XN702WA)

Other vegetative classification: Sloping to Steep Soils

(G002XN702WA)

Hydric soil rating: No

Minor Components

Bellingham

Percent of map unit: 1 percent

Landform: Depressions

Other vegetative classification: Wet Soils (G002XN102WA)

Hydric soil rating: Yes

Seattle

Percent of map unit: 1 percent

Landform: Depressions

Other vegetative classification: Wet Soils (G002XN102WA)

Hydric soil rating: Yes

Tukwila

Percent of map unit: 1 percent

Landform: Depressions

Other vegetative classification: Wet Soils (G002XN102WA)


Hydric soil rating: Yes

Data Source Information

Soil Survey Area: King County Area, Washington

Survey Area Data: Version 17, Aug 23, 2021


FIGURE 5
DOWNSTREAM MAP




APPENDICES

APPENDIX A

FLOW CHART





APPENDIX B

WWHM Report

WWHM2012

PROJECT REPORT

General Model Information

Project Name: pipe
Site Name: Lorenzini
Site Address:
City:
Report Date: 3/10/2022
Gage: Seatac
Data Start: 1948/10/01
Data End: 2009/09/30
Timestep: 15 Minute
Precip Scale: 1.000
Version Date: 2021/08/19
Version: 4.2.18

POC Thresholds

Low Flow Threshold for POC1: 50 Percent of the 2 Year
High Flow Threshold for POC1: 50 Year

Landuse Basin Data

Predeveloped Land Use

Basin 1

| | |
|-------------------------------------|---------------|
| Bypass: | No |
| GroundWater: | No |
| Pervious Land Use C, Forest, Mod | acre 0.638 |
| Pervious Total | 0.638 |
| Impervious Land Use | acre |
| Impervious Total | 0 |
| Basin Total | 0.638 |

Element Flows To:

| | | |
|---------|-----------|-------------|
| Surface | Interflow | Groundwater |
|---------|-----------|-------------|

Mitigated Land Use

Basin 1

| | |
|--|--------------------------------|
| Bypass: | No |
| GroundWater: | No |
| Pervious Land Use C, Pasture, Flat | acre 0.364 |
| Pervious Total | 0.364 |
| Impervious Land Use ROOF TOPS FLAT DRIVEWAYS MOD SIDEWALKS FLAT | acre 0.178 0.09 0.006 |
| Impervious Total | 0.274 |
| Basin Total | 0.638 |

Element Flows To:

| | | |
|-------------------|---------------------|-------------|
| Surface Tank 1 | Interflow Tank 1 | Groundwater |
|-------------------|---------------------|-------------|

Routing Elements

Predeveloped Routing

Mitigated Routing

Tank 1

Dimensions

Dimensions
Depth: 8 ft.
Tank Type: Circular
Diameter: 8 ft.
Length: 109 ft.

Long... Discharge Structure

Riser Height: 7 ft.
Riser Diameter: 24 in.

Orifice 1 Diameter: 0.410 in. Elevation:0 ft.
Orifice 2 Diameter: 0.670 in. Elevation:4.7 ft.
Orifice 3 Diameter: 0.430 in. Elevation:6 ft.

Element Flows To:

Outlet 2


Tank Hydraulic Table

| Stage(feet) | Area(ac.) | Volume(ac-ft.) | Discharge(cfs) | Infilt(cfs) |
|--------------------|------------------|-----------------------|-----------------------|--------------------|
| 0.0000 | 0.000000 | 0.000000 | 0.000 | 0.000 |
| 0.0889 | 0.004197 | 0.000249 | 0.001 | 0.000 |
| 0.1778 | 0.005902 | 0.000703 | 0.001 | 0.000 |
| 0.2667 | 0.007187 | 0.001286 | 0.002 | 0.000 |
| 0.3556 | 0.008251 | 0.001974 | 0.002 | 0.000 |
| 0.4444 | 0.009171 | 0.002749 | 0.003 | 0.000 |
| 0.5333 | 0.009987 | 0.003601 | 0.003 | 0.000 |
| 0.6222 | 0.010723 | 0.004522 | 0.003 | 0.000 |
| 0.7111 | 0.011394 | 0.005505 | 0.003 | 0.000 |
| 0.8000 | 0.012011 | 0.006546 | 0.004 | 0.000 |
| 0.8889 | 0.012582 | 0.007639 | 0.004 | 0.000 |
| 0.9778 | 0.013114 | 0.008782 | 0.004 | 0.000 |
| 1.0667 | 0.013610 | 0.009970 | 0.004 | 0.000 |
| 1.1556 | 0.014075 | 0.011200 | 0.004 | 0.000 |
| 1.2444 | 0.014511 | 0.012471 | 0.005 | 0.000 |
| 1.3333 | 0.014921 | 0.013779 | 0.005 | 0.000 |
| 1.4222 | 0.015307 | 0.015123 | 0.005 | 0.000 |
| 1.5111 | 0.015671 | 0.016500 | 0.005 | 0.000 |
| 1.6000 | 0.016015 | 0.017908 | 0.005 | 0.000 |
| 1.6889 | 0.016339 | 0.019346 | 0.005 | 0.000 |
| 1.7778 | 0.016645 | 0.020812 | 0.006 | 0.000 |
| 1.8667 | 0.016934 | 0.022305 | 0.006 | 0.000 |
| 1.9556 | 0.017206 | 0.023822 | 0.006 | 0.000 |
| 2.0444 | 0.017463 | 0.025363 | 0.006 | 0.000 |
| 2.1333 | 0.017705 | 0.026926 | 0.006 | 0.000 |
| 2.2222 | 0.017933 | 0.028510 | 0.006 | 0.000 |
| 2.3111 | 0.018146 | 0.030114 | 0.006 | 0.000 |
| 2.4000 | 0.018347 | 0.031736 | 0.007 | 0.000 |
| 2.4889 | 0.018535 | 0.033375 | 0.007 | 0.000 |
| 2.5778 | 0.018710 | 0.035031 | 0.007 | 0.000 |
| 2.6667 | 0.018873 | 0.036701 | 0.007 | 0.000 |
| 2.7556 | 0.019025 | 0.038386 | 0.007 | 0.000 |
| 2.8444 | 0.019165 | 0.040083 | 0.007 | 0.000 |
| 2.9333 | 0.019293 | 0.041792 | 0.007 | 0.000 |
| 3.0222 | 0.019411 | 0.043513 | 0.007 | 0.000 |
| 3.1111 | 0.019518 | 0.045243 | 0.008 | 0.000 |

| | | | | |
|--------|----------|----------|-------|-------|
| 3.2000 | 0.019614 | 0.046982 | 0.008 | 0.000 |
| 3.2889 | 0.019699 | 0.048730 | 0.008 | 0.000 |
| 3.3778 | 0.019775 | 0.050484 | 0.008 | 0.000 |
| 3.4667 | 0.019840 | 0.052245 | 0.008 | 0.000 |
| 3.5556 | 0.019894 | 0.054011 | 0.008 | 0.000 |
| 3.6444 | 0.019939 | 0.055781 | 0.008 | 0.000 |
| 3.7333 | 0.019974 | 0.057555 | 0.008 | 0.000 |
| 3.8222 | 0.019999 | 0.059332 | 0.008 | 0.000 |
| 3.9111 | 0.020013 | 0.061110 | 0.009 | 0.000 |
| 4.0000 | 0.020018 | 0.062890 | 0.009 | 0.000 |
| 4.0889 | 0.020013 | 0.064669 | 0.009 | 0.000 |
| 4.1778 | 0.019999 | 0.066447 | 0.009 | 0.000 |
| 4.2667 | 0.019974 | 0.068224 | 0.009 | 0.000 |
| 4.3556 | 0.019939 | 0.069998 | 0.009 | 0.000 |
| 4.4444 | 0.019894 | 0.071768 | 0.009 | 0.000 |
| 4.5333 | 0.019840 | 0.073534 | 0.009 | 0.000 |
| 4.6222 | 0.019775 | 0.075295 | 0.009 | 0.000 |
| 4.7111 | 0.019699 | 0.077049 | 0.011 | 0.000 |
| 4.8000 | 0.019614 | 0.078797 | 0.013 | 0.000 |
| 4.8889 | 0.019518 | 0.080536 | 0.015 | 0.000 |
| 4.9778 | 0.019411 | 0.082266 | 0.016 | 0.000 |
| 5.0667 | 0.019293 | 0.083987 | 0.017 | 0.000 |
| 5.1556 | 0.019165 | 0.085696 | 0.018 | 0.000 |
| 5.2444 | 0.019025 | 0.087393 | 0.019 | 0.000 |
| 5.3333 | 0.018873 | 0.089078 | 0.020 | 0.000 |
| 5.4222 | 0.018710 | 0.090748 | 0.021 | 0.000 |
| 5.5111 | 0.018535 | 0.092404 | 0.021 | 0.000 |
| 5.6000 | 0.018347 | 0.094043 | 0.022 | 0.000 |
| 5.6889 | 0.018146 | 0.095665 | 0.023 | 0.000 |
| 5.7778 | 0.017933 | 0.097269 | 0.023 | 0.000 |
| 5.8667 | 0.017705 | 0.098853 | 0.024 | 0.000 |
| 5.9556 | 0.017463 | 0.100416 | 0.024 | 0.000 |
| 6.0444 | 0.017206 | 0.101957 | 0.026 | 0.000 |
| 6.1333 | 0.016934 | 0.103474 | 0.027 | 0.000 |
| 6.2222 | 0.016645 | 0.104967 | 0.028 | 0.000 |
| 6.3111 | 0.016339 | 0.106433 | 0.029 | 0.000 |
| 6.4000 | 0.016015 | 0.107871 | 0.030 | 0.000 |
| 6.4889 | 0.015671 | 0.109279 | 0.031 | 0.000 |
| 6.5778 | 0.015307 | 0.110656 | 0.032 | 0.000 |
| 6.6667 | 0.014921 | 0.112000 | 0.033 | 0.000 |
| 6.7556 | 0.014511 | 0.113308 | 0.033 | 0.000 |
| 6.8444 | 0.014075 | 0.114579 | 0.034 | 0.000 |
| 6.9333 | 0.013610 | 0.115809 | 0.035 | 0.000 |
| 7.0222 | 0.013114 | 0.116997 | 0.106 | 0.000 |
| 7.1111 | 0.012582 | 0.118140 | 0.821 | 0.000 |
| 7.2000 | 0.012011 | 0.119233 | 1.923 | 0.000 |
| 7.2889 | 0.011394 | 0.120274 | 3.277 | 0.000 |
| 7.3778 | 0.010723 | 0.121257 | 4.783 | 0.000 |
| 7.4667 | 0.009987 | 0.122178 | 6.346 | 0.000 |
| 7.5556 | 0.009171 | 0.123030 | 7.865 | 0.000 |
| 7.6444 | 0.008251 | 0.123805 | 9.248 | 0.000 |
| 7.7333 | 0.007187 | 0.124493 | 10.41 | 0.000 |
| 7.8222 | 0.005902 | 0.125076 | 11.33 | 0.000 |
| 7.9111 | 0.004197 | 0.125530 | 12.00 | 0.000 |
| 8.0000 | 0.000000 | 0.125779 | 12.50 | 0.000 |
| 8.0889 | 0.000000 | 0.000000 | 13.18 | 0.000 |

Analysis Results

POC 1



Predeveloped Landuse Totals for POC #1

Total Pervious Area: 0.638
Total Impervious Area: 0

Mitigated Landuse Totals for POC #1

Total Pervious Area: 0.364
Total Impervious Area: 0.274

Flow Frequency Method: Log Pearson Type III 17B

Flow Frequency Return Periods for Predeveloped. POC #1

| Return Period | Flow(cfs) |
|----------------------|------------------|
| 2 year | 0.018997 |
| 5 year | 0.031128 |
| 10 year | 0.038928 |
| 25 year | 0.048206 |
| 50 year | 0.054633 |
| 100 year | 0.060636 |

Flow Frequency Return Periods for Mitigated. POC #1

| Return Period | Flow(cfs) |
|----------------------|------------------|
| 2 year | 0.011462 |
| 5 year | 0.01902 |
| 10 year | 0.025767 |
| 25 year | 0.036723 |
| 50 year | 0.046969 |
| 100 year | 0.059298 |

Annual Peaks

Annual Peaks for Predeveloped and Mitigated. POC #1

| Year | Predeveloped | Mitigated |
|-------------|---------------------|------------------|
| 1949 | 0.022 | 0.008 |
| 1950 | 0.026 | 0.014 |
| 1951 | 0.042 | 0.051 |
| 1952 | 0.013 | 0.007 |
| 1953 | 0.011 | 0.008 |
| 1954 | 0.016 | 0.009 |
| 1955 | 0.026 | 0.009 |
| 1956 | 0.021 | 0.019 |
| 1957 | 0.017 | 0.009 |
| 1958 | 0.019 | 0.009 |

| | | |
|------|-------|-------|
| 1959 | 0.016 | 0.008 |
| 1960 | 0.029 | 0.027 |
| 1961 | 0.016 | 0.009 |
| 1962 | 0.010 | 0.007 |
| 1963 | 0.013 | 0.009 |
| 1964 | 0.019 | 0.009 |
| 1965 | 0.013 | 0.013 |
| 1966 | 0.012 | 0.008 |
| 1967 | 0.029 | 0.009 |
| 1968 | 0.016 | 0.009 |
| 1969 | 0.016 | 0.008 |
| 1970 | 0.013 | 0.009 |
| 1971 | 0.014 | 0.010 |
| 1972 | 0.032 | 0.024 |
| 1973 | 0.014 | 0.014 |
| 1974 | 0.015 | 0.010 |
| 1975 | 0.022 | 0.009 |
| 1976 | 0.015 | 0.009 |
| 1977 | 0.002 | 0.007 |
| 1978 | 0.013 | 0.010 |
| 1979 | 0.008 | 0.007 |
| 1980 | 0.037 | 0.025 |
| 1981 | 0.012 | 0.009 |
| 1982 | 0.024 | 0.019 |
| 1983 | 0.021 | 0.010 |
| 1984 | 0.012 | 0.008 |
| 1985 | 0.007 | 0.008 |
| 1986 | 0.033 | 0.018 |
| 1987 | 0.029 | 0.022 |
| 1988 | 0.011 | 0.008 |
| 1989 | 0.008 | 0.007 |
| 1990 | 0.069 | 0.029 |
| 1991 | 0.036 | 0.029 |
| 1992 | 0.015 | 0.010 |
| 1993 | 0.015 | 0.008 |
| 1994 | 0.005 | 0.007 |
| 1995 | 0.021 | 0.011 |
| 1996 | 0.048 | 0.050 |
| 1997 | 0.037 | 0.032 |
| 1998 | 0.009 | 0.008 |
| 1999 | 0.041 | 0.022 |
| 2000 | 0.014 | 0.009 |
| 2001 | 0.003 | 0.007 |
| 2002 | 0.017 | 0.016 |
| 2003 | 0.025 | 0.008 |
| 2004 | 0.027 | 0.029 |
| 2005 | 0.020 | 0.010 |
| 2006 | 0.022 | 0.013 |
| 2007 | 0.052 | 0.043 |
| 2008 | 0.063 | 0.034 |
| 2009 | 0.030 | 0.017 |

Ranked Annual Peaks

Ranked Annual Peaks for Predeveloped and Mitigated. POC #1

| Rank | Predeveloped | Mitigated |
|------|--------------|-----------|
| 1 | 0.0688 | 0.0507 |
| 2 | 0.0634 | 0.0495 |
| 3 | 0.0520 | 0.0428 |

| | | |
|----|--------|--------|
| 4 | 0.0482 | 0.0342 |
| 5 | 0.0415 | 0.0324 |
| 6 | 0.0408 | 0.0293 |
| 7 | 0.0372 | 0.0290 |
| 8 | 0.0371 | 0.0290 |
| 9 | 0.0365 | 0.0274 |
| 10 | 0.0326 | 0.0248 |
| 11 | 0.0315 | 0.0239 |
| 12 | 0.0295 | 0.0224 |
| 13 | 0.0292 | 0.0218 |
| 14 | 0.0287 | 0.0192 |
| 15 | 0.0286 | 0.0189 |
| 16 | 0.0268 | 0.0175 |
| 17 | 0.0260 | 0.0175 |
| 18 | 0.0258 | 0.0164 |
| 19 | 0.0251 | 0.0142 |
| 20 | 0.0241 | 0.0141 |
| 21 | 0.0224 | 0.0134 |
| 22 | 0.0219 | 0.0126 |
| 23 | 0.0215 | 0.0111 |
| 24 | 0.0208 | 0.0098 |
| 25 | 0.0208 | 0.0097 |
| 26 | 0.0206 | 0.0097 |
| 27 | 0.0199 | 0.0096 |
| 28 | 0.0191 | 0.0095 |
| 29 | 0.0186 | 0.0095 |
| 30 | 0.0168 | 0.0094 |
| 31 | 0.0168 | 0.0094 |
| 32 | 0.0164 | 0.0094 |
| 33 | 0.0162 | 0.0094 |
| 34 | 0.0160 | 0.0094 |
| 35 | 0.0160 | 0.0093 |
| 36 | 0.0157 | 0.0092 |
| 37 | 0.0155 | 0.0091 |
| 38 | 0.0154 | 0.0090 |
| 39 | 0.0149 | 0.0087 |
| 40 | 0.0145 | 0.0087 |
| 41 | 0.0145 | 0.0086 |
| 42 | 0.0145 | 0.0086 |
| 43 | 0.0140 | 0.0085 |
| 44 | 0.0135 | 0.0084 |
| 45 | 0.0130 | 0.0084 |
| 46 | 0.0130 | 0.0083 |
| 47 | 0.0128 | 0.0083 |
| 48 | 0.0127 | 0.0081 |
| 49 | 0.0124 | 0.0080 |
| 50 | 0.0122 | 0.0079 |
| 51 | 0.0116 | 0.0079 |
| 52 | 0.0113 | 0.0078 |
| 53 | 0.0105 | 0.0077 |
| 54 | 0.0098 | 0.0075 |
| 55 | 0.0091 | 0.0075 |
| 56 | 0.0079 | 0.0071 |
| 57 | 0.0075 | 0.0069 |
| 58 | 0.0074 | 0.0069 |
| 59 | 0.0049 | 0.0069 |
| 60 | 0.0026 | 0.0067 |
| 61 | 0.0023 | 0.0065 |

Duration Flows

The Facility PASSED

| Flow(cfs) | Predev | Mit | Percentage | Pass/Fail |
|------------------|---------------|------------|-------------------|------------------|
| 0.0095 | 17075 | 10671 | 62 | Pass |
| 0.0100 | 15481 | 6519 | 42 | Pass |
| 0.0104 | 14067 | 6049 | 43 | Pass |
| 0.0109 | 12810 | 5685 | 44 | Pass |
| 0.0113 | 11569 | 5364 | 46 | Pass |
| 0.0118 | 10532 | 5176 | 49 | Pass |
| 0.0122 | 9569 | 4986 | 52 | Pass |
| 0.0127 | 8765 | 4793 | 54 | Pass |
| 0.0131 | 8044 | 4633 | 57 | Pass |
| 0.0136 | 7347 | 4502 | 61 | Pass |
| 0.0141 | 6744 | 4327 | 64 | Pass |
| 0.0145 | 6192 | 4126 | 66 | Pass |
| 0.0150 | 5739 | 3927 | 68 | Pass |
| 0.0154 | 5311 | 3756 | 70 | Pass |
| 0.0159 | 4924 | 3557 | 72 | Pass |
| 0.0163 | 4571 | 3364 | 73 | Pass |
| 0.0168 | 4237 | 3200 | 75 | Pass |
| 0.0172 | 3957 | 3018 | 76 | Pass |
| 0.0177 | 3645 | 2838 | 77 | Pass |
| 0.0182 | 3388 | 2697 | 79 | Pass |
| 0.0186 | 3133 | 2565 | 81 | Pass |
| 0.0191 | 2915 | 2402 | 82 | Pass |
| 0.0195 | 2706 | 2246 | 83 | Pass |
| 0.0200 | 2490 | 2094 | 84 | Pass |
| 0.0204 | 2314 | 1936 | 83 | Pass |
| 0.0209 | 2136 | 1826 | 85 | Pass |
| 0.0214 | 1972 | 1689 | 85 | Pass |
| 0.0218 | 1826 | 1547 | 84 | Pass |
| 0.0223 | 1702 | 1434 | 84 | Pass |
| 0.0227 | 1579 | 1346 | 85 | Pass |
| 0.0232 | 1443 | 1266 | 87 | Pass |
| 0.0236 | 1325 | 1181 | 89 | Pass |
| 0.0241 | 1233 | 1067 | 86 | Pass |
| 0.0245 | 1147 | 932 | 81 | Pass |
| 0.0250 | 1086 | 856 | 78 | Pass |
| 0.0255 | 1020 | 820 | 80 | Pass |
| 0.0259 | 947 | 773 | 81 | Pass |
| 0.0264 | 887 | 736 | 82 | Pass |
| 0.0268 | 824 | 679 | 82 | Pass |
| 0.0273 | 761 | 615 | 80 | Pass |
| 0.0277 | 725 | 566 | 78 | Pass |
| 0.0282 | 674 | 519 | 77 | Pass |
| 0.0286 | 623 | 453 | 72 | Pass |
| 0.0291 | 589 | 391 | 66 | Pass |
| 0.0296 | 549 | 353 | 64 | Pass |
| 0.0300 | 506 | 324 | 64 | Pass |
| 0.0305 | 469 | 292 | 62 | Pass |
| 0.0309 | 427 | 260 | 60 | Pass |
| 0.0314 | 388 | 237 | 61 | Pass |
| 0.0318 | 356 | 217 | 60 | Pass |
| 0.0323 | 328 | 193 | 58 | Pass |
| 0.0327 | 298 | 164 | 55 | Pass |
| 0.0332 | 270 | 129 | 47 | Pass |

| | | | | |
|--------|-----|----|----|------|
| 0.0337 | 241 | 99 | 41 | Pass |
| 0.0341 | 218 | 76 | 34 | Pass |
| 0.0346 | 198 | 47 | 23 | Pass |
| 0.0350 | 174 | 26 | 14 | Pass |
| 0.0355 | 152 | 23 | 15 | Pass |
| 0.0359 | 130 | 19 | 14 | Pass |
| 0.0364 | 119 | 19 | 15 | Pass |
| 0.0369 | 104 | 18 | 17 | Pass |
| 0.0373 | 95 | 16 | 16 | Pass |
| 0.0378 | 83 | 16 | 19 | Pass |
| 0.0382 | 74 | 14 | 18 | Pass |
| 0.0387 | 69 | 12 | 17 | Pass |
| 0.0391 | 61 | 11 | 18 | Pass |
| 0.0396 | 53 | 10 | 18 | Pass |
| 0.0400 | 46 | 10 | 21 | Pass |
| 0.0405 | 39 | 10 | 25 | Pass |
| 0.0410 | 29 | 10 | 34 | Pass |
| 0.0414 | 25 | 10 | 40 | Pass |
| 0.0419 | 22 | 10 | 45 | Pass |
| 0.0423 | 20 | 10 | 50 | Pass |
| 0.0428 | 17 | 8 | 47 | Pass |
| 0.0432 | 14 | 5 | 35 | Pass |
| 0.0437 | 12 | 5 | 41 | Pass |
| 0.0441 | 8 | 5 | 62 | Pass |
| 0.0446 | 7 | 5 | 71 | Pass |
| 0.0451 | 7 | 5 | 71 | Pass |
| 0.0455 | 7 | 5 | 71 | Pass |
| 0.0460 | 6 | 5 | 83 | Pass |
| 0.0464 | 6 | 4 | 66 | Pass |
| 0.0469 | 6 | 3 | 50 | Pass |
| 0.0473 | 6 | 3 | 50 | Pass |
| 0.0478 | 6 | 3 | 50 | Pass |
| 0.0483 | 5 | 3 | 60 | Pass |
| 0.0487 | 5 | 2 | 40 | Pass |
| 0.0492 | 5 | 2 | 40 | Pass |
| 0.0496 | 5 | 1 | 20 | Pass |
| 0.0501 | 5 | 1 | 20 | Pass |
| 0.0505 | 5 | 1 | 20 | Pass |
| 0.0510 | 5 | 0 | 0 | Pass |
| 0.0514 | 4 | 0 | 0 | Pass |
| 0.0519 | 4 | 0 | 0 | Pass |
| 0.0524 | 3 | 0 | 0 | Pass |
| 0.0528 | 3 | 0 | 0 | Pass |
| 0.0533 | 3 | 0 | 0 | Pass |
| 0.0537 | 3 | 0 | 0 | Pass |
| 0.0542 | 3 | 0 | 0 | Pass |
| 0.0546 | 3 | 0 | 0 | Pass |

Water Quality

Water Quality BMP Flow and Volume for POC #1

On-line facility volume: 0 acre-feet

On-line facility target flow: 0 cfs.

Adjusted for 15 min: 0 cfs.

Off-line facility target flow: 0 cfs.

Adjusted for 15 min: 0 cfs.

LID Report

| LID Technique | Used for Treatment ? | Total Volume Needs Treatment (ac-ft) | Volume Through Facility (ac-ft) | Infiltration Volume (ac-ft) | Cumulative Volume Infiltration Credit | Percent Volume Infiltrated | Water Quality | Percent Water Quality Treated | Comment |
|--|--------------------------|--------------------------------------|---------------------------------|-----------------------------|---------------------------------------|----------------------------|---------------|-------------------------------|-----------------------------------|
| Tank 1 POC | <input type="checkbox"/> | 56.66 | | <input type="checkbox"/> | 0.00 | | | | |
| Total Volume Infiltrated | | 56.66 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0% | No Treat. Credit |
| Compliance with LID Standard 8% of 2-yr to 50% of 2-yr | | | | | | | | | Duration Analysis Result = Failed |

Model Default Modifications

Total of 0 changes have been made.

PERLND Changes


No PERLND changes have been made.

IMPLND Changes


No IMPLND changes have been made.

Appendix

Predeveloped Schematic



Mitigated Schematic



Predeveloped UCI File

```
RUN

GLOBAL
  WWHM4 model simulation
  START      1948 10 01          END      2009 09 30
  RUN INTERP OUTPUT LEVEL      3      0
  RESUME     0 RUN    1           UNIT SYSTEM      1
END GLOBAL

FILES
<File> <Un#> <-----File Name----->***  

<-ID->
WDM      26 pipe.wdm
MESSU    25 Prepipe.MES
        27 Prepipe.L61
        28 Prepipe.L62
        30 POCpipe1.dat
END FILES

OPN SEQUENCE
  INGRP          INDELT 00:15
    PERLND      11
    COPY         501
    DISPLAY     1
  END INGRP
END OPN SEQUENCE
DISPLAY
  DISPLAY-INFO1
    # - #-----Title----->***TRAN PIVL DIG1 FIL1 PYR DIG2 FIL2 YRND
    1             Basin 1                   MAX           1   2   30   9
  END DISPLAY-INFO1
END DISPLAY
COPY
  TIMESERIES
    # - # NPT NMN ***
    1           1   1
  501          1   1
  END TIMESERIES
END COPY
GENER
  OPCODE
    # # OPCD ***
  END OPCODE
  PARM
    # # K ***
  END PARM
END GENER
PERLND
  GEN-INFO
    <PLS ><-----Name----->NBLKS Unit-systems Printer ***
    # - #
                  User t-series Engl Metr ***
                  in   out
    11   C, Forest, Mod       1   1   1   1   27   0
  END GEN-INFO
  *** Section PWATER***

ACTIVITY
  <PLS > ***** Active Sections *****
  # - # ATMP SNOW PWAT SED PST PWG PQAL MSTL PEST NITR PHOS TRAC ***
  11   0   0   1   0   0   0   0   0   0   0   0   0   0
END ACTIVITY

PRINT-INFO
  <PLS > ***** Print-flags *****
  # - # ATMP SNOW PWAT SED PST PWG PQAL MSTL PEST NITR PHOS TRAC *****
  11   0   0   4   0   0   0   0   0   0   0   0   0   0   1   9
END PRINT-INFO
```

```

PWAT-PARM1
<PLS > PWATER variable monthly parameter value flags ***
# - # CSNO RTOP UZFG VCS VUZ VNN VIFW VIRG VLE INFC HWT ***
11 0 0 0 0 0 0 0 0 0 0 0 0
END PWAT-PARM1

PWAT-PARM2
<PLS > PWATER input info: Part 2 ***
# - # ***FOREST LZSN INFILT LSUR SLSUR KVARY AGWRC
11 0 4.5 0.08 400 0.1 0.5 0.996
END PWAT-PARM2

PWAT-PARM3
<PLS > PWATER input info: Part 3 ***
# - # ***PETMAX PETMIN INFEXP INFILD DEEPFR BASETP AGWETP
11 0 0 2 2 0 0
END PWAT-PARM3

PWAT-PARM4
<PLS > PWATER input info: Part 4 ***
# - # CEPSC UZSN NSUR INTFW IRC LZETP ***
11 0.2 0.5 0.35 6 0.5 0.7
END PWAT-PARM4

PWAT-STATE1
<PLS > *** Initial conditions at start of simulation
           ran from 1990 to end of 1992 (pat 1-11-95) RUN 21 ***
# - # *** CEPS SURS UZS IFWS LZS AGWS GWVS
11 0 0 0 0 2.5 1 0
END PWAT-STATE1

END PERLND

IMPLND
GEN-INFO
<PLS ><-----Name-----> Unit-systems Printer ***
# - # User t-series Engl Metr ***
          in out ***
END GEN-INFO
*** Section IWATER***

ACTIVITY
<PLS > ***** Active Sections *****
# - # ATMP SNOW IWAT SLD IWG IQAL ***
END ACTIVITY

PRINT-INFO
<ILS > ***** Print-flags ***** PIVL PYR
# - # ATMP SNOW IWAT SLD IWG IQAL *****
END PRINT-INFO

IWAT-PARM1
<PLS > IWATER variable monthly parameter value flags ***
# - # CSNO RTOP VRS VNN RTLI ***
END IWAT-PARM1

IWAT-PARM2
<PLS > IWATER input info: Part 2 ***
# - # *** LSUR SLSUR NSUR RETSC
END IWAT-PARM2

IWAT-PARM3
<PLS > IWATER input info: Part 3 ***
# - # ***PETMAX PETMIN
END IWAT-PARM3

IWAT-STATE1
<PLS > *** Initial conditions at start of simulation
# - # *** RETS SURS
END IWAT-STATE1

```

```

END IMPLND

SCHEMATIC
<-Source->          <-Area-->      <-Target->    MBLK   ***
<Name>   #           <-factor->     <Name>   #   Tbl#   ***
Basin 1***             PERLND    0.638    COPY    501    12
PERLND  11            PERLND    0.638    COPY    501    13

*****Routing*****
END SCHEMATIC

NETWORK
<-Volume-> <-Grp> <-Member-><-Mult-->Tran <-Target vols> <-Grp> <-Member-> ***
<Name>   #           <Name> # #<-factor->strg <Name>   #   #   <Name> # #   ***
COPY    501 OUTPUT MEAN  1 1    48.4        DISPLAY  1       INPUT  TIMSER 1

<-Volume-> <-Grp> <-Member-><-Mult-->Tran <-Target vols> <-Grp> <-Member-> ***
<Name>   #           <Name> # #<-factor->strg <Name>   #   #   <Name> # #   ***
END NETWORK

RCHRES
GEN-INFO
  RCHRES      Name       Nexits   Unit Systems   Printer      ***
  # - #-----><---> User T-series Engl Metr LKFG      ***
                           in   out                                ***
END GEN-INFO
*** Section RCHRES***

ACTIVITY
<PLS > ***** Active Sections *****
# - # HYFG ADFG CNFG HTFG SDFG GQFG OXFG NUFG PKFG PHFG ***
END ACTIVITY

PRINT-INFO
<PLS > ***** Print-flags *****
# - # HYDR ADCA CONS HEAT SED GQL OXRX NUTR PLNK PHCB PIVL PYR ****
END PRINT-INFO

HYDR-PARM1
  RCHRES Flags for each HYDR Section
  # - # VC A1 A2 A3 ODFVFG for each *** ODGTFG for each      ***
    FG FG FG FG possible exit *** possible exit      FUNCT for each
    * * * * * * * * * * * * * * * * * * * * * * * * * * * * * * * * * * * *
END HYDR-PARM1

HYDR-PARM2
  # - # FTABNO      LEN      DELTH      STCOR      KS      DB50      ***
<----><----><----><----><----><----><----><----><---->      ***
END HYDR-PARM2
HYDR-INIT
  RCHRES Initial conditions for each HYDR section
  # - # *** VOL      Initial value of COLIND      Initial value of OUTDGT
    *** ac-ft      for each possible exit      for each possible exit
<----><---->      <----><----><----><----> *** <----><----><----><---->
END HYDR-INIT
END RCHRES

SPEC-ACTIONS
END SPEC-ACTIONS
FTABLES
END FTABLES

EXT SOURCES
<-Volume-> <Member> SsysSgap<-Mult-->Tran <-Target vols> <-Grp> <-Member-> ***
<Name>   # <Name> # tem strg<-factor->strg <Name>   #   #   <Name> # #   ***
WDM      2 PREC      ENGL    1           PERLND   1 999 EXTNL  PREC
WDM      2 PREC      ENGL    1           IMPLND   1 999 EXTNL  PREC

```

```

WDM      1 EVAP      ENGL      0.76          PERLND     1 999 EXTNL    PETINP
WDM      1 EVAP      ENGL      0.76          IMPLND     1 999 EXTNL    PETINP

END EXT SOURCES

EXT TARGETS
<-Volume-> <-Grp> <-Member-><--Mult-->Tran <-Volume-> <Member> Tsys Tgap Amd ***
<Name> # <Name> # #<-factor->strg <Name> # <Name> tem strg strg***  

COPY 501 OUTPUT MEAN 1 1 48.4 WDM 501 FLOW ENGL REPL
END EXT TARGETS

MASS-LINK
<Volume> <-Grp> <-Member-><--Mult--> <Target> <-Grp> <-Member->***  

<Name> <Name> # #<-factor-> <Name> <Name> # #***  

MASS-LINK 12  

PERLND PWATER SURO 0.083333 COPY INPUT MEAN
END MASS-LINK 12

MASS-LINK 13
PERLND PWATER IFWO 0.083333 COPY INPUT MEAN
END MASS-LINK 13

END MASS-LINK

END RUN

```

Mitigated UCI File

```
RUN

GLOBAL
  WWHM4 model simulation
  START      1948 10 01          END      2009 09 30
  RUN INTERP OUTPUT LEVEL      3      0
  RESUME     0 RUN      1
  UNIT SYSTEM      1
END GLOBAL

FILES
<File> <Un#> <-----File Name----->***  

<-ID->
WDM      26 pipe.wdm
MESSU    25 Mitpipe.MES
        27 Mitpipe.L61
        28 Mitpipe.L62
        30 POCpipe1.dat
END FILES

OPN SEQUENCE
  INGRP           INDELT 00:15
    PERLND      13
    IMPLND      4
    IMPLND      6
    IMPLND      8
    RCHRES      1
    COPY         1
    COPY        501
    DISPLAY      1
  END INGRP
END OPN SEQUENCE
DISPLAY
  DISPLAY-INFO1
    # - #<-----Title----->***TRAN PIVL DIG1 FIL1 PYR DIG2 FIL2 YRND
    1           Tank 1             MAX       1   2   30   9
  END DISPLAY-INFO1
END DISPLAY
COPY
  TIMESERIES
    # - # NPT NMN ***
    1           1   1
    501         1   1
  END TIMESERIES
END COPY
GENER
  OPCODE
    # # OPCD ***
  END OPCODE
  PARM
    # # K ***
  END PARM
END GENER
PERLND
  GEN-INFO
    <PLS ><-----Name----->NBLKS Unit-systems Printer ***
    # - #           User t-series Engl Metr ***
                  in out ***
    13      C, Pasture, Flat      1   1   1   27   0
  END GEN-INFO
  *** Section PWATER***

ACTIVITY
  <PLS > ***** Active Sections *****
  # - # ATMP SNOW PWAT SED PST PWG PQAL MSTL PEST NITR PHOS TRAC ***
  13      0   0   1   0   0   0   0   0   0   0   0   0   0
END ACTIVITY

PRINT-INFO
```

```

<PLS > **** Print-flags **** PIVL PYR
# - # ATMP SNOW PWAT SED PST PWG PQAL MSTL PEST NITR PHOS TRAC *****
13      0    0    4    0    0    0    0    0    0    0    0    0    0    0    1    9
END PRINT-INFO

PWAT-PARM1
<PLS > PWATER variable monthly parameter value flags ***
# - # CSNO RTOP UZFG VCS VUZ VNN VIFW VIRG VLE INF C HWT ***
13      0    0    0    0    0    0    0    0    0    0    0    0    0    0
END PWAT-PARM1

PWAT-PARM2
<PLS > PWATER input info: Part 2 ***
# - # ***FOREST LZSN INFILT LSUR SLSUR KVARY AGWRC
13      0        4.5     0.06   400    0.05   0.5    0.996
END PWAT-PARM2

PWAT-PARM3
<PLS > PWATER input info: Part 3 ***
# - # ***PETMAX PETMIN INFEXP INFILD DEEPFR BASETP AGWETP
13      0        0        2        2        0        0        0
END PWAT-PARM3

PWAT-PARM4
<PLS > PWATER input info: Part 4 ***
# - # CEPSC UZSN NSUR INTFW IRC LZETP ***
13      0.15    0.4     0.3       6       0.5    0.4
END PWAT-PARM4

PWAT-STATE1
<PLS > *** Initial conditions at start of simulation
           ran from 1990 to end of 1992 (pat 1-11-95) RUN 21 ***
# - # *** CEPS SURS UZS IFWS Lzs AGWS GWVS
13      0        0        0        0      2.5    1        0
END PWAT-STATE1

END PERLND

IMPLND
GEN-INFO
<PLS ><-----Name-----> Unit-systems Printer ***
# - # User t-series Engl Metr ***
          in out ***
4      ROOF TOPS/FLAT      1    1    1    27    0
6      DRIVEWAYS/MOD       1    1    1    27    0
8      SIDEWALKS/FLAT       1    1    1    27    0
END GEN-INFO
*** Section IWATER***

ACTIVITY
<PLS > ***** Active Sections *****
# - # ATMP SNOW IWAT SLD IWG IQAL ***
4      0    0    1    0    0    0
6      0    0    1    0    0    0
8      0    0    1    0    0    0
END ACTIVITY

PRINT-INFO
<ILS > ***** Print-flags ***** PIVL PYR
# - # ATMP SNOW IWAT SLD IWG IQAL *****
4      0    0    4    0    0    0    1    9
6      0    0    4    0    0    0    1    9
8      0    0    4    0    0    0    1    9
END PRINT-INFO

IWAT-PARM1
<PLS > IWATER variable monthly parameter value flags ***
# - # CSNO RTOP VRS VNN RTL I ***
4      0    0    0    0    0
6      0    0    0    0    0
8      0    0    0    0    0

```

```

END IWAT-PARM1

IWAT-PARM2
<PLS >      IWATER input info: Part 2      ***
# - # *** LSUR     SLSUR     NSUR     RETSC
4          400       0.01      0.1       0.1
6          400       0.05      0.1       0.08
8          400       0.01      0.1       0.1
END IWAT-PARM2

IWAT-PARM3
<PLS >      IWATER input info: Part 3      ***
# - # ***PETMAX    PETMIN
4          0         0
6          0         0
8          0         0
END IWAT-PARM3

IWAT-STATE1
<PLS > *** Initial conditions at start of simulation
# - # *** RETS      SURS
4          0         0
6          0         0
8          0         0
END IWAT-STATE1

END IMPLND

SCHEMATIC
<-Source->           <-Area-->      <-Target->      MBLK      ***
<Name>   #           <-factor->      <Name>   #       Tbl#      ***
Basin   1****
PERLND  13            0.364        RCHRES    1       2
PERLND  13            0.364        RCHRES    1       3
IMPLND  4             0.178        RCHRES    1       5
IMPLND  6             0.09         RCHRES    1       5
IMPLND  8             0.006        RCHRES    1       5

*****Routing*****
PERLND  13            0.364        COPY      1       12
IMPLND  4              0.178        COPY      1       15
IMPLND  6              0.09         COPY      1       15
IMPLND  8              0.006        COPY      1       15
PERLND  13            0.364        COPY      1       13
RCHRES  1              1           COPY      501      16
END SCHEMATIC

NETWORK
<-Volume-> <-Grp> <-Member-><--Mult-->Tran <-Target vols> <-Grp> <-Member-> ***
<Name>   #           <Name>   # #<-factor->strg <Name>   #   #       <Name>   # #   ***
COPY     501 OUTPUT MEAN   1 1   48.4           DISPLAY   1       INPUT   TIMSER 1

<-Volume-> <-Grp> <-Member-><--Mult-->Tran <-Target vols> <-Grp> <-Member-> ***
<Name>   #           <Name>   # #<-factor->strg <Name>   #   #       <Name>   # #   ***
END NETWORK

RCHRES
GEN-INFO
  RCHRES      Name       Nexits   Unit Systems   Printer      ***
  # - #-----><----> User T-series   Engl Metr LKFG      ***
                           in   out
  1     Tank  1           1     1     1     1     28     0     1
END GEN-INFO
*** Section RCHRES***

ACTIVITY
<PLS > **** Active Sections ****
# - # HYFG ADFG CNFG HTFG SDFG GQFG OXFG NUFG PKFG PHFG ***

```

```

1      1   0   0   0   0   0   0   0   0   0   0   0
END ACTIVITY

PRINT-INFO
<PLS > **** Print-flags **** PIVL PYR
# - # HYDR ADCA CONS HEAT SED GQL OXRX NUTR PLNK PHCB PIVL PYR ****
1      4   0   0   0   0   0   0   0   0   0   0   1   9
END PRINT-INFO

HYDR-PARM1
RCHRES Flags for each HYDR Section ****
# - # VC A1 A2 A3 ODFVFG for each *** ODGTFG for each
FG FG FG FG possible exit *** possible exit
* * * * * * * * * * * * * *
1      0   1   0   0   4   0   0   0   0   0   0   2   2   2   2   2
END HYDR-PARM1

HYDR-PARM2
# - # FTABNO LEN DELTH STCOR KS DB50 ***
<----><----><----><----><----><----><---->
1      1     0.02    0.0     0.0     0.5     0.0
END HYDR-PARM2
HYDR-INIT
RCHRES Initial conditions for each HYDR section ****
# - # *** VOL Initial value of COLIND Initial value of OUTDGT
*** ac-ft for each possible exit for each possible exit
<----><----> <----><----><----> *** <----><----><----><---->
1      0     4.0     0.0     0.0     0.0     0.0     0.0     0.0     0.0
END HYDR-INIT
END RCHRES

SPEC-ACTIONS
END SPEC-ACTIONS
FTABLES
FTABLE      1
91      4
Depth      Area      Volume  Outflow1 Velocity  Travel Time ***
(ft)      (acres)   (acre-ft) (cfs)    (ft/sec)   (Minutes) ***
0.000000  0.000000  0.000000  0.000000
0.088889  0.004197  0.000249  0.001360
0.177778  0.005902  0.000703  0.001923
0.266667  0.007187  0.001286  0.002356
0.355556  0.008251  0.001974  0.002720
0.444444  0.009171  0.002749  0.003041
0.533333  0.009987  0.003601  0.003331
0.622222  0.010723  0.004522  0.003598
0.711111  0.011394  0.005505  0.003847
0.800000  0.012011  0.006546  0.004080
0.888889  0.012582  0.007639  0.004301
0.977778  0.013114  0.008782  0.004511
1.066667  0.013610  0.009970  0.004711
1.155556  0.014075  0.011200  0.004904
1.244444  0.014511  0.012471  0.005089
1.333333  0.014921  0.013779  0.005267
1.422222  0.015307  0.015123  0.005440
1.511111  0.015671  0.016500  0.005608
1.600000  0.016015  0.017908  0.005770
1.688889  0.016339  0.019346  0.005928
1.777778  0.016645  0.020812  0.006082
1.866667  0.016934  0.022305  0.006232
1.955556  0.017206  0.023822  0.006379
2.044444  0.017463  0.025363  0.006523
2.133333  0.017705  0.026926  0.006663
2.222222  0.017933  0.028510  0.006800
2.311111  0.018146  0.030114  0.006935
2.400000  0.018347  0.031736  0.007067
2.488889  0.018535  0.033375  0.007197
2.577778  0.018710  0.035031  0.007324
2.666667  0.018873  0.036701  0.007449
2.755556  0.019025  0.038386  0.007572

```

| | | | |
|----------|----------|----------|----------|
| 2.844444 | 0.019165 | 0.040083 | 0.007694 |
| 2.933333 | 0.019293 | 0.041792 | 0.007813 |
| 3.022222 | 0.019411 | 0.043513 | 0.007930 |
| 3.111111 | 0.019518 | 0.045243 | 0.008046 |
| 3.200000 | 0.019614 | 0.046982 | 0.008160 |
| 3.288889 | 0.019699 | 0.048730 | 0.008273 |
| 3.377778 | 0.019775 | 0.050484 | 0.008384 |
| 3.466667 | 0.019840 | 0.052245 | 0.008493 |
| 3.555556 | 0.019894 | 0.054011 | 0.008602 |
| 3.644444 | 0.019939 | 0.055781 | 0.008708 |
| 3.733333 | 0.019974 | 0.057555 | 0.008814 |
| 3.822222 | 0.019999 | 0.059332 | 0.008918 |
| 3.911111 | 0.020013 | 0.061110 | 0.009021 |
| 4.000000 | 0.020018 | 0.062890 | 0.009123 |
| 4.088889 | 0.020013 | 0.064669 | 0.009224 |
| 4.177778 | 0.019999 | 0.066447 | 0.009324 |
| 4.266667 | 0.019974 | 0.068224 | 0.009423 |
| 4.355556 | 0.019939 | 0.069998 | 0.009520 |
| 4.444444 | 0.019894 | 0.071768 | 0.009617 |
| 4.533333 | 0.019840 | 0.073534 | 0.009713 |
| 4.622222 | 0.019775 | 0.075295 | 0.009807 |
| 4.711111 | 0.019699 | 0.077049 | 0.011185 |
| 4.800000 | 0.019614 | 0.078797 | 0.013846 |
| 4.888889 | 0.019518 | 0.080536 | 0.015381 |
| 4.977778 | 0.019411 | 0.082266 | 0.016598 |
| 5.066667 | 0.019293 | 0.083987 | 0.017644 |
| 5.155556 | 0.019165 | 0.085696 | 0.018580 |
| 5.244444 | 0.019025 | 0.087393 | 0.019435 |
| 5.333333 | 0.018873 | 0.089078 | 0.020229 |
| 5.422222 | 0.018710 | 0.090748 | 0.020975 |
| 5.511111 | 0.018535 | 0.092404 | 0.021680 |
| 5.600000 | 0.018347 | 0.094043 | 0.022352 |
| 5.688889 | 0.018146 | 0.095665 | 0.022994 |
| 5.777778 | 0.017933 | 0.097269 | 0.023612 |
| 5.866667 | 0.017705 | 0.098853 | 0.024207 |
| 5.955556 | 0.017463 | 0.100416 | 0.024782 |
| 6.044444 | 0.017206 | 0.101957 | 0.026398 |
| 6.133333 | 0.016934 | 0.103474 | 0.027714 |
| 6.222222 | 0.016645 | 0.104967 | 0.028774 |
| 6.311111 | 0.016339 | 0.106433 | 0.029721 |
| 6.400000 | 0.016015 | 0.107871 | 0.030597 |
| 6.488889 | 0.015671 | 0.109279 | 0.031421 |
| 6.577778 | 0.015307 | 0.110656 | 0.032206 |
| 6.666667 | 0.014921 | 0.112000 | 0.032958 |
| 6.755556 | 0.014511 | 0.113308 | 0.033683 |
| 6.844444 | 0.014075 | 0.114579 | 0.034384 |
| 6.933333 | 0.013610 | 0.115809 | 0.035064 |
| 7.022222 | 0.013114 | 0.116997 | 0.106054 |
| 7.111111 | 0.012582 | 0.118140 | 0.821138 |
| 7.200000 | 0.012011 | 0.119233 | 1.923675 |
| 7.288889 | 0.011394 | 0.120274 | 3.276970 |
| 7.377778 | 0.010723 | 0.121257 | 4.783643 |
| 7.466667 | 0.009987 | 0.122178 | 6.346395 |
| 7.555556 | 0.009171 | 0.123030 | 7.865931 |
| 7.644444 | 0.008251 | 0.123805 | 9.248484 |
| 7.733333 | 0.007187 | 0.124493 | 10.41818 |
| 7.822222 | 0.005902 | 0.125076 | 11.33270 |
| 7.911111 | 0.004197 | 0.125530 | 12.00147 |
| 8.000000 | 0.001000 | 0.125779 | 12.50607 |

END FTABLE 1

END FTABLES

EXT SOURCES

| <-Volume-> | <Member> | SsysSgap | <--Mult--> | Tran | <-Target vols> | <-Grp> | <-Member-> | *** | | | | | |
|------------|----------|----------|------------|----------|----------------|--------|------------|-----|-----|--------|--------|---|-----|
| <Name> | # | <Name> | # | tem strg | <-factor-> | strg | <Name> | # | # | <Name> | # | # | *** |
| WDM | 2 | PREC | | ENGL | 1 | | PERLND | 1 | 999 | EXTNL | PREC | | |
| WDM | 2 | PREC | | ENGL | 1 | | IMPLND | 1 | 999 | EXTNL | PREC | | |
| WDM | 1 | EVAP | | ENGL | 0.76 | | PERLND | 1 | 999 | EXTNL | PETINP | | |
| WDM | 1 | EVAP | | ENGL | 0.76 | | IMPLND | 1 | 999 | EXTNL | PETINP | | |

END EXT SOURCES

EXT TARGETS

```
<-Volume-> <-Grp> <-Member-><--Mult-->Tran <-Volume-> <Member> Tsys Tgap Amd ***
<Name> # <Name> # #<-factor->strg <Name> # <Name> tem strg strg***  
RCHRES 1 HYDR RO 1 1 1 WDM 1002 FLOW ENGL REPL  
RCHRES 1 HYDR STAGE 1 1 1 WDM 1003 STAG ENGL REPL  
COPY 1 OUTPUT MEAN 1 1 48.4 WDM 701 FLOW ENGL REPL  
COPY 501 OUTPUT MEAN 1 1 48.4 WDM 801 FLOW ENGL REPL  
END EXT TARGETS
```

MASS-LINK

```
<Volume> <-Grp> <-Member-><--Mult--> <Target> <-Grp> <-Member->***  
<Name> <Name> # #<-factor-> <Name> # #***  
MASS-LINK 2  
PERLND PWATER SURO 0.083333 RCHRES INFLOW IVOL  
END MASS-LINK 2
```

```
MASS-LINK 3  
PERLND PWATER IFWO 0.083333 RCHRES INFLOW IVOL  
END MASS-LINK 3
```

```
MASS-LINK 5  
IMPLND IWATER SURO 0.083333 RCHRES INFLOW IVOL  
END MASS-LINK 5
```

```
MASS-LINK 12  
PERLND PWATER SURO 0.083333 COPY INPUT MEAN  
END MASS-LINK 12
```

```
MASS-LINK 13  
PERLND PWATER IFWO 0.083333 COPY INPUT MEAN  
END MASS-LINK 13
```

```
MASS-LINK 15  
IMPLND IWATER SURO 0.083333 COPY INPUT MEAN  
END MASS-LINK 15
```

```
MASS-LINK 16  
RCHRES ROFLOW COPY INPUT MEAN  
END MASS-LINK 16
```

END MASS-LINK

END RUN

Predeveloped HSPF Message File

Mitigated HSPF Message File

Disclaimer

Legal Notice

This program and accompanying documentation are provided 'as-is' without warranty of any kind. The entire risk regarding the performance and results of this program is assumed by End User. Clear Creek Solutions Inc. and the governmental licensee or sublicensees disclaim all warranties, either expressed or implied, including but not limited to implied warranties of program and accompanying documentation. In no event shall Clear Creek Solutions Inc. be liable for any damages whatsoever (including without limitation to damages for loss of business profits, loss of business information, business interruption, and the like) arising out of the use of, or inability to use this program even if Clear Creek Solutions Inc. or their authorized representatives have been advised of the possibility of such damages. Software Copyright © by : Clear Creek Solutions, Inc. 2005-2022; All Rights Reserved.

Clear Creek Solutions, Inc.
6200 Capitol Blvd. Ste F
Olympia, WA. 98501
Toll Free 1(866)943-0304
Local (360)943-0304

www.clearcreeksolutions.com

APPENDIX C

Geotechnical Report