

IV. PEDESTRIANS and TRAFFIC

- A. The applicant shall comply with the traffic control plan attached to this permit. However, the contractor may submit a revised traffic control plan for City review.

- E. One lane, two-way traffic control (see traffic control plan drawing E07-TMP002) may only be performed Monday – Friday 9:00 am – 3:30 pm and as needed on Saturdays 9:00 am – 3:30 pm. Additional time restrictions may be added to this permit to mitigate one lane, flagger controlled construction impacts on traffic when frequent and significant traffic delays extend through intersections beyond the limits of the approved traffic control plan(s).

VII. CONSTRUCTION and RESTORATION

- H. Final asphalt restoration must be completed prior to substantial completion and inspection of each phase of construction in the traffic control plan(s). The limits of pavement restoration in the public right of way shall be limited to the approved permit plan set unless pavement has been clearly damaged beyond said limits.

- I. Class B hot mix asphalt or polymer-modified cold asphalt (EZ Street or equal) shall be used for temporary asphalt patches. MC250 cold mix is not allowed. Temporary asphalt patches shall be marked “TEMP” in white paint.