

October 18, 2016

JN 16441

Mark Frohlich
7236 – 78th Avenue Southeast
Mercer Island, Washington 98040

via email: mwfrohlich@gmail.com, amkrivers@gmail.com

Subject: Transmittal Letter – Geotechnical Engineering Study
Proposed Single-Family Residence
23 Holly Hill Drive
Mercer Island, Washington

Dear Mr. Frohlich:

We are pleased to present this geotechnical engineering report for the single-family residence to be constructed in Mercer Island, Washington. The scope of our services consisted of exploring site surface and subsurface conditions, and then developing this report to provide recommendations for general earthwork and design criteria for foundations, retaining walls, and shoring. This work was authorized by your acceptance of our proposal, P-9567, dated September 15, 2016.

The attached report contains a discussion of the study and our recommendations. Please contact us if there are any questions regarding this report, or for further assistance during the design and construction phases of this project.

Respectfully submitted,

GEOTECH CONSULTANTS, INC.



Thor Christensen, P.E.
Senior Engineer

cc: **Soldano Luth Architects** – Jeff Luth
via email: jeff@soldanoluth.com

TRC/DRW:mw

GEOTECHNICAL ENGINEERING STUDY
Proposed Single-Family Residence
23 Holly Hill Drive
Mercer Island, Washington

This report presents the findings and recommendations of our geotechnical engineering study for the site of the proposed single-family residence to be located in Mercer Island.

We were provided with a topographic survey, a site plan, and cross-sections prepared by Soldano Luth Architects dated August 23 and October 13, 2016. Based on these plans, we understand that the development will consist of a two-story residence that will have a partial basement that daylights toward the west. In addition, there will be a deck at the northwest corner of the structure and a daylight basement level below that deck. Based on the plans, excavations of up to 8 feet will be required for the basement levels of the residence and for the garage. A garage with two levels will be attached to the northeast corner of the proposed residence. The upper level of the garage will be accessed from a driveway to the east and the lower level will be accessed from an autocourt to the south. The residence and the north side of the garage will be set back 12 feet from the northern property line. The south side of the residence will be 7 feet or more from the southern property line.

A retaining wall is proposed on the north side of the residence for a flight of stairs that will be 6 feet from that property line. The excavation for this wall will be as much as 6 feet. An autocourt and new driveway are proposed southeast and east of the residence that will be up to 10 feet below the existing ground surface. It appears that some grading adjacent to these will be as close as 6 feet from the southern property line. A grass lawn will be southwest of the residence and will have an elevation up to 8 feet above the existing ground surface.

If the scope of the project changes from what we have described above, we should be provided with revised plans in order to determine if modifications to the recommendations and conclusions of this report are warranted.

SITE CONDITIONS

SURFACE

The Vicinity Map, Plate 1, illustrates the general location of the site in Mercer Island. The site is bordered to the west by Lake Washington and is otherwise surrounded by residences.

A driveway enters the site's northeast corner and leads to the centrally located existing house, which has one story and a basement that daylights toward the west. There is a detached garage southeast of the house. The ground surface within the site, and in the surrounding vicinity, slopes gently to moderately down toward the west. The most moderately sloped area, with inclinations in the range of 30 percent, is located on the western portion of the site, west of the house. There are no steep slopes within the site and we did not observe indications of slope instability at the site. Small flat to gently sloping lawns are east and west of the house. Most of the undeveloped areas of the site are vegetated with landscaping bushes. There is a gently sloping grass lawn about 50 feet wide at the west edge of the property adjacent to the lake. This area was below Lake Washington before it was lowered about 10 feet in 1916. There is a rock bulkhead about 3 to 4 feet high along the Lake Washington shoreline and a dock extends into the lake.

The Mercer Island Landslide Hazard Assessment map by Kathy Troost and Aaron Wischer dated April 2009 shows that the site has been designated as a Landslide Hazard Area. That map also shows that the site has a slope inclination of 15 percent or steeper. No landslides are mapped within the site or in the immediate vicinity.

SUBSURFACE

The subsurface conditions were explored by drilling six test borings at the approximate locations shown on the Site Exploration Plan, Plate 2. Our exploration program was based on the proposed construction, anticipated subsurface conditions and those encountered during exploration, and the scope of work outlined in our proposal.

The test borings were drilled on October 10, 2016 using a track-mounted, hollow-stem auger drill. Samples were taken at approximate 2.5 and 5-foot intervals with a standard penetration sampler. This split-spoon sampler, which has a 2-inch outside diameter, is driven into the soil with a 140-pound hammer falling 30 inches. The number of blows required to advance the sampler a given distance is an indication of the soil density or consistency. A geotechnical engineer from our staff observed the drilling process, logged the test borings, and obtained representative samples of the soil encountered. The Test Boring Logs are attached as Plates 3 through 8.

Soil Conditions

Below some topsoil, the test borings encountered native silty sand with gravel soil that was in a loose to medium-dense condition. This soil became dense to very dense at about 2 to 7 feet below the ground surface. This dense to very dense soil is known geologically as glacial till; this soil exhibits high strength and very low permeability. The depth to the very dense glacial till was deepest in the three test borings close to the existing house (Test Borings 4, 5, and 6); at approximately 4 to 7 feet. The glacial till extended to the maximum explored depths of 11 to 16 feet.

Groundwater Conditions

No groundwater seepage was observed in the borings, which were completed following a dry summer. It should be noted, however, that groundwater levels vary seasonally with rainfall and other factors, and they are generally highest during the normally wet winter and spring months. It is possible that groundwater could be found in more permeable soil layers and between the looser near-surface soil and the underlying denser glacial till.

The stratification lines on the logs represent the approximate boundaries between soil types at the exploration locations. The actual transition between soil types may be gradual, and subsurface conditions can vary between exploration locations. The logs provide specific subsurface information only at the locations tested. If a transition in soil type occurred between samples in the borings, the depth of the transition was interpreted. The relative densities and moisture descriptions indicated on the test boring logs are interpretive descriptions based on the conditions observed during drilling.

CONCLUSIONS AND RECOMMENDATIONS

GENERAL

THIS SECTION CONTAINS A SUMMARY OF OUR STUDY AND FINDINGS FOR THE PURPOSES OF A GENERAL OVERVIEW ONLY. MORE SPECIFIC RECOMMENDATIONS AND CONCLUSIONS ARE CONTAINED IN THE REMAINDER OF THIS REPORT. ANY PARTY RELYING ON THIS REPORT SHOULD READ THE ENTIRE DOCUMENT.

The test borings conducted for this study encountered dense to very dense glacial till soil at depths of about 2 to 7 feet. These soils will provide excellent support to the proposed residence. Conventional footings can be used as the foundations for the residence and retaining walls provide they bear on the glacial till soil. Some over-excavation may be required to expose the competent glacial till soil in some footing locations. Although dense, the glacial till soil is silty; thus it is highly moisture sensitive and can be easily disturbed when wet. If subgrades will be prepared during wet weather they should be protected from disturbance by the placement of several inches of crushed rock.

Temporary excavations in the upper loose to medium-dense soil can have an inclination of 1:1 (H:V). The underlying glacial till can be excavated at a steeper inclination of 0.75:1. If temporary excavations cannot be contained within the site, temporary easements to extend excavations into adjacent properties should be the next alternative. Excavation shoring would be necessary if open excavations of these inclinations on or outside of the property cannot be made. The width of excavations can be limited, which could possibly avoid easements or shoring, if foundations are designed as "property line foundations" that do not extend outward toward the nearby property lines. Information regarding shoring is included in a later section of this study.

The driveway that will access the upper level of the garage will be underlain by retaining wall backfill. As a result, it will be important that the basement wall backfill be thoroughly compacted to prevent noticeable post-construction settlement. Depending on the moisture content of the on-site soil and the weather conditions at the time of backfilling, it may be necessary to import granular fill to attain adequate compaction.

The erosion control measures needed during the site development will depend heavily on the weather conditions that are encountered during the site work. The location of the site on the shore of Lake Washington will make proper erosion control implementation important to prevent adverse impacts to the lake. However, we have been associated with numerous waterfront projects that have avoided siltation of the lake and surrounding properties by exercising care and being proactive with the maintenance and potential upgrading of the erosion control system through the entire construction process. One of the most important considerations, particularly during wet weather, is to immediately cover any bare soil to prevent accumulated water or runoff from the work area from becoming silty in the first place. Silty water cannot be discharged to the lake. A wire-backed silt fence bedded in compost, not native soil or sand, should be erected as close as possible to the planned work area, and the existing vegetation between the silt fence and the lake left in place. Rocked construction access and staging areas should be established wherever trucks will have to drive off of pavement, in order reduce the amount of soil or mud carried off the property by trucks and equipment. It will also be important to cap any existing drain lines found running toward the lake until excavation is completed. This will reduce the potential for silty water finding an old pipe and flowing into the lake. Covering the base of the excavation with a layer of clean gravel or rock is also prudent to reduce the amount of mud and silty water generated. Utilities reaching between the house and the lake should not be installed during rainy weather, and any

disturbed area caused by the utility installation should be minimized by using small equipment. Cut slopes and soil stockpiles should be covered with plastic during wet weather. Soil stockpiles should be minimized. Following rough grading, it may be necessary to mulch or hydroseed bare areas that will not be immediately covered with landscaping or an impervious surface.

It is unclear if earthwork for this project will be done in during the "wet season". Wet weather construction on this site should be possible without adverse impacts to the surrounding properties. In preventing erosion control problems on any site, it is most important that any disturbed soil areas be immediately protected. This requires diligence and frequent communication on the part of the general contractor and earthwork subcontractor. As with all construction projects undertaken during potentially wet conditions, it is important that the contractor's on-site personnel are familiar with erosion control measures and that they monitor their performance on a regular basis. It is also appropriate for them to take immediate action to correct any erosion control problems that may develop, without waiting for input from the geotechnical engineer or representatives of the City.

In order to satisfy the City of Mercer Island's requirements, a "statement of risk" is required. As such, we make the following statement:

Provided recommendations in this study are followed, the development has been designed so that the risk to the lot and adjacent property is mitigated such that the site is determined to be safe.

The drainage and/or waterproofing recommendations presented in this report are intended only to prevent active seepage from flowing through concrete walls or slabs. Even in the absence of active seepage into and beneath structures, water vapor can migrate through walls, slabs, and floors from the surrounding soil, and can even be transmitted from slabs and foundation walls due to the concrete curing process. Water vapor also results from occupant uses, such as cooking and bathing. Excessive water vapor trapped within structures can result in a variety of undesirable conditions, including, but not limited to, moisture problems with flooring systems, excessively moist air within occupied areas, and the growth of molds, fungi, and other biological organisms that may be harmful to the health of the occupants. The designer or architect must consider the potential vapor sources and likely occupant uses, and provide sufficient ventilation, either passive or mechanical, to prevent a build up of excessive water vapor within the planned structure.

Geotech Consultants, Inc. should be allowed to review the final development plans to verify that the recommendations presented in this report are adequately addressed in the design. Such a plan review would be additional work beyond the current scope of work for this study, and it may include revisions to our recommendations to accommodate site, development, and geotechnical constraints that become more evident during the review process.

We recommend including this report, in its entirety, in the project contract documents. This report should also be provided to any future property owners so they will be aware of our findings and recommendations.

SEISMIC CONSIDERATIONS

In accordance with the International Building Code (IBC), the site soil profile within 100 feet of the ground surface is best represented by Site Class Type C (Very Dense Soil). As noted in the USGS website, the mapped spectral acceleration value for a 0.2 second (S_s) and 1.0 second period (S_1) equals 1.47g and 0.56g, respectively.

The IBC states that a site-specific seismic study need not be performed provided that the peak ground acceleration be equal to $S_{DS}/2.5$, where S_{DS} is determined in ASCE 7. It is noted that S_{DS} is equal to $2/3S_{MS}$. S_{MS} equals F_a times S_s , where F_a is determined in Table 11.4-1. For our site, $F_a = 1.0$. The calculated peak ground acceleration that we utilized for the seismic-related parameters (earth pressures, seismic surcharges, and slope stability) of this report equals 0.39g.

The site soils are not susceptible to seismic liquefaction because of their very dense nature and the absence of near-surface groundwater. This statement regarding liquefaction includes the knowledge of the peak ground acceleration that is anticipated under a 1-in-2,500-year seismic event, which is significantly higher than the above-calculated ground acceleration.

CONVENTIONAL FOUNDATIONS

The proposed structure can be supported on conventional continuous and spread footings bearing on undisturbed, dense to very dense glacial till. We recommend that continuous and individual spread footings have minimum widths of 12 and 16 inches, respectively. Exterior footings should also be bottomed at least 18 inches below the lowest adjacent finish ground surface for protection against frost and erosion. The local building codes should be reviewed to determine if different footing widths or embedment depths are required. Footing subgrades must be cleaned of loose or disturbed soil prior to pouring concrete. Depending upon site and equipment constraints, this may require removing the disturbed soil by hand.

An allowable bearing pressure of 3,000 pounds per square foot (psf) is appropriate for footings supported on competent native soil. A one-third increase in this design bearing pressure may be used when considering short-term wind or seismic loads. For the above design criteria, it is anticipated that the total post-construction settlement of footings founded on competent native soil will be about one-inch, with differential settlements on the order of one-half-inch in a distance of 30 feet along a continuous footing with a uniform load.

Lateral loads due to wind or seismic forces may be resisted by friction between the foundation and the bearing soil, or by passive earth pressure acting on the vertical, embedded portions of the foundation. For the latter condition, the foundation must be either poured directly against relatively level, undisturbed soil or be surrounded by level, well-compacted fill. We recommend using the following ultimate values for the foundation's resistance to lateral loading:

PARAMETER	ULTIMATE VALUE
Coefficient of Friction	0.45
Passive Earth Pressure	300 pcf

Where: pcf is Pounds per Cubic Foot, and Passive Earth Pressure is computed using the Equivalent Fluid Density.

If the ground in front of a foundation is loose or sloping, the passive earth pressure given above will not be appropriate. We recommend maintaining a safety factor of at least 1.5 for the foundation's resistance to lateral loading, when using the above ultimate values.

FOUNDATION AND RETAINING WALLS

Retaining walls backfilled on only one side should be designed to resist the lateral earth pressures imposed by the soil they retain. The following recommended parameters are for walls that restrain level backfill:

PARAMETER	VALUE
Active Earth Pressure *	35 pcf
Passive Earth Pressure	300 pcf
Coefficient of Friction	0.45
Soil Unit Weight	130 pcf

Where: pcf is Pounds per Cubic Foot, and Active and Passive Earth Pressures are computed using the Equivalent Fluid Pressures.

* For a restrained wall that cannot deflect at least 0.002 times its height, a uniform lateral pressure equal to 10 psf times the height of the wall should be added to the above active equivalent fluid pressure.

The design values given above do not include the effects of any hydrostatic pressures behind the walls and assume that no surcharges, such as those caused by slopes, vehicles, or adjacent foundations will be exerted on the walls. If these conditions exist, those pressures should be added to the above lateral soil pressures. Where sloping backfill is desired behind the walls, we will need to be given the wall dimensions and the slope of the backfill in order to provide the appropriate design earth pressures. The surcharge due to traffic loads behind a wall can typically be accounted for by adding a uniform pressure equal to 2 feet multiplied by the above active fluid density. Heavy construction equipment should not be operated behind retaining and foundation walls within a distance equal to the height of a wall, unless the walls are designed for the additional lateral pressures resulting from the equipment.

The values given above are to be used to design only permanent foundation and retaining walls that are to be backfilled, such as conventional walls constructed of reinforced concrete or masonry. It is not appropriate to use the above earth pressures and soil unit weight to back-calculate soil strength parameters for design of other types of retaining walls, such as soldier pile, reinforced earth, modular or soil nail walls. We can assist with design of these types of walls, if desired. The passive pressure given is appropriate only for a shear key poured directly against undisturbed native soil, or for the depth of level, well-compacted fill placed in front of a retaining or foundation wall. The values for friction and passive resistance are ultimate values and do not include a safety factor. Restrained wall soil parameters should be utilized for a distance of 1.5 times the wall height from corners or bends in the walls. This is intended to reduce the amount of cracking that can occur where a wall is restrained by a corner.

Wall Pressures Due to Seismic Forces

The surcharge wall loads that could be imposed by the design earthquake can be modeled by adding a uniform lateral pressure to the above-recommended active pressure. The recommended surcharge pressure is $8H$ pounds per square foot (psf), where H is the design retention height of the wall. Using this increased pressure, the safety factor against sliding and overturning can be reduced to 1.2 for the seismic analysis.

Retaining Wall Backfill and Waterproofing

Backfill placed behind retaining or foundation walls should be coarse, free-draining structural fill containing no organics. This backfill should contain no more than 5 percent silt or clay particles and have no gravel greater than 4 inches in diameter. The percentage of particles passing the No. 4 sieve should be between 25 and 70 percent. If the native silty soil is used as backfill, a drainage composite similar to Miradrain 6000 should be placed against the backfilled retaining walls. The drainage composites should be hydraulically connected to the foundation drain system.

The purpose of these backfill requirements is to ensure that the design criteria for a retaining wall are not exceeded because of a build-up of hydrostatic pressure behind the wall. Also, subsurface drainage systems are not intended to handle large volumes of water from surface runoff. The top 12 to 18 inches of the backfill should consist of a compacted, relatively impermeable soil or topsoil, or the surface should be paved. The ground surface must also slope away from backfilled walls to reduce the potential for surface water to percolate into the backfill. Water percolating through pervious surfaces (pavers, gravel, permeable pavement, etc.) must also be prevented from flowing toward walls or into the backfill zone. The compacted subgrade below pervious surfaces and any associated drainage layer should therefore be sloped away. Alternatively, a membrane and subsurface collection system could be provided below a pervious surface.

It is critical that the wall backfill be placed in lifts and be properly compacted, in order for the above-recommended design earth pressures to be appropriate. The wall design criteria assume that the backfill will be well-compacted in lifts no thicker than 12 inches. The compaction of backfill near the walls should be accomplished with hand-operated equipment to prevent the walls from being overloaded by the higher soil forces that occur during compaction. The section entitled **General Earthwork and Structural Fill** contains additional recommendations regarding the placement and compaction of structural fill behind retaining and foundation walls.

The above recommendations are not intended to waterproof below-grade walls, or to prevent the formation of mold, mildew or fungi in interior spaces. Over time, the performance of subsurface drainage systems can degrade, subsurface groundwater flow patterns can change, and utilities can break or develop leaks. Therefore, waterproofing should be provided where future seepage through the walls is not acceptable. This typically includes limiting cold-joints and wall penetrations, and using bentonite panels or membranes on the outside of the walls. There are a variety of different waterproofing materials and systems, which should be installed by an experienced contractor familiar with the anticipated construction and subsurface conditions. Applying a thin coat of asphalt emulsion to the outside face of a wall is not considered waterproofing, and will only help to reduce moisture generated from water vapor or capillary action from seeping through the concrete. As with any project, adequate ventilation of basement and crawl space areas is important to prevent a build up of water vapor that is commonly transmitted through concrete walls from the surrounding soil, even when seepage is not present. This is appropriate even when waterproofing is applied to the outside of foundation and retaining walls. We recommend that you contact an experienced envelope consultant if detailed recommendations or specifications related to waterproofing design, or minimizing the potential for infestations of mold and mildew are desired.

The **General**, **Slabs-On-Grade**, and **Drainage Considerations** sections should be reviewed for additional recommendations related to the control of groundwater and excess water vapor for the anticipated construction.

SLABS-ON-GRADE

The building floors can be constructed as slabs-on-grade atop competent native soil, or on structural fill. The subgrade soil must be in a firm, non-yielding condition at the time of slab construction or underslab fill placement. Any soft areas encountered should be excavated and replaced with select, imported structural fill.

Even where the exposed soils appear dry, water vapor will tend to naturally migrate upward through the soil to the new constructed space above it. This can affect moisture-sensitive flooring, cause imperfections or damage to the slab, or simply allow excessive water vapor into the space above the slab. All interior slabs-on-grade should be underlain by a capillary break drainage layer consisting of a minimum 4-inch thickness of clean gravel or crushed rock that has a fines content (percent passing the No. 200 sieve) of less than 3 percent and a sand content (percent passing the No. 4 sieve) of no more than 10 percent. Pea gravel or crushed rock are typically used for this layer. This capillary break/drainage layer is not necessary if an underslab drainage system is installed.

As noted by the American Concrete Institute (ACI) in the *Guides for Concrete Floor and Slab Structures*, proper moisture protection is desirable immediately below any on-grade slab that will be covered by tile, wood, carpet, impermeable floor coverings, or any moisture-sensitive equipment or products. ACI also notes that vapor *retarders* such as 6-mil plastic sheeting have been used in the past, but are now recommending a minimum 10-mil thickness for better durability and long term performance. A vapor retarder is defined as a material with a permeance of less than 0.3 perms, as determined by ASTM E 96. It is possible that concrete admixtures may meet this specification, although the manufacturers of the admixtures should be consulted. Where vapor retarders are used under slabs, their edges should overlap by at least 6 inches and be sealed with adhesive tape. The sheeting should extend to the foundation walls for maximum vapor protection. If no potential for vapor passage through the slab is desired, a vapor *barrier* should be used. A vapor barrier, as defined by ACI, is a product with a water transmission rate of 0.01 perms when tested in accordance with ASTM E 96. Reinforced membranes having sealed overlaps can meet this requirement.

The **General**, **Permanent Foundation and Retaining Walls**, and **Drainage Considerations** sections should be reviewed for additional recommendations related to the control of groundwater and excess water vapor for the anticipated construction.

EXCAVATIONS AND SLOPES

Excavation slopes should not exceed the limits specified in local, state, and national government safety regulations. Temporary cuts to a depth of about 4 feet may be attempted vertically in unsaturated soil, if there are no indications of slope instability. However, vertical cuts should not be made near property boundaries, or existing utilities and structures. Based upon Washington Administrative Code (WAC) 296, Part N, the upper loose to medium-dense soil at the subject site would generally be classified as Type B and the underlying glacial till would be classified as Type A. Therefore, temporary cut slopes greater than 4 feet in height should not be excavated at an

inclination steeper than 1:1 and 0.75:1 (Horizontal:Vertical), respectively, extending continuously between the top and the bottom of a cut.

The above-recommended temporary slope inclinations are based on the conditions exposed in our explorations, and on what has been successful at other sites with similar soil conditions. It is possible that variations in soil and groundwater conditions will require modifications to the inclination at which temporary slopes can stand. Temporary cuts are those that will remain unsupported for a relatively short duration to allow for the construction of foundations, retaining walls, or utilities. Temporary cut slopes should be protected with plastic sheeting during wet weather. It is also important that surface runoff be directed away from the top of temporary slope cuts. Cut slopes should also be backfilled or retained as soon as possible to reduce the potential for instability. Please note that sand or loose soil can cave suddenly and without warning. Excavation, foundation, and utility contractors should be made especially aware of this potential danger. These recommendations may need to be modified if the area near the potential cuts has been disturbed in the past by utility installation, or if settlement-sensitive utilities are located nearby.

All permanent cuts into native soil should be inclined no steeper than 2:1 (H:V). Water should not be allowed to flow uncontrolled over the top of any temporary or permanent slope. All permanently exposed slopes should be seeded with an appropriate species of vegetation to reduce erosion and improve the stability of the surficial layer of soil.

TEMPORARY SHORING

As noted earlier, temporary shoring may be needed for this project. However, because the shoring would very likely be under 15 feet in height, cantilevered soldier pile shoring would like be suitable as shoring. Thus, this shoring section discusses cantilevered soldier pile shoring. It is typical to use a safety factor of 1.2 in the design of this type of shoring system if it is considered temporary. A safety factor of 1.5 should be used for a permanent shoring system.

Soldier Pile Installation

Soldier pile walls would be constructed after making planned cut slopes, and prior to commencing the mass excavation, by setting steel H-beams in a drilled hole and grouting the space between the beam and the soil with concrete for the entire height of the drilled hole. We anticipate that the holes could be drilled without casing, but the contractor should be prepared to case the holes or use the slurry method if caving soil is encountered. Excessive ground loss in the drilled holes must be avoided to reduce the potential for settlement on adjacent properties. If water is present in a hole at the time the soldier pile is poured, concrete must be tremied to the bottom of the hole.

As excavation proceeds downward, the space between the piles should be lagged with timber, and any voids behind the timbers should be filled with pea gravel, or a slurry comprised of sand and fly ash. Treated lagging is usually required for permanent walls, while untreated lagging can often be utilized for temporary shoring walls. Temporary vertical cuts will be necessary between the soldier piles for the lagging placement. The prompt and careful installation of lagging is important, particularly in loose or caving soil, to maintain the integrity of the excavation and provide safer working conditions. Additionally, care must be taken by the excavator to remove no more soil between the soldier piles than is necessary to install the lagging. Caving or overexcavation during lagging placement could result in loss of ground on neighboring properties. Timber lagging should be

designed for an applied lateral pressure of 30 percent of the design wall pressure, if the pile spacing is less than three pile diameters. For larger pile spacings, the lagging should be designed for 50 percent of the design load.

Soldier Pile Wall Design

Temporary soldier pile shoring that is cantilevered and that has a level backslope should be designed for an active soil pressure equal to that pressure exerted by an equivalent fluid with a unit weight of 27 pounds per cubic foot (pcf). For shoring, use 32 pcf for the active pressure.

Traffic surcharges can typically be accounted for by increasing the effective height of the shoring wall by 2 feet. Slopes above the shoring walls will exert additional surcharge pressures. These surcharge pressures will vary, depending on the configuration of the cut slope and shoring wall. We can provide recommendations regarding slope surcharge pressures when the preliminary shoring design is completed.

It is important that the shoring design provides sufficient working room to drill and install the soldier piles, without needing to make unsafe, excessively steep temporary cuts. Cut slopes should be planned to intersect the backside of the drilled holes, not the back of the lagging.

Lateral movement of the soldier piles below the excavation level will be resisted by an ultimate passive soil pressure equal to that pressure exerted by a fluid with a density of 600 pcf. This soil pressure is valid only for a level excavation in front of the soldier pile; it acts on two times the grouted pile diameter. Cut slopes made in front of shoring walls significantly decrease the passive resistance. This includes temporary cuts necessary to install internal braces or rakers. The minimum embedment below the floor of the excavation for cantilever soldier piles should be equal to the height of the "stick-up."

EXCAVATION AND SHORING MONITORING

As with any shoring system, there is a potential risk of greater-than-anticipated movement of the shoring and the ground outside of the excavation. This can translate into noticeable damage of surrounding on-grade elements, such as foundations and slabs. Therefore, we recommend making an extensive photographic and visual survey of the project vicinity, prior to demolition activities, installing shoring or commencing excavation. This documents the condition of buildings, pavements, and utilities in the immediate vicinity of the site in order to avoid, and protect the owner from, unsubstantiated damage claims by surrounding property owners.

Additionally, the shoring walls, and any adjacent foundations, should be monitored during construction to detect soil movements. To monitor their performance, we recommend establishing a series of survey reference points to measure any horizontal deflections of the shoring system. Control points should be established at a distance well away from the walls and slopes, and deflections from the reference points should be measured throughout construction by survey methods. At least two soldier piles should be monitored by taking readings at the top of the pile. Additionally, benchmarks installed on the surrounding buildings should be monitored for at least vertical movement. We suggest taking the readings at least once a week, until it is established that no deflections are occurring. The initial readings for this monitoring should be taken before starting any demolition or excavation on the site.

DRAINAGE CONSIDERATIONS

Footing drains placed inside the building or behind backfilled walls should consist of 4-inch, perforated PVC pipe surrounded by at least 6 inches of 1-inch-minus, washed rock wrapped in a non-woven, geotextile filter fabric (Mirafi 140N, Supac 4NP, or similar material). At its highest point, a perforated pipe invert should be at least 6 inches below the level of a crawl space or the bottom of a floor slab, and it should be sloped slightly for drainage. Plate 9 presents typical considerations for footing drains. All roof and surface water drains must be kept separate from the foundation drain system.

If the structure includes an elevator, it may be necessary to provide special drainage or waterproofing measures for the elevator pit. If no seepage into the elevator pit is acceptable, it will be necessary to provide a footing drain and free-draining wall backfill, and the walls should be waterproofed. If the footing drain will be too low to connect to the storm drainage system, then it will likely be necessary to install a pumped sump to discharge the collected water. Alternatively, the elevator pit could be designed to be entirely waterproof; this would include designing the pit structure to resist hydrostatic uplift pressures.

As a minimum, a vapor retarder, as defined in the **Slabs-On-Grade** section, should be provided in any crawl space area to limit the transmission of water vapor from the underlying soils. Crawl space grades are sometimes left near the elevation of the bottom of the footings. As a result, an outlet drain is recommended for all crawl spaces to prevent an accumulation of any water that may bypass the footing drains. Providing even a few inches of free draining gravel underneath the vapor retarder limits the potential for seepage to build up on top of the vapor retarder.

No groundwater was observed during our field work. If seepage is encountered in an excavation, it should be drained from the site by directing it through drainage ditches, perforated pipe, or French drains, or by pumping it from sumps interconnected by shallow connector trenches at the bottom of the excavation.

The excavation and site should be graded so that surface water is directed off the site and away from the tops of slopes. Water should not be allowed to stand in any area where foundations, slabs, or pavements are to be constructed. Final site grading in areas adjacent to a building should slope away at least 2 percent, except where the area is paved. Surface drains should be provided where necessary to prevent ponding of water behind foundation or retaining walls. A discussion of grading and drainage related to pervious surfaces near walls and structures is contained in the **Foundation and Retaining Walls** section. Water from roof, storm water, and foundation drains should not be discharged onto slopes; it should be tightlined to a suitable outfall located away from any slopes.

GENERAL EARTHWORK AND STRUCTURAL FILL

All building and pavement areas should be stripped of surface vegetation, topsoil, organic soil, and other deleterious material. It is important that existing foundations be removed before site development. The stripped or removed materials should not be mixed with any materials to be used as structural fill, but they could be used in non-structural areas, such as landscape beds.

Structural fill is defined as any fill, including utility backfill, placed under, or close to, a building, behind permanent retaining or foundation walls, or in other areas where the underlying soil needs to support loads. All structural fill should be placed in horizontal lifts with a moisture content at, or

near, the optimum moisture content. The optimum moisture content is that moisture content that results in the greatest compacted dry density. The moisture content of fill is very important and must be closely controlled during the filling and compaction process. The on-site soils are not suitable for reuse as structural fill, due to their moisture sensitivity.

The allowable thickness of the fill lift will depend on the material type selected, the compaction equipment used, and the number of passes made to compact the lift. The loose lift thickness should not exceed 12 inches. We recommend testing the fill as it is placed. If the fill is not sufficiently compacted, it can be recompacted before another lift is placed. This eliminates the need to remove the fill to achieve the required compaction. The following table presents recommended relative compactions for structural fill:

LOCATION OF FILL PLACEMENT	MINIMUM RELATIVE COMPACTION
Beneath slabs or walkways	95%
Filled slopes and behind retaining walls	90%
Beneath pavements	95% for upper 12 inches of subgrade; 90% below that level

Where: Minimum Relative Compaction is the ratio, expressed in percentages, of the compacted dry density to the maximum dry density, as determined in accordance with ASTM Test Designation D 1557-91 (Modified Proctor).

Structural fill that will be placed in wet weather should consist of a coarse, granular soil with a silt or clay content of no more than 5 percent. The percentage of particles passing the No. 200 sieve should be measured from that portion of soil passing the three-quarter-inch sieve.

LIMITATIONS

The conclusions and recommendations contained in this report are based on site conditions as they existed at the time of our exploration and assume that the soil and groundwater conditions encountered in the test borings are representative of subsurface conditions on the site. If the subsurface conditions encountered during construction are significantly different from those observed in our explorations, we should be advised at once so that we can review these conditions and reconsider our recommendations where necessary. Unanticipated conditions are commonly encountered on construction sites and cannot be fully anticipated by merely taking samples in test borings. Subsurface conditions can also vary between exploration locations. Such unexpected conditions frequently require making additional expenditures to attain a properly constructed project. It is recommended that the owner consider providing a contingency fund to accommodate such potential extra costs and risks. This is a standard recommendation for all projects.

This report has been prepared for the exclusive use of Mark Frohlich and his representatives for specific application to this project and site. Our conclusions and recommendations are professional opinions derived in accordance with our understanding of current local standards of practice, and within the scope of our services. No warranty is expressed or implied. The scope of our services does not include services related to construction safety precautions, and our

recommendations are not intended to direct the contractor's methods, techniques, sequences, or procedures, except as specifically described in our report for consideration in design. Our services also do not include assessing or minimizing the potential for biological hazards, such as mold, bacteria, mildew and fungi in either the existing or proposed site development.

ADDITIONAL SERVICES

Geotech Consultants, Inc. should be retained to provide geotechnical consultation, testing, and observation services during construction. This is to confirm that subsurface conditions are consistent with those indicated by our exploration, to evaluate whether earthwork and foundation construction activities comply with the general intent of the recommendations presented in this report, and to provide suggestions for design changes in the event subsurface conditions differ from those anticipated prior to the start of construction. However, our work would not include the supervision or direction of the actual work of the contractor and its employees or agents. Also, job and site safety, and dimensional measurements, will be the responsibility of the contractor.

During the construction phase, we will provide geotechnical observation and testing services when requested by you or your representatives. Please be aware that we can only document site work we actually observe. It is still the responsibility of your contractor or on-site construction team to verify that our recommendations are being followed, whether we are present at the site or not.

The following plates are attached to complete this report:

Plate 1	Vicinity Map
Plate 2	Site Exploration Plan
Plates 3 - 8	Test Boring Logs
Plate 9	Typical Footing Drain Detail

We appreciate the opportunity to be of service on this project. Please contact us if you have any questions, or if we can be of further assistance.

Respectfully submitted,

GEOTECH CONSULTANTS, INC.




Thor Christensen, P.E.
Senior Engineer

RC/DRW:mw

D. Robert Ward, P.E.
Principal



NORTH



(Source: Microsoft MapPoint, 2013)

VICINITY MAP

23 Holly Hill Drive
Mercer Island, Washington





GEOTECH
CONSULTANTS, INC.

Job No: 16441	Date: Oct. 2016	Plate: 1
------------------	--------------------	-------------

Lake Washington

NORTH



Legend:

 Test Boring Location



GEOTECH
CONSULTANTS, INC.

SITE EXPLORATION PLAN


23 Holly Hill Drive
Mercer Island, Washington

Job No: 16441	Date: Oct. 2016	No Scale	Plate: 2
------------------	--------------------	----------	-------------

BORING 1

Depth (ft.)
Moisture
Water
Table
Blows
per Foot
Sample
USCS

Description



* Test boring was terminated at 13 feet on October 10, 2016.
* No groundwater was encountered during drilling.




TEST BORING LOG
23 Holly Hill Drive
Mercer Island, Washington

Job 16441	Date: Oct. 2016	Logged by: TRC	Plate: 3
---------------------	---------------------------	--------------------------	--------------------

BORING 2

Depth (ft.)
Moisture
Water
Table
Blows
per Foot
Sample
USCS

Description



- * Test boring was terminated at 11.5 feet on October 10, 2016.
- * No groundwater was encountered during drilling.




TEST BORING LOG
23 Holly Hill Drive
Mercer Island, Washington

Job 16441	Date: Oct. 2016	Logged by: TRC	Plate: 4
---------------------	---------------------------	--------------------------	--------------------

BORING 3

Depth (ft.)
Moisture
Water
Table
Blows
per Foot
Sample
USCS

Description



- * Test boring was terminated at 11 feet on October 10, 2016.
- * No groundwater was encountered during drilling.




TEST BORING LOG
23 Holly Hill Drive
Mercer Island, Washington

Job 16441	Date: Oct. 2016	Logged by: TRC	Plate: 5
---------------------	---------------------------	--------------------------	--------------------

BORING 4

Depth (ft.)
Moisture
Water
Table
Blows
per Foot
Sample
USCS

Description



- * Test boring was terminated at 16 feet on October 10, 2016.
- * No groundwater was encountered during drilling.




TEST BORING LOG
23 Holly Hill Drive
Mercer Island, Washington

Job 16441	Date: Oct. 2016	Logged by: TRC	Plate: 6
---------------------	---------------------------	--------------------------	--------------------

BORING 5

Depth (ft.)
Moisture
Water
Table
Blows
per Foot
Sample
USCS


Description



TEST BORING LOG
23 Holly Hill Drive
Mercer Island, Washington

Job 16441	Date: Oct. 2016	Logged by: TRC	Plate: 7
---------------------	---------------------------	--------------------------	--------------------

BORING 6




* Test boring was terminated at 16 feet on October 10, 2016.
 * No groundwater was encountered during drilling.



TEST BORING LOG
 23 Holly Hill Drive
 Mercer Island, Washington

Job	Date:	Logged by:	Plate:
16441	Oct. 2016	TRC	8



NOTES:

- (1) In crawl spaces, provide an outlet drain to prevent buildup of water that bypasses the perimeter footing drains.
- (2) Refer to report text for additional drainage, waterproofing, and slab considerations.



FOOTING DRAIN DETAIL
23 Holly Hill Drive
Mercer Island, Washington

Job No: 16441	Date: Oct. 2016		Plate: 9
------------------	--------------------	--	-------------